

# User's Guide

# XGS2220 Series

30/54-port GbE/SFP Smart Managed Layer-3 Switch

Default Logir	Details	Version 4.80 Edition 1, 07/2022
LAN IP Address	http://setup.zyxel or http://DHCP-assigned IP or http://192.168.1.1	
User Name	admin	
Password	1234	•

Copyright  $\ensuremath{\textcircled{\sc c}}$  2022 Zyxel and/or its affiliates. All Rights Reserved.

#### IMPORIANT!

#### READ CAREFULLY BEFORE USE

#### KEEP THIS GUIDE FOR FUTURE REFERENCE.

This is a User's Guide for a series of products. Not all products support all firmware features. Screenshots and graphics in this book may differ slightly from your products due to differences in your product firmware or your computer operating system. Every effort has been made to ensure that the information in this manual is accurate.

#### Related Documentation

• Quick Start Guide

The Quick Start Guide shows how to connect the Switch.

• CLI Reference Guide

This guide explains how to use the Command-Line Interface (CLI) to configure the Switch.

Note: It is recommended you use the Web Configurator to configure the Switch.

• Web Configurator Online Help

Click the help link for a description of the fields in the Switch menus.

Nebula Control Center (NCC) User's Guide

Go to the Ne bula Control Center to get this User's Guide on how to configure the Switch using Nebula

• More Information

Go to https://busine ssforum.zyxelcom for product discussions.

Go to *support.zyxe lcom* to find other information on the Switch.



### Document Conventions

#### Warnings and Notes

These are how warnings and notes are shown in this guide.

#### Wamings tell you about things that could harm you or your device.

Note: Notes tell you other important information (for example, other things you may need to configure or helpful tips) or recommendations.

#### Syntax Conventions

- All models may be referred to as the "Switch" in this guide.
- Product labels, screen names, field labels and field choices are all in **bold** font.
- A right angle bracket (>) within a screen name denotes a mouse click. For example, SYSTEM > IP Setup > Network Proxy Configuration means you first click SYSTEM in the navigation panel, then the IP Setup sub menu, then Network Proxy Configuration to get to that screen.

#### Icons Used in Figures

Figures in this user guide may use the following generic icons. The Switch icon is not an exact representation of your device.

Switch	Generic Router	Wireless Router / Access Point
Generic Switch	Smart TV	Desktop
	IP Camera	Printer
Server		

### Contents Overview

User's Guide	
Getting to Know Your Switch	
Hardware Installation and Connection	
Hardware Panels	
Te c hnic a l Reference	56
Web Configurator	
Initial Setup Example	
Tutorials	
DASHBOARD	
MONITOR	
ARP Table	
IP Table	
IPv6 Neighbor Table	
MAC Table	
Neighbor	
Path MTU Table	
Port Status	
Routing Table	
System Information	
System Log	
SYSTEM	
Cloud Management	
General Setup	
Interface Setup	
IP Setup	
IPv6	
Logins	
SNMP	
Switch Setup	
Syslog Setup	
Time Range	
PORT	
Auto PD Recovery	
Flex Link	
Green Ethernet	
Link Aggregation	
Link Layer Discovery Protocol (LLDP)	

OAM	. 248
PoE Setup	. 256
Port Setup	. 264
ZULD	. 266
SWITCHING	. 270
Layer 2 Protocol Tunneling	. 271
Loop Guard	. 275
MAC Pinning	. 278
Mirroring	. 280
Multicast	. 282
Static Multicast Forwarding	. 310
PPPoE	. 315
Differentiated Services	. 323
Queuing Method	. 327
Priority Queue	. 330
Bandwidth Control	. 332
sFlow	. 334
Spanning Tree Protocol	. 338
Static MAC Filtering	. 362
Static MAC Forwarding	. 364
VLAN	. 366
VLAN Isolation	. 390
VLAN Mapping	. 393
VLAN Stacking	. 397
NETWORKING	. 404
ARP Setup	. 405
DHCP	. 411
Static Route	. 424
SECURITY	. 428
AAA	. 429
Access Control	. 443
Classifier	. 453
Policy Rule	. 462
Anti-Arpscan	. 468
BPDU Guard	. 474
Storm Control	. 477
Error-Disable	. 479
IP Source Guard	. 485
DHCP Snooping	. 489
ARP Inspection	. 500
Port Authentication	. 518
Port Security	. 530
MAINTENANCE	. 533

Networked AV Mode	556
Trouble shooting and Appendices	616
Troubleshooting	617

## Table of Contents

Document Conventions		
Contents Overview	4	
Table of Contents	7	
Part I: Use r's Guide		
Chapter 1 Getting to Know Your Switch	28	
1.1 Introduction		
1.1.1 Multi-Gigabit		
1.1.2 Management Modes		
1.1.3 Mode Changing		
1.1.4 ZON Utility		
1.1.5 Web Configurator Networked AV Mode		
1.1.6 PoE		
1.2 Example Applications		
1.2.1 PoE Example Application		
1.2.2 Backbone Example Application		
1.2.3 Bridging Example Application		
1.2.4 High Performance Switching Example		
1.2.5 IEEE 802.1Q VLAN Application Examples		
1.2.6 IPv6 Support		
1.3 Ways to Manage the Switch		
1.4 Good Habits for Managing the Switch		
Chapter 2		
Hardware Installation and Connection		
2.1 Installation Scenarios	40	
2.2 Safety Precautions	40	
2.3 Freestanding Installation Procedure	40	
2.4 Mounting the Switch on a Rack		
2.4.1 Installation Requirements		
2.4.2 Precautions		
2.4.3 Attaching the Mounting Brackets to the Switch		
2.4.4 Mounting the Switch on a Rack		

Chapter 3	
Hardware	Paı

a rd w	vare Panels	44
	2.1 Frank Daniel Canada atland	
	3.1 Front Panel Connections	
	3.1.1 Gigabit Ethernet Ports	45
	3.1.2 SFP/SFP+ Slots	46
	3.1.3 Console Port	48
	3.2 Rear Panel	48
	3.2.1 Grounding	49
	3.2.2 AC Power Connection	51
	3.3 LEDs	53

Part II: Te chnic al Reference	
--------------------------------	--

#### Chapter 4

4.1 Overview	
4.2 System Login	
4.3 Zyxel One Network (ZON) Utility	
4.3.1 Requirements	
4.3.2 Run the ZON Utility	
4.4 Networked AV Mode Wizard	
4.4.1 Basic Settings	
4.4.2 Advanced Settings	
4.5 Wizard	
4.5.1 Basic	
4.5.2 Protection	
4.5.3 VLAN	
4.5.4 QoS	
4.6 Web Configurator Layout	
4.6.1 Tables and Lists	
4.6.2 Change Your Password	
4.7 Save Your Configuration	
4.8 Switch Lockout	
4.9 Reset the Switch	
4.9.1 Reboot the Switch	
4.9.2 Reload the Configuration File	
4.10 Log Out of the Web Configurator	
4.11 Help	

5.1 Overview	
5.1.1 Create a VLAN	
5.1.2 Set Port VID	
5.1.3 Configure Switch Management IP Address	
Chapter 6	
Tuto ria ls	
6.1 Overview	
6.2 How to Use DHCPv4 Snooping on the Switch	
6.3 How to Use DHCPv4 Relay on the Switch	
6.3.1 DHCP Relay Tutorial Introduction	
6.3.2 Create a VLAN	
6.3.3 Configure DHCPv4 Relay	
6.3.4 Troubleshooting	
6.4 How to Use Auto Configuration through a DHCP Server on the Switch	
Chapter 7	
DASHBOARD	
7.1 New User Interface	
7.2 DASHBOARD	
7.2.1 Port Status	
7.2.2 Quick Links to Use	
Chapter 8	
MONITOR	
Chapter 9	
ARP Ta b le	
9.1 ARP Table Overview	
9.1.1 What You Can Do	
9.1.2 What You Need to Know	
9.2 Viewing the ARP Table	
Chapter 10	
IP Ta b le	125
10.1 IP Table Overview	
10.2 Viewing the IP Table	
Chapter 11	
IPv6 Neighbor Table	127
11.1 IPv6 Neighbor Table Overview	
11.2 Viewing the IPv6 Neighbor Table	

Chapter 12 MAC Table	129
12.1 MAC Table Overview	
12.1.1 What You Can Do	
12.1.2 What You Need to Know	
12.2 Viewing the MAC Table	
Chapter 13 Neighbor	132
13.1 Neighbor Overview	
13.1.1 What You Can Do	
13.2 Neighbor	
13.2.1 Neighbor Details	
C hapter 14 Path MTU Table	136
14.1 Path MTU Overview	
14.2 Viewing the Path MTU Table	
C hapter 15 Port Status	137
15.0.1 What You Can Do	137
15.1 Port Status	
15.1.1 Port Details	
15.2 DDMI	
15.2.1 DDMI Details	
15.3 Port Utilization	
Chapter 16	
Routing Table	145
16.1 Routing Table Overview	
16.1.1 What You Can Do	
16.2 IPv4 Routing Table	
16.3 IPv6 Routing Table	
Chapter 17 System Information	147
17.0.1 What You Can Do	
17.1 System Information	
Chapter 18 System Log	150
18.1 System Log Overview	

18.2 System Log	
Chapter 19	
SYSTEM	152
Chapter 20 Cloud Management	153
20.1 Cloud Management Overview	
20.2 Nebula Center Control Discovery	
C hapter 21 General Setup	157
21.1 General Setup	
21.2 Hardware Monitor Setup	
Chapter 22	
Interface Setup	161
22.1 Interface Setup Overview	
22.2 Interface Setup	
22.2.1 Add/Edit Interfaces	
C hapter 23 IP Se tup	163
23.1 IP Setup Overview	
23.1.1 What You Can Do	
23.1.2 IP Interfaces	
23.2 IP Status	
23.2.1 IP Status Details	
23.3 IP Setup	
23.3.1 Add/Edit IP Interfaces	
23.4 Network Proxy Configuration	
Chapter 24	
IPv6	170
24.1 IPv6 Overview	
24.1.1 What You Can Do	
24.2 IPv6 Status	
24.2.1 IPv6 Interface Status Details	
24.3 IPv6 Global Setup	
24.4 IPv6 Interface Setup	
24.4.1 Edit an IPv6 Interface	175
24.5 IPv6 Link-Local Address Setup	
24.5.1 Edit an IPv6 Link-Local Address	
24.6 IPv6 Global Address Setup	

24.6.1 Add/Edit an IPv6 Global Address	
24.7 IPv6 Neighbor Discovery Setup	
24.7.1 Edit an IPv6 Neighbor Discovery	
24.8 IPv6 Router Discovery Setup	
24.8.1 Edit IPv6 Router Discovery	
24.9 IPv6 Prefix Setup	
24.9.1 Add/Edit IPv6 Prefix	
24.10 IPv6 Neighbor Setup	
24.10.1 Add/Edit IPv6 Neighbor	
24.11 DHCPv6 Client Setup	
24.11.1 Edit DHCPv6 Client	
Chapter 25	
Logins	
25.1 Set Up Login Accounts	
C hapter 26 SNMP	190
26.1 SNMP Overview	
26.1.1 What You Can Do	
26.2 Configure SNMP	
26.3 Configure SNMP User	
26.3.1 Add/Edit SNMP User	
26.4 Configure SNMP Trap Group	
26.5 Enable or Disable Sending of SNMP Traps on a Port	
26.6 Technical Reference	
Chapter 27	
Switc h Se tup	198
27.1 Switch Setup Overview	
27.1.1 Introduction to VLANs	
27.2 Switch Setup	
Chapter 28	
Syslog Setup	201
28.1 Syslog Overview	
28.1.1 What You Can Do	
28.2 Syslog Setup	
28.2.1 Add/Edit a Syslog Server	
Chapter 29	<b>6</b> . (
Time Range	

29.1 Time Range Overview	
29.1.1 What You Can Do	
29.2 Configuring Time Range	
29.2.1 Add/Edit Time Range	
Chapter 30	
PORT	207
Chapter 31	200
Auto PD Recovery	208
31.1 Auto PD Recovery (for PoE models only) Overview	
31.1.1 What You Can Do	
31.2 Auto PD Recovery	
31.2.1 Activate the Automatic PD Recovery	
Chapter 32	010
Flex Link	
32.1 Flex Link Overview	
32.1.1 What You Can Do	
32.2 Flex Link Status	
32.3 Flex Link Setup	
32.3.1 Add/Edit Flex Link	
Chapter 33	
Green Ethemet	216
33.1 Green Ethernet Overview	
33.1 Green Ethernet Overview 33.2 Configuring Green Ethernet	
33.1 Green Ethernet Overview 33.2 Configuring Green Ethernet <b>Chapter 34</b>	
33.1 Green Ethernet Overview 33.2 Configuring Green Ethernet	
33.1 Green Ethernet Overview 33.2 Configuring Green Ethernet <b>Chapter 34</b>	
33.1 Green Ethernet Overview 33.2 Configuring Green Ethernet Chapter 34 Link Aggregation	
<ul> <li>33.1 Green Ethernet Overview</li></ul>	
<ul> <li>33.1 Green Ethernet Overview</li></ul>	
<ul> <li>33.1 Green Ethernet Overview</li></ul>	216 216 <b>218</b> 218 218 218 218 218 218 219
<ul> <li>33.1 Green Ethernet Overview</li></ul>	216 216 <b>218</b> 218 218 218 218 218 218 219 221
<ul> <li>33.1 Green Ethernet Overview</li></ul>	216 216 <b>218</b> 218 218 218 218 218 218 219 221 221
<ul> <li>33.1 Green Ethernet Overview</li></ul>	216 216 <b>218</b> 218 218 218 218 218 219 221 221 222 224
<ul> <li>33.1 Green Ethernet Overview</li></ul>	216 216 <b>218</b> 218 218 218 218 218 219 221 221 222 224 224
<ul> <li>33.1 Green Ethernet Overview</li></ul>	216 216 <b>218</b> 218 218 218 218 218 219 221 221 222 224 224
<ul> <li>33.1 Green Ethernet Overview</li></ul>	216 216 218 218 218 218 218 219 221 221 222 224 224 224 224 224 224
<ul> <li>33.1 Green Ethernet Overview</li></ul>	216 216 218 218 218 218 218 218 219 221 221 222 224 224 224 224 224 224 224

35.2.2 What You Can Do – LLDP MED	
35.3 LLDP Local Status	
35.3.1 LLDP Local Port Status Detail	
35.4 LLDP Remote Status	
35.4.1 LLDP Remote Port Status Detail	
35.5 LLDP Setup	
35.6 Basic TLV Setting	
35.7 Org-specific TLV Setting	
35.8 LLDP-MED Setup	
35.9 LLDP-MED Network Policy	
35.9.1 Add/Edit LLDP-MED Network Policy	
35.10 LLDP-MED Location	
35.10.1 Add/Edit LLDP-MED Location	
Chapter 36 OAM	949
36.1 OAM Overview	
36.1.1 What You Can Do	
36.2 OAM Status	
36.2.1 OAM Details	
36.4 OAM Remote Loopback	
C hapter 37 Po E Se tup	256
37.1 PoE Status (for PoE models only)	
37.2 PoE Setup	
37.3 PoE Time Range Setup	
37.3.1 Add/Edit PoE Time Range	
C hap ter 38 Port Se tup	
38.1 Port Setup	
Chapter 39	
ZUID	
39.1 ZULD Overview	
39.1.1 What You Can Do	
39.1.2 What You Need to Know	
39.2 ZULD Status	
39.3 ZULD Setup	
C hapter 40 SWIIC HING	070

Chapter 41 Iayer 2 Protocol Tunneling	971
Layer 2 Frowcol lunneing	
41.1 Layer 2 Protocol Tunneling Overview	
41.1.1 What You Can Do	
41.1.2 What You Need to Know	
41.2 Configuring Layer 2 Protocol Tunneling	
Chapter 42	
Loop Guard	
42.1 Loop Guard Overview	
42.1.1 What You Can Do	
42.1.2 What You Need to Know	
42.2 Loop Guard Setup	
Chapter 43	
MAC Pinning	
43.1 MAC Pinning Overview	
43.2 MAC Pinning Configuration	
Chapter 44	
Mirroring	
44.1 Mirroring Overview	280
44.1.1 What You Need to Know	
44.2 Local Port Mirroring	
Chapter 45 Multic a st.	
45.1 Multicast Overview	
45.1.1 What You Can Do – IPv4 Multicast	
45.1.2 What You Can Do – IPv6 Multicast	
45.1.3 What You Can Do – MVR	
45.1.3 What You Need to Know	
45.2 IPv4 Multicast Status	
45.3 IGMP Snooping	
45.4 IGMP Snooping VLAN	
45.4.1 Add/Edit IGMP Snooping VLANs	
45.5 IGMP Filtering Profile	
45.5.1 Add IGMP Filtering Profile	
45.5.2 Add IGMP Filtering Rule	
45.5.2 Add IGMI Thering Kole 45.6 IPv6 Multicast Status	
45.7 MLD Snooping-proxy	
45.7 MLD Shooping-proxy VLAN	
45.8.1 Add/Edit MLD Snooping-proxy VLAN	

45.10 MLD Snooping-proxy Filtering	
In the proping proxy moning	
45.11 MLD Snooping-proxy Filtering Profile	
45.11.1 Add MLD Snooping-proxy Filtering Profile	
45.11.2 Add MLD Snooping-proxy Filtering Rule	
45.12 General MVR Configuration	
45.12.1 Add/Edit MVR	
45.13 MVR Group Setup	
45.13.1 Add/Edit MVR Group	
45.13.2 MVR Configuration Example	307
Chapter 46	
Static Multic ast Forwarding	
46.1 Static Multicast Forwarding Overview	
46.1.1 What You Can Do	
46.1.2 What You Need To Know	
46.2 Static Multicast Forwarding By MAC	
46.2.1 Add/Edit Static Multicast Forwarding By MAC	
46.3 Configure a Static Multicast IPv4 Address	
46.3.1 Add/Edit a Static Multicast Address By IP	
Chapter 47	015
PPPo E	315
47.1 PPPoE Intermediate Agent Overview	
47.1.1 What You Can Do	
47.1.1 What You Can Do 47.1.2 What You Need to Know	
47.1.2 What You Need to Know	
47.1.2 What You Need to Know 47.2 PPPoE Intermediate Agent	
47.1.2 What You Need to Know 47.2 PPPoE Intermediate Agent 47.3 PPPoE IA Port	
47.1.2 What You Need to Know 47.2 PPPoE Intermediate Agent 47.3 PPPoE IA Port 47.4 PPPoE IA Port VLAN 47.5 PPPoE IA VLAN <b>Chapter 48</b>	
47.1.2 What You Need to Know 47.2 PPPoE Intermediate Agent 47.3 PPPoE IA Port 47.4 PPPoE IA Port VLAN 47.5 PPPoE IA VLAN	
47.1.2 What You Need to Know 47.2 PPPoE Intermediate Agent 47.3 PPPoE IA Port 47.4 PPPoE IA Port VLAN 47.5 PPPoE IA VLAN <b>Chapter 48</b>	315 317 319 320 322 <b>323</b>
47.1.2 What You Need to Know	315 317 319 320 322 <b>323</b> 323
47.1.2 What You Need to Know	
47.1.2 What You Need to Know	
47.1.2 What You Need to Know	315 317 319 320 322 <b>323</b> 323 323 323 323 324 325
47.1.2 What You Need to Know	315 317 319 320 322 <b>323</b> 323 323 323 323 324 325
47.1.2 What You Need to Know	315 317 319 320 322 <b>323</b> 323 323 323 323 323 324 324 325 326
<ul> <li>47.1.2 What You Need to Know</li></ul>	315 317 319 320 322 <b>323</b> 323 323 323 323 323 324 324 325 326

49.1.1 What You Can Do	
49.1.2 What You Need to Know	
49.2 Configuring Queuing	
Chapter 50	220
Prio rity Que ue	
50.1 Priority Queue Overview	
50.1.1 What You Can Do	
50.2 Assign Priority Queue	
Chapter 51	
Bandwidth Control	
51.1 Bandwidth Control Overview	
51.1.1 What You Can Do	
51.1.2 CIR and PIR	
51.2 Bandwidth Control Setup	
Chapter 52	
sFlow	
52.1 sFlow Overview	
52.2 sFlow Port Configuration	
52.3 sFlow Collector Configuration	
52.3.1 Add/Edit sFlow Collector	
Chapter 53	
Spanning Tree Protocol	338
52.1 Segmetres Tree Protocol Quertions	220
53.1 Spanning Tree Protocol Overview	
53.1.1 What You Can Do	
53.1.2 What You Need to Know	
53.2 Spanning Tree Protocol Status	
53.3 Spanning Tree Setup	
53.4 Rapid Spanning Tree Protocol Status	
53.5 Configure Rapid Spanning Tree Protocol	
53.6 Multiple Rapid Spanning Tree Protocol Status	
53.7 Configure Multiple Rapid Spanning Tree Protocol	
53.8 Multiple Spanning Tree Protocol Status	
53.9 Configure Multiple Spanning Tree Protocol	
53.9.1 Add/Edit Multiple Spanning Tree	
53.10 Multiple Spanning Tree Protocol Port Setup	
53.11 Technical Reference	
53.11.1 MSTP Network Example	
53.11.2 MST Region	
53.11.3 MST Instance	

53.11.4 Common and Internal Spanning Tree (CIST)	
Chapter 54	
Static MAC Filtering	
54.1 Static MAC Filtering Overview	
54.1.1 What You Can Do	
54.2 Configure a Static MAC Filtering Rule	
54.2.1 Add/Edit a Static MAC Filtering Rule	
Chapter 55	
Static MAC Forwarding	
55.1 Static MAC Forwarding Overview	
55.1.1 What You Can Do	
55.2 Configure Static MAC Forwarding	
55.2.1 Add/Edit Static MAC Forwarding Rules	
Chapter 56	
VIAN	
56.1 VLAN Overview	
56.1.1 What You Can Do	
56.1.2 What You Need to Know	
56.2 Introduction to IEEE 802.1Q Tagged VLANs	
56.3 VLAN Status	
56.3.1 VLAN Details	
56.4 Configure a Static VLAN	
56.4.1 Add/Edit a Static VLAN	
56.5 VLAN Port Setup	
56.6 Configure GVRP	
56.7 Subnet Based VLANs	
56.8 Configuring Subnet Based VLAN	
56.8.1 Add/Edit Subnet Based VLAN	
56.9 Protocol Based VLANs	
56.10 Configuring Protocol Based VLAN	
56.10.1 Add/Edit a Protocol Based VLAN	
56.11 Voice VLAN	
56.11.1 Add/Edit a Voice VLAN	
56.12 MAC Based VLAN	
56.12.1 Add/Edit a MAC Based VLAN	
56.13 Vendor ID Based VLAN	
56.13.1 Add/Edit a Vendor ID Based VLAN	
56.14 Port-Based VLAN Setup	
56.15 Configure a Port-Based VLAN	

Chapter 57	
VIAN Isolation	
57.1 VLAN Isolation Overview	
57.2 Configuring VLAN Isolation	
57.2.1 Add/Edit a VLAN Isolation Rule	
Chapter 58	
VIAN Mapping	
58.1 VLAN Mapping Overview	
58.1.1 VLAN Mapping Example	
58.1.2 What You Can Do	
58.2 Enable VLAN Mapping	
58.3 VLAN Mapping Setup	
58.3.1 Add/Edit VLAN Mapping	
Chapter 59	
VIAN Stacking	
59.1 VLAN Stacking Overview	
59.1.1 VLAN Stacking Example	
59.2 VLAN Stacking Port Roles	
59.3 VLAN Tag Format	
59.3.1 Frame Format	
59.4 Configuring VLAN Stacking	
59.5 Port-Based Q-in-Q	
59.6 Selective Q-in-Q	
59.6.1 Add/Edit Selective Q-in-Q	403
Chapter 60	
NEIWO RKING	
Chapter 61	
ARP Se tup	405
61.1 ARP Overview	
61.1.1 What You Can Do	
61.1.2 What You Need to Know	
61.2 ARP Learning	
61.3 Static ARP	
61.3.1 Add/Edit Static ARP	
Chapter 62	
DHCP	411
62.1 DHCP Overview	
62.1.1 What You Can Do	

411
412
412
413
418
419
419
420
421
422
424
426
427
429
437
437
439
439
439 439
439 439

66.2 Service Access Control	443
66.3 Remote Management	
66.4 Account Security	
66.5 Technical Reference	447
66.5.1 SSH Overview	
66.5.2 Introduction to HTTPS	
66.5.3 Google Chrome Warning Messages	451
C ha p te r 67 C la ssifie r	453
67.1 Classifier Overview	
67.1.1 What You Can Do	
67.1.2 What You Need to Know	
67.2 Classifier Status	
67.3 Classifier Setup	
67.3.1 Add/Edit a Classifier 67.4 Classifier Global Setting	
67.4 Classifier Global senting	
Chapter 68	
Policy Rule	
68.1 Policy Rules Overview	
68.1.1 What You Can Do	
68.1.2 DiffServ	
68.1.3 DSCP and Per-Hop Behavior	
68.2 Policy Rules	
68.2.1 Add/Edit a Policy Rule	
68.3 Policy Example	
Chapter 69	
Anti-Arpscan	
69.1 Anti-Arpscan Overview	
69.1.1 What You Can Do	
69.1.2 What You Need to Know	
69.2 Anti-Arpscan Status	
69.3 Anti-Arpscan Host Status	
69.4 Anti-Arpscan Setup	
69.5 Anti-Arpscan Trust Host	
69.5.1 Add/Edit Anti-Arpscan Trust Hosts	
Chapter 70	
BPDU Guard	474
70.1 BPDU Guard Overview	

70.2 BPDU Guard Status	
70.3 BPDU Guard Setup	
Chapter 71	
Storm Control	
71.1 Storm Control Overview	
71.1.1 What You Can Do	
71.2 Storm Control Setup	
Chapter 72	
Error Disable	
72.1 Error-Disable Overview	
72.1.1 CPU Protection Overview	
72.1.2 Error-Disable Recovery Overview	
72.1.3 What You Can Do	
72.2 Error-Disable Status	
72.3 CPU Protection Setup	
72.4 Error-Disable Detect Setup	
72.5 Error-Disable Recovery Setup	
Chapter 73	
IP Source Guard	
73.1 IP Source Guard Overview	
73.1.1 What You Can Do	
73.1.2 What You Need to Know	
73.2 IPv4 Source Guard	
73.3 IPv4 Source Guard Static Binding	
73.3.1 Add/Edit IPv4 Source Guard Static Binding	
C hapter 74 DHC P Snooping	490
DHCP Shooping	
74.1 DHCP Snooping Overview	
74.1.1 What You Can Do	
74.2 DHCP Snooping Status	
74.3 DHCP Snooping Setup	
74.4 DHCP Snooping Port Setup	
74.5 DHCP Snooping VLAN Setup	
74.6 DHCP Snooping VLAN Port Setup	
74.6.1 Add/EDIT DHCP Snooping VLAN Ports	
74.7 Technical Reference	
74.7.1 DHCP Snooping Overview	
Chapter 75	
ARP Inspection	

75.1 ARP Inspection Status	500
75.2 ARP Inspection VLAN Status	501
75.3 ARP Inspection Log Status	501
75.4 ARP Inspection Setup	
75.5 ARP Inspection Port Setup	
75.6 ARP Inspection VLAN Setup	505
75.7 IPv6 Source Guard	
75.8 IPv6 Source Binding Status	507
75.9 IPv6 Static Binding	508
75.9.1 Add/Edit IPv6 Static Binding	508
75.10 IPv6 Source Guard Policy	
75.10.1 Add/Edit an IPv6 Source Guard Policy	
75.11 IPv6 Source Guard Port Setup	
75.12 IPv6 Snooping Policy Setup	
75.12.1 Add/Edit a IPv6 Snooping Policy	
75.13 IPv6 Snooping VLAN Setup	
75.13.1 Add/Edit an IPv6 Snooping VLAN	
75.14 IPv6 DHCP Trust Setup	
75.15 Technical Reference	
75.15.1 ARP Inspection Overview	
Chapter 76 Port Authentic ation	510

76.1 Port Authentication Overview	
76.1.1 What You Can Do	
76.1.2 What You Need to Know	
76.1.3 MAC Authentication	
76.2 Activate IEEE 802.1x Security	
76.3 Activate MAC Authentication	
76.4 Guest VLAN	
76.5 Compound Authentication	
76.6 Technical Reference	
76.6.1 IEEE 802.1x	
76.6.2 RADIUS	
76.6.3 EAP (Extensible Authentication Protocol) Authentication .	
76.6.4 EAPOL (EAP over LAN)	

77.1 Port Security Overview	530
77.2 About Port Security	530
77.3 Port Security Setup	530

#### Chapter 78 MAINTENANCE

A IN	TENANCE	533
	78.1 Overview	. 533
	78.1.1 What You Can Do	533
	78.2 Certificates	533
	78.2.1 HTTPS Certificates	534
	78.3 Technical Reference	535
	78.3.1 FTP Command Line	535
	78.3.2 Filename Conventions	535
	78.3.3 FTP Command Line Procedure	. 536
	78.3.4 GUI-based FTP Clients	537
	78.3.5 FTP Restrictions	537
	78.4 Cluster Management Overview	537
	78.4.1 What You Can Do	538
	78.5 Cluster Management Status	538
	78.6 Clustering Management Setup	539
	78.7 Technical Reference	541
	78.7.1 Cluster Member Switch Management	541
	78.8 Restore Configuration	543
	78.9 Backup Configuration	543
	78.10 Auto Configuration	544
	78.11 Erase Running-Configuration	545
	78.12 Save Configuration	546
	78.13 Configure Clone	547
	78.14 Diagnostic	548
	78.15 Firmware Upgrade	550
	78.16 Reboot System	552
	78.17 Tech-Support	553
	78.17.1 Tech-Support Download	554

#### Chapter 79

onked AV Mode	
79.1 Overview	
79.2 Help	
79.3 Summary	
79.4 MONITOR	
79.5 What You Can Do	
79.6 System Information	
79.7 SYSTEM	
79.8 What You Can Do	
79.9 Cloud Management	
79.10 General Setup	
79.11 IP Setup	

79.11.1 Add/Edit IP Interfaces	566
79.12 Logins	567
79.13 Configure SNMP	569
79.14 Configure SNMP User	571
79.14.1 Add/Edit SNMP User	572
79.15 Configure SNMP Trap Group	573
79.16 Enable or Disable Sending of SNMP Traps on a Port	574
79.17 PORT	575
79.18 Link Aggregation	576
79.18.1 What You Can Do	576
79.19 Link Aggregation Status	576
79.20 Link Aggregation Setting	578
79.21 Link Aggregation Control Protocol	579
79.22 PoE Status	581
79.23 PoE Setup	583
79.24 Port Setup	586
79.25 SWITCHING	588
79.26 Port Mirroring	588
79.27 Multicast	589
79.27.1 What You Can Do	589
79.28 IPv4 Multicast Status	589
79.29 IGMP Snooping	590
79.30 IGMP Snooping VLAN	594
79.30.1 Add/Edit IGMP Snooping VLANs	595
79.31 IGMP Filtering Profile	596
79.31.1 Add IGMP Filtering Profile	597
79.31.2 Add IGMP Filtering Rule	597
79.32 VLAN	598
79.32.1 What You Can Do	598
79.32.2 What You Need to Know	598
79.33 VLAN Status	601
79.33.1 VLAN Details	602
79.34 Configure a Static VLAN	603
79.34.1 Add/Edit a Static VLAN	604
79.35 VLAN Port Setup	605
79.36 SECURITY	606
79.37 Access Control	606
79.37.1 What You Can Do	607
79.38 Service Access Control	. 607
79.39 Remote Management	. 608
79.40 Storm Control	609
79.41 MAINTENANCE	610
79.42 What You Can Do	611

79.43 Restore Configuration	611
79.44 Backup Configuration	
79.45 Save Configuration	612
79.46 Firmware Upgrade	613
79.47 Reboot System	613
79.48 Tech-Support	614
79.48.1 Tech-Support Download	615

#### 

C hapter 80 Trouble shooting	
80.1 Power, Hardware Connections, and LEDs	
80.2 Switch Access and Login	
80.3 Switch Configuration	
Appendix A Customer Support	621
Appendix B Common Services	626
Appendix C IPv6	629
Appendix D Legal Information	638
Index	643

# PART I User's Guide

## C HAPTER 1 Getting to Know Your Switch

#### 1.1 Introduction

This chapter introduces the main features and applications of the Switch.

The XGS2220 Series consists of the following models:

- XGS2220-30
- XGS2220-30HP
- XGS2220-30F
- XGS2220-54
- XGS2220-54HP
- XGS2220-54FP

References to PoE model in this User's Guide only apply to XGS2220-30HP, XGS2220-54HP, and XGS2220-54FP.

The Switch is a stackable, layer-3, Gigabit Ethernet (GbE) switch with one power slot for single power supply. The Switch provides six 10 GbE ports for uplink. By integrating router functions, the Switch performs wire-speed layer-3 routing in addition to layer-2 switching.

With its built-in Web Configurator, including the Zyxel One Network (ZON) Neighbor Management feature, viewing, managing and configuring the Switch and its neighboring devices is easy. The Switch can also be managed through Telnet, any terminal emulator program on the console port, or third-party SNMP management.

In addition, Zyxel offers a proprietary software program called Zyxel One Network (ZON) Utility, it is a utility tool that assists you to set up and maintain network devices in a more simple and efficient way. You can download the ZON Utility at www.zyxel.com and install it on a computer.

All models are referred to as the "Switch" in this guide.

The Switch supports NebulaFlex for hybrid mode which can set the Switch to operate in either standalone or Nebula cloud management mode. When the Switch is in standalone mode, it can be configured and managed by the Web Configurator. When the Switch is in Nebula cloud management mode, it can be managed and provisioned by the Zyxel Nebula Control Center (NCC).

The following table describes the hardware features of the Switch by model.

	Table 1	XGS2220 Series Comparison Table
--	---------	---------------------------------

FEATURE	XG S2220-30	XGS2220-30HP	XG S2220-30F	XG S2220-54	XGS2220-54HP	XGS2220-54FP
Stacking Mode	Yes	Yes	Yes	Yes	Yes	Yes
10/100/1000 Mbps Ethernet Ports	24	24	No	48	48	48

FEATURE	XG S2220-30	XGS2220-30HP	XG S2220-30F	XG S2220-54	XG S2220-54HP	XGS2220-54FP
10/100/1000 Mbps PoE Ports	No	24	No	No	48	48
100/1000 Mbps SFP Interface	No	No	24	No	No	No
1/10 Gbps SFP+ Interface	4	4	4	4	4	4
1000 Mbps / 2.5/5/ 10 Gbps Ethernet Ports	2	2	2	2	2	2
1000 Mbps / 2.5/5/ 10 Gbps PoE Ports	No	2	No	No	2	2
Smart FAN	1 (8,500 RPM)	3 (8,500 RPM)	2 (8,500 RPM)	2 (8,500 RPM)	4 (8,500 RPM)	1 (8,500 RPM) 2 (16,000 RPM)
Console Port	USB-C	USB-C	USB-C	USB-C	USB-C	USB-C

Table 1 XGS2220 Series Comparison Table (continued)

The last four 10G ports can also be used for stacking. Use the four 10G fiber ports. When working in stacking mode, the Switch can operate together with other Switches of the same model and firmware version and allows you to remotely manage them from one switch using one single IP address.

This section shows a few examples of using the Switch in various network environments.

#### 1.1.1 Multi-Gigabit


A 10 Gigabit port supports speeds of 10G if the connected device supports 10G and a Cat 6a (up to 100 m) or Cat 6 cable (up to 50 m) is used. The speed drops to 1G if these criteria are not met; it drops to 100M if a Cat 5 cable is used (up to 100 m).

If a network device such as a 5G network card, gaming computer, server, Network Attached Storage (NAS) or Access Point (AP) only supports 2.5 Gigabit or 5 Gigabit connectivity, then the maximum speed potential of these devices is never reached.

In addition, at the time of writing, most existing cabling is Cat 5e or Cat 6, further limiting maximum speed or distance potential.

Multi-Gigabit (IEEE 802.3bz) solves these problems by additionally supporting 2.5 Gigabit and 5 Gigabit Ethernet connections over Cat 5e and higher Ethernet cables. Multi-Gigabit ports are also backward compatible with 100 Mbps and 1 Gigabit ports.





See the following table for the cables required and distance limitation to attain the corresponding speed.

	Types		
CABLE	TRANSMISSION SPEED	MAXIMUM DISTANCE	BANDWIDTH CAPACITY
Category 5	100M	100 m	100 MHz
Category 5e	1G / 2.5G / 5G	100 m	100 MHz
Category 6	5G / 10G	50 m	250 MHz
Category 6a	10G	100 m	500 MHz
Category 7	10G	100 m	650 MHz

#### Table 2 Cable Types

Note: Make sure to select the correct speed for the port in PORT > Port Setup.

#### 1.1.2 Management Modes

NebulaFlex means you can set the Switch to operate in either standalone or cloud mode (but not both at the same time).

Use the DHCP-assigned IP address to access the Web Configurator. To know the IP address, use the NCC, the ZON utility, or the console port if available. You can also use the domain name "setup.zyxel" to access the Web Configurator when you are directly connected to the Switch.

Note: Make sure your computer can connect to a DNS server through the Switch.

Use the Web Configurator to configure and manage the Switch directly in standalone mode or use Nebula Control Center (NCC) to configure and manage the Switch in cloud mode. The Nebula Control Center (NCC) is an alternative cloud-based network management system that allows you to remotely manage and monitor the Switch. You may also access a minimized version of the Web Configurator in cloud mode.

#### Nebula Cloud Management

To have Nebula manage the Switch, you must first register it at the Nebula web portal at https:// nebula.zyxel.com, and ensure that **Nebula Control Center (NCC) Discovery** is enabled in **SYSTEM** > **Cloud Management** in the Switch Web Configurator.

Note: See the Switch's datasheet for the feature differences between standalone and Nebula cloud management modes. You can find the Switch's datasheet at the Zyxel website.

See the NCC (Nebula Control Center) User's Guide for how to configure the Switch using Nebula.




Figure 2 NCC Example Network Topology

#### 1.1.3 Mode Changing

This section describes how to change the Switch's management mode. Refer to the Switch's standalone mode User's Guide for LED descriptions, including **CIOUD** LED behavior.

#### From Standalone to Nebula Cloud Management

To manage your Switch through Nebula, connect the Switch to the Internet, and register it to a site and organization at the Nebula web portal (https://nebula.zyxel.com).

See the following steps or the Switch Quick Start Guide for registering the Switch.

#### Go to the NCC to Register the Switch

- 1 Go to the Nebula web portal in one of three ways.
  - Enter https://nebula.zyxel.com in a supported web browser. See the Nebula User's Guide for more information about supported browsers.
  - Click Visit Nebula in the Switch's login page.
  - Click the Nebula Control Center icon in the upper right of the Switch's Web Configurator.
- 2 Click Get Started in the Nebula web portal. Enter your myZyxel account information. You will be redirected to another screen where you can sign up for a myZyxel account if you do not have one.
- 3 Create an organization and a site (using the Nebula setup wizard) or select an existing site.
- 4 Register the Switch by entering its Registration MAC address and serial number and assign it to the site. The serial number and Registration MAC address can be found in the **DASHBOARD** screen or the device back label on the Switch.

#### Use the Zyxel Ne bula Mobile App to Register the Switch

- 1 Download and open the Zyxel Nebula Mobile app in your mobile device (see Section on page 155 to download the app). Click **Start** on the first page. Click **Create account** to create a myZyxel account or enter your existing account information to log in.
- 2 Create an organization and site, or select an existing site using the Zyxel Nebula Mobile app.
- 3 Select a site and scan the Switch's QR code or manually enter the information to add it to the site. You can find the QR code:
  - On a label on the Switch or
  - On its box or
  - In the Web Configurator at SYSTEM > Cloud Management.

See Section 3.3 on page 53 for more information about the CLOUD LED or Section Table 33 on page 118 for more information about the Cloud Control Status field in the DASHBOARD screen to see if the Switch goes into Nebula cloud management mode successfully.

The Switch goes into Nebula-managed mode automatically after it can access the Nebula web portal and is successfully registered there. Its log in password and settings are then overwritten with what you have configured in the Nebula web portal. To access the Web Configurator when the Switch is in Cloud mode, use the Local credentials password to log in.

Note: The Local credentials: Password can be found in Site-wide > Configure > General settings > Device configuration in the NCC portal. See the NCC User's Guide for more information.

MODE	ACCESS	LOGIN USER NAME	LOGIN PASSWORD	LOGIN IP ADDRESS/ URL/ DOMAIN NAME		
Cloud mode	NCC (Nebula Control Center) portal	myZyxel account name	myZyxel account password	https://nebula.zyxel.com		
	Web Configurator (Local GUI)	admin	Local credentials password	http://setup.zyxel OR http://DHCP-assigned IP OR a configured static IP address		
Note: The Web Configurator (Local GUI) of Cloud mode supports limited features for troubleshooting use only.						
Standalone mode	Web Configurator	admin	1234	http://setup.zyxel OR http://DHCP-assigned IP OR http://192.168.1.1		

Table 3 Management Method Comparison

#### From Nebula-managed to Standalone

To return to direct management standalone mode, remove (unregister) the Switch from the inventory in the Nebula web portal.

Note: When you change the Switch's management mode from Nebula-manged mode to standalone mode, the Switch will reboot and restore its factory-default settings.

To unregister the Switch:

- 1 Go to the Nebula Control Center (https://nebula.zyxel.com).
- 2 Go to the Organization-wide > License & inventory > Devices screen.
- 3 Select the Switch you want to remove (unregister) from the organization.
- 4 Click Actions, then click Remove from organization.

It will take a while for the Switch to reboot and reset to factory default.


#### 1.1.4 ZON Utility

With its built-in Web Configurator, including the Neighbor Management feature (Section 13.1 on page 132), viewing, managing and configuring the Switch and its neighboring devices is simplified.

In addition, Zyxel offers a proprietary software program called Zyxel One Network (ZON) Utility, it is a utility tool that assists you to set up and maintain network devices in a more simple and efficient way. You can download the ZON Utility at www.zyxel.com and install it on a PC (Windows operation system). For more information on ZON Utility see Section 4.3 on page 62.

#### 1.1.5 Web Configurator Networked AV Mode

Aside from the Web Configurator in Standard mode, you can switch to Networked AV mode that is specifically designed to simplify configuration and management of the Switch for AVoIP (Audio-Video over Internet Protocol) application. In AV over IP, the AV transmitter is the transmitter, the AV receiver is the receiver, and the matrix switch is a standard IP Switch. See Section 4.4 on page 66 for details on using the Setup Wizard screen for configuring the Switch's Networked AV mode's basic and advanced settings.



#### Figure 3 Comparison Between Traditional AV and AVoIP Setups

#### 1.1.6 PoE

The Switch is a Power Sourcing Equipment (PSE) because it provides a source of power through its Ethernet ports. Each device that receives power through an Ethernet port is a Powered Device (PD).

The Switch can adjust the power supplied to each PD according to the PoE standard the PD supports. PoE standards are:

- IEEE 802.3af Power over Ethernet (PoE)
- IEEE 802.3at Power over Ethernet (PoE) +
- IEEE 802.3bt Power over Ethernet (PoE) ++

The following table describes the PoE features of the Switch by model.

PO E FEA TURES	XG S2220-30HP	XG S2220-54HP	XG S2220-54FP
IEEE 802.3at PoE+	Ports 1 – 16	Ports 1 – 40	Ports 1 – 40
IEEE 802.3bt PoE++	Ports 17 – 26	Ports 41 – 50	Ports 41 – 50
Power Management Mode	Consumption Classification (default)	Consumption Classification (default)	Consumption Classification (default)
PoE Power Budget	400 W	600 W	960 W

Table 4 XGS2220 Series Models and PoE Features

Po E FEA TURES	PoE	Po E+	PoE++			
IEEE Standard	IEEE 802.3af	IEEE 802.3at	IEEE 802.3bt			
PoE Type	Type 1	Type 2	Туре 3			
Switch Port Power						
Maximum Power Per Port	15.4 W	30 W	60 W			
Port Voltage Range	44 – 57 V	50 – 57 V	50 – 57 V			
Cables						
Twisted Pairs Used	2-pair	2-pair	4-pair			
Supported Cables	Cat3 or better	Cat5 or better	Cat5 or better			

Table 5 PoE Standards


#### 1.2 Example Applications

This section shows a few examples of using the Switch in various network environments. Note that the Switch in the figure is just an example Switch and not your actual Switch.

#### 1.2.1 PoEExample Application

The following example figure shows a Switch supplying PoE (Power over Ethernet) to Powered Devices (PDs) such as an IP camera, a wireless router, an IP telephone and a general outdoor router that are not within reach of a power outlet.





#### 1.2.2 Backbone Example Application

The Switch is an ideal solution for small networks where rapid growth can be expected in the near future. The Switch can be used standalone for a group of heavy traffic users. You can connect computers and servers directly to the Switch's port or connect other switches to the Switch.

In this example, all computers can share high-speed applications on the server. To expand the network, simply add more networking devices such as switches, routers, computers, print servers, and so on.




Figure 5 Backbone Application

#### 1.2.3 Bridging Example Application

In this example, the Switch connects different company departments (**RD** and **Sales**) to the corporate backbone. It can alleviate bandwidth contention and eliminate server and network bottlenecks. All users that need high bandwidth can connect to high-speed department servers through the Switch. You can provide a super-fast uplink connection by using a Gigabit Ethernet or SFP port on the Switch.

Moreover, the Switch eases supervision and maintenance by allowing network managers to centralize multiple servers at a single location.





Figure 6 Bridging Application

#### 1.2.4 High Performance Switching Example

The Switch is ideal for connecting two geographically dispersed networks that need high bandwidth. In the following example, a company uses the 10 Gigabit uplink ports to connect the headquarters to a branch office network. Within the headquarters network, a company can use trunking to group several physical ports into one logical higher-capacity link. Trunking can be used if for example, it is cheaper to use multiple lower-speed links than to under-utilize a high-speed, but more costly, single-port link.





#### 1.2.5 IEEE 802.1Q VIAN Application Examples

A VLAN (Virtual Local Area Network) allows a physical network to be partitioned into multiple logical networks. Stations on a logical network belong to one or more groups. With VLAN, a station cannot directly talk to or hear from stations that are not in the same groups unless such traffic first goes through a router.

#### 1.2.5.1 Tag-based VIAN Example

Ports in the same VLAN group share the same frame broadcast domain thereby increase network performance through reduced broadcast traffic. VLAN groups can be modified at any time by adding, moving or changing ports without any re-cabling.

Shared resources such as a server can be used by all ports in the same VLAN as the server. In the following figure only ports that need access to the server need to be part of VLAN 1. Ports can belong to other VLAN groups too.




Figure 8 Shared Server Using VLAN Example

#### 1.2.6 IPv6 Support

IPv6 (Internet Protocol version 6), is designed to enhance IP address size and features. The increase in IPv6 address size to 128 bits (from the 32-bit IPv4 address) allows up to  $3.4 \times 10^{38}$  IP addresses. At the time of writing, the Switch supports the following features.

- Static address assignment and stateless auto-configuration
- Neighbor Discovery Protocol (a protocol used to discover other IPv6 devices in a network)
- Remote Management using ping, SNMP, SSH, telnet, HTTP and FTP services
- ICMPv6 to report errors encountered in packet processing and perform diagnostic functions, such as "ping"
- IPv4/IPv6 dual stack; the Switch can run IPv4 and IPv6 at the same time
- DHCPv6 client and relay
- Multicast Listener Discovery (MLD) snooping and proxy

For more information on IPv6, refer to Appendix C on page 629 and the CLI Reference Guide.

#### 1.3 Ways to Manage the Switch

Use any of the following methods to manage the Switch.

• NCC (Zyxel Nebula Control Center). With the NCC, you can remotely manage and monitor the Switch through a cloud-based network management system. See the NCC User's Guide for detailed information about how to access the NCC and manage your Switch through the NCC. See the NCC User's Guide for how to configure Nebula managed devices.

- Web Configurator. This is recommended for everyday management of the Switch using a (supported) web browser. See Chapter 4 on page 57.
- Command Line Interface. Line commands offer an alternative to the Web Configurator and in some cases are necessary to configure advanced features. See the CLI Reference Guide.
- FTP. Use File Transfer Protocol for firmware upgrades and configuration backup or restore. See Section 78.3.1 on page 535.
- SNMP. The Switch can be monitored and/or managed by an SNMP manager. See Section 26.6.1 on page 195.
- Cluster Management. Cluster Management allows you to manage multiple switches through one switch, called the cluster manager. See Chapter 78 on page 537.
- ZON Utility. ZON Utility is a program designed to help you deploy and perform initial setup on a network more efficiently. See Section 4.3 on page 62.

#### 1.4 Good Habits for Managing the Switch

Do the following regularly to make the Switch more secure and to manage the Switch more effectively.

- Change the password. Use a password that is not easy to guess and that consists of different types of characters, such as numbers and letters.
- Write down the password and put it in a safe place.
- Back up the configuration (and make sure you know how to restore it). Restoring an earlier working configuration may be useful if the device becomes unstable or even crashes. If you forget your password, you will have to reset the Switch to its factory default settings. If you backed up an earlier configuration file, you would not have to totally re-configure the Switch. You could simply restore your last configuration.

# CHAPTER 2 Hardware Installation and Connection

#### 2.1 Installation Scenarios

This chapter shows you how to install and connect the Switch.

The Switch can be:

- Placed on a desktop.
- Rack-mounted on a standard EIA rack.

#### 2.2 Safe ty Precautions

Please observe the following before using the Switch:

- It is recommended to ask an authorized technician to attach the Switch on a desk or to the rack or wall. Use the proper screws to prevent damage to the Switch. See the **Installation Requirements** sections in this chapter to know the types of screws and screwdrivers for each mounting method.
- Make sure there is at least 2 cm of clearance on the top and bottom of the Switch, and at least 5 cm of clearance on all four sides of the Switch. This allows air circulation for cooling.
- Do NOT block the ventilation holes nor store cables or power cords on the Switch. Allow clearance for the ventilation holes to prevent your Switch from overheating. This is especially crucial when your Switch does not have fans. Overheating could affect the performance of your Switch, or even damage it.
- The surface of the Switch could be hot when it is functioning. Do NOT put your hands on it. You may get burned. This could happen especially when you are using a fanless Switch.
- The Switches with fans are not suitable for use in locations where children are likely to be present.


To start using the Switch, simply connect the power cables to turn it on.

#### 2.3 Freestanding Installation Procedure

- 1 Make sure the Switch is clean and dry.
- 2 Remove the adhesive backing from the rubber feet.

3 Attach the rubber feet to each corner on the bottom of the Switch. These rubber feet help protect the Switch from shock or vibration and ensure space between devices when stacking.





4 Set the Switch on a smooth, level surface strong enough to support the weight of the Switch and the connected cables. Make sure there is a power outlet nearby.

#### Cautions:

- Avoid stacking fanless Switches to prevent overheating.
- Ensure enough clearance around the Switch to allow air circulation for cooling.
- Do NOT remove the rubber feet as it provides space for air circulation.

#### 2.4 Mounting the Switch on a Rack

The Switch can be mounted on an EIA standard size, 19-inch rack or in a wiring closet with other equipment. Follow the steps below to mount your Switch on a standard EIA rack using a rack-mounting kit.

Note: Make sure there is enough clearance between each equipment on the rack for air circulation.

#### 2.4.1 Installation Requirements

- Two mounting brackets.
- Eight M3 flat head screws and a #2 Philips screwdriver.
- Four M5 flat head screws and a #2 Philips screwdriver.


#### 2.4.2 Precautions

- Make sure the rack will safely support the combined weight of all the equipment it contains. The maximum weight a bracket can hold is 21.5 kg.
- Make sure the position of the Switch does not make the rack unstable or top-heavy. Take all necessary precautions to anchor the rack securely before installing the unit.

#### 2.4.3 Attaching the Mounting Brackets to the Switch

1 Position a mounting bracket on one side of the Switch, lining up the four screw holes on the bracket with the screw holes on the side of the Switch.


Figure 10 Attaching the Mounting Brackets



- 2 Using a #2 Philips screwdriver, install the M3 flat head screws through the mounting bracket holes into the Switch.
- **3** Repeat steps 1 and 2 to install the second mounting bracket on the other side of the Switch.
- 4 You may now mount the Switch on a rack. Proceed to the next section.

#### 2.4.4 Mounting the Switch on a Rack

1 Position a mounting bracket (that is already attached to the Switch) on one side of the rack, lining up the two screw holes on the bracket with the screw holes on the side of the rack.



2 Using a #2 Philips screwdriver, install the M5 flat head screws through the mounting bracket holes into

the rack.

Note: Make sure you tighten all the four screws to prevent the Switch from getting slanted.

**3** Repeat steps 1 and 2 to attach the second mounting bracket on the other side of the rack.

## C HAPTER 3 Hardware Panels

This chapter describes the front panel and rear panel of the Switch and shows you how to make the hardware connections.

#### 3.1 Front Panel Connections

The following figures show the front panels of the Switch.

Figure 12 Front Panel: XGS2220-30

EYXEL more	
	Front Panel: XGS2220-30HP
ZYXEL some	
	Front Panel: XGS2220-30F
ZYXEL	
Figure 15	Front Panel: XGS2220-54
H	
Figure 16	Front Panel: XGS2220-54HP
Figure 17	Front Panel: XGS2220-54FP
Ē	

The following table describes the ports.

CONNECTOR	DESC RIPTIO N			
24/48 1000Base-T	These are 10/100/1000Base-T auto-negotiating and auto-crossover Ethernet ports.			
RJ-45 Ethernet Ports	Connect these ports to a computer, a hub, a router, or an Ethernet switch.			
2 10GBase-T RJ-45	These are 1/2.5/5/10G auto-negotiating and auto-crossover Ethernet ports.			
Ethernet Ports	Connect these ports to a gaming computer, a NAS (network-attached storage), or a server.			
16/40 1000Base-T RJ-45 PoE Ports	These are 10/100/1000Base-T auto-negotiating and auto-crossover IEEE802.3at PoE+ 30 W ports.			
	Connect these ports to a PTZ (pan, tilt and zoom) camera, a WiFi 6 (802.11ax) router, a WiFi 6 (802.11ax) AP, or an Ethernet switch.			
8 1000Base-T RJ-45 PoE Ports	These are 10/100/1000Base-T auto-negotiating and auto-crossover IEEE802.3bt PoE++ 60 W ports.			
	Connect these ports to a PTZ (pan, tilt and zoom) camera, a WiFi 6 (802.11ax) router, a WiFi 6 (802.11ax) AP, or an Ethernet switch.			
2 10GBase-T RJ-45 PoE Ports	These are 1G, 2.5G, 5G, and 10G auto-negotiating and auto-crossover IEEE802.3bt PoE++ 60 W ports.			
	Connect these ports to a PTZ (pan, tilt and zoom) camera, a WiFi 6 (802.11ax) router, a WiFi 6 (802.11ax) AP, or an Ethernet switch.			
4 1/10G SFP+ Slots	Use SFP+ transceivers in these ports for high-bandwidth backbone connections. You can also insert an SFP+ Direct Attach Copper (DAC) in the SFP+ slot.			
Reset	Press the <b>RESET</b> button to reboot the Switch without turning the power off. See Section 3.3 on page 53 for more information about the LED behavior.			
Restore	IN STANDALONE MODE			
	Press the <b>RESTO RE</b> button for 3 to 7 seconds to have the Switch automatically reboot and restore the last-saved custom default file. See Section 3.3 on page 53 for more information about the LED behavior.			
	Press the <b>RESTO RE</b> button for more than 7 seconds to have the Switch automatically reboot and restore the factory default file. See Section 3.3 on page 53 for more information about the LED behavior.			
	IN NEBULA CLOUD MODE			
	Press the <b>RESTO RE</b> button for more than 7 seconds to have the Switch automatically reboot and restore the factory default file.			

Table 6	Front Panel Connections

#### 3.1.1 Gig a bit Ethernet Ports

The Switch has 1000Base-T auto-negotiating, auto-crossover Ethernet ports. In 10/100/1000 Mbps Gigabit Ethernet, the speed can be 10 Mbps, 100 Mbps or 1000 Mbps. The duplex mode can be half duplex or full duplex.

An auto-negotiating port can detect and adjust to the optimum Ethernet speed (10/100/1000 Mbps) and duplex mode (full duplex or half duplex) of the connected device.

An auto-crossover (auto-MDI/MDI-X) port automatically works with a straight-through or crossover Ethernet cable.

When auto-negotiation is turned on, an Ethernet port negotiates with the peer automatically to determine the connection speed and duplex mode. If the peer Ethernet port does not support auto-

negotiation or turns off this feature, the Switch determines the connection speed by detecting the signal on the cable and using half duplex mode. When the Switch's auto-negotiation is turned off, an Ethernet port uses the pre-configured speed and duplex mode when making a connection, thereby requiring you to make sure that the settings of the peer Ethernet port are the same in order to connect.

#### 3.1.1.1 De fault Ethe met Negotiation Settings

The factory default negotiation settings for the Gigabit ports on the Switch are:

- Speed: Auto
- Duplex: Auto
- Flow control: Off
- Link Aggregation: Disabled

#### 3.1.1.2 Auto-crossover

All ports support auto-crossover, that is auto-MDIX ports (Media Dependent Interface Crossover), so you may use either a straight-through Ethernet cable or crossover Ethernet cable for all Gigabit port connections. Auto-crossover ports automatically sense whether they need to function as crossover or straight ports, so crossover cables can connect both computers and switches or hubs.

#### 3.1.2 SFP/ SFP+ Slots

These are four slots for Small Form-Factor Pluggable (SFP) or SFP+ modules, such as an SFP or SFP+ transceiver. The SFP+ (SFP Plus) is an enhanced version of the SFP and supports data rates of 10 Gbps. A transceiver is a single unit that houses a transmitter and a receiver. Use a transceiver to connect a fiber optic cable to the Switch. The Switch does not come with transceivers. You must use transceivers that comply with the Small Form-Factor Pluggable (SFP) Transceiver MultiSource Agreement (MSA). See the SFF committee's INF-8074i specification Rev 1.0 for details.

You can change transceivers while the Switch is operating. You can use different transceivers to connect to Ethernet switches with different types of fiber optic connectors.

- Type: SFP or SFP+ connection interface
- Connection speed: 1 or 10 Gigabit per second (Gbps)

WARNING! To avoid possible eye injury, do not look into an operating fiber optic module's connectors.

HANDLING! All transceivers are static sensitive. To prevent damage from electrostatic discharge (ESD), it is recommended you attach an ESD preventive wrist strap to your wrist and to a bare metal surface when you install or remove a transceiver.

STO RAGE All modules are dust sensitive. When not in use, always keep the dust plug on. Avoid getting dust and other contaminant into the optical bores, as the optics do not work correctly when obstructed with dust.

#### 3.1.2.1 Transceiver Installation

Use the following steps to install a transceiver.

1 Attach an ESD preventive wrist strap to your wrist and to a bare metal surface.

- 2 Align the transceiver in front of the slot opening.
- 3 Make sure the latch is in the lock position (latch styles vary), then insert the transceiver into the slot with the exposed section of PCB board facing down.
- 4 Press the transceiver firmly until it clicks into place.
- 5 The Switch automatically detects the installed transceiver. Check the LEDs to verify that it is functioning properly.
- 6 Remove the dust plugs from the transceiver and cables (dust plug styles vary).
- 7 Identify the signal transmission direction of the fiber optic cables and the transceiver. Insert the fiber optic cable into the transceiver.

Figure 18 Latch in the Lock Position





Figure 19 Transceiver Installation Example



Figure 20 Connecting the Fiber Optic Cables



#### 3.1.2.2 Transceiver Removal

Use the following steps to remove an SFP transceiver.

- 1 Attach an ESD preventive wrist strap to your wrist and to a bare metal surface on the chassis.
- 2 Remove the fiber optic cables from the transceiver.
- **3** Pull out the latch and down to unlock the transceiver (latch styles vary).

Note: Make sure the transceiver's latch is pushed all the way down, so the transceiver can be pulled out successfully.

4 Pull the latch, or use your thumb and index finger to grasp the tabs on both sides of the transceiver, and carefully slide it out of the slot.

- Note: Do NOT pull the transceiver out by force. You could damage it. If the transceiver will not slide out, grasp the tabs on both sides of the transceiver with a slight up or down motion and carefully slide it out of the slot. If unsuccessful, contact Zyxel Support to prevent damage to your Switch and transceiver.
- 5 Insert the dust plug into the ports on the transceiver and the cables.

Figure 21 Removing the Fiber Optic Cables





Figure 22 Opening the Transceiver's Latch Example



Figure 23 Transceiver Removal Example



#### 3.1.3 Console Port

This USB Type C connector is for troubleshooting only.

#### 3.2 RearPanel

The following figures show the rear panels of the Switch. The rear panels contain:





#### 3.2.1 Grounding

Grounding is a safety measure to direct excess electric charge to the ground. It prevents damage to the Switch, and protects you from electrocution. Use the grounding screw on the rear panel and the ground wire of the AC power supply to ground the Switch.

The grounding terminal and AC power ground where you install the Switch must follow your country's regulations. Qualified service personnel must ensure the building's protective earthing terminals are valid terminals.


Installation of Ethernet cables must be separate from AC power lines. To avoid electric surge and electromagnetic interference, use a different electrical conduit or raceway (tube/trough or enclosed conduit for protecting electric wiring) that is 15 cm apart, or as specified by your country's electrical regulations.

Any device that is located outdoors and connected to this product must be properly grounded and surge protected. To the extent permissible by your country's applicable law, failure to follow these guidelines could result in damage to your Switch which may not be covered by its warranty.

Note: The specification for surge or ESD protection assumes that the Switch is properly grounded.

- 1 Remove the M4 ground screw from the Switch's rear panel.
- 2 Secure a green or yellow ground cable (16 AWG or smaller) to the Switch's rear panel using the M4 ground screw.






3 Attach the other end of the ground cable to a grounding bar located on the rack where you install the Switch or to an on-site grounding terminal.



Figure 31 Attach Ground Cable to Grounding Bar or On-site Grounding Terminal

4 The grounding terminal of the server rack or on-site grounding terminal must also be grounded and connected to the building's main grounding electrode. Make sure the grounding terminal is connected to the buildings grounding electrode and has an earth resistance of less than 10 ohms, or according to your country's electrical regulations.

Figure 32 Connecting to the Building's Main Grounding Electrode



If you are uncertain that suitable grounding is available, contact the appropriate electrical inspection

authority or an electrician.

## This device must be grounded. Do this before you make other connections.

#### 3.2.2 AC PowerConnection

Note: Make sure you are using the correct power source as shown on the panel and that no objects obstruct the airflow of the fans (located on the side of the unit).

To connect power to the Switch, insert the female end of the power cord to the AC power receptacle on the rear panel. Connect the other end of the supplied power cord to a power outlet.

#### PowerCord Requirement (XGS2220-54HP/XGS2220-54FP)

### Make sure to use the provided or designated powercord for your Switch.

The following table describes the power cord requirements for XGS2220-54HP / XGS2220-54FP.

COUNTRIES	SPEC IFIC ATIO N	SUPPLY VOLTAGE
Europe and United Kingdom	18 AWG	230 V
North America	14 AWG	110 V


Table 7 XGS2220-54HP / XGS2220-54FP Power Cord Specifications

Note: If you need to replace the power cord, contact your local vendor.


#### Installing the Retainer Clip

Install the retainer clip to prevent accidental removal of the power cord.


1 Loosely wrap the clip on the retainer to the power cord.




2 Push the pronged-end of the retainer clip into the **Retainer Holder** hole until it locks into place.



3 Slide the clip up to the end of the power cord.



4 Close the clip tightly around the power cord until secure.



XGS2220 Series User's Guide

#### 3.3 IEDs

After you connect the power to the Switch, view the LEDs to ensure proper functioning of the Switch and as an aid in troubleshooting.

IED	COLOR	STATUS	DESC RIPTIO N
PWR/SYS	Green	On	The Switch is on and functioning properly.
		Blinking	The Switch is rebooting and performing self-diagnostic tests.
	Yellow	On	The Switch is functioning abnormally, FAN status alert/error, or the system power detected is under 10.8 V.
		Blinking	The Switch is returning to its factory default configuration settings.
		Off	The Switch is not receiving power from the power source.
CLOUD	Green	On	The Switch has successfully connected to the NCC (Nebula Control Center).
		Blinking	The Switch cannot connect to the NCC because it is not registered. Please register the Switch with NCC.
	Yellow	On	The Switch is registered with NCC but cannot connect to the NCC. Please check the Internet connection of the Switch.
		Blinking	The Switch is not registered with NCC and cannot connect to the NCC. Please check the Internet connection of the Switch and register the Switch with NCC.
		Off	The Switch is operating in standalone mode. Nebula Control Center (NCC) Discovery is disabled in SYSTEM > Cloud Management in the Switch Web Configurator.
LOCATOR	Blue	On	The Switch is uploading firmware. While the Switch is doing this, do not turn off the power.
		Blinking	Shows the actual location of the Switch between several devices in a rack. The default timer is 30 minutes when you are configuring the Switch.
		Off	The locator is not functioning or malfunctioning.
	Red	On	PoE power usage is more than 95 percent of the power supplied budget.
(XGS2220-30HP / XGS2220-54HP / XGS2220-54FP)	Yellow	On	PoE power usage is below 95 percent of the power supplied budget, but over 80 percent of the power supplied budget.
		Off	PoE power usage is below 80 percent of the power supplied budget.
STACK ID			The LED is showing the Stack ID number of the Switch.
			ID 0 means it is a standalone Switch.
PRIMARY	Green	On	The Switch is acting as a standalone switch or the master in stacking.
	Yellow	On	An error occurred when the Switch is selected as the master member in a stack.
		Off	The Switch is acting as a non-master member in a stack.

Table 8 LED Descriptions

LED	COLOR	STATUS	DESC RIPTIO N		
10M/100M/1000M Base-T Ports					
Link / ACT	Green	On	The link to a 1000M Ethernet network is up.		
1 - 24		Blinking	The Switch is transmitting/receiving to/from a 1000M Ethernet network.		
(XGS2220-30 / XGS2220-30HP)	Yellow	On	The link to a 10M/100M Ethernet network is up.		
1 – 48		Blinking	The Switch is transmitting/receiving to/from a 10M/100M Ethernet network.		
(XGS2220-54 / XGS2220-54HP / XGS2220-54FP)		Off	The link to an Ethernet network is down.		

1G/2.5G/5G/10G	Base-T Ports		
Link / ACT	Blue	On	The link to a 10G Ethernet network is up.
25 – 26		Blinking	The Switch is transmitting/receiving to/from a 10G Ethernet network.
(XGS2220-30 / XGS2220-30HP /	Green	On	The link to a 1G/2.5G/5G Ethernet network is up.
XGS2220-30F) 49 – 50		Blinking	The Switch is transmitting/receiving to/from a 1G/2.5G/5G Ethernet network.
(XGS2220-54 / XGS2220-54HP / XGS2220-54FP)		Off	The link to an Ethernet network is down.

PoE Mode			
1 – 16 (XGS2220-30HP)	Green	On	Power supplied to all PoE Ethernet ports meets the IEEE 802.3at or IEEE 802.3af standard.
1 – 40 (XGS2220-54HP / XGS2220-54FP)		Off	There is no power supplied.
17 – 26 (XGS2220-30HP)	Yellow	On	Power supplied to all PoE Ethernet ports meets the IEEE 802.3bt standard.
41 - 50	Green	On	Power supplied to all PoE Ethernet ports meets the IEEE 802.3at / IEEE 802.3af standards.
(XGS2220-54HP / XGS2220-54FP)		Off	There is no power supplied.

LED	COLOR	STATUS	DESC RIPIIO N
1G SFP Slots			
Link / ACT	Green	On	The port has a successful 1000M connection.
1 – 24		Blinking	The port is transmitting or receiving data at 1000M.
(XGS2220-30F)	Yellow	On	The port has a successful 100M connection.
		Blinking	The port is transmitting or receiving data at 100M.
		Off	This link is disconnected.

IED	COLOR	STATUS	DESC RIPTIO N
1G/10G SFP+ Slots	S		
Link / ACT	Blue	On	The port has a successful 10G connection.
27 – 30		Blinking	The port is transmitting or receiving data at 10G.
(XGS2220-30 / XGS2220-30HP /	Green	On	The port has a successful 1000M connection.
XGS2220-30F)		Blinking	The port is transmitting or receiving data at 1000M.
51 – 54 (XGS2220-54 / XGS2220-54HP / XGS2220-54FP)		Off	This link is disconnected.

# PART II Te c hnic a l Re fe re nc e

# C HAPTER 4 Web Configurator

#### 4.1 Overview

This section introduces the configuration and functions of the Web Configurator.

The Web Configurator is an HTML-based management interface that allows easy system setup and management through Internet browser. Use a browser that supports HTML5, such as Microsoft Edge, Mozilla Firefox, or Google Chrome. The recommended minimum screen resolution is 1024 by 768 pixels.

In order to use the Web Configurator you need to allow:

- Web browser pop-up windows on your computer.
- JavaScript (enabled by default).
- Java permissions (enabled by default).

#### 4.2 System Login

- 1 Start your web browser.
- 2 The Switch is a DHCP client by default. Type "http://DHCP-assigned IP" in the Location or Address field. Press [ENTER].

Note: You can always use the domain name "setup.zyxel" to access the Web Configurator whether the Switch is using a DHCP-assigned IP or static IP address. This requires your computer to be directly connected to the Switch. Make sure your computer can connect to a DNS server through the Switch.

If the Switch is not connected to a DHCP server, enter "http://" and the static IP address of the Switch (for example, the default management IP address is 192.168.1.1 through an in-band port) in the **Location** or **Address** field. Press [ENTER]. Your computer must be in the same subnet in order to access this website address.

Also, you can use the ZON Utility to check your Switch's IP address. See Section 4.3 on page 62 for more information on the ZON utility.

3 The Login screen appears.


#### Figure 33 Web Configurator: Login


	XGS22	20-54	FP
ti da	Contribution Pro	meens and	shek segin
	135/1701	8 <sup></sup>	
	tiniwoid		
		ogin	
		1	
Wings W	ar Newscard val n of Closes		12

4 Click the **Visit Nebula** button if you want to open the Zyxel Nebula Control Center (NCC) login page in a new tab or window. The NCC is a cloud-based network management system that allows you to remotely manage and monitor the Switch. See Section 1.1.3 on page 31 for information on changing your Switch to Nebula Cloud management.



- 5 Click Login to log into the Web Configurator to manage the Switch directly. The default user name is admin and associated default password is 1234.
- 6 The Select Mode screen appears.





- 7 Select the Web Configurator in **Standard Mode** that has a complete set of configuration for network installation. Or select the Web Configurator in **Networked AV Mode** that has a set of menus specifically designed to simplify configuration and management of the Switch for AVoIP (Audio-Video over Internet Protocol) application.
- 8 If you select Standard Mode, go directly to step 10.
- 9 The Setup Wizard screen will appear after selecting the Networked AV Mode. You can use the Setup Wizard screen to configure the Switch's Networked AV mode's basic or advanced settings (see Section 4.4 on page 66 for details).
  - Use the **Basic Settings** to configure networked AV operation on management VLAN. Such as the Switches' IP address, DNS server, system password, SNMP community, accept or skip the default Networked AV mode settings, and view a summary of the basic settings.
  - Use the Advanced Settings for networks that wants to separate networked AV VLAN from management VLAN, specify which ports connect to AVoIP application, and for setting link aggregation across switches.

Once you click the **Finish** button, the settings configured in the **Setup Wizard** screen will overwrite the existing settings.

Otherwise, click the **Exit** button. If you want to open the **Setup Wizard** screen later, click the **Wizard** icon in the upper right hand corner of the Web Configurator in Networked AV mode.

Figure 36 Web Configurator: Wizard

Advanced	Settings	
----------	----------	--

10 If you did not change the default administrator password and/or SNMP community values, a warning screen displays each time you log into the Web Configurator and select Standard Mode. Click Password
 / SNMP to open a screen where you can change the administrator password and SNMP community string simultaneously. Otherwise, click Ignore to close it.

If you log into the Web Configurator and select **Networked AV Mode**, open the screen in the **Wizard** > **Step 2 Password** to change the administrator password and SNMP community string. Click **Finish** on the last step of the **Wizard** to save your settings.

#### Password/SNMP Setting

Figure 37 Web Configurator: Warning

Miessage Gentre	×
A Warring:	
<ol> <li>As a certainty pre-contrary. It is highly recommended, that you should change the column possesses.</li> <li>It is swear community is used for a way monogement and is set to public by realized. The coverts security based in elected, change, the community shing to a value other than defeult setting.</li> </ol>	
Configure Postword / SNMP_ setting	
Ignore	I

Figure 38 Web Configurator: Password/SNMP

Password/SNMP	
Password - Admir	strator
Old Possword	
New Possword	
Retype to confirm	
SNMP - General S	vic •
Get Community	public
Set Community	public
Trop Community	public
	Apply Concel

Note: The input string of any field in this screen should not contain [?], [|], ['], ["], or [,]. In the **Password** fields, [space] is also not allowed.

Change the default administrator and/or SNMP passwords, and then click Apply to save your changes.

LABEL	DESC RIPTIO N
Password – Adminis	trator
This is the default ac user name.	Iministrator account with the "admin" user name. You cannot change the default administrator
Old Password	Enter the existing system password (1234 is the default password when shipped).
New Password	Enter your new system password. Up to 32 printable ASCII characters are allowed for the new password.
Retype to confirm	Re-enter your new system password for confirmation.
SNMP – General Set	ting
Use this section to sp	pecify the SNMP version and community (password) values.
Version	Select the SNMP version for the Switch. The SNMP version on the Switch must match the version on the SNMP manager. Choose SNMP version 2c $(v2c)$ , SNMP version 3 $(v3)$ or both $(v3v2c)$ .
	Note: SNMP version 2c is backwards compatible with SNMP version 1.
Get Community	Enter the <b>GetCommunity</b> string, which is the password for the incoming Get- and GetNext- requests from the management station. The <b>GetCommunity</b> string is only used by SNMP managers using SNMP version 2c or lower.
Set Community	Enter the Set Community string, which is the password for the incoming Set- requests from the management station.
	The Set Community string is only used by SNMP managers using SNMP version 2c or lower.
Trap Community	Enter the <b>Thap Community</b> string, which is the password sent with each trap to the SNMP manager.
	The Thap Community string is only used by SNMP managers using SNMP version 2c or lower.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click <b>Cancel</b> to begin configuring this screen afresh.

Table 9 Web Configurator: Password/SNMP

#### 4.3 ZyxelOne Network (ZON) Utility

ZON Utility is a program designed to help you deploy and manage a network more efficiently. It detects devices automatically and allows you to do basic settings on devices in the network without having to be near it.

The ZON Utility issues requests through Zyxel Discovery Protocol (ZDP) and in response to the query, the device responds back with basic information including IP address, firmware version, location, system and model name in the same broadcast domain. The information is then displayed in the ZON Utility screen and you can perform tasks like basic configuration of the devices and batch firmware upgrade in it. You can download the ZON Utility at www.zyxel.com and install it in a computer (Windows operating system).

#### 4.3.1 Requirements

Before installing the ZON Utility in your computer, please make sure it meets the requirements listed below.

#### Operating System

At the time of writing, the ZON Utility is compatible with:

- Windows 7 (both 32-bit / 64-bit versions)
- Windows 8 (both 32-bit / 64-bit versions)
- Windows 8.1 (both 32-bit / 64-bit versions)
- Windows 10 (both 32-bit / 64-bit versions)

Note: To check for your Windows operating system version, right-click on **My Computer** > **Properties** on your computer. You should see this information in the **General** tab.


#### Hardware


Here are the minimum hardware requirements to use the ZON Utility on your computer.

- Core i3 processor
- 2 GB RAM
- 100 MB free hard disk
- WXGA (Wide XGA 1280 by 800)

#### 4.3.2 Run the ZON Utility

- **1** Double-click the ZON Utility to run it.
- 2 The first time you run the ZON Utility, you will see if your device and firmware version support the ZON Utility. Click the **OK** button to close this screen.





If you want to check the supported models and firmware versions later, you can click the **Show information about ZON** icon in the upper right of the screen. Then select the **Supported model and firmware version** link. If your device is not listed here, see the device release notes for ZON Utility support. The release notes are in the firmware zip file on the Zyxel web site.



at the later of the	ZYXEL			а . В . [9]
	19 G. (	) (6. (9) B	G ⊉ 🖨 ₩	0 0 0
				-
			0224830 AM30946	
-		VERMAND, ROOMAND.		
R -	an and a second	HORNOGEN DEMOSPHE	Printer and the	
2	Heritani	. NAMES OF BRADE OF A	WEIGHT WHATTENEST	

3 Select a network adapter to which your supported devices are connected.

Figure 41 Network Adapter

🔝 Initia Setupi	×
ZYXEL	
Weissone to 20% utility. In solid to top with the proof to solutility removed, accepted on electron of acceleration for fact. For Record codes the interface for discovering devices on the connected relevant one dist. Solid then to discover device	u 11.
The work with the second state of the second s	7

4 Click the Go button for the ZON Utility to discover all supported devices in your network.

Figure 42	Discovery	
😫 Sistemy		$\times$
ZYXE	Ľ	
	Discovery program	
	Concel	

5 The ZON Utility screen shows the devices discovered.

Figure 43	ZON Utility Screen

	ZYXE	Ē.						0	8
	1.0 2	(e) <b>s</b> e)	46.	8 B	70	62.9	10:0 1	10 115	13:6
. W	0.0			and cares	-	and the		-	
	-	1001230-004	11/0/09/8	m+0.00.	112248-10	MARTINE .			
-		2010234	10.75/444.01	10.01444.0	without a	1011902	ingenetation -		
SS.				IDECEMPTE.	HENEIS MADERIS	an and a second	1.000		

6 Select a device and then use the icons to perform actions. Some functions may not be available for your devices.

Note: You must know the selected device admin password before taking actions on the device using the ZON Utility icons.

Figure 44	Password	Prompt
-----------	----------	--------

E Pageword Author	né action	×
ZYXEL		
बि	Teore effer the odm handlot pidit/void to proceed. Service (	
	Tanwere	
	ER (FAM) SIAN	an <sup>a</sup>

The following table describes the icons numbered from left to right in the ZON Utility screen.

ICON	DESC RIPIIO N
1 IP Configuration	Change the selected device's IP address.
2 Renew IP Address	Update a DHCP-assigned dynamic IP address.
3 Reboot Device	Use this icon to restart the selected devices. This may be useful when troubleshooting or upgrading new firmware.
4 Reset Configuration to Default	Use this icon to reload the factory-default configuration file. This means that you will lose all previous configurations.
5 Locator LED	Use this icon to locate the selected device by causing its <b>Locator</b> LED to blink.
6 Web GUI	Use this to access the selected device Web Configurator from your browser. You will need a user name and password to log in.
7 Firmware Upgrade	Use this icon to upgrade new firmware to selected devices of the same model. Make sure you have downloaded the firmware from the Zyxel website to your computer and unzipped it in advance.
8 Change Password	Use this icon to change the admin password of the selected device. You must know the current admin password before changing to a new one.
9 Configure NCC Discovery	You must have Internet access to use this feature. Use this icon to enable or disable the Nebula Control Center (NCC) discovery feature on the selected device. If it is enabled, the selected device will try to connect to the NCC. Once the selected device device is connected to and has registered in the NCC, it will go into the Nebula cloud management mode.
10 ZAC	Use this icon to run the Zyxel AP Configurator of the selected AP.
11 Clear and Rescan	Use this icon to clear the list and discover all devices on the connected network again.
12 Save Configuration	Use this icon to save configuration changes to permanent memory on a selected device.
13 Settings	Use this icon to select a network adapter for the computer on which the ZON utility is installed, and the utility language.

Table 10 ZON Utility Icons

The following table describes the fields in the ZON Utility main screen.

Table 11 ZON Utility Fields
-----------------------------

LA BEL DESC RIPTIO N	
Туре	This field displays an icon of the kind of device discovered.
Model	This field displays the model name of the discovered device.
Firmware Version	This field displays the firmware version of the discovered device.
MAC Address	This field displays the MAC address of the discovered device.

XGS2220 Series User's Guide

IABEL	DESC RIPTIO N	
IP Address	This field displays the IP address of an internal interface on the discovered device that first received a ZDP discovery request from the ZON Utility.	
System Name	This field displays the system name of the discovered device.	
Location	This field displays where the discovered device is.	
Status	This field displays whether changes to the discovered device have been done successfully. As the Switch does not support <b>IP Configuration</b> , <b>Renew IP address</b> and <b>Flash Locator IED</b> , this field displays "Update failed", "Not support Renew IP address" and "Not support Flash Locator LED" respectively.	
Controller Discovery	This field displays if the discovered device supports the Nebula Control Center (NC discovery feature. If it is enabled, the selected device will try to connect to the NC Once the selected device is connected to and has registered in the NCC, it will g into the Nebula cloud management mode.	
Serial Number	Enter the admin password of the discovered device to display its serial number.	
Hardware Version	This field displays the hardware version of the discovered device.	
IPv6 Address	This field displays the IPv6 address on the discovered device that first received a ZDP discovery request from the ZON Utility.	

Table 11 ZON Utility Fields (continued)

#### 4.4 Networked AV Mode Wizard

The Setup Wizard can be accessed using the following methods:

- When the Switch is in its factory-default state, selecting Networked AV mode will automatically access the Setup Wizard.
- When in Networked AV mode, click the Wizard link to access the Setup Wizard.

Figure 45 Wizard Link in Networked AV Mode



The Setup Wizard contains the following parts:

- Use the **Basic Settings** when networked AV service runs on management VLAN, using the combo/ fiber port for inter-switch connection.
- Use the Advanced Settings when you need to specify the VLAN for networked AV service and configure the port's role manually.

#### 4.4.1 Basic Settings

In **Basic Settings**, you can set up IP or DNS, set up your password, SNMP community, accept or skip the default Networked AV mode settings, and view finished results.

In order to set up your IP or DNS, please do the following. Click Wizard > Basic Settings > Next > Step 1 IP to access this screen.

Hup IP       rot turnin       roterbox       (1996) Printing       Printing       Printing       State Printing       State Printing       State Printing       State Printing	17 <sup>-10</sup>	2 Mi	aword	3	Networked AV	4	Summery
Primetron     Cliffond analysis       VC     I       VC     I <th>1.000</th> <th></th> <th></th> <th></th> <th></th> <th></th> <th></th>	1.000						
	Prospikow 1922 Prozinie Prosinanie Detach Gotseng 2012 Januar	(15-6 Printse) I	October				

Figure 46 Wizard > Basic Settings > Step 1 IP

Each field is described in the following table.

LABEL	DESC RIPTIO N				
Host Name	This field displays a host name.				
IP Interface	Select <b>DHCPClient</b> if the Switch is connected to a router with the DHCP server enabled. You then need to check the router for the IP address assigned to the Switch in order to access the Switch's Web Configurator again.				
	Select <b>Static IP Interface</b> when the Switch is NOT connected to a router or you want to assign it a fixed IP address.				
VID	This field displays the VLAN ID.				
IP Address	The Switch needs an IP address for it to be managed over the network.				
IP Subnet Mask	The subnet mask specifies the network number portion of an IP address.				
Default Gateway Type the IP address of the default outgoing gateway in dotted decimal notation, texample 192.168.1.254.					
DNS Server	DNS (Domain Name System) is for mapping a domain name to its corresponding IP address and vice versa. Enter a domain name server IP address in order to be able to use a domain name instead of an IP address.				
Next	Click <b>Next</b> to show the next screen.				
Cancel	Click Cancel to exit this screen without saving.				

Table 12 Wizard > Basic Settings > Step 1 IP

After clicking Next, the Password screen appears.

Figure 47	Wizard > Basic Settings > Step 2 Password
-----------	---

1 р	2 Pessword	3	Networked AV	4 Sum	nory
-	histrator's password		vid polenijaj wwwity b	evenda.	
Actininish alor's Pasa Curved converts Naturation and Construction and		De VA SRVA Version Cell Doma Sell Come age Come	⊖ Chooled   v2x   v   web/c   peace		
			Previous	Heal	Concel

## Note: The input string of any field in this screen should not contain [?], [|], ['], ["], or [,]. In the **Password** fields, [space] is also not allowed.

Each field is described in the following table.

IABEL	DESC RIPTIO N			
Administrator's Passwo	brd			
Current password	Enter the existing system password (1234 is the default password when shipped).			
New password	Enter your new system password. Up to 32 printable ASCII characters are allowed for the new password.			
Confirm password	Re-enter your new system password for confirmation.			
SNMP				
SNMP	Select <b>Enabled</b> to let the Switch act as an SNMP agent, which allows a manager station manage and monitor the Switch through the network. Select <b>Disabled</b> to turn this feature off.			
Version	Select the SNMP version for the Switch. The SNMP version on the Switch must match the version on the SNMP manager. Choose SNMP version 2c $(v2c)$ , SNMP version 3 $(v3)$ or both $(v3v2c)$ .			
	Note: SNMP version 2c is backwards compatible with SNMP version 1.			
Get Community	Enter the <b>GetCommunity</b> string, which is the password for the incoming Get- and GetNextrequests from the management station.			
	The GetCommunity string is only used by SNMP managers using SNMP version 2c or lower.			
Set Community	Enter the Set Community string, which is the password for the incoming Set- requests from the management station.			
	The Set Community string is only used by SNMP managers using SNMP version 2c or lower.			


XGS2220 Series User's Guide

IABEL	DESC RIPTIO N
Trap Community	Enter the <b>Thap Community</b> string, which is the password sent with each trap to the SNMP manager.
	The $\operatorname{Titap} \operatorname{Community}$ string is only used by SNMP managers using SNMP version 2c or lower.
Previous	Click <b>Previous</b> to show the previous screen.
Next	Click Next to show the next screen.
Cancel	Click <b>Cancel</b> to exit this screen without saving.

Table 13 Wizard > Basic Settings > Step 2 Password (continued)

After clicking Next, the Networked AV screen appears.

#### Figure 48 Wizard > Basic Settings > Step 3 Networked AV



Each field is described in the following table.

Table 14	Wizard > Basic Settings > Step 3 N	letworked AV
----------	------------------------------------	--------------

LABEL	DESC RIPTIO N
Skip Networked AV Mode Settings	Click this option to avoid using the basic default AVoIP settings. The default AVoIP settings can be seen in Step 4 Summary under <b>Ne tworked AV - Basic Settings</b> .
	Otherwise, clear the check box and follow the diagram for connecting RJ45 ports to audio and video equipment. The Interswitch Connection is for connecting to another switch.
	Note: Use the <b>Wizard</b> > <b>Advanced Settings</b> > <b>Step 3 Networked AV</b> to configure connections for non-Audio-Video equipment (for example computer, NAS) to the RJ45 ports.
Previous	Click <b>Previous</b> to show the previous screen.
Next	Click Next to show the next screen.
Cancel	Click Cancel to exit this screen without saving.

After clicking Next, the Summary screen appears.

la con					
Summary				C	
letup if		Change administ and activate SNN		Networked AV - Basi	c Settings
Hid Texas	102033200	Transit (Constant)		Institutional Art Manual	
or youthing .	DHOP COME	10.646	tioni edit	percented Available	
100-	1	The second se	100	Intel® stranging	datters.
Partne	110110-018	diel dermonent	pa.690	<b>Conference Downer</b>	Autom
e interview man	2008.000.000.0	Set purchasely.	0.000	Manager Mathematikan	
Defect Generation	11231-46264	And Decomposity	12,2,41	Solution (Include) Conversation	3.48
				Wei Aktor Committed	et (1.44
				Fiesdays Track	Center

Figure 49 Wizard > Basic Settings > Step 4 Summary

Each field is described in the following table.

Table 15 Wizard > Basic Settings > Step 4 Summary

IABEL	DESC RIPTIO N			
Setup IP				
Host Name	This field displays a host name.			
IP Interface	This field displays whether the WAN interface is using a DHCP IP address or a static IP address.			
VID	This field displays the VLAN ID.			
IP Address	This field displays the Switch's IP address for it to be managed over the network.			
IP Subnet Mask	This field displays the subnet mask that specifies the network number portion of an IP address.			
Default Gateway	This field displays the IP address of the default outgoing gateway in dotted decimal notation, for example 192.168.1.254.			
DNS Server	This field displays the DNS (Domain Name System) for mapping a domain name to its corresponding IP address and so forth.			
Change administrator	's password and activate SNMP			
New Password	This field displays asterisks when a new password has been created.			
SNMP	This field displays whether the Switch acts as an SNMP agent.			
Version	This field displays the SNMP version for the Switch.			
Get Community	This field displays the Get Community string.			
Set Community	This field displays the Set Community string.			
Trap Community	This field displays the <b>Thap Community</b> string.			
Networked AV – Basic	Settings			
Networked AV VLAN This field displays the VLAN ID for the AVoIP network.				

LABEL	DESC RIPTIO N				
Networked AV VLAN IP	This field displays the Switch's IP address for it to be managed over the AVoIP network.				
IGMP Snooping	This field displays $Active$ when IGMP Snooping is enabled to forward group multicast traffic only to ports that are members of that group.				
	Otherwise, it displays <b>Inactive</b> .				
IGMP Snooping Querier	This field displays $Active$ when the Switch is allowed to send IGMP General Query messages to the VLANs with the multicast hosts attached.				
	Otherwise, it displays <b>Inactive</b> .				
Unknown Mulficast Frame	This field displays the action to perform when the Switch receives an unknown multicast frame. It displays <b>Drop</b> when the frames are discarded. It displays <b>Flooding</b> when the frames are sent to all ports.				
Transmitter/ Receiver Connected Port	This field shows the Switch's port numbers for connection to networked audio and video equipment.				
Inter-switch Connected Port	This field shows the Switch's port numbers for connection to another switch.				
Previous	Click <b>Previous</b> to show the previous screen.				
Finish	Review the information and click <b>Finish</b> to create the task.				
Cancel	Click Cancel to exit this screen without saving.				

Table 15 Wizard > Basic Settings > Step 4 Summary (continued)

#### 4.4.2 Advanced Settings

In Advanced Settings, you can set up IP or DNS, set up your password, SNMP community, configure Networked AV service to a VLAN, select and assign port role, link aggregation (trunking), and view finished results.

In order to set up your IP or DNS, please do the following. Click Wizard > Advanced Settings > Step 1 IP to access this screen.

1 m <sup>2</sup>	<b>2</b> Ni	noverd	3	Networked AV	4	Scenencry
etup IP						
real surve Proprieta ID Proprieta Proprieta Detachicology Detachicology Detachicology	adarreati () trada d' artigrico a ) ) ) ) ) ) ) ) ) ) ) ) ) ) ) ) ) ) )	0007264				
					Next	Cance

Figure 50 Wizard > Advanced Settings > Step 1 IP

Each field is described in the following table.

LABEL	DESC RIPIIO N			
Host Name	This field displays a host name.			
	You can enter a new host name here. Up to 64 printable ASCII characters are allowed except [ ? ], [   ], ['], or [ , ].			
IP Interface	Select <b>DHCP Client</b> if the Switch is connected to a router with the DHCP server enabled. You then need to check the router for the IP address assigned to the Switch in order to access the Switch's Web Configurator again.			
	Select <b>Static IP Interface</b> when the Switch is NOT connected to a router or you want to assign it a fixed IP address.			
VID	This field displays the VLAN ID.			
IP Address	The Switch needs an IP address for it to be managed over the network.			
IP Subnet Mask	The subnet mask specifies the network number portion of an IP address.			
Default Gateway	Type the IP address of the default outgoing gateway in dotted decimal notation, for example 192.168.1.254.			
DNS Server	DNS (Domain Name System) is for mapping a domain name to its corresponding IP addre and so forth. Enter a domain name server IP address in order to be able to use a domain name instead of an IP address.			
Next	Click <b>Next</b> to show the next screen.			
Cancel	Click Cancel to exit this screen without saving.			

Table 16 Wizard > Advanced Settings > Step 1 IP

After clicking Next, the Password screen appears.

1 m	2 ster	Password	3 Netw	orked AV	4 Sum	тоту
Change administra						
II is not connected of the obvious And relial shortwork: Prosesson Connect processor Nonegous series Control processors :		and and SMAP do not	enity string to evold per parts state Contract Contractory of community bags structures		O Dicc ed	
			Pre	vious	Next	Cancel

Figure 51 Wizard > Advanced Settings > Step 2 Password

## Note: The input string of any field in this screen should not contain [?], [|], ['], ["], or [,]. In the **Password** fields, [space] is also not allowed.

Each field is described in the following table.

Tabla 17	Wizard >	Advanced S	attings > S	Stop 2 Passivo	rd
	vvizara -	Advanced 3	ennigs – s	Step 2 Passwo	IU

LABEL	DESC RIPTIO N
Administrator's Passwo	brd
Current password	Type the existing system password (1234 is the default password when shipped).
New password	Enter your new system password. Up to 32 printable ASCII characters are allowed for the new password.
Confirm password	Re-enter your new system password for confirmation.
SNMP	•
SNMP	Select <b>Enabled</b> to let the Switch act as an SNMP agent, which allows a manager station to manage and monitor the Switch through the network. Select <b>Disabled</b> to turn this feature off.
Version	Select the SNMP version for the Switch. The SNMP version on the Switch must match the version on the SNMP manager. Choose SNMP version 2c $(v2c)$ , SNMP version 3 $(v3)$ or both $(v3v2c)$ .
	Note: SNMP version 2c is backwards compatible with SNMP version 1.
Get Community	Enter the GetCommunity string, which is the password for the incoming Get- and GetNextrequests from the management station.
	The GetCommunity string is only used by SNMP managers using SNMP version 2c or lower.
Set Community	Enter the <b>Set Community</b> string, which is the password for the incoming Set- requests from the management station.
	The Set $Community$ string is only used by SNMP managers using SNMP version 2c or lower.

XGS2220 Series User's Guide

LABEL	DESC RIPTIO N
Trap Community	Enter the <b>Thap Community</b> string, which is the password sent with each trap to the SNMP manager.
	The $\operatorname{Thap} \operatorname{Community}$ string is only used by SNMP managers using SNMP version 2c or lower.
Previous	Click <b>Previous</b> to show the previous screen.
Next	Click Next to show the next screen.
Cancel	Click <b>Cancel</b> to exit this screen without saving.

Table 17	Wizard > Advanced Settings > Step 2 Password (	(continued)
----------	--	-------------

After clicking Next, the Networked AV screen appears.

Figure 52	Wizard > Advanced Settings > Step 3 Networked AV
Ing une of	

1			2	Fa	zword		<b>3</b> 9152	Neter	orked a	w	4 :	Summa	T¥
Adva	nc <del>e</del> d:	Setting	gs				$\mathbf{T}$						
Allocate	network	ed AV be	rvice to s	INIAN									
Networks	AV MAR	1											
IF Achieves		152.16	0210	(0)	i cont								
E Sobre D	4.ch	253.25	52550	(Oc	lonef.								
Selections 2	ab 🔲				12	14	15	18	~	<i>r</i> .	24	25	24
-	-	-	-		-	14		L M	25 (186)	20 Lance	24	24	5.4
- E -													
	2	5	7	2		12	15	12	12	21	25	55	27
	r				eine -	The ex		er Seregere		-		□ Unk s;	
								<b>Per</b> ta	Alous -		Hed		Joneol
								1.155	1000		116.60		AND PARTY

Each field is described in the following table.

Table 18Wizard > Advanced Settings > Step 3 Networked AV

LABEL	DESC RIPTIO N						
Allocate networked A	Allocate networked AV service to a VLAN						
Networked AV VLAN	Enter a number between 1 and 4094 to create a VLAN for the AVoIP network (see Figure 3 on page 34 for details on an AVoIP network).						
IP Address (Optional)	You must enter a different VLAN ID in the previous field ( <b>Networked AV VIAN</b> ) to be able to assign another IP address for the Switch to be managed over the AVoIP network.						
IP Subnet Mask (Optional)	You must enter a different VLAN ID in the <b>Networked AV VIAN</b> field to be able to assign another subnet mask that specifies the network number portion of an IP address.						
Select Ports and Assig	n a Port Role						

LABEL	DESC RIPTIO N
Select all ports	After you create a VLAN, select the ports to be assigned to the Networked AV VLAN.
	Select all ports to assign the same role to all ports.
	You can select a port by clicking it. Then click any of the following:
	Click $\mathbf{T}_{\mathbf{x}}/\mathbf{R}_{\mathbf{x}}$ to assign the ports for connecting to audio and video equipment.
	Click Interswitch to assign the ports for connecting to other switches.
	Click <b>Management</b> to assign the ports for connecting to non-Audio-Video equipment (for example, computer and NAS).
Link aggregate	Select this option to aggregate multiple port bandwidth if you are connecting to another switch. Link aggregation (trunking) is the grouping of physical ports into one logical higher-capacity link.
Previous	Click <b>Previous</b> to show the previous screen.
Next	Click Next to show the next screen.
Cancel	Click Cancel to exit this screen without saving.

#### Table 18 Wizard > Advanced Settings > Step 3 Networked AV (continued)

After clicking Next, the Summary screen appears.

#### Figure 53 Wizard > Advanced Settings > Step 4 Summary

1 (fr		2 Proswiend	3	Networked AV	4	Summary
Summary					Y	
Setup IP		Change administ and activate SNA		Networked A	V - AdSor	iced Settings
Had Starsey	-	New property.		ton facility and the	i de la composición d	A.
A DESCRIPTION OF	Destrollers -	110-0-1	Concerned in the	HERVORAD AVE	Galille .	072.21.46.2
100 ····	Acres	10000	100.0	out similar		Active
C Application	01000-012	Gel Gammanite	2020	CAP Dromating	Goener :	Autor
* installed education	300.584.561.0	int contentity.	24.000	0.0000000000000000000000000000000000000	er Baher	Dyte:
Defined Generation	12231-0220	Page Community	10.000	A Grant (Carl Inc.)	ilen i	
246 Januari	3.22,23,2623			Consideration		
				100-00111-000	inschool Par	÷.
				Previous	Reise	Conte
					1.000	

Each field is described in the following table.

Table 19 Wizard > Advanced Settings > Step 4 Summary

LABEL	DESC RIPTIO N
Setup IP	
Host Name	This field displays a host name.
IP Interface	This field displays whether the WAN interface is using a DHCP IP address or a static IP address.

IABEL	DESC RIPTIO N
VID	This field displays the VLAN ID.
IP Address	This field displays the Switches' IP address for it to be managed over the network.
IP Subnet Mask	This field displays the subnet mask that specifies the network number portion of an IP address.
Default Gateway	This field displays the IP address of the default outgoing gateway in dotted decimal notation, for example 192.168.1.254.
DNS Server	This field displays the DNS (Domain Name System) for mapping a domain name to its corresponding IP address and so forth.
Change administrator	's password and activate SNMP
New Password	This field displays asterisks when a new password has been created.
SNMP	This field displays whether the Switch acts as an SNMP agent.
Version	This field displays the SNMP version for the Switch.
Get Community	This field displays the GetCommunity string.
Set Community	This field displays the Set Community string.
Trap Community	This field displays the <b>Tap Community</b> string.
Networked AV – Advo	inced Settings
Networked AV VLAN	This field displays the VLAN ID for the AVoIP network.
Networked AV VLAN IP	This field displays the corresponding VLAN ID's IP address for the AVoIP network.
IGMP Snooping	This field displays <b>Active</b> when IGMP Snooping is enabled to forward group multicast traffic only to ports that are members of that group.
	Otherwise, it displays <b>Inactive</b> .
IGMP Snooping Querier	This field displays <b>Active</b> when the Switch is allowed to send IGMP General Query messages to the VLANs with the multicast hosts attached.
	Otherwise, it displays <b>Inactive</b> .
Unknown Multicast Frame	This field displays the action to perform when the Switch receives an unknown multicast frame. It displays <b>Drop</b> when the frames are discarded. It displays <b>Flooding</b> when the frames are sent to all ports.
Transmitter/ Receiver Connected Port	This field shows the Switches' port numbers for connection to networked audio and video equipment.
Inter-switch Connected Port (Link Aggregation)	This field shows the Switches' port numbers for connection to another switch.
Previous	Click <b>Previous</b> to show the previous screen.
Finish	Review the information and click <b>Finish</b> to create the task.
Cancel	Click Cancel to exit this screen without saving.

## 4.5 Wizard

The Setup Wizard contains the following parts:

• **Basic** – to configure the Switch IP address, DNS server, system password, SNMP community and link aggregation (trunking).

- Protection to enable loop guard and broadcast storm control on the Switch and its ports.
- VIAN to create a static VLAN, assign ports to the VLAN and set the ports to tag or untag outgoing frames.
- QoS to determine a port's IEEE 802.1p priority level for QoS.

#### Figure 54 Setup Wizard

Setup Wizard			
<ul> <li>Priced will serve the tree</li> <li>I is recommended to che</li> <li>Priced receiption</li> </ul>	nga patwore and sNMP community	ratig is availablen to seco	to breach.
i Basic	Protection		Quá (7)
50		- m	
There have a second to	w.		Activities Eatt

## 4.5.1 Basic

In  $\mathbf{Basic}$ , you can set up IP/DNS, set up your password, SNMP community, link aggregation, and view finished results.

In order to set up your IP/DNS, please do the following. Click Wiza rd > Ba sic > Step 1 IP to access this screen.

Not Name	x(332230	lise and			
E présidences	() Upper Survey	Opposition			
VID: F Accilent	1	1			
	1012-001				
e subterry des	11 10 10 10 10 10 10 10 10 10 10 10 10 1				
Terrail Previous	100 - 100 10	1			
2195 Derived	10103-001				

Figure 55 Wizard > Basic > Step 1 IP

Each field is described in the following table.

Table 20	Wizard > Basic > Step 1 IP
----------	----------------------------

IABEL	DESC RIPTIO N
Host Name	This field displays a host name. Enter a string to set a new host name.
	The host name should not contain [ ? ], [   ], [ ' ], [ " ], or [ , ].
IP Interface	Select <b>DHCP C lie nt</b> if the Switch is connected to a router with the DHCP server enabled. You then need to check the router for the IP address assigned to the Switch in order to access the Switch's Web Configurator again. Select <b>Sta tic IP Address</b> when the Switch is NOT connected to a router or you want to assign
	it a fixed IP address.
VID	This field displays the VLAN ID.
IP Address	The Switch needs an IP address for it to be managed over the network.
IP Subnet Mask	The subnet mask specifies the network number portion of an IP address.
Default Gateway	Type the IP address of the default outgoing gateway in dotted decimal notation, for example 192.168.1.254.
DNS Server	DNS (Domain Name System) is for mapping a domain name to its corresponding IP address and so forth. Enter a domain name server IP address in order to be able to use a domain name instead of an IP address.
Next	Click Next to show the next screen.
Cancel	Click Cancel to exit this screen without saving.

After clicking Next, the Password screen appears.

1 19	2 Pe	ssword	3 link	Aggregation	<b>4</b> au	mmary
Change admini						
His recommended to o Administrator's Possw Concellocowart			ing to avoid po NMP 1974	OPendent		
Hew provoso: transfere provisional			enion & Commonity	yazi wi public		
			el Community age Chancemeily	public public		
			Fri	wious	Next	Cancel

#### Figure 56 Wizard > Basic > Step 2 Password

#### Note: The input string of any field in this screen should not contain [?], [|], ['], ["], or [,]. In the **Password** fields, [space] is also not allowed.

Each field is described in the following table.

Table 21 Wizard > Basic > Step 2 Password

IABEL	DESC RIPTIO N
Administrator's Passwe	ord
Current password	Type the existing system password (1234 is the default password when shipped).
New password	Enter your new system password. Up to 32 printable ASCII characters are allowed for the new password.
Confirm password	Retype your new system password for confirmation.
SNMP	
SNMP	Select <b>Enabled</b> to let the Switch act as an SNMP agent, which allows a manager station to manage and monitor the Switch through the network. Select <b>Disabled</b> to turn this feature off.
Version	Select the SNMP version for the Switch. The SNMP version on the Switch must match the version on the SNMP manager. Choose SNMP version 2c (v2c), SNMP version 3 (v3) or both (v3v2c).
	Note: SNMP version 2c is backwards compatible with SNMP version 1.
Get Community	Enter the <b>GetCommunity</b> string, which is the password for the incoming Get- and GetNextrequests from the management station.
	The GetCommunity string is only used by SNMP managers using SNMP version 2c or lower.
Set Community	Enter the <b>Set Community</b> string, which is the password for the incoming Set- requests from the management station.
	The Set Community string is only used by SNMP managers using SNMP version 2c or lower.


XGS2220 Series User's Guide

IABEL	DESC RIPTIO N
Trap Community	Enter the <b>Thap Community</b> string, which is the password sent with each trap to the SNMP manager.
	The Thap Community string is only used by SNMP managers using SNMP version 2c or lower.
Previous	Click <b>Previous</b> to show the previous screen.
Next	Click Next to show the next screen.
Cancel	Click Cancel to exit this screen without saving.

Table 21 Wizard > Basic > Step 2 Password (continued)

After clicking Next, the Link Aggregation screen appears.

#### Figure 57 Wizard > Basic > Step 3 Link Aggregation



Each field is described in the following table.

Table 22 Wizard > Basic > Step 3 Link Aggregation

LABEL	DESC RIPTIO N
Link Aggregation	
T1-Tx	Click the arrows to add or delete icons located on the left to desired preference.
	Select $\mathbf{Static}$ if the ports are configured as static members of a trunk group.
	Select <b>IACP</b> if the ports are configured to join a trunk group through LACP.
Previous	Click <b>Previous</b> to show the previous screen.
Next	Click Next to show the next screen.
Cancel	Click <b>Cancel</b> to exit this screen without saving.

After clicking Next, the Summary screen appears.

Figure 58 Wizard > Basic > Step 4 Summary

					STEP	
Jmmary						
Setup IP			Change adminish	ator's posswore	and ac	ffvate SNMP
Heel Norses	9/032/222		New postword:			
Pinterloce:	DHOP Client		21842	Disard de suit		
V05	1.1		Versions	wing .		
P Address	175.21,40.2		start storemenitys	partille.		
P Sole of Merch	2010/02/02/2012		Set Community	public		
Default Gateways	175.01.40.054		rop community.	partelle.		
Disk Shinying	179,21,10,1					
link Aggregation						
Group	Type	Member				

Each field is described in the following table.

Table 23 Wizard > Basic > Step 4 Summary	Table 23	Wizard >	Basic >	Step	4 Summary
--	----------	----------	---------	------	-----------

LABEL	DESC RIPTIO N
Setup IP	
Host Name	This field displays a host name.
IP Interface	This field displays whether the WAN interface is using a DHCP IP address or a static IP address.
VID	This field displays the VLAN ID.
IP Address	The Switch needs an IP address for it to be managed over the network.
IP Subnet Mask	The subnet mask specifies the network number portion of an IP address.
Default Gateway	Type the IP address of the default outgoing gateway in dotted decimal notation, for example 192.168.1.254.
DNS Server	DNS (Domain Name System) is for mapping a domain name to its corresponding IP address and vice versa. Enter a domain name server IP address in order to be able to use a domain name instead of an IP address.
Change administrat	or's password and activate SNMP
New Password	This field displays asterisks when a new password has been created.
SNMP	This field displays whether the Switch acts as an SNMP agent.
Version	This field displays the SNMP version for the Switch.
Get Community	This field displays the Get Community string.
Set Community	This field displays the Set Community string.
Trap Community	This field displays the Thap Community string.
Link Aggregation	· ·
Group	This field displays the group number.
Туре	This field displays <b>Static</b> or <b>IACP</b> of this group.
Member	This field displays the members of this group.

XGS2220 Series User's Guide

Table 23 Wizard > Basic > Step 4 Summary (continued)

LABEL	DESC RIPTIO N
Previous	Click <b>Previous</b> to show the previous screen.
Finish	Review the information and click <b>Finish</b> to create the task.
Cancel	Click <b>Cancel</b> to exit this screen without saving.

#### 4.5.2 Protection

In Protection, you can set up loop guard and broadcast storm control.

In order to set up loop guard, please do the following. Click **Wizard** > **Protection** > **Step 1 Loop Guard** to access this screen.

Figure 59 Wizard > Protection > Step 1 Loop Guard

1 эпр	ι	өөр	Gu	ard					2		Bro	adk	cost	t Sto	rm (	Cor	itrol		3	S	um	mar	Y			
Lo	op	Gu	ard																							
Selec	t ol (	sarta																								
						14				22 1	21			22									-12			*
1	8	7	7	*	11	10	M	17	18	21		26	w	27	21	200	20.	<u></u>	24	-	20.		A7	dir.	71 (11)	in a
																					Next			0	lond	al

Each field is described in the following table.

Table 24	Wizard > Protection > Step 1 Loop Guard
----------	---

IABEL	DESC RIPTIO N
Loop Guard	
Select all ports	Select all ports to enable the loop guard feature on all ports.
	You can select a port by clicking it.
Next	Click <b>Next</b> to show the next screen.
Cancel	Click Cancel to exit this screen without saving.

After clicking Next, the Broadcast Storm Control screen appears.

1	loop (	Juan	1				2 आ		Bro	oade	easi	Slor	m C	Cont	rol	;	3	SU	mm	ory				
Broa	deast	Stor	m I	Cor	ntra																			
electical po readcostip	en. Sto	<b>2</b> 102	0																					
			12	14			20	77 1	2.4					24	24				44	43. 100	24 10			AL
			1	12		12		21	20				21	<b>11</b> 30	20		<b>1</b>	-41	45	45		-		
oo    1990	1000    1000		1000	1000	1000	1000	1000	1000	1000	100	1000	1000	1858	1000	1010	1000	100	1000	1606		icco) aniect			
																					_			
														Pre	wiou	8		R	lext?			Cn	ncel	

Figure 60 Wizard > Protection > Step 2 Broadcast Storm Control

Each field is described in the following table.

IABEL	DESC RIPIIO N							
Broadcast Storm Control								
Select all ports	Select all ports to apply settings on all ports.							
	You can select a port by clicking it.							
Broadcast pkt/s	Specify how many broadcast packets the port receives per second.							
Previous	Click Previous to show the previous screen.							
Next	Click Next to show the next screen.							
Cancel	Click Cancel to exit this screen without saving.							

After clicking Next, the Summary screen appears.

1		1.00	p C	anar Anar	d				2	2	Rec	enek	tan	Sto	im ¢	Con	trol		3	<b>S</b> 0	mm	кагу	1			
S	Jmi	mai	ry																							
.oop	Guo	nd																								
$\mathcal{D}_{i}$	А.		D.	80	12	14	Цė.	111	20	7.5	201	200	341	303	${\bf r} t$	2.4	20	201	30	AD4	43	4.6	- 610	100	107	- 64
Ξ.	3	<u>.</u>	7	N	1	12	14	12	The second	21	24	126	10	22	21	24	25	100	325	- 10	48	45	11		<u>.</u> .	100
																						T V	a el ect	ed	- Se	(Hech
nco	deca	i Stor	m C	entre	1																	i ur	walec)	led .	i Se	And In
iree 2	deces 4	i Shar	m C 8	entre 10	al 12	14	16	18	20	22	24	24	28	30	22	-24	38	38	40	42	44	45 U	antect	ed 80	2 Se 80	de cie
		i Shar				14	16	18	20	22	24	24	28		<u></u>	34	38	28	*	-2	44					84
	4 A NO 1	i Shar K				14	16	18	20 1120	22	24	2/	28	30 110	32 130	-24 	28 1049	28 1120	40	42 1115	44				ла П	
	4	( ) ) ) ) ) )				14	16 100 1000	18	20 1.3.0	22	24 10:30	24	2	30 1000	22   310   310	34 1000	28 10:00	22 1021			44				ла П	84 1
	4 4 1000 1000	i Shar i Nacional i Shari i Shari i Shari i Shari i Shari i Shari i Shari i Shari i Shari i Shari i Shari i Shari				14 1100 1100	16. 10.00 115	18 1100 1100 17	20 1000 1000	22 12.0 21	24 1039 20	24 1000 28	22 1000 1000 27	30 1000 20	22 1010 31	24 10:50 20	28 1000 28	28 1000 27	40 1000 1000 1000	42 11.00 14.10	44 1000 140				ла П	84 1
	4 1000 0 1000	1 Shar 7 1000				14 11000 12 1000	16 1000 1000	18 1000	20 1000 1200 1200	22 1000 21 1000	24 1039 23 1000	2	22 10000 27 10000	30 1000 29 1000	22 1000 21 1000	34 10:00 33 10:00	28 10:00 28 10:00	28 1000 27 1000		42 1436 41 1000	44 1300 40 1000	45 1000 45	48 1000 47		83 1000 81	84 130 50
2	4 1000 0 1000	f Shar A R.D.C R.D.C R R R R R R R R R R R R R R R R R R R				14 1100 12 1000	18 18	17 17	20 1 300 19 1000	22 1 200 21 1 200	24 1000 20 1000	2	27 100		010 01	34 1039 33 1000	1000 1000 20			42 1436 41 1000	44 1900 40 1000	45 1030 45 1000	45 1100 47 1000		82 1000 81 1000	84 1.00 80 100

Figure 61 Wizard > Protection > Step 3 Summary

Each field is described in the following table.

Table 26 Wizard > Protection > Step 3 Summary

LABEL	DESC RIPIIO N
Summary	
Loop Guard	If the loop guard feature is enabled on a port, the Switch will prevent loops on this port.
Broadcast Storm Control	If the broadcast storm control feature is enabled on a port, the number of broadcast packets the Switch receives per second will be limited on this port.
Previous	Click <b>Previous</b> to show the previous screen.
Finish	Review the information and click <b>Finish</b> to create the task.
Cancel	Click Cancel to exit this screen without saving.

## 4.5.3 VIAN

In  $\ensuremath{\mathbf{VLAN}}$  , you can create VLAN, and tag VLAN settings.

Click Wizard > VIAN > VIAN Setting to access this screen.

Figure 62 Wizard > VLAN > VLAN Setting

VEAN		
VLAN Setting		
2 The second sec	The first product of a second and of the second sec	
He and a set of the first set set of the first set of the first set of the first set of the		Ensieches 🗮 Seaches
		Truby Concel

Each field is described in the following table.

Table 27 Wizard > VLAN > VLAN Setting

IABEL	DESC RIPIIO N
VLAN Setting	
Default VLAN 1 / Access Untagged port	After you create a VLAN and select the VLAN ID from the drop-down list box, select ports and use the right arrow to add them as the untagged ports to a VLAN group.
VLAN member port	
VLAN	Type a number between 2 and 4094 to create a VLAN.
Trunk Tagged port	Select ports and use the downward arrow to add them as the tagged ports to the VLAN groups you created.
Finish	Review the information and click <b>Finish</b> to create the task.
Cancel	Click Cancel to exit this screen without saving.

## 4.5.4 QoS

In  $\mathbf{QoS}$  , you can create QoS settings.

In order to create QoS settings, please do the following. Click Wizard > QoS > QoS setting to access this screen.

Figure 63	Wizard > QoS > QoS Setting
-----------	----------------------------

Qc	>5																								
Q	05	Setti	ng																						
		arts fins	t the	n apj	aly Q	oð pr	ionly																		
	din ta k	aber A	E.		12	14	14	111	100	22	24	24.	182	80	5.2	30	344	53	4.2	 		44	81	102	M
	×	-	7	-	11	14	14		•		23	26	22	- 22	21	200		20	24	-	-	10	av	<b>A</b> 1	<b>1</b> 0
									Hig	ħ		Mee	ium		l	юн									
																				 Finki	h _		0	lona	al
																				fin ki	6		0	land	al

Each field is described in the following table.

IABEL	DESC RIPIIO N
QoS Setting	
Select all ports	Select all ports to apply settings on all ports.
	You can select a port by clicking it.
High	Select ports and click the $\operatorname{Hig} h$ button, so they will have high priority.
	The port's IEEE 802.1p priority level will be set to 5. Use the <b>Basic Setting</b> > <b>Port Setup</b> screen to adjust the value.
Medium	Select ports and click the <b>Medium</b> button and, so they will have medium priority.
	The port's IEEE 802.1p priority level will be set to 3. Use the <b>Basic Setting</b> > <b>Port Setup</b> screen to adjust the value.
Low	Select ports and click the $\mathbf{Low}$ button, so they will have low priority.
	The port's IEEE 802.1 p priority level will be set to 1. Use the $Basic Setting > Port Setup$ screen to adjust the value.
Finish	Review the information and click <b>Finish</b> to create the task.
Cancel	Click Cancel to exit this screen without saving.

Table 28 Wizard > QoS > QoS Setting

## 4.6 Web Configurator Layout

The **DASHBOARD** screen is the first screen that displays when you access the Web Configurator.

This guide uses the XGS2220-54FP screens as examples. The screens may vary slightly for different models.

The following figure shows the navigating components of a Web Configurator screen.

ZYKEL : MINIZIO			Contract sectors		G H I	TK
🛛 akiatoka	257.0 -50		85	1.128.53		ren instante
(III) - marine (m. m.	For Siche					
ne area	1004(2290-4447 Laborat				the second se	alles i
臣		<u>ة يُخ يُخ في في قي م</u>	<u>i ti ti</u>	ÖÖÖÖ Ö		
🚊 tvittera 🔺		÷ ni di ni ŝi ŝi ŝi ŝi ŝi				144 S
C states	Section visionection	2251 22	d)alasae	Mency Crow	For manage (1976)	
G near	The form fields	Salar Summer	2078	11:04	00,000.00	
ty names i	TINE GARNE	**************************************	Reported 0	Spender 14	e 🛛 🔁 Holend	
	MORDONAL AND A CHARGE AND A CHA	Set days Scheme 2 minute and	Cubic Link			().
	The fact and the second	AT A Standard Contract Content	1.04 m		operation and the	
	X PADRX8	WY182.988	-to-pair	1993.004		
			- Charles -	(her/) (h	0	
	About Control States	1	1000	a identit	4	
	- 10	pener) ( Londa ) ( Deleter	( jo krone			

Figure 64 Web Configurator Layout

 ${\bf A}$  – Click the menu items to open sub-menu links, and then click on a sub-menu link to open the screen in the main window.

B, C, D, E, F, G, H, I, J, K – These are quick links which allow you to perform certain tasks no matter which screen you are currently working in.

B, C - Click this icon to switch between the Web Configurator's Standard or Networked AV mode.

**D** – Click this icon to go to the NCC (Nebula Control Center) portal website.

 $\mathbf{E}$  - Click this icon to search for specific configurations or status you are looking for. Enter the keywords and click the result link. This will direct you to the specific configuration or status page.

F-Click this icon to update the information in the screen you are currently viewing.

**G** – Click this icon to save your configuration into the Switch's non-volatile memory. Non-volatile memory is the configuration of your Switch that stays the same even if the Switch's power is turned off.

H – Click this icon to display the Setup Wizard that contains the Basic, Protection, VIAN, and QoS setup screens.

I - Click this icon to display web help pages. The help pages provide descriptions for all of the configuration screens.

 ${\bf J}$  – Click this icon to go to the Zyxel Community Biz Forum.

 $\kappa$  - Click this icon to log out of the Web Configurator.

L-This displays the Nebula Cloud Control Status. The ON/OFF switch displays if NCC Discovery is enabled. If a status circle turns Orange, it means the Switch is unable to connect to NCC. Hover the mouse over the status circle to check the diagnostic message. You can also click the ON/OFF switch to go to the SYSTEM > Cloud Management screen and check the diagnostic messages. See Section Table 33 on page 118 for more information.

In the navigation panel, click a main link to reveal a list of sub-menu links.

The following table describes the links in the navigation panel. The navigation panel varies depending on the product model you use.

LINK	DESC RIPIIO N
DASHBOARD	This link takes you to the main dashboard screen that displays general system and device infor- mation.
MONITOR	
ARP Table	This link takes you to a screen that displays the current ARP table of the Switch. You can view the IP and MAC address mapping, VLAN ID, ARP aging time, and ARP entry type of a device attached to a port.
IP Table	This link takes you to a screen where you can view the IP address and VLAN ID of a device attached to a port.
IPv6 Neighbor Table	This link takes you to a screen where you can view the Switch's IPv6 neighbor table.
MAC Table	This link takes you to a screen where you can view the MAC address and VLAN ID of a device attach to a port. You can also view what kind of MAC address it is.
Neighbor	This link takes you to a screen where you can view neighbor devices (including non-Zyxel devices) connected to the Switch.
Path MTU Table	This link takes you to a screen where you can view the IPv6 path MTU information on the Switch.
Port Status	This link takes you to a screen where you can view the port statistics.
Routing Table	Click the link to unfold the following sub-link menu.
IPv4 Routing Table	This link takes you to a screen where you can view the IPv4 routing table for routing information including IP interface and hop count to certain network destinations.
IPv6 Routing Table	This link takes you to a screen where you can view the IPv6 routing table for routing information including IP interface and hop count to certain network destinations.
System Infor- mation	This link takes you to a screen that displays general system information.
System Log	This link takes you to a screen where you can view the system log including fail log and system status.
SYSTEM	
Cloud Man- agement	This link takes you to a screen where you can enable or disable the <b>Nebula Control Center</b> (NCC) <b>Discovery</b> feature and view the NCC connection status. If <b>Nebula Control Center</b> (NCC) <b>Discov-</b> <b>ery</b> is enabled, you can have the Switch search for the NCC (Nebula Control Center). The screen also displays a QR code containing the Switch's serial number and MAC address for handy regis- tration of the Switch at NCC.
General Setup	This link takes you to a screen where you can configure general identification information about the Switch.
Hardware Monitor Setup	This link takes you to a screen where you can configure hardware monitor related features such as SFP Detect.
Interface Setup	This link takes you to a screen where you can configure settings for individual interface type and ID.

Table 29 Navigation Panel Links (Standard Mode)

LINK	DESC RIPIIO N
IP Setup	This link takes you to a screen where you can configure the DHCP client, and a static IP address (IP address and subnet mask).
IPv6	Click the link to unfold the following sub-link menu.
IPv6 Status	This link takes you to a screen where you can view the IPv6 table and DNS server.
IPv6 Global Setup	This link takes you to a screen where you can configure the global IPv6 settings.
IPv6 Interface Setup	This link takes you to a screen where you can view and configure IPv6 interfaces.
IPv6 Addressing	This link takes you to a screen where you can view and configure IPv6 link-local and global addresses.
IPv6 Neighbor Discovery	This link takes you to a screen where you can view and configure neighbor discovery settings on each interface.
IPv6 Neighbor Setup	configure static IPv6 neighbor entries in the Switch's IPv6 neighbor table.
DHCPv6 Client Setup	This link takes you to a screen where you can configure the Switch's DHCP settings when it is act- ing as a DHCPv6 client.
Logins	This link takes you to a screen where you can change the system login password, as well as con- figure up to four login details.
SNMP	This link takes you to screens where you can specify the SNMP version and community (password) values, configure where to send SNMP traps from the Switch, enable loopguard/errdisable/poe/linkup/linkdown/lldp/transceiver-ddm/storm-control on the Switch, specify the types of SNMP traps that should be sent to each SNMP manager, and add/edit user information.
Stacking	This link takes you to screens where you can view the stacking status in the stacking system, enable stacking on the Switch, and configure stacking details.
Switch Setup	This link takes you to a screen where you can set up global Switch parameters such as VLAN type.
Syslog Setup	This link takes you to a screen where you can configure the Switch's system logging settings and configure a list of external syslog servers.
Time Range	This link takes you to a screen where you can configure time range for time-oriented features like Classifier.
PORT	
Auto PD Recovery	This link takes you to a screen where you can enable and configure Auto PD Recovery on the Switch.
Flex Link	This screen takes you to a screen where you can view configure backup links in the Data Link layer.
Green Ethernet	This link takes you to a screen where you can configure the Switch to reduce port power con- sumption.
Link Aggrega- tion	This link takes you to a screen where you can logically aggregate physical links to form one logi- cal, higher-bandwidth link.
LLDP	Click the link to unfold the following sub-link menu.
LLDP	This link takes you to screens where you can view LLDP information and configure LLDP and TLV settings.
LLDP MED	This link takes you to screens where you can configure LLDP-MED parameters.
OAM	This link takes you to screens where you can enable Ethernet OAM on the Switch, view the config- uration of ports on which Ethernet OAM is enabled and perform remote-loopback tests.

 Table 29
 Navigation Panel Links (Standard Mode) (continued)

LINK	DESC RIPTIO N
PoE Setup	For PoE models.
	This link takes you to a screen where you can set priorities, PoE power-up settings and schedule so that the Switch is able to reserve and allocate power to certain PDs.
Port Setup	This link takes you to a screen where you can configure settings for individual Switch ports.
ZULD	This link takes you to screens where you can enable ZULD on a port and configure related set- tings.
SWITCHING	
Layer 2 Proto- col Tunneling	This link takes you to a screen where you can configure L2PT (Layer 2 Protocol Tunneling) settings on the Switch.
Loop Guard	This link takes you to a screen where you can configure protection against network loops that occur on the edge of your network.
MAC Pinning	This link takes you to a screen where you can set specific ports to have priority over other ports in MAC address learning.
Mirroring	Click the link to unfold the following sub-link menu.
Mirroring	This link take you to a screen where you can copy traffic from one port or ports to another port in order to examine the traffic from the first port without interference.
Multicast	Click the link to unfold the following sub-link menu.
IPv4 Multicast	This link takes you to screen where you can configure various IPv4 multicast features, IGMP snoop- ing, filtering and create multicast VLANs.
IPv6 Multicast	This link takes you to screen where you can configure various IPv6 multicast features, MLD snoop- ing-proxy, filtering and create multicast VLANs.
MVR	This link takes you to screens where you can create multicast VLANs and select the receiver ports and a source port for each multicast VLAN.
Static Multicast Forwarding By MAC	This link takes you to a screen where you can configure static multicast MAC addresses for port(s). These static multicast MAC addresses do not age out.
Static Multicast Forwarding By IP	This link takes you to a screen where you can configure static multicast IP addresses for port(s). These static multicast IP addresses do not age out.
PPPoE Interme- diate Agent	This link takes you to screens where you can enable PPPoE (Point-to-Point Protocol over Ethernet) Intermediate Agent and configure per-port, per-port-per-VLAN settings.
QoS	Click the link to unfold the following sub-link menu.
Diffserv	This link takes you to screens where you can enable DiffServ, configure marking rules and set DSCP-to-IEEE802.1p mappings.
Queuing Method	This link takes you to a screen where you can set priorities for the queues of the Switch. This distrib- utes bandwidth across the different traffic queues.
Priority Queue	This link takes you to a screen where you can set priority tags for different traffic types and specify the priority levels.
Bandwidth Control	This link takes you to a screen where you can cap the maximum bandwidth allowed on a port.
sFlow	This link takes you to screens where you can configure sFlow settings on the Switch.
Spanning Tree Protocol	Click the link to unfold the following sub-link menu.
Spanning Tree Protocol Status	This link takes you to a screen where you can view the STP status in the different STP modes (RSTP, MRSTP or MSTP) you can configure on the Switch.

 Table 29
 Navigation Panel Links (Standard Mode) (continued)

LINK	DESC RIPTIO N
Spanning Tree Setup	This link takes you to a screen where you can activate one of the STP modes (RSTP, MRSTP or MSTP) on the Switch.
RSTP	This link takes you to a screen where you can configure the RSTP (Rapid Spanning Tree Protocol) settings on the Switch.
MRSTP	This link takes you to a screen where you can configure the MRSTP (Multiple Rapid Spanning Tree Protocol) settings on the Switch.
MSTP	This link takes you to a screen where you can configure the MSTP (Multiple Spanning Tree Proto- col) settings on the Switch.
Static MAC Fil- tering	This link takes you to a screen to set up static MAC filtering rules.
Static MAC For- warding	This link takes you to a screen where you can configure static MAC addresses for a port. These static MAC addresses do not age out.
VLAN	Click the link to unfold the following sub-link menu.
VLAN Status	This link takes you to a screen where you can view and search all VLAN groups.
VLAN Setup	<ul> <li>This link takes you to screens where you can:</li> <li>configure port-based or 802.1Q VLAN.</li> <li>view detailed port settings and status of the VLAN group.</li> <li>configure and view 802.1Q VLAN parameters for the Switch.</li> <li>configure the static VLAN settings on a port.</li> </ul>
Subnet Based VLAN Setup	This link takes you to a screen where you can set up VLANs that allow you to group traffic into log- ical VLANs based on the source IP subnet you specify.
Protocol Based VLAN Setup	This link takes you to a screen where you can set up VLANs that allow you to group traffic into log- ical VLANs based on the protocol you specify.
Voice VLAN Setup	This link takes you to a screen where you can set up VLANs that allow you to group voice traffic with defined priority and enable the Switch port to carry the voice traffic separately from data traffic to ensure the sound quality does NOT deteriorate.
MAC Based VLAN Setup	This link takes you to a screen where you can set up VLANs that allow you to group untagged packets into logical VLANs based on the source MAC address of the packet. This eliminates the need to reconfigure the Switch when you change ports. The Switch will forward the packets based on the source MAC address you set up previously.
Vendor ID Based VLAN Setup	This link takes you to screens where you can set up VLANs that allow you to group untagged packets into logical VLANs based on the source MAC address of the packet. You can specify a mask for the MAC address to create a MAC address filter and enter a weight to set the VLAN rule's priority.
VLAN Isolation	This link takes you to a screen where you can block traffic between ports in a VLAN on the Switch.
VLAN Mapping	This link takes you to screens where you can configure VLAN mapping settings on the Switch.
VLAN Stacking	This link takes you to screens where you can activate and configure VLAN stacking.
NETWORKING	
ARP Setup	Click the link to unfold the following sub-link menu.
ARP Learning	This link takes you to a screen where you can configure ARP learning mode on a per-port basis.
Static ARP	This link takes you to a screen where you can create static ARP entries which do not age out.
DHCP	Click the link to unfold the following sub-link menu.
DHCPv4 Relay	This link takes you to screens where you can view DHCPv4 relay status, mode, and configure DHCPv4 relay settings.
DHCPv6 Relay	This link takes you to a screen where you can enable and configure DHCPv6 relay.

 Table 29
 Navigation Panel Links (Standard Mode) (continued)

Table 29 Navigation Panel Links (Standard Mode) (continued)

LINK	DESC RIPTIO N
DHCP Server Guard	This link takes you to a screen where you can specify whether ports are trusted or untrusted ports for DHCP packets.
Static Routing	Click the link to unfold the following sub-link menu.
IPv4 Static Route	This link takes you to a screen where you can configure IPv4 static routes. A static route defines how the Switch should forward traffic by destination IP address and subnet mask.
IPv6 Static Route	This link takes you to a screen where you can configure IPv6 static routes. A static route defines how the Switch should forward traffic by destination IP address and prefix length.
SECURITY	
AAA	Click the link to unfold the following sub-link menu.
RADIUS Server Setup	This link takes you to a screen where you can configure your RADIUS (Remote Authentication Dial- In User Service) server settings for authentication.
TACACS+ Server Setup	This link takes you to a screen where you can configure your TACACS+ (Terminal Access Control- ler Access Control System Plus) server settings for authentication.
AAA Setup	This link takes you to a screen where you can configure authentication, authorization and accounting services through external servers. The external servers can be either RADIUS or TACACS+ (Terminal Access Controller Access Control System Plus).
Access Control	Click the link to unfold the following sub-link menu.
Service Access Control	This link takes you to a screen where you can decide what services you may use to access the Switch.
Remote Managem ent	This link takes you to a screen where you can specify a group of one or more "trusted computers" from which an administrator may use a service to manage the Switch.
Account Security	This link takes you to a screen where you can configure account security settings on the Switch.
ACL	Click the link to unfold the following sub-link menu.
Classifier	This link takes you to screens where you can configure the Switch to group packets based on the specified criteria.
Policy Rule	This link takes you to a screen where you can configure the Switch to perform special treatment on the grouped packets.
Anti-Arpscan	This link takes you to screens where you can enable anti-arpscan on the Switch and ports, and view the port state. You can also create trusted hosts, view blocked hosts and unblock them.
BPDU Guard	This link takes you to screens where you can enable BPDU guard on the Switch and ports, and view the port state.
Storm Control	This link takes you to a screen to set up broadcast filters.
Errdisable	This link takes you to a screens where you can view errdisable status and configure errdisable set- tings in CPU protection, errdisable detect, and errdisable recovery.
IPv4 Source Guard	Click the link to unfold the following sub-link menu.
IP Source Guard	This link takes you to screens where you can configure filtering of unauthorized DHCP and ARP packets in your network.
DHCP Snooping	This link takes you to screens where you can view DHCP snooping database details and configure DHCP snooping settings on ports or VLANs. You can use DHCP snooping to filter unauthorized DHCP packets on the network and to build the binding table dynamically.
ARP Inspection	This link takes you to screens where you can view ARP inspection status, and configure ARP inspection settings on ports or VLANs. You can use ARP inspection to filter unauthorized ARP packets on the network.
IPv6 Source Guard	Click the link to unfold the following sub-link menu.
IPv6 Static Binding	The link takes you to screens where you can view IPv6 static binding status and manually create IPv6 source guard static binding entries.

XGS2220 Series User's Guide

LINK	DESC RIPTIO N
IPv6 Source Guard	The link takes you to screens where you can define policies to have IPv6 source guard forward valid addresses and/or prefixes and allow or block data traffic from all link-local addresses, and apply the configured IPv6 source guard policy to a port.
IPv6 Snooping	The link takes you to screens where you can set up DHCPv6 snooping policies for the binding table and enable the policies on VLAN interfaces.
DHCPv6 Trust Setup	The link takes you to a screen where you can specify which ports are trusted for DHCPv6 snoop- ing.
Port Authenti-	Click the link to unfold the following sub-link menu.
cation	These links take you to screens where you can configure IEEE 802.1x port authentication as well as MAC authentication for clients communicating through the Switch.
802.1x	The link takes you to a screen where you can activate IEEE 802.1x security on a port.
MAC Authentica tion	The link takes you to a screen where you can activate MAC authentication on a port.
Guest VLAN	The link takes you to a screen where you can activate enable and assign a guest VLAN to a port.
Compound Authentica tion Mode	The link takes you to a screen where you can allow network access for clients that pass either IEEE 802.1x authentication or MAC authentication, or pass both IEEE 802.1x authentication and MAC authentication.
Port Security	This link takes you to a screen where you can activate MAC address learning and set the maximum number of MAC addresses to learn on a port.
MAINTENANCE	
Certificates	The link takes you to a screen where you can import the Switch's CA-signed certificates.
Cluster Man- agement	This link takes you to a screen where you can configure clustering management and view its sta- tus.
Configuration	Click the link to unfold the following sub-link menu.
Restore Configurati on	This link takes you to a screen where you can upload a stored device configuration file.
Backup Configurati on	This link takes you to a screen where you can save your Switch's configurations (settings) for later use.
Auto Configurati on	This link takes you to a screen where you can overwrite the running configuration stored in the Switch's RAM.
Erase Running- Configurati on	This link takes you to a screen where you can reset the configuration to the Zyxel default configu- ration settings.
Save Configurati on	This link takes you to a screen where you can save the current configuration (settings) to a spe- cific configuration file on the Switch.
Configure Clone	This link takes you to a screen where you can copy the basic and advanced settings from a source port to a destination port or ports.
Diagnostic	This link takes you to a screen where you can ping IP addresses, run traceroute, test ports and show the location of the Switch.
Firmware Upgrade	This link takes you to a screen to upload firmware to your Switch.
Reboot System	This link takes you to a screen to reboot the Switch without turning the power off.
Tech-Support	This link takes you to a screen where you can download related log reports for issue analysis. Log reports include CPU history and utilization, crash and memory.

 Table 29
 Navigation Panel Links (Standard Mode) (continued)

The following table describes the links in the navigation panel when the Switch is in Networked AV mode.

Table 30	Navigation Panel Links (N	etworked AV Mode)
----------	---------------------------	-------------------

LINK	DESC RIPIIO N
SUMMARY	This screen displays the Switch's front panel port status, connected ports, used power, Nebula Cloud Control status, and Networked AV status.
MONITOR	
System Information	This link takes you to a screen that displays general system information.
SYSTEM	
General Setup	This link takes you to a screen where you can configure general identification information about the Switch.
IP Setup	This screen allows you to configure the IP address and subnet mask (necessary for Switch management) and set up to 64 IP routing domains.
Logins	This link takes you to a screen where you can change the system login password, as well as configure up to four login details.
SNMP	This link takes you to screens where you can specify the SNMP version and community (password) values, configure where to send SNMP traps from the Switch, enable loopguard/ errdisable/poe/linkup/linkdown/lldp/transceiver-ddm/storm-control on the Switch, specify the types of SNMP traps that should be sent to each SNMP manager, and add/edit user information.
PORT	
Link Aggregation	This link takes you to screens where you can logically aggregate physical links to form one logical, higher-bandwidth link.
PoE Setup	For PoE models.
	This link takes you to a screen where you can set priorities, PoE power-up settings and schedule so that the Switch is able to reserve and allocate power to certain PDs.
Port Setup	This screen allows you to configure settings for individual Switch ports.
SWITCHING	
Mirroring	This link takes you to screens where you can copy traffic from one port or ports to another port in order that you can examine the traffic from the first port without interference.
Multicast	This link takes you to screens where you can view multicast group information, configure various multicast features like IGMP snooping and filtering profile, and create multicast VLANs.
VLAN	This link takes you to screens where you can view and search all static VLAN groups, view detailed port settings and status of the static VLAN group, configure a static VLAN for the Switch, and configure the static VLAN (IEEE 802.1Q) settings on a port.
SECURITY	
Access Control	
Service Access Control	This link takes you to a screen where you can decide what services you may use to access the Switch.
Remote Management	This link takes you to a screen where you can specify a group of one or more "trusted computers" from which an administrator may use a service to manage the Switch.
Storm Control	This link takes you to a screen to set up broadcast filters.
MAINTENANCE	
Configuration	
Restore Configuration	This link takes you to a screen where you can upload a stored device configuration file.
Backup Configuration	This link takes you to a screen where you can save your Switch's configurations (settings) for later use.

LINK	DESC RIPIIO N
Save Configuration	This link takes you to a screen where you can save the current configuration (settings) to a specific configuration file on the Switch.
Firmware Upgrade	This link takes you to a screen to upload firmware to your Switch.
Reboot System	This link takes you to a screen to reboot the Switch without turning the power off.
Tech-Support	This link takes you to a screen where you can download related log reports for issue analysis. Log reports include CPU history and utilization, crash and memory.

Table 30 Navigation Panel Links (Networked AV Mode) (continued)

#### 4.6.1 Tables and Lists

The Web Configurator tables and lists provide several options for how to work with their entries.

#### 4.6.1.1 Working with Table Entries

Tables have tool icons for working with table entries as shown next. You can select one or more entries, or select the check box in the heading row to select all entries. Use the tool icons to modify the selected entries.

#### Figure 65 Working with a Table

<mark>' Int</mark> erfac					
A	- 2	and a	in the	O AND'S	
	Index	IF Address	IF Subnel Mesk	CIV	Ispe
EF	- 9 -	1920403.015	255 255 255 0	1	Static
		(2.21.40.3	200 200 20 M	() ()	DEX.P

The following table describes the most common table icons.

Table 31 Common Table Icons

LABEL	DESC RIPTIO N
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click this to create a new entry or edit a selected entry. A configuration screen where you can add a new entry or modify the settings of the selected entry will open.
	In some configuration screens, the <b>Add/Edit</b> button is replaced by the <b>Edit</b> button. This means you can only edit the existing entries in the table.
Delete	To remove entries, select the entries and click <b>Delete</b> .

When viewing a list, you can click on an index number to view more details about the entry. If the list has more than one page, click the arrow button to navigate to different pages of entries.

	er of VLAI					
					TREAK	022.9
Index	V D	Nome	logged for	Unlagged Peri	tiopaut time	Manus
0	3	1		1.29	19:37:49	She fie
12	4	9			695-616	(helle)
7	200	315			0903300	31686
4	3 <b>4</b>				1.0. 22	Siche
-	SP.1	8			000057	Store
	÷	8			000032	Stoffe
-	10	10			030546	Static
11	11	26			00340	40:00
12	19	12			Catters	tiels:
0.0	15	12			0.002	Stolic
					= SPARE	4333

Figure 66 Working on a List

## 4.6.2 Change Your Password

After you log in for the first time, it is recommended you change the default administrator password. Click **SYSTEM** > Logins to display the next screen.

Figure 67 Change Administrator Login Password

Logins						
Administra	ator					
Old Passwor	rdi					
New Passwo	bed					
Retype to o						
	▲ P	lease record your i ou out if you have	new possword wheney forgotten your passwo	er you chang id.	ge it. The system will is	GR.
Edit Logina	i					
Login	User Name	Postword	Betype to confirm	Privilege		
1						
2						
3						
4						
		Ap	Goncel			

## 4.7 Save Your Configuration

When you are done modifying the settings in a screen, click **Apply** to save your changes back to the run-time memory. Settings in the run-time memory are lost when the Switch's power is turned off.

Click the **Save** link in the upper right of the Web Configurator to save your configuration to non-volatile memory. Non-volatile memory refers to the Switch's storage that remains even if the Switch's power is turned off.

Note: Use the  $\mathbf{Save}$  link when you are done with a configuration session.

## 4.8 Switch Lockout

You could block yourself (and all others) from managing the Switch if you do one of the following:

- 1 Delete the management VLAN (default is VLAN 1).
- 2 Delete all port-based VLANs with the CPU port as a member. The "CPU port" is the management port of the Switch.
- **3** Filter all traffic to the CPU port.
- 4 Disable all ports.
- 5 Misconfigure the text configuration file.
- 6 Forget the password and/or IP address.
- 7 Prevent all services from accessing the Switch.
- 8 Change a service port number but forget it.
- 9 You forgot to log out of the Switch from a computer before logging in again on another computer.

Note: Be careful not to lock yourself and others out of the Switch.

## 4.9 Reset the Switch

If you lock yourself (and others) from the Switch or forget the administrator password, you will need to reload the factory-default configuration file or reset the Switch back to the factory defaults.

See Section 3.1 on page 44 to see how to use the RESTO RE button to restore the factory default file.

#### 4.9.1 Reboot the Switch

Press the **RESET** button to reboot the Switch without turning the power off. See Section 3.3 on page 53 for more information about the LED behavior.

## 4.9.2 Reload the Configuration File

Uploading the factory-default configuration file replaces the current configuration file with the factorydefault configuration file. This means that you will lose all previous configurations and the speed of the console port will be reset to the default of 115200 bps with 8 data bit, no parity, one stop bit and flow control set to none. The password will also be reset to "1234" and the IP address to 192.168.1.1 or DHCPassigned IP.

To upload the configuration file, do the following:

- 1 Connect to the console port using a computer with terminal emulation software.
- 2 Disconnect and reconnect the Switch's power to begin a session. When you reconnect the Switch's power, you will see the initial screen.
- 3 When you see the message "Press any key to enter Debug Mode within 3 seconds ..." press any key to enter debug mode.
- 4 Enter atlc after the "Enter Debug Mode" message.
- **5** Wait for the "Starting XMODEM upload" message before activating XMODEM upload on your terminal.
- 6 After a configuration file upload, type atgo to restart the Switch.

Figure 68 Resetting the Switch: through the Console Port

```
Bootbase Version: V1.00 | 02/21/2016 15:43:29
RAM: Size = 1048576 Kbytes
FLASH: 64M
ZyNOS Version: V4.60(ABML.0) | 04/18/2017 11:41:8
Press any key to enter debug mode within 1 second.
.....
Enter Debug Mode
ras> atlc
Starting XMODEM upload (CRC mode)....
Cccccccccccccc
Total 393216 bytes received.
Erasing.
....
OK
ras> atgo
```

The Switch is now reinitialized with a default configuration file including the default password of "1234".

## 4.10 Log Out of the Web Configurator

Click **Logout** in a screen to exit the Web Configurator. You have to log in with your password again after you log out. This is recommended after you finish a management session for security reasons.

98

Figure 69 Logout button

## 4.11 Help

The Web Configurator's online help has descriptions of individual screens and some supplementary information.

Click the He lp icon on a Web Configurator screen to view an online help description (shown as below) of that screen.



≡ <u>ZY</u>	(EL	Bitersparen	ferrior enrese	Q	- 0	38		20	
100		DASHBOA	RD						
<ul> <li>Goning to Know Your Switch</li> <li>Howwork is a closer and Connection</li> <li>Web Configurator</li> <li>How How Arm</li> </ul>		and test de	isplay; general device information the grades describes the labels in fait so	2 ( 3) (S) (S)	.a syste	mresbu	ieo isa;	2	
New User Interface		LABEL	DESCRIPTION						
Buddhard States Galacter States		Folice Auto Refer	The DASHBOARD screen automatically refreshes every 30 sccenes. Click this to claable the sure refresh. Click Resume Auto Refresh to reactive						
MONTOR SYSTEM		and the second second							
IN FLORI		Part Status This a splays includual a art type, status, and dennication space instruction						di di El	
NETWORKS			10 C	e he volto information, Fer					
SECURITY	CF .		example. Box speed and part utilization. In Stocking mode, this displays the participatus of the slot (Switch) selected in the SLOT field						

# C HAPTER 5 Initial Setup Example

## 5.1 Overview

This chapter shows how to set up the Switch for an example network.

The following lists the configuration steps for the initial setup:


- Create a VLAN
- Set Port VID
- Configure Switch Management IP Address

## 5.1.1 Create a VLAN

VLANs confine broadcast frames to the VLAN group in which the ports belongs. You can do this with port-based VLAN or tagged static VLAN with fixed port members.

In this example, you want to configure port 1 as a member of VLAN 2.

Figure 71 Initial Setup Network Example: VLAN



1 Go to the SWIICHING > VIAN > VIAN Setup > Static VIAN screen. Click Add/Edit.

Static VLAN		Port Setup		
				Q Addtat
121	.VI0	Actve	Hone	
	+	CTONE D	1	

2 The following screen appears. Click the switch to set this VLAN to Active, enter a descriptive name in the Name field and enter "2" in the VIAN Group ID field for the VIAN2 network.

volivo Kome		CAN C DempleVLAH	]	
LON CO	oop 10	2		
Port		Control		Togging
•		Normal M		🔤 Ta Daga ng
1	Onomol	Q Ford	🔿 earbiddon	🗌 u togging i
2	Ottomol	() Fixed	() Ferbilden	🛛 tetogging
5	Ottenret	C fixed	<ul> <li>Torbadden</li> </ul>	🔤 Tri Pagging
4	O Normal	() Fixed	🔿 Torbidden	🖉 Tr Togang
5	O Norwal	C Read	<ul> <li>Portuistien</li> </ul>	🛛 D: Dooglag
κ.	Onerrol	<ul> <li>Flored</li> </ul>	🔿 Horbiddon	🛛 n nagý ng
$I_{i,j} = 0$	O Hamad	C.C.	Orobitto	
10	Onemal	C Find	O exhilden	🛛 u togý sg
54	O Normal	() Fixed	() terbilden	🖾 te to gying
			Apply	Oleon Concel

Note: The VIAN Group ID field in this screen and the VID field in the SYSTEM > IP Setup > IP Status screen refer to the same VLAN ID.

- 3 Since the VIAN2 network is connected to port 1 on the Switch, select Fixed to configure port 1 to be a permanent member of the VLAN only.
- 4 To ensure that VLAN-unaware devices (such as computers and hubs) can receive frames properly, clear the **Tk Tagging** check box to set the Switch to remove VLAN tags before sending.
- 5 Click **Apply** to save the settings to the run-time memory. Settings in the run-time memory are lost when the Switch's power is turned off.


#### 5.1.2 Set Port VID

Use PVID to add a tag to incoming untagged frames received on that port so that the frames are forwarded to the VLAN group that the tag defines.

In the example network, configure 2 as the port VID on port 1 so that any untagged frames received on

that port get sent to VLAN 2.





1 Go to the SWIICHING > VIAN > VIAN Setup > VIAN Port Setup screen.


ŵr -	Figures Chertin	9700 -	acceptor (s)	en Romen F	ман осного д	tristice.
<u>.</u>	Q:		(A)	- 20	123	0.0
÷	10	- The second sec	(41)		10	(ri.)
2			2.8	<b>v</b> )	0	0
î.	Ē.	<u> </u>	AU	÷.	10	- 63
£	C1		(74)	÷1	10	11
2	17	- Tr	108	v.	1	100
à	0	<u>.</u>	(A)	÷,	(C)	0
•	5			-1		$\checkmark$
$\sim$						

2 Enter 2 in the **PVID** field for port 1 and click **Apply** to save your changes back to the run-time memory. Settings in the run-time memory are lost when the Switch's power is turned off.

## 5.1.3 Configure Switch Management IP Address

If the Switch fails to obtain an IP address from a DHCP server, the Switch will use 192.168.1.1 as the management IP address. You can configure another IP address in a different subnet for management purposes. The following figure shows an example.





- 1 Connect your computer to any Ethernet port on the Switch. Make sure your computer is in the same subnet as the Switch.
- 2 Open your web browser and enter "setup.zyxel" or "192.168.1.1" (the default IP address) in the address bar to access the Web Configurator. See Section 4.2 on page 57 for more information.

Note: You can always use the domain name "setup.zyxel" to access the Web Configurator whether the Switch is using a DHCP-assigned IP or static IP address. This requires your PC to be directly connected to the Switch.

3 Go to the SYSTEM > IP Setup > IP Setup screen. Click Add/Edit.

it Selve					
an di Canaza,	hana				
ondr schebe	65 GM				
in a set of			Se 19		
			and the second second		
Interface/					
Parts (See					Question I an
f his face		e 2000-1	B ( Born March	.40	Question I

The following screen appears.

O DHCP Client	
Option-60 Class-ID	Zivel Corporation
Static P Address	Final collocato
IP Address IP Subnet Mask	192.168.2.1
VID 2	200,200,200,0
Apply	Clear Cancel

- 4 For the VIAN2 network, enter 192.168.2.1 as the IP address and 255.255.255.0 as the subnet mask.
- 5 In the VID field, enter the ID of the VLAN group to which you want this management IP address to belong. In this example, enter VLAN ID 2. This is the same as the VLAN ID you configure in the Static VIAN screen.
- 6 Click **Apply** to save your changes back to the run-time memory. Settings in the run-time memory are lost when the Switch's power is turned off.

## C HAPTER 6 Tuto ria ls


## 6.1 Overview


This chapter provides some examples of using the Web Configurator to set up and use the Switch. The tutorials include:

- How to Use DHCPv4 Snooping on the Switch
- How to Use DHCPv4 Relay on the Switch
- How to Use Auto Configuration through a DHCP Server on the Switch

## 6.2 How to Use DHC Pv4 Snooping on the Switch

You only want DHCP server **A** connected to port 5 to assign IP addresses to all devices in VLAN network (**V**). Create a VLAN containing ports 4, 5 and 6. Connect a computer **M** to the Switch for management.





The settings in this tutorial are as the following.

 Table 32
 Tutorial: Settings in this Tutorial

HOST	PORTCONNECTED	VIAN	PVID	DHC P SNO O PING PORT TRUSTED
DHCP Server (A)	4	1 and 100	100	Yes
DHCP Client (B)	5	1 and 100	100	No
DHCP Client (C)	6	1 and 100	100	No

1 Access the Switch through http://192.168.1.1 by default. Log into the Switch by entering the user name (default: **admin**) and password (default: **1234**).

2 Go to SWIICHING > VIAN > VIAN Setup > Static VIAN. Click Add/Edit.

Static VLAN	VLAN	Port Setup	GVRP	
				0 Add/Edit
	VID	Active	Nome	
	1	ON	1	

3 The following screen appears. Enable the switch button to set this VLAN to **ACTIVE**. Create a VLAN with ID of 100. Add ports 4, 5 and 6 in the VLAN by selecting **Fixed** in the **Control** field as shown.

De-select  $\mathbf{T}_{\mathbf{X}} \mathbf{T}_{\mathbf{A}} \mathbf{g} \mathbf{g} \mathbf{i} \mathbf{g}$  because you do not want outgoing traffic to contain this VLAN tag.

 $\mathsf{Click}\,\mathbf{Apply}.$ 

activo.		(at (i)	1	
Name VLAN CA	ap D	VLAN100		
		1		
Port		Control		Togging
-		Nonicel v		🛃 1x Taggingi
1	Q Normal	🗇 -band	Crechickien	🔽 mingging
2	O Normal	O Fixed	O Porbidden	🖾 to torgainer
3	O Normal	C food	C Participien	🛛 1. Toggingi
4	🔿 Normal	Onced	O Forbidden	🗌 🛛 Taggingi
6	🔿 Normal	O Real	C Barbidden	🗆 1x Tagalog
A	O Normal	Q stand	O Hochickion	🗌 in logging.
1	O Normal	O fixed	C Forbickion	🖬 to torganize
4	O Normal	<ul> <li>Dowt</li> </ul>	O Particidam	🛃 1a Taggangi
5	O Normal		Corbidden	🛃 tx Tagging
$\sim$				
50	O Namal	C Cover	O Particidades	🖾 1x Toggingi
54	O Normal		O Forbidden	🛃 tx Tagana
			Apply	cierre cancel

4 Go to SWIIC HING > VIAN > VIAN Setup > VIAN Port Setup, and set the PVID of the ports 4, 5 and 6 to 100. This tags untagged incoming frames on ports 4, 5 and 6 with the tag 100. Click Apply.

Piet :	i do goriev. Di theo de	EVIS.		olode night	MAN Is not of	interio.
3			100	۷.		- E
1	1	- TE	2011	v -	E.	11
2,5	Щ.		AL I	×	0	3
3	14	<u>1</u>	4		<u>D</u> .	<u>11</u>
	Щ.	in-		×.		<b>—</b>
		200	4	×.	C:	άī
5	Ξ.	wo	- AU	÷.	03	
	14	T	<b>M</b>	×.	10	11
	$\sim$		$\sim$	$\leq$		$\sim$

5 Go to SEC URITY > IPv4 Source Guard > DHCP Snooping > DHCP Snp. Setup, activate and specify VLAN 100 as the DHCP VLAN as shown. Click Apply.

IP requests from VLANs you enable on the SEC URITY > IPv4 Source Guard > DHCP Snooping > DHCP Snp. VIAN Setup screen will be broadcast to the DHCP VLAN you set on this screen, which is VLAN100 in this example.

DECP Sep. Sinks	BHCP Snp: Setup	DHCP Snp. Port 5	etup
DILCE Shooping Sele	¢.		
écta:	CITE 1	)	
DI DA VICA	0 100		
Dolobase			
Acarticat			
$(I-a) = (I-b) \cdot (a \cdot b)$	19.04	10.05	
webs for an increase.	300 8	seconda	
Tenew 2000 looks op	IN		Kenner
	Aggdy (2)	line .	

6 Go to SEC URITY > IPv4 Source Guard > DHCP Snooping > DHCP Snp. Port Setup. Select Trusted in the Server Trusted state field for port 4 because the DHCP server is connected to port 4. Keep ports 5 and 6 Untrusted because they are connected to DHCP clients. Click Apply.

BRCF Ster, Slubs	UNCY Stips Selup	DHCF Snp. Fort Salop	UNCE Stips 1
201	Second to test state.		
8	Unitation (*)		
	Industry w	d	
2	Uninsited M	a	
9	Distances +	<u>n</u>	
	fux ne 👘	<del>a</del>	3
- 5	United yet wi	9	
1	Unhanes of	<u>n</u>	
100	- normenia	"	
$\sim$			$\sim$
	(Apply)	Sancel	

7 Go to SEC URITY > IPv4 Source Guard > DHCP Snooping > DHCP Snp. VIAN Setup, show VLAN 100 by entering 100 in the VIAN Search by VID field and click Search.

Select Yes in the Enabled field of the VLAN 100 entry shown in the search result. Click Apply.

This enables DHCP snooping on VLAN100 (and other VLANs you enabled on this screen).

If you want the Switch to add more information in the DHCP request packets, such as source VLAN ID or system name, you can select an **Option82 Profile** in the entry. The Switch will add DHCP option 82 information to DHCP requests that the Switch relays to a DHCP server for the specified VLAN.

HCP Snp. Status	DHCP Snp. Setup	DHCP sop. Fort Setup	DHCP Snp. VLAN Selup
V.ANJeach by MD.	200	Secrut	
The Romber of Vis	N 2		
V D		incible:	Option 32 holl +
		the w	-
-	-	NUCK.	
199	1	Distr.	(w)
			$= + r_{024} (\frac{1}{2} \cdots (n_{i}) + \cdots )$
	C		
		Sector Second	

- 8 Connect your DHCP server to port 4 and a DHCP client (an AP, for example) to either port 5 or 6. The AP should be able to get an IP address from the DHCP server. If you put the DHCP server on port 5 or 6, the computer will NOT be able to get an IP address.
- 9 Click Save at the top right of the Web Configurator to save the configuration permanently.



10 To check if DHCP snooping works, go to SEC URITY > IPv4 Source Guard > IP Source Guard, you should see an IP assignment with the type DHCP. Snooping as shown.

IP Source	Guard Stat	ic Bindir	ig i			
Index	P Arkineo.	VIAN	MAC Address	Port	Leose	Type
1	1921-021-0	IW.	80,880,860,860,860,9	5	0.231/4003	DECP- Stroophip

You can also use telnet. Use the command "show dhcp snooping binding" to see the DHCP snooping binding table as shown next.

sysname# sh	now dhcp sno	ooping binding					
Ma	acAddress	IpAddress	Lease	Туре	VLAN	Port	
		192.168.2.178	0d23h59m20s	dhcp-snooping	100	5	
Total num	nber of bind	dings: l					

## 6.3 How to Use DHC Pv4 Relay on the Switch

This tutorial describes how to configure your Switch to forward DHCP client requests to a specific DHCP server. The DHCP server can then assign a specific IP address based on the information in the DHCP requests.

### 6.3.1 DHC P Re lay Tuto rial Introduction

In this example, you have configured your DHCP server (192.168.2.3) and want to have it assign a specific IP address (say 172.16.1.18) to DHCP client **A** based on the system name, VLAN ID and port number in the DHCP request. Client **A** connects to the Switch's port 2 in VLAN 102.




Figure 75 Tutorial: DHCP Relay Scenario

### 6.3.2 Create a VIAN

Follow the steps below to configure port 2 as a member of VLAN 102.

- 1 Access the Web Configurator through the Switch's management port.
- 2 Go to SYSTEM > Switch Setup and set the VIAN Type to 802.1Q. Click Apply to save the settings to the run-time memory.

an goo	OPPORT SECONDER
age Control Protocol Transporency	() on
WAC Address Learning	
Appropriate and	NO DOCTOR
ASP Aging Time	
og og inne	50 2000C
GAR <sup>a</sup> Timer	
Added for each	80 In Becords
bezve Diner	000 millesconds
letter Al Ther	1000 nusations

3 Go to SWITCHING > VIAN > VIAN Setup > Static VIAN. Click Add/Edit.

late VDAN	YU	N full Selver CVIP		
			AddEd:	· Catala
0	V.D.	Aster Name		
- Ci - L	12			

4 The following screen appears. Enable the switch button to set this VLAN to Active. Enter a descriptive name (VLAN 102 for example) in the Name field and enter "102" in the VIAN Group ID field.

una	90510	102		
rwi		Gorinal		Pogging
		Marrie W.		📑 Te Tagger gr
1	<b>O</b> termo	Ceard	C entrainer	🔯 ta taga ng
236	Querner.	Orad	C to Grouper	iii tetege eg
3	Ottering	C fixed	Citologia	📓 fefegging
9	O Hama	C Freed	() Torbidden	🖬 Fritzagina
5	O Norma	C Ford	C) Rochiscien	📓 Is Ioan na
X	O hermal	Dead 1	() estimation	📓 h 1030 ° ĝ .
e.) -	O Heane	Chived	One Calden	Si tetagang
÷	Q Henry	C fixed	C TOURDAY	Trilvyg fy
è				
63	Otherwood	Ctoud	() helyddar	Si le lo gy i g
55	Ortenne	CT red	Citorunder	🛱 tertogengi
54	Q Name:	_) Fixed	Q fotidate	📴 To Telagina

- 5 Set port 2 to be a permanent member of this VLAN by selecting **Fixed** in the **Control** field.
- 6 Clear the Tx Tagging check box to set the Switch to remove VLAN tags before sending.
- 7 Click **Apply** to save the settings to the run-time memory. Settings in the run-time memory are lost when the Switch's power is turned off.
- 8 Go to VIAN > VIAN Setup > VIAN Port Setup. Enter "102" in the PVID field for port 2 to add a tag to incoming untagged frames received on that port so that the frames are forwarded to the VLAN group that the tag defines.

665	teranov Dorach	<b>261</b>	Recepted de France Espe	VIAN beckers	Solution
<b>3</b> 20	44		- 10	-111	4.3
1		1	<u>×</u>	#	10
<b>8</b> 2	<u>, (2</u>	102		,E]	(E)
${\mathbb R}^{n}_{i}$	Ц	0	4 4	4	Ú.
÷	Ξ.	0.	[si] (s	Ē	10
\$	Ō	11	(AL	1	10
8	0	[i: ]		0	Ö
21	11		10 -		
$\sim$		7		$\sim$	
		. <u>18</u> – 1			

- 9 Click Apply to save your changes back to the run-time memory.
- 10 Click the Save link in the upper right of the Web Configurator to save your configuration permanently.

### 6.3.3 Configure DHC Pv4 Re lay

Follow the steps below to enable DHCP relay on the Switch and allow the Switch to add relay agent information (such as the VLAN ID) to DHCP requests.

1 Click NEIWORKING > DHCP > DHCPv4 Relay > DHCP Smart Relay. Enable the Active switch button.

Concession in succession				
	-Auto-	AND THE REAL PROPERTY	Autor Incom	Land Internet

- 2 Enter the DHCP server's IP address (192.168.2.3 in this example) in the **Remote DHCP Server 1** field.
- 3 Select default1 or default2 in the Option 82 Profile field.
- 4 Click **Apply** to save your changes back to the run-time memory.
- 5 Click the Save link in the upper right of the Web Configurator to save your configuration permanently.
- 6 The DHCP server can then assign a specific IP address based on the DHCP request.

#### 6.3.4 Trouble shooting

Check client **A**'s IP address. If it did not receive the IP address 172.16.1.18, make sure:

- 1 Client **A** is connected to the Switch's port 2 in VLAN 102.
- 2 You configured the correct VLAN ID, port number and system name for DHCP relay on both the DHCP server and the Switch.
- 3 You clicked the **Save** link on the Switch to have your settings take effect.

# 6.4 How to Use Auto Configuration through a DHCP Server on the Switch

Follow the steps below to set up configurations on a DHCP server, TFTP server, and the Switch, so you can load an auto configuration file automatically from a TFTP server when you reboot the Switch.

Note that you can set up a DHCP server and TFTP server either on the same device or different devices. Also, make sure the Switch can communicate with the TFTP server.

Note: Steps order could vary according to different programs you use.

Note: You need to set up configurations on a DHCP server and TFTP server first to use auto configuration.

#### Setting up a DHCP Server

- 1 Set up a dynamic IP addresses pool so the DHCP server will assign an IP address to the Switch in that range.
- 2 Set up a TFTP server IP address, so the Switch will know where to load the auto configuration file.
- 3 Set up the filename of the auto configuration file, so the Switch will know which file to load when you reboot the Switch.
  - Enter the filename of an auto configuration file. The Switch will load this auto configuration file when rebooting with DHCP option 60 disabled.
  - If you want to load the auto configuration file with DHCP option 60 enabled and a Vendor Class Identifier assigned when you reboot the Switch, follow the instruction below. Otherwise, skip this step.

Enter the filename of an auto configuration file. Set up a Vendor Class Identifier. To have the Switch load this auto configuration file, two conditions listed above must be met. Please refer to the following steps to see how to set up a Vendor Class Identifier on the Switch.

#### Setting up a TFIP Server

- 1 Select a directory on the TFTP server.
- 2 Put the configuration files in that directory.

#### Setting Up the Switch

Open the Web Configurator. Go to the MAINTENANCE > Configuration > Auto Configuration screen.
 Figure 76 Tutorial: Auto Configuration Screen

Avto Configuration	
Rede	Nerv
Cloie	None
Hivi an e	
	( <b>1999</b> )
Asthet	C I DH P
Macile.	DUCE Y
DECEMBER 1	1
L TIPA URI	
	Apply Cancel

2 Enable the switch button in the Active field to enable auto configuration. Select DHCP in the Mode field, and enter the VLAN ID where the DHCP server belongs to in the DHCP VIAN ID field. Click Apply to save your changes.

	Apply	Coppel	
10.12.38			
DECEMBER 15	1		
Neco	DHOP WI		
extee	(GN ())		
Freedow			
51515	14916 (		
Nece	None		
Auto Configurat	1011		

Figure 77 Tutorial: Enable Auto Configuration

3 Go to the SYSTEM > IP Setup > IP Setup screen. Click the Add/Edit button in the IP Interface table to open the configuration screen.

#### 4 Select DHCP Client.

5 If you want to load the auto configuration file with DHCP option 60 enabled and a Vendor Class Identifier assigned when you reboot the Switch, follow the instruction below. Otherwise, skip this step. In the SYSTEM > IP Setup > IP Setup > Add/Edit screen, select the check box in the Option-60 field. Enter a Vendor Class Identifier in the Class-ID field, and specify the VLAN interface in the VID field. In this example, we use "ZyxelCorp" and VID 1. Click Apply.


Figure 78	Tutorial: Enable DHCP Client & Option 60

O DHCP Client Cotion 40	Z	
Classifi	Zyrel Corp	
O Statio IF Address		
P Address		
P Subnot Mask		
VD 1		
Apply	Choor	Centred

- 6 You need to save the current configuration in a configuration file, so the Switch will load the auto configuration file from the TFTP server automatically when rebooting. Go to the MAINTENANCE> Configuration > Save Configuration screen. Click the Config 1, Config 2, or Custom Default button.
- 7 Click the same button in the **MAINTENANCE** > **Reboot System** screen to reboot the Switch, and load the auto configuration setting as configured before. For example, if you save the auto configuration setting to **Config 1**, you need to click the **Config 1** button in the **Reboot System** screen.

Figure 79 Tutorial: Sc	ave Configuration	-
Scree Cooligoration		
Savo Configuration as	Canifer 1 Cantig 2 Cantom Detault	
Figure 80 Tutorial: Sc	ave Configuration and Reboo	ot System
Rebool System		
Corent Contigoret on is	Comparation 1	
rebeal System with	config 2 Featury Dafaal	
	Custom Default	

- 8 Go to the MONTIOR > System Log screen to see if auto configuration was performed successfully.



12	012-11 01000004:042 13 Oulling SKD Opeale Saller	
10	072 TE TECO-04-022 ES palter Vient 916-8.8 stilled	
120	022 (1 11:00:03:038 10 ovidth) 038 Coury Foiled	
14	3.25-31-31 000024038. Other heatings have strengthen added in heating by ad-	Macrosco B
	021-01-01 found of Mark weathers with the title and fare from a firm when	$a^{-1}$ for $1.63$
12	427-01-01990-01:202 IN performitions consider term admin logic	
191	1927-01-017905-07:595 IR interface. Rout 14 Airs op 1.8/F	
1	MAX-01-017000005050778 evenerg BTOP some consideration is some eted on	A TP AGE
	012 (1 01700/01:512 IN reaters kits concisive cycles contiguration fur	Sectored by
3.7	dië in 18500-01-525 CB interlece: Dool 14 diek court	
1.	012-11-01200-00:518-19 perform See, plan, sub- realizable resulter con-	
$\pm 2$	072 (1 01000)01:418 26 introduce: Port 24 time op 1575	
432	022/01/01/00/01/038 in avoider Starr Little oute confidenties	
14	022-11-11-005-022 RD mystems Synthesis et al. ()	n an
32	2021-11-11-2010-01-11-2010-01-11-2010-01-11-2010-01-2010-01-2010-01-2010-01-2010-01-2010-01-2010-01-2010-01-20	64,779,7296
36	027-01-01700:07:072 ND systems insten hts teset den to a throughput ap	676576
33	437-01-01740:00:7.15 KD stylings Gather rebots	
33.	45.4-01-01700cub:405 FR archentication: Sonan e coest autrin logit	
12	ALZ CL CICUD: 03: IX myltone XIT Uscate Tailed	
	dir il (1500:05:623 IS pallone Creck d.1.1.0 Talled	
22)	olg ti (1900-06:575-19 ovitch- BCS (easy Failed	160-101-1283
	2012 (1. 11900)Opp062 El pysicer Meta teo into ane cate inter a comunication 2023 (1. 11900)Opp072 Al mastra de 1990	No desident.
$\frac{7}{24}$		S100 (0.5)
S2.	022-01-01-000000485 is in the normal sector of the light op late 022-01-01-01-0000000 is in accordance sector according to the figure the	
21	are to reach the reaction of the Association of the second contraction of the second sec	
$\frac{60}{23}$	HIZ - SEVENUSSA SEN AN AVAILAR DISTON NUM ATAUT NECT-11-11-11-100:01:515 IN RECEARD TEAMS I TAU MARANAM VISION/NOF.200111	01/19/20

9 Check the screens to see if it is the configuration file you want to load. If it is not, go through the steps above to check your configurations. If it is, click **Save** at the top right corner of the Web Configurator to save the configuration permanently.

# C HA PTER 7 DA SHBO A RD

This chapter gives a quick introduction on the **DASHBOARD** screen.

The DASHBOARD screen automatically appears after you log into the Web Configurator.

## 7.1 New User Interface

With ZyNOS 4.80 and later, the Web Configurator's user interface is restructured. In the new **DASHBOARD** screen, you can easily monitor the system status with the following tools (see DASHBOARD for more information):

- Visualized **Port Status** section with clickable port icons that provide information of that port and an ON/OFF switch button to enable/disable the port (see Port Status).
- Visualized Cloud Control Status section that displays the NCC connection status using three connection-stage circles.
- Clickable hardware status monitoring sections that directly link to the **MONITOR** > System Inform a tion screen.
- Editable Quick Link section which provides shortcuts to configuration screens that you might frequently use (See Quick Links to Use).
- A Search tool on the upper right of the screen that you can use to search for the configuration screens you want to access (see Web Configurator Layout).

The left navigation panel is also restructured into task-based UI. You can display the sub-menu in the **MONTIOR, SYSTEM, PORT, SWITCHING, NETWORKING, SECURITY**, or the **MAINTENANCE** section by clicking their icons. See Web Configurator Layout for more information.

Find the latest release note in: **Download Library** on www.zyxe l.com.

## 7.2 DASHBOARD

This screen displays general device information, system status, system resource usage, and port status.

This guide uses XGS2220-54FP screens as an example. The screens may vary slightly for different models.

Click **DASHBOARD** in the navigation panel to open the following screen.




Figure 82 DASHBOARD (example PoE model)

#### Table 33 DASHBOARD

LABEL	DESC RIPTIO N				
Pause Auto	The <b>DASHBOARD</b> screen automatically refreshes every 30 seconds.				
Refresh	Click this to disable the auto refresh. Click <b>Resume Auto Refresh</b> to enable.				
Port Status	This displays individual port type, status, and connection speed of the Switch.				
	Click on a port to open the port's status panel. Use the status panel to enable/disable a port and view its basic information. For example, link speed and port utilization.				
	Note: The port status may vary for non-PoE and PoE models.				
System Informatio	n				
System Name	This field displays the name used to identify the Switch on any network.				
System This field displays the geographic location name you set for the Switch.					
Boot Version	This field displays the version number and date of the boot module that is currently on the Switch.				
ZyNOS F/W Version	This field displays the version number and date of the firmware the Switch is currently running.				
System Time	This field displays the current date and time in the UAG. The format is mm/dd/yyyy hh:mm:ss.				
System Uptime	This field displays how long the Switch has been running since it last restarted or was turned on.				
Serial Number	This field displays the serial number of this Switch. The serial number is used for device tracking and control.				
Hardware Version	This field displays the hardware version of the Switch.				
System MAC Address	This field displays the MAC address of the Switch.				
Registration MAC Address         This is the MAC address reserved for NCC registration. Use this MAC address to register the on NCC.					

XGS2220 Series User's Guide

LABEL	DESC RIPIIO N						
Cloud Control	This field displays:						
Status	<ul> <li>The Switch Internet connection status.</li> <li>The connection status between the Switch and NCC.</li> <li>The Switch registration status on NCC.</li> </ul>						
	Mouse over the circles to display detailed information.						
	To pass your Switch management to NCC, first make sure your Switch is connected to the Internet. Then go to NCC and register your Switch.						
	Click Cloud Control Status or the switch button to go to the SYSTEM > Cloud Management screen. You can enable/disable NCC Discovery or view the NCC connection status in the Cloud Management screen.						
	l. Inte me t						
	Green – The Switch is connected to the Internet.						
	Orange – The Switch is not connected to the Internet.						
	2. Ne bula						
	Green – The Switch is connected to NCC.						
	Orange – The Switch is not connected to NCC.						
	3. Registration						
	Green – The Switch is registered on NCC.						
	Gray – The Switch is not registered on NCC.						
	Note: All circles will gray out if you disable Nebula Discovery.						
	Note: If a circle displays orange or gray, hover the mouse over the circle to check the diagnostic message.						
NCC Discovery	This displays if NCC discovery is enabled on the Switch. The Switch will connect to NCC and change to the NCC management mode if it:						
	<ul><li>is connected to the Internet.</li><li>has been registered on NCC.</li></ul>						
CPU Usage	This displays the current CPU usage percentage.						
	Click to go to the MONTIOR $>$ System Information screen to check the detailed information.						
Memory Usage	This displays the current RAM usage percentage.						
	Click to go to the MONITOR > System Information screen to check the detailed information.						
PoE Usage	For PoE models.						
	This field displays the amount of power the Switch is currently supplying to the connected PoE- enabled devices and the total power the Switch can provide to the connected PDs. It also shows the percentage of PoE power usage.						
	When PoE usage reaches 100%, the Switch will shut down PDs one-by-one according to the PD priority which you configured in <b>PORT</b> > <b>PoE Se tup</b> > <b>PoE Se tup</b> .						
Temperature	The Switch has temperature sensors that are capable of detecting and reporting if the temperature rises above the threshold.						
	This displays the Switch's current device temperature level.						
	Click to go to the <b>MONTIOR</b> > System Information screen to check the detailed information.						

Table 33 DASHBOARD (continued)


LABEL	DESC RIPTIO N
Fan	Each fan of the Switch has a sensor that is capable of detecting and reporting if the fan speed falls below the threshold.
	This displays the Switch's overall fan speed status.
	Click to go to the MONTIOR $>$ System Information screen to check the detailed information.
Quick Link	This section provides shortcut links to specific configuration screens.
	Click the edit button to choose the quick links to show.

Table 33 DASHBOARD (continued)

### 7.2.1 Port Status

The **Port Status** section provides visualized port status for monitoring. Each port displays a status color determined by the their link speed.

Figure 83 Port Status (example PoE model)



Click on a port to display a port's status pane.

Figure 84 Port details Pane (example PoE mode
---

Port \$1	, ( 0 N ( )
PeC	Power Orale
Port Nome	
Link	19
status	HORWARDINE:
PVC Drow	0.0%
Utilization	0.1%(D/10.0%(RM)
Opline	36239545

The port details pane includes the **PowerCycle** button for PoE models (turn the power off and then back on again), displays information such as link speed, status, PoE draw (for PoE models), port utilization, up time and has an ON/OFF switch button. Click the switch button to enable/disable the port.

## 7.2.2 Quick Links to Use

The quick links in the Quick Link section provide shortcuts to specific configuration screens. You can use the quick links to directly access the screens that you would frequently use. You can also decide which quick links to be put on the DASHBOARD screen using the Edit button.

Figure 85	Quick Links	(example PoE model)	
rig ule 00			

Quick Link			
P Stofus		Link Aggregation Status	
Neighbor		Pel Statux	
Port Status		SHMP Stotur	0
Sterm Control	0000	System Log	
VLANGetup			

The setup panel displays after you click the **Edit** button.

 Figure 86
 Quick Link Selection (example PoE model)

Gulck Unit (%/10)		
DHCP Relay	Diognostic	🔲 502.1x Status
🗌 Kawaboo ping	E MAR	💌 🛤 scholter.
🗌 IP Toole	Pvs Configuration	Enk Aggregetion States
MAC Table	Meighbor	💽 PoF Status
Peri Stolos	🗆 Perl Minoring	El Remole Access Centrel
Routing Table	Service Access Control	SNMP Status
ziom control	□ are	🗌 zystem mito
🖉 System Log	Pact-Support	VEAN Seriop
Infe: Mardmum 16 here: can be selected		

Select the quick links you want and click **Apply**. The selected quick links will be displayed in the **Quick Link** section on the **DASHBOARD** screen.

# C HAPTER 8 MONITOR

The following chapters introduces the configurations of the links under the **MONTIOR** navigation panel.

Quick links to chapters:

- ARP Table
- IP Table
- IPv6 Neighbor Table
- MAC Table
- Neighbor
- Path MTU Table
- Port Status
- Routing Table
- System Information
- System Log

# C HAPTER 9 ARP Table

## 9.1 ARP Table Overview

This chapter introduces the ARP Table.

Address Resolution Protocol (ARP) is a protocol for mapping an Internet Protocol address (IP address) to a physical machine address, also known as a Media Access Control or MAC address, on the local area network.

An IP (version 4) address is 32 bits long. In an Ethernet LAN, MAC addresses are 48 bits long. The ARP Table maintains an association between each MAC address and its corresponding IP address.

## 9.1.1 What You Can Do

Use the ARP Table screen (Section 9.2 on page 123) to view IP-to-MAC address mappings.

### 9.1.2 What You Need to Know

When an incoming packet destined for a host device on a local area network arrives at the Switch, the Switch's ARP program looks in the ARP Table and if it finds the address, it sends it to the device.

## 9.2 Viewing the ARP Table

Use the ARP table to view IP-to-MAC address mappings and remove specific dynamic ARP entries.

Click **MONITOR** >  $ARP T_{a b le}$  in the navigation panel to open the following screen.

Figure 8	7	MONITOR > AF	RP Table
----------	---	--------------	----------

9						
ARP Table						
Condition	O P Add O P Add O Port		0.0.0.0 Flush Concel		el	
Index	IP Address	MAC Address	VID	Port	Age(1)	Туре
1.04955	IF PACALERS	ALTER AND ALTER	TIM	1.011	section in the	1315-00
1	192.168.2.1	4c to 5(3e cof (39:20	1	22	215	dynamic
2	192.168.2.115	be 59:11:cbod3ni5	1	CFU	0	ingfic
3	192.168.2.241	001300505878044	1	18	125	dynamia

LABEL	DESC RIPTIO N
Condition	Specify how you want the Switch to remove ARP entries when you click <b>Flush</b> .
	Select All to remove all of the dynamic entries from the ARP table.
	Select <b>IP Address</b> and enter an IP address to remove the dynamic entries learned with the specified IP address.
	Select Port and enter a port number to remove the dynamic entries learned on the specified port.
	You can enter multiple ports separated by (no space) comma (,) or hyphen (-) for a range. For example, enter "3-5" for ports 3, 4, and 5. Enter "3,5,7" for ports 3, 5, and 7.
Flush	Click <b>Flush</b> to remove the ARP entries according to the condition you specified.
Cancel	Click Cancel to return the fields to the factory defaults.
Index	This is the ARP table entry number.
IP Address	This is the IP address of a device connected to a Switch port with the corresponding MAC address below.
MAC Address	This is the MAC address of the device with the corresponding IP address above.
VID	This field displays the VLAN to which the device belongs.
Port This field displays the port to which the device connects. <b>CPU</b> means this IP addre management IP address.	
Age(s)	This field displays how long (in seconds) an entry can still remain in the ARP table before it ages out and needs to be relearned. This shows ${\bf 0}$ for a static entry.
Туре	This shows whether the IP address is dynamic (learned by the Switch) or static (manually configured in SYSTEM > IP Se tup > IP Se tup or NETWORKING > ARP Se tup > Static ARP).

Table 34 MONITOR > ARP Table

# C HAPTER 10 IP Table


This chapter introduces the IP table screen.

## 10.1 IP Table Overview

The **IP Table** screen shows how packets are forwarded or filtered across the Switch's ports. When a device (which may belong to a VLAN group) sends a packet which is forwarded to a port on the Switch, the IP address of the device is shown on the Switch's **IP Table**. The **IP Table** also shows whether the IP address is dynamic (learned by the Switch) or static (belonging to the Switch).

The Switch uses the IP Table to determine how to forward packets. See the following figure.

- 1 The Switch examines a received packet and learns the port from which this source IP address came.
- 2 The Switch checks to see if the packet's destination IP address matches a source IP address already learned in the IP Table.
  - If the Switch has already learned the port for this IP address, then it forwards the packet to that port.
  - If the Switch has not already learned the port for this IP address, then the packet is flooded to all ports. Too much port flooding leads to network congestion then the Switch sends an ARP to request the MAC address. The Switch then learns the port that replies with the MAC address.
  - If the Switch has already learned the port for this IP address, but the destination port is the same as the port it came in on, then it filters the packet.



XGS2220 Series User's Guide

# 10.2 Viewing the IP Table

Click  $MONTIOR > IP T_{a b le}$  in the navigation panel to display the following screen.

Figure 89	MONITOR > IP Table
-----------	--------------------

Table				
Index.	IF Address	V10	Part	Тура
I.	122.168.2.1	I.	22	Dynamic
2	122.178.2.11s	I.	CPU	Storika
5	1923/802321	I.	15	Dynamic
4	192,170,3,115	100	<7P0	Stario
Adding by:	IP VID	Port		

Table 35 MONITOR > IP Table

IABEL	DESC RIPTIO N
Index	This field displays the index number.
IP Address	This is the IP address of the device from which the incoming packets came.
VID	This is the VLAN group to which the packet belongs.
Port	This is the port from which the above IP address was learned. This field displays <b>CPU</b> to indicate the IP address belongs to the Switch.
Туре	This shows whether the IP address is $\mathbf{Dynamic}$ (learned by the Switch) or Static (belonging to the Switch).
Sorting by	Click one of the following buttons to display and arrange the data according to that button type. The result is then displayed in the IP table.
IP	Click this button to display and arrange the data according to IP address.
VID	Click this button to display and arrange the data according to VLAN group.
Port	Click this button to display and arrange the data according to port number.

# C HAPTER 11 IPv6 Neighbor Table

## 11.1 IPv6 Neighbor Table Overview

This chapter introduces the IPv6 neighbor table.

An IPv6 host is required to have a neighbor table. If there is an address to be resolved or verified, the Switch sends out a neighbor solicitation message. When the Switch receives a neighbor advertisement in response, it stores the neighbor's link-layer address in the neighbor table. You can also manually create a static IPv6 neighbor entry using the **SYSTEM** > **IPv6** > **IPv6** Neighbor Setup screen.

When the Switch needs to send a packet, it first consults other table to determine the next hop. Once the next hop IPv6 address is known, the Switch looks into the neighbor table to get the link-layer address and sends the packet when the neighbor is reachable. If the Switch cannot find an entry in the neighbor table or the state for the neighbor is not reachable, it starts the address resolution process. This helps reduce the number of IPv6 solicitation and advertisement messages.

## 11.2 Viewing the IPv6 Neighbor Table

Use this screen to view IPv6 neighbor information on the Switch. Click **MONITOR** > IPv6 Neighbor Table in the navigation panel to display the screen as shown.

bor Table				
Address	MAC	Status	Type	Interface
te80::39thcf44/b86/78e3	90:2b:34.b b:70:04	5	D	VLANT
fe8014087.sr9odt15e71221 9	dc:4c:3e:40:ec:47	D	D	VLANT
1e80:5072:4221.9:dd3:c73	50(81):40(97):99:04	8	D	VLANT
fe80:dxe99:11fffecbcz365	bc:99:11:cboq2:65	R	L.	VLAN1
Address MA	D interface			
	Address 1680::3Pft:of44:088:78e3 1980::4087:99:00:1597:221 9 1980::5072:4221:90:03:c73 1980::5072:4221:90:03:c73 1980::50979:11ft:fecb:s2343	Address         MAC           16800:3Pftbcf44/b08/78e3         P0(2bc34/b07/0004)           16800:4087/s9Podt1597/221         dcc4cc3ec40cecc67           9         dcc4cc3ec40cecc67           16800:507204221:90d03co73         50(81):40(97)99:04           16800:be999:11ftflecbcc245         bcc999:11:cbccd245	Address         MAC         Shoke           1660::3Pft:of44:b86:78e3         P0c2b:34:b b:70:o4         5           1680::4087:w9odt15e7:221         dc:4c:3e:40:ec:67         D           0         dc:4c:3e:40:ec:67         D           1680::5072:4221:9dd3:o73         50:91:40:97:99:04         3           1e80::be?99:11ftfecbox345         bc:99:11:cbox3245         R	Address         MAC         Stellus         Pype           1660::3Pft:of44:b66:78e3         P0:2b:34:b6:70:o4         5         D           1660::4087:se9odt1567:221 -e         dc:4c:3e:40:ec:67         D         D           1660::5072:4221:9dd3::o73         50:91:40:97:99:04         3         D           1660::be?99:11ftfectbox245         bc:99:11:cbox245         R         L

Figure 90 MONITOR > IPv6 Neighbor Table

IABEL	DESC RIPIIO N
Index	This field displays the index number of each entry in the table.
Address	This field displays the IPv6 address of the Switch or a neighboring device.
MAC	This field displays the MAC address of the IPv6 interface on which the IPv6 address is configured or the MAC address of the neighboring device.
Status	<ul> <li>This field displays whether the neighbor IPv6 interface is reachable. In IPv6, "reachable" means an IPv6 packet can be correctly forwarded to a neighbor node (host or router) and the neighbor can successfully receive and handle the packet. The available options in this field are:</li> <li>reachable (R): The interface of the neighboring device is reachable. (The Switch has received a response to the initial request.)</li> <li>stale (S): The last reachable time has expired and the Switch is waiting for a response to another initial request. The field displays this also when the Switch receives an unrequested response from the neighbor's interface.</li> <li>delay (D): The neighboring interface is no longer known to be reachable, and traffic has been sent to the neighbor recently. The Switch delays sending request packets for a short to give upper-layer protocols a chance to determine reachability.</li> <li>probe (P): The Switch is sending request packets and waiting for the neighbor's response.</li> <li>invalid (IV): The neighbor address is with an invalid IPv6 address.</li> <li>unknown (?): The status of the neighboring interface cannot be determined for some reason.</li> <li>incomplete (I): Address resolution is in progress and the link-layer address of the neighbor has not yet been determined. The interface of the neighboring device did not give a complete</li> </ul>
Туре	response. This field displays the type of an address mapping to a neighbor interface. The available options in this field are:
	<ul> <li>other (O): none of the following type.</li> <li>local (L): A Switch interface is using the address.</li> <li>dynamic (D): The IP address to MAC address can be successfully resolved using IPv6 Neighbor Discovery protocol. Is it similar as IPv4 ARP (Address Resolution protocol).</li> <li>static (S): The interface address is statically configured.</li> </ul>
Interface	This field displays the ID number of the IPv6 interface on which the IPv6 address is created or through which the neighboring device can be reached.
Sorting by	Click one of the following buttons to display and arrange the data according to that button type. The result is then displayed in the summary table above.
Address	Click this button to display and arrange the data according to IPv6 address.
MAC	Click this button to display and arrange the data according to MAC address.
Interface	Click this button to display and arrange the data according to IPv6 interface.

Table 36 MONITOR > IPv6 Neighbor Table

# CHAPTER 12 MAC Table

## 12.1 MAC Table Overview

This chapter introduces the MAC Table screen.

The **MAC Table** screen (a MAC table is also known as a filtering database) shows how frames are forwarded or filtered across the Switch's ports. It shows what device MAC address, belonging to what VLAN group (if any) is forwarded to which ports and whether the MAC address is dynamic (learned by the Switch) or static (manually entered in the **SWIICHING** > **Static MAC Forwarding** screen).


## 12.1.1 What You Can Do

Use the **MAC Table** screen (Section 12.2 on page 130) to check whether the MAC address is dynamic or static.

### 12.1.2 What You Need to Know

The Switch uses the MAC Table to determine how to forward frames. See the following figure.

- 1 The Switch examines a received frame and learns the port on which this source MAC address came.
- 2 The Switch checks to see if the frame's destination MAC address matches a source MAC address already learned in the MAC Table.
  - If the Switch has already learned the port for this MAC address, then it forwards the frame to that port.
  - If the Switch has not already learned the port for this MAC address, then the frame is flooded to all ports. Too much port flooding leads to network congestion, then the Switch sends an ARP to request the MAC address. The Switch then learns the port that replies with the MAC address.
  - If the Switch has already learned the port for this MAC address, but the destination port is the same as the port it came in on, then it filters the frame.



## 12.2 Viewing the MAC Table

Use this screen to search specific MAC addresses. You can also directly add dynamic MAC addresses into the static MAC forwarding table or MAC filtering table from the MAC table using this screen.

Click MONTIOR > MAC Table in the navigation panel to display the following screen.

<u> </u>				
MAC Table				
Condition Sort by Type Transfer	All Statio AAAC AAAC VID Port Turk NAC Dynamic to AAA Dynamic to AAA		Carcol	
Index	MAC Address	VID	Port	Туре
1	00:00:5e:00:01:02	1	21	Dynamic
2	00:00:xe5:55:e7:52	1	21	Dynamic
3	00:03:21:10:txe:00	1	21	Dynamic
4	00:03:21:10:17:76	1	21	Dynamic
5	00:08:21:11:02:01	1	21	Dynamic
ó	00:68:21:11:60:60	1	21	Dynamia
7	00:03:21:11:o2:db	1	21	Dynamic
8	00:03:21:11:cb:55	1	21	Dynamic
9	00:02:21:11:d58ci	1	21	Dynamic

Figure 92 MONITOR > MAC Table

XGS2220 Series User's Guide

Table 37	MONITOR > MAC Table
10010 07	

LABEL	DESC RIPTIO N			
Condition	Select one of the below search conditions and click $\mathbf{Seach}$ to only display the data which matches the criteria you specified.			
	Select All to display any entry in the MAC table of the Switch.			
	Select <b>Static</b> to display the MAC entries manually configured on the Switch.			
	Select <b>MAC</b> and enter a MAC address in the field provided to display a specified MAC entry.			
	Select <b>VID</b> and enter a VLAN ID in the field provided to display the MAC entries belonging to the specified VLAN.			
	Select <b>Port</b> and enter a port number in the field provided to display the MAC addresses which are forwarded on the specified port.			
	Select <b>Trunk</b> and type the ID of a trunk group to display all MAC addresses learned from the ports in the trunk group.			
Sort by	Define how the Switch displays and arranges the data in the summary table below.			
	Select <b>MAC</b> to display and arrange the data according to MAC address.			
	Select $\mathbf{VID}$ to display and arrange the data according to VLAN group.			
	Select <b>PO RT</b> to display and arrange the data according to port number.			
Type Transfer	Select <b>Dynamic to MAC forwarding</b> and click the <b>Transfer</b> button to change all dynamically learned MAC address entries in the summary table below into static entries. They also display in the <b>SWITCHING</b> > <b>Static MAC Forwarding</b> screen.			
	Select <b>Dynamic to MAC filtering</b> and click the <b>Tiransfer</b> button to change all dynamically learned MAC address entries in the summary table below into MAC filtering entries. These entries will then display only in the <b>SWIICHING &gt; Static MAC Filtering</b> screen and the default filtering action is <b>Disc ard source</b> .			
Search	Click this to search data in the MAC table according to your input criteria.			
Transfer	Click this to perform the MAC address transferring you selected in the Type Transfer field.			
Cancel	Click Cancel to change the fields back to their last saved values.			
Index	This is the incoming frame index number.			
MAC Address	This is the MAC address of the device from which this incoming frame came.			
VID	This is the VLAN group to which this frame belongs.			
Port	This is the port where the above MAC address is forwarded.			
Туре	This shows whether the MAC address is <b>Dynamic</b> (learned by the Switch) or <b>Static</b> (manually entered in the <b>SWIICHING</b> > <b>Static MAC Forwarding</b> screen).			

# CHAPTER 13 Neighbor

## 13.1 NeighborOverview

The **Neighbor** screen allows you to view a summary and manage the Switch's neighboring devices. It uses Layer Link Discovery Protocol (LLDP) to discover all neighbor devices connected to the Switch including non-Zyxel devices. You can use this screen to perform tasks on the neighboring devices like login, power cycle (turn the power off and then back on again), and reset to factory default settings.

This screen shows the neighboring device first recognized on an Ethernet port of the Switch. Device information is displayed in gray when the neighboring device is offline.

## 13.1.1 What You Can Do

Use the **Neighbor** screen (Section 13.2 on page 132) to view a summary and manage the Switch's neighbor devices.

Use the **Neighbor Details** screen (Section 13.2.1 on page 133) to view more detailed information on the Switch's neighbor devices.

## 13.2 Neighbor

Click **MONITOR** > **Neighbor** to see the following screen.

Figure 93 MONITOR > Neighbor (example PoE model)

á i	Sales a	<b>ROBATIN</b>	Lex	545 B (10) (10)	Typical barren	10-4	0.896	14. he 1
		3 <u>2</u>	16.00	200	20			C++ Bhier
101			$- e_{A} e_{A}$	<b>2</b> 20	11520	LINE		Sec. Weene
93			Trave	50				Shiel Branc
		12	1977	<b>1</b> 4	50	22	- 23	Sam Sheer
0			The set	22				K Winner
ŝ.,		- 52	4	2.0	23	2	100	Barriel Barriel
65		3.±	( Dece)	201	(#)			A term in the second
63			fame.	62				Second Brands

The following table describes the fields in the above screen.

LABEL	DESC RIPTIO N
Port	This shows the port of the Switch, on which the neighboring device is discovered.
Port Name	This shows the port description of the Switch.
PD Health	For PoE models.
	This shows the status of auto PD recovery on this port.
	<ul> <li>Red: The Switch failed to get information from the PD connected to the port using LLDP, or the connected PD did not respond to the Switch's ping requests.</li> <li>Yellow: The Switch is restarting the connected PD by turning the power off and turning it</li> </ul>
	<ul> <li>on again.</li> <li>Green: The Switch successfully discovered the connected PD using LLDP or ping.</li> <li>-: Auto PD Recovery is not enabled on the Switch and the port, or the Switch does not supply power to the connected PD.</li> </ul>
	Note: The status will NOT be updated instantaneously after enabling or disabling the <b>Active</b> switch in the <b>Port &gt; Auto PD Recovery</b> screen. It will wait until the configured <b>Resume Polling Interval</b> (sec) has lapsed.
Link	This shows the speed (either 10M for 10 Mbps, 100M for 100 Mbps, 1G for 1 Gbps, 2.5G for 2.5 Gbps, 5G for 5 Gbps, or 10G for 10 Gbps) and the duplex (F for full duplex or H for half). This field displays <b>Down</b> if the port is not connected to any device.
PoE Draw (mW)	For PoE models.
	This shows the consumption that the neighboring device connected to this port draws from the Switch. This allows you to plan and use within the power budget of the Switch.
System Name	This shows the system name of the neighbor device.
IPv4	This shows the IPv4 address of the neighbor device. The IPv4 address is a <b>hyperlink</b> that you can click to log into and manage the neighbor device through its Web Configurator.
IPv6	This shows the IPv6 address of the neighbor device. The IPv6 address is a <b>hyperlink</b> that you can click to log into and manage the neighbor device through its Web Configurator.
Action	For PoE models.
	Click the $\operatorname{Reset}$ button to turn OFF the power of the neighbor device and turn it back ON again. A count down button (from 5 to 0) starts.
	Note: The Switch must support power sourcing (PSE) or the network device is a powered device (PD).
	Click the <b>Restore</b> button to restore the neighboring device to its factory default settings. A warning message " <b>Are you sure you want to load factory default?</b> " appears prompting you to confirm the action. After confirming the action a count down button (from 5 to 0) starts.
	Note:
	<ul> <li>The Switch must support power sourcing (PSE) or the network device is a powered device (PD).</li> <li>If multiple neighbor devices use the same port, the Reset button is not available.</li> </ul>
	<ul> <li>You can only reset Zyxel powered devices that support the ZON utility.</li> </ul>

Table 38 MONITOR > Neighbor

### 13.2.1 Neighbor Details

Use this screen to view detailed information about the neighboring devices. Device information is displayed in gray when the neighboring device is currently offline.

Up to 10 neighboring device records per Ethernet port can be retained in this screen even when the

devices are offline. When the maximum number of neighboring device records per Ethernet port is reached, new device records automatically overwrite existing offline device records, starting with the oldest existing offline device record first.

Click **MONIIOR** > **Neighbor** > **Neighbor** Details to see the following screen.

Figure 94 MONITOR > Neighbor > Neighbor Details (example PoE model)

Second median	0				9" Pere 48
est:					
- For 2					6.2.24
ba	1.4 Meralli	L. M. Levins, . Sec.	Andread and a second se		
Sec. 11		100.0	1755		
German Disease :	Red Pridges	Sec.	date .	American and a second	
177.2.9	24 24	5.000 Million	-111 (S. 17 10 - 20)	AN R MARCH INSIDE	
Appendix Section	1/18	194	6.35		
002,200		60.00			
- Part					
- 1					10.000
lear-	PAthonik	t an taran Sera	127		ALC: N
Berger .		\$3.200	661620		
75.8110.8	the factor of the second se	Masaki S	and a count		-
To or our	Target	Ph-8	200		1 march 1 march 1 m
946-1911 - C	- H	90.0	5 mil 1		

The following table describes the fields in the above screen.

Table 39		Neighbor Details
10016 37	MONIOR /	

LABEL	DESC RIPTIO N		
Search Ports	Enter the port number to search and display the ports you specified. The result will display in the below list.		
	You can enter multiple ports separated by comma (",") or hyphen ("-") for a range. For example, enter "3-5" for ports 3, 4, and 5. Enter "3,5,7" for ports 3, 5, and 7.		
Port	This shows the port of the Switch, on which the neighboring device is discovered.		
Desc.	This shows the port description of the Switch.		
PD Health	<ul> <li>For PoE models.</li> <li>This shows the status of auto PD recovery on this port.</li> <li>Red: The Switch failed to get information from the PD connected to the port using LLDP, or the connected PD did not respond to the Switch's ping requests.</li> <li>Yellow: The Switch is restarting the connected PD by turning the power off and turning it on again.</li> <li>Green: The Switch successfully discovered the connected PD using LLDP or ping.</li> <li>-: Auto PD Recovery is not enabled on the Switch and the port, or the Switch does not supply power to the connected PD.</li> </ul>		
Link Speed	This shows the speed (either <b>10M</b> for 10 Mbps, <b>100M</b> for 100 Mbps, <b>1G</b> for 1 Gbps, <b>2.5G</b> for 2.5 Gbps, <b>5G</b> for 5 Gbps, or <b>10G</b> for 10 Gbps) and the duplex ( <b>F</b> for full duplex or <b>H</b> for half). This field displays <b>Down</b> if the port is not connected to any device.		

IABEL	DESC RIPIIO N
PoE Draw (W)	For PoE models.
	This shows the consumption that the neighboring device connected to this port draws from the Switch. This allows you to plan and use within the power budget of the Switch.
Reset	Click this button to turn OFF the power of the neighbor device and turn it back ON again. A count down button (from 5 to 0) starts.
	Note: The Switch must support power sourcing (PSE) or the network device is a powered device (PD).
Remote	
System Name	This shows the system name of the neighbor device.
Port Bridge	This shows the neighboring device's MAC address or the port number connected to the Switch.
Model	This shows the model name of the neighbor device. This field will show "-" for devices that do not support the ZON utility.
MAC	This shows the MAC address of the neighbor device.
Firmware	This shows the firmware version of the neighbor device. This field will show "-" for devices that do not support the ZON utility.
Location	This shows the geographic location of the neighbor device. This field will show "-" for devices that do not support the ZON utility.
Desc.	This shows the description of the neighbor device's port which is connected to the Switch.
IPv4	This shows the IPv4 address of the neighbor device. The IPv4 address is a <b>hyperlink</b> that you can click to log into and manage the neighbor device through its Web Configurator.
IPv6	This shows the IPv6 address of the neighbor device. The IPv6 address is a <b>hyper link</b> that you can click to log into and manage the neighbor device through its Web Configurator.
Restore	Click this button to restore the neighbor device to its factory default settings. A warning message "Are you sure you want to load factory default?" appears prompting you to confirm the action. After confirming the action a count down button (from 5 to 0) starts.
	Note:
	<ul> <li>The Switch must support power sourcing (PSE) or the network device is a powered device (PD).</li> </ul>
	<ul> <li>If multiple neighbor devices use the same port, the Reset button is not available.</li> <li>You can only reset Zyxel powered devices that support the ZON utility.</li> </ul>
Flush	Click the <b>Flush</b> button on the port tab to remove information about neighbors learned on a specific ports.
Flush All	Click the <b>Flush All</b> button to remove information about neighbors learned on all ports.

 Table 39
 MONITOR > Neighbor > Neighbor Details (continued)

# C HA PTER 14 Path MTU Table

## 14.1 Path MTU Overview

This chapter introduces the IPv6 Path MTU table.

The largest size (in bytes) of a packet that can be transferred over a data link is called the Maximum Transmission Unit (MTU). The Switch uses Path MTU Discovery to discover Path MTU (PMTU), that is, the minimum link MTU of all the links in a path to the destination. If the Switch receives an ICMPv6 Packet Too Big error message after sending a packet, it fragments the next packet according to the suggested MTU in the error message.

## 14.2 Viewing the Path MTU Table

Use this screen to view IPv6 path MTU information on the Switch. Click MONHOR > Path MTU Table in the navigation panel to display the screen as shown.

#### Figure 95 MONITOR > Path MTU Table

Path MTU Table			
Path MILLooing	Hime : 10 minutes		
Indec	Death attain Address	MTU	Espire

Table 40	MONITOR >	Path	MTU Table
		I UIII	

IABEL	DESC RIPTIO N
Path MTU aging time	This field displays how long an entry remains in the Path MTU table before it ages out and needs to be relearned.
Index	This field displays the index number of each entry in the table.
Destination Address	This field displays the destination IPv6 address of each path or entry.
MTU	This field displays the maximum transmission unit of the links in the path.
Expire	This field displays how long (in minutes) an entry can still remain in the Path MTU table before it ages out and needs to be relearned.

# C HAPTER 15 Port Status

This chapter introduces the Port Status screens.

### 15.0.1 What You Can Do

Use the Port Status screen (Section 15.1 on page 137) to view the port status of the Switch.

Use the **DDMI** screen (Section 15.2 on page 141) to view the DDMI (Digital Diagnostics Monitoring Interface) status of the SFP transceivers on the Switch.

Use the **Port Utilization** screen (Section 15.3 on page 143) to view the current data rate and utilization percentage of each port on the Switch.

## 15.1 Port Status

This screen displays a port statistical summary with links to each port showing statistical details. To view the port statistics, click **MONITOR** > **Port Status** to display the **Port Status** screen as shown next. You can also click the **Port Status** link in the **Quick Link** section of the **DASHBOARD** screen to see the following screen.

ori Stoles	DOWI Parts	Villashion									
Reat	Norm	Link	2 at a	MD:	LACP.	Tel: No.	Daffi is	Bener	Dalidari	En billen	Mp Free
1.1		Denser	-000 C	08	Theshold		0		3.0	00	00000
2		1.64	CONVERSE.	- 64	Caster	\$00,00	325021	£	0.55	\$000	19030
2		NOW!	3.824	- 94	Stopled	=	Υ.	<b>c</b>	240	9.2	900.00
- <b>B</b>		Deven	33/24	- 64	Contract	=	0	<b>2</b>	20	0.0	Phat 63
5		Terrer (	2022	64	Second and	<b>-</b>	Δ.	<b>2</b>	5.0	60	0.0200
5		1640	002%A60 N0	- 05	Orothed	00635	15.0125	E.	0.365	1.921	156650
100		LC:NF	5.001	1.0	Stabled.	<b>-</b>	V.	<b>2</b>	200	0.0	00000
2		DC WY	3.824	- 64	3-000-6-0	=	9	5	225	60	0.05.00
1		Darwe	2008	01	Deside a l	<b>-</b>	0	5	3.0	00	0.020.00
13		Terrer (	- 100 C		Smith all	<b>F</b>	0		10	<u> </u>	00000
				$\sim$		$\sim$	$\sim$	$\sim$			$\leq$
No. 11 Aug	de Oktobel	OF at [	Cier	Counter						$\sim$	

Figure 96	MONITOR >	Port Status
-----------	-----------	-------------

IABEL	DESC RIPTIO N
Port	This identifies the Ethernet port. Click a port number to display the <b>Port De tails</b> screen.
Name	This is the name you assigned to this port in the <b>PORT</b> > <b>Port Setup</b> screen.
Link	This field displays the speed (either 100M for 100 Mbps, 1G for 1 Gbps, 2.5G for 2.5 Gbps, 5G for 5 Gbps, or 10G for 10 Gbps) and the duplex (F for full duplex or H for half). It also shows the cable type (Copper or Fiber) for the combo ports. This field displays Down if the port is not connected to any device.
State	If STP (Spanning Tree Protocol) is enabled, this field displays the STP state of the port.
	If STP is disabled, this field displays <b>FO RWARDING</b> if the link is up, otherwise, it displays <b>STO P</b> .
	When LACP (Link Aggregation Control Protocol) and STP are in blocking state, it displays <b>BLOCKING</b> .
PD	For PoE models only.
	This field displays whether or not a powered device (PD) is allowed to receive power from the Switch on this port.
LACP	This fields displays whether LACP (Link Aggregation Control Protocol) has been enabled on the port.
TxPkts	This field shows the number of transmitted frames on this port.
RxPkts	This field shows the number of received frames on this port.
Errors	This field shows the number of received errors on this port.
Tx kB/s	This field shows the number of kilobytes per second transmitted on this port.
Rx kB/s	This field shows the number of kilobytes per second received on this port.
Up Time	This field shows the total amount of time in hours, minutes and seconds the port has been up.
Clear the counter	Select <b>Port</b> , enter a port number and then click <b>ClearCounter</b> to erase the recorded statistical information for that port, or select <b>AILPorts</b> to clear statistics for all ports.

Table 41 MONITOR > Port Status

## 15.1.1 Port De tails

Click an index in the **Port** column in the **MONITOR** > **Port** Status screen to display individual port statistics. Use this screen to check status and detailed performance data about an individual port on the Switch.

Politicius DOWI	Fort Otherhon		
Port Stoke - Ism De	colo		
And links		TV Product	
INT NO.	2	uricati	210613
New		La le -	102
la A	1009	Press and ad	194
Viole -	15.8 A 41 - 498 -	12.04	2
1 - 525	East All and A	Si Barbel	
LANL.	218.0	unicati	2012
iende	10000	Line for the	971 M
Co. et	r	El enclusion de	7.711
La restru	1.2-1	12.04	2
o unicational	. v	T/ Collision	
De la Sel	6 Kal	single	
Kalif and same	D-3	14 14 2	
vp. ine	≥ 0.101.	to ensure	
		Lafe	
Jaco Backet		Distance of	
Karakara Karaka			
les subs		51 251 - 177	73137 5460
No.		1.21 5 2.20	
	•	1241 (x - 224) 206 (1951)	24122
		200 10 CT 212 is 1020	1000
		EST FORM	1.612
		set the set of the set	
		UIC T	1

Figure 97 MONITOR > Port Status > Port Details

S
---

LABEL	DESC RIPTIO N
Port Info	
Port NO.	This field displays the port number you are viewing.
Name	This field displays the name of the port.
Link	This field displays the speed (either 100M for 100Mbps, 1G for 1 Gbps, 2.5G for 2.5 Gbps, 5G for 5 Gbps, or 10G for 10 Gbps) and the duplex (F for full duplex or H for half). It also shows the cable type (Copperor Fiber) for the combo ports. This field displays Down if the port is not connected to any device.
State	If STP (Spanning Tree Protocol) is enabled, this field displays the STP state of the port. If STP is disabled, this field displays <b>FO RWARDING</b> if the link is up, otherwise, it displays <b>STO P</b> . When LACP (Link Aggregation Control Protocol), STP, and dot1x are in blocking state, it displays <b>BLO C KING</b> .
LACP	This field shows if LACP is enabled on this port or not.
TxPkts	This field shows the number of transmitted frames on this port.
RxPkts	This field shows the number of received frames on this port.
Errors	This field shows the number of received errors on this port.
Tx kB/s	This field shows the number of kilobytes per second transmitted on this port.

XGS2220 Series User's Guide

LABEL	DESC RIPIIO N
Tx Utilization%	This field shows the percentage of actual transmitted frames on this port as a percentage of the <b>Link</b> speed.
Rx kB/s	This field shows the number of kilobytes per second received on this port.
Rx Utilization%	This field shows the percentage of actual received frames on this port as a percentage of the <b>Link</b> speed.
Up Time	This field shows the total amount of time the connection has been up.
TX Packet	
The following fie	elds display detailed information about packets transmitted.
Unicast	This field shows the number of good unicast packets transmitted.
Multicast	This field shows the number of good multicast packets transmitted.
Broadcast	This field shows the number of good broadcast packets transmitted.
Pause	This field shows the number of 802.3x pause packets transmitted.
RX Packet	•
The following fie	elds display detailed information about packets received.
Unicast	This field shows the number of good unicast packets received.
Multicast	This field shows the number of good multicast packets received.
Broadcast	This field shows the number of good broadcast packets received.
Pause	This field shows the number of 802.3x pause packets received.
The following fie	elds display information on collisions while transmitting.
Single	This is a count of successfully transmitted packets for which transmission is inhibited by exactly one collision.
Multiple	This is a count of successfully transmitted packets for which transmission was inhibited by more than one collision.
Excessive	This is a count of packets for which transmission failed due to excessive collisions. Excessive collision is defined as the number of maximum collisions before the retransmission count is reset.
Late	This is the number of times a late collision is detected, that is, after 512 bits of the packets have already been transmitted.
Error Packet	
The following fie	elds display detailed information about packets received that were in error.
RX CRC	This field shows the number of packets received with CRC (Cyclic Redundant Check) errors.
Length	This field shows the number of packets received with a length that was out of range.
Runt	This field shows the number of packets received that were too short (shorter than 64 octets), including the ones with CRC errors.
Distribution	
64	This field shows the number of packets (including bad packets) received that were 64 octets in length.
65 to 127	This field shows the number of packets (including bad packets) received that were between 65 and 127 octets in length.
128 to 255	This field shows the number of packets (including bad packets) received that were between 128 and 255 octets in length.
256 to 511	This field shows the number of packets (including bad packets) received that were between 256 and 511 octets in length.

 Table 42
 MONITOR > Port Status > Port Details (continued)

LABEL	DESC RIPIIO N
512 to 1023	This field shows the number of packets (including bad packets) received that were between 512 and 1023 octets in length.
1024 to 1518	This field shows the number of packets (including bad packets) received that were between 1024 and 1518 octets in length.
Giant	This field shows the number of packets (including bad packets) received that were between 1519 octets and the maximum frame size.
	The maximum frame size varies depending on your switch model.

Table 42 MONITOR > Port Status > Port Details (continued)

## 15.2 **DDMI**

The optical SFP transceiver's support for the Digital Diagnostics Monitoring Interface (DDMI) function lets you monitor the transceiver's parameters to perform component monitoring, fault isolation and failure prediction tasks. This allows proactive, preventative network maintenance to help ensure service continuity.

Use this screen to view the DDMI status of the Switch's SFP transceivers. Click MONITOR > Port Status > DDMI to see the following screen. Alternatively, click DASHBOARD from any Web Configurator screen and then the Port Status link in the Quick Link section of the DASHBOARD screen to display the Port Status screen and then click the **DDMI** link tab.

Figure 98 MONITOR > Port Status > DDMI

Port Status	DDMI	<b>Port Utilization</b>				
Port	Vendor	Port Kumber	Seriol Nomber	Restrict	Dole Code	Imascelver
la.	eyxn	AFP 1000F		15	2017 12 25	100036077

The following table describes the labels in this screen.

Table 43 MONITOR > Port Status > DDMI				
LABEL	DESC RIPTIO N			
Port	This identifies the SFP port. Click a port number to display the <b>DDMI De tails</b> screen.			
Vendor	This displays the vendor name of the optical transceiver.			
Part Number	This displays the part number of the optical transceiver.			
Serial Number	This displays the serial number of the optical transceiver.			
Revision	This displays the revision number of the optical transceiver.			
Date Code	This displays the date when the optical transceiver was manufactured.			
Transceiver	This displays the type of transceiver installed in the SGP slot.			

### 15.2.1 DDMI De tails

Use this screen to view the real-time SFP (Small Form Factor Pluggable) transceiver information and operating parameters on the SFP port. The parameters include, for example, transmitting and receiving power, and module temperature.

Click an index in the Port column in the DDMI screen to view current transceivers' status.

ort Status D	OMI Po	d Utilization			
ranscelver info	mation				
Port No	16				
Connector Type	51	r i i i i i i i i i i i i i i i i i i i			
Vender	2/	*EL			
Part Number	31	10007			
iorial Number	31				
Revision	1.0	•			
bole Code	20	17-12-20			
iranseelver	10	008A55T			
Colloration	10	erreal			
DMI Informatio	on				
DMI Informatio	ofi Current	High Alarm Threshold	High Work Threshold	Low Wern Threshold	Low Alorm Threshold
		High Alarm Threshold			
Туре	Current	Threshold	Threshold	Invshold	Threshold
type Inttpercipe(C)	Current .	Threshold	Threshold	Innshold	Threshold
lemperoruse(0) Volkape(2)	Current .	Threshold	Threshold	Innshold	Threshold

Figure 99 MONITOR > Port Status > DDMI > DDMI Details

The following table describes the labels in this screen.

	Table 44	MONITOR > Port Status > DDMI > DDMI Details
--	----------	---

LABEL	DESC RIPTIO N
Transceiver Informe	ation
Port No	This identifies the SFP port.
Connector Type	This displays the connector type of the optical transceiver.
Vendor	This displays the vendor name of the optical transceiver.
Part Number	This displays the part number of the optical transceiver.
Serial Number	This displays the serial number of the optical transceiver.
Revision	This displays the revision number of the optical transceiver.
Date Code	This displays the date when the optical transceiver was manufactured.
Transceiver	This displays details about the type of transceiver installed in the SFP slot.
Calibration	This field is available only when an SFP transceiver is inserted into the SFP slot.
	<b>Internal</b> displays if the measurement values are calibrated by the transceiver. <b>External</b> displays if the measurement values are raw data which the Switch calibrates.
DDMI Information	
Туре	This displays the DDMI parameter.
Temperature (C/F)	This displays the temperature inside the SFP transceiver in degrees Celsius or Fahrenheit.
Voltage (V)	This displays the level of voltage being supplied to the SFP transceiver.

XGS2220 Series User's Guide

LABEL	DESC RIPTIO N
TX Bias (mA)	This displays the milliamps (mA) being supplied to the SFP transceiver's Laser Diode Transmitter.
TX Power (dbm)	This displays the amount of power the SFP transceiver is transmitting.
RX Power (dbm)	This displays the amount of power the SFP transceiver is receiving from the fiber cable.
Current	This displays the current status for each monitored DDMI parameter.
High Alarm Threshold	This displays the high value alarm threshold for each monitored DDMI parameter. An alarm signal is reported to the Switch if the monitored DDMI parameter reaches this value.
High Warn Threshold	This displays the high value warning threshold for each monitored DDMI parameter. A warning signal is reported to the Switch if the monitored DDMI parameter reaches this value.
Low Warn Threshold	This displays the low value warning threshold for each monitored DDMI parameter. A warning signal is reported to the Switch if the monitored DDMI parameter reaches this value.
Low Alarm Threshold	This displays the low value alarm threshold for each monitored DDMI parameter. An alarm signal is reported to the Switch if the monitored DDMI parameter reaches this value.

Table 44 MONITOR > Port Status > DDMI > DDMI Details (continued)

## 15.3 Port Utilization

This screen displays the percentage of actual transmitted or received frames on a port as a percentage of the **Link** speed. To view port utilization, click **MONITOR** > **Port Status** > **Port Utilization** to see the following screen. Alternatively, click **DASHBOARD** from any Web Configurator screen and then the **Port Status** link in the **Quick Link** section of the **DASHBOARD** screen to display the **Port Status** screen and then click the **Port Utilization** link tab.

Port Status	DDMI	Port Utilization			
Port	Link	To: hB/r	Ta uti Isofian 🐔	Ba kB/a	Re utilization &
1	Down	0.0	000	0.0	000
×	Derim	0.0	001	(1.1)	000
5	Lor ni	0.0	001	<b>410</b>	000
8 - C	10,4	0.524	001	0.247	001
5	Down	0.0	50	0.0	0.0
6	Down	0.2	000	0.0	000
	Dynn				
			$\sim$		

Figure 100 MONITOR > Port Status > Port Utilization

Table 45 MONITOR > Port Status > Port Utilization	Table 45	MONITOR >	Port Status >	Port Utilization
---	----------	-----------	---------------	------------------

IABEL	DESC RIPIIO N
Port	This identifies the Ethernet port.
Link	This field displays the speed (either 100M for 100Mbps, 1G for 1 Gbps, 2.5G for 2.5 Gbps, 5G for 5 Gbps, or 10G for 10 Gbps) and the duplex (F for full duplex or H for half). It also shows the cable type (Copper or Fiber) for the combo ports. This field displays Down if the port is not connected to any device.

LABEL	DESC RIPIIO N
Tx kB/s	This field shows the transmission speed of data sent on this port in kilobytes per second.
Tx Utilization%	This field shows the percentage of actual transmitted frames on this port as a percentage of the <b>Link</b> speed.
Rx kB/s	This field shows the transmission speed of data received on this port in kilobytes per second.
Rx Utilization%	This field shows the percentage of actual received frames on this port as a percentage of the <b>Jink</b> speed.

 Table 45
 MONITOR > Port Status > Port Utilization (continued)

# C HAPTER 16 Routing Table

#### 16.1 Routing Table Overview

This chapter introduces the IPv4/IPv6 routing tables.

The IPv4/IPv6 routing tables record routing information of the best path to destinations where packets were forwarded. Use this table to check information like routing destination, gateway, interface IP addresses, hop count, and routing methods.

#### 16.1.1 What You Can Do

Use the IPv4 Routing Table screen (Section 16.2 on page 145) to view the Switch's IPv4 routing table information.

Use the IPv6 Routing Table screen (Section 16.3 on page 146) to view the Switch's IPv6 routing table information.

#### 16.2 IPv4 Routing Table

Use this screen to view IPv4 routing table information. Click **MONITOR** > **Routing Table** > **IPv4 Routing Table** in the navigation panel to display the screen as shown.

IPv4 Routing	a Table					
Index	Destinction	Gateway	Interlace	Meirle	Руре	Uptime
I	197.178,73/24	12212522115	122.1602.115	I.	LOC AL	1:10:25
2	127.00.0/16	127.0.0.1	127.0.0.1	I	10004	1540.575
5	de Mult	199 172 9 1	192,130,2113	2	ATA DO	1540.200

Figure 101 MONITOR > Routing Table > IPv4 Routing Table

The following table describes the labels in this screen.

IABEL	EL DESC RIPTIO N	
Index	This field displays the index number.	
Destination	This field displays the destination IP routing domain.	
Gateway	This field displays the IP address of the gateway device.	
Interface	This field displays the IP address of the IPv4 Interface.	

Table 46 MONITOR > Routing Table > IPv4 Routing Table

XGS2220 Series User's Guide

LABEL	DESC RIPIIO N	
Metric	This field displays the cost of the route.	
Туре	This field displays the method used to learn the route.	
	STATIC – added as a static entry.	
	IDCAL- added as a local interface entry.	
Uptime	This field displays how long the route has been running since the Switch learned the route and added an entry in the routing table.	

Table 46 MONITOR > Routing Table > IPv4 Routing Table (continued)

## 16.3 IPv6 Routing Table

Use this screen to view IPv6 routing table information. Click **MONIIOR** > Routing Table > IPv6 Routing Table in the navigation panel to display the screen as shown.

Figure 102 MONITOR > Routing Table > IPv6 Routing Table

IPvé Rouling	a toble				
Index	Roote Designation Prefix Length	Next Hop	interfoce.	Meltic	Туре

Table 47	MONITOR > Routing	Table >	IPv6 Routing Table
----------	-------------------	---------	--------------------

LABEL	DESC RIPTIO N
Index	This field displays the index number.
Route Destination/ Prefix Length	This field displays the IPv6 subnet prefix and prefix length of the final destination.
Next Hop	This field displays the IPv6 address of the gateway that helps forward the packet to the destination.
Interface	This field displays the descriptive name of the IPv6 interface that is used to forward the packets to the destination.
Metric	This field displays the cost of the route.
Туре	This field displays the method used to learn the route.
	STATIC – added as a static entry.
	Connect – added as a local interface entry.

# C HAPTER 17 System Information

#### 17.0.1 What You Can Do

Use the **System Information** screen (Section 17.1 on page 147) to view general system information and hardware status of the Switch.

### 17.1 System Information

In the navigation panel, click **MONITOR** > **System Information** to display the screen as shown. Use this screen to view general system information.

-12 v. 1210				
an and a los				
tatore	b.e.d	Case (Science)		K they are (The
		HEAD.		2
C Mater To	Correst.	2647	0.0436	inser her bi
tional)	40	4.1	195	20.5
Case of L	6.2	e 2	2/2	6.2
tion and 1	# N	45.5	24.2	W.5
data	Same M.	FAX.	E.H.	Poet hold
I former	2827	10.8	825	5.0
Band I	. 60	1325	1941	14
( lowers,	(36	-090		, <b>S</b> W
- States	The of	ert2.	e e	Tato will
tand)	1218	12-91	1.991	-12. 44
		1.50	0.26	1.0366-739
	Epro Meter Jaconski J Meter Meter John J Meter John J Meter John J John J John J	et an et al a serie de la seri	An 2004)	strately of and a set of and a set of a

Figure 103 MONITOR > System Information

Table 48	MONITOR > System Information

IABEL	DESC RIPIIO N	
System Informati	on	
System Name	This displays the descriptive name of the Switch for identification purposes.	
Product Model	This displays the product model of the Switch. Use this information when searching for firmware upgrade or looking for other support information in the website.	
ZyNOS F/W Version	This displays the version number of the Switch 's current firmware including the date created.	
Ethernet Address	This refers to the Ethernet MAC (Media Access Control) address of the Switch.	
CPU Utilization Current (%)	This displays the current percentage of CPU utilization.	
Memory Utilizatio	n	
Memory utilizatic of memory utilizo	n shows how much DRAM memory is available and in use. It also displays the current percentage tion.	
Name	This displays the name of the memory pool.	
Total (byte)	This displays the total number of bytes in this memory pool.	
Used (byte)	This displays the number of bytes being used in this memory pool.	
Utilization (%)	This displays the percentage (%) of memory being used in this memory pool.	
Hardware Monite	r	
Temperature Unit	The Switch has temperature sensors that are capable of detecting and reporting if the temperature rises above the threshold. You may choose the temperature unit (Centigrade or Fahrenheit) in this field.	
Temperature (C/F)	MAC, BOARD, and PHY refer to the location of the temperature sensor on the Switch printed circuit board.	
Status	This field displays $Nomal$ for temperatures below the threshold and $Enor$ for those above.	
Current	This shows the current temperature at this sensor.	
MAX	This field displays the maximum temperature measured at this sensor.	
MIN	This field displays the minimum temperature measured at this sensor.	
Threshold	This field displays the upper temperature limit at this sensor.	
Fan Speed (RPM)	A properly functioning fan is an essential component (along with a sufficiently ventilated, cool operating environment) in order for the device to stay within the temperature threshold. Each fan has a sensor that is capable of detecting and reporting if the fan speed falls below the threshold shown.	
Status	<b>Nomal</b> indicates that this fan is functioning above the minimum speed. <b>Enor</b> indicates that this fan is functioning below the minimum speed.	
Current	This field displays this fan's current speed in Revolutions Per Minute (RPM).	
MAX	This field displays this fan's maximum speed measured in Revolutions Per Minute (RPM).	
MIN	This field displays this fan's minimum speed measured in Revolutions Per Minute (RPM). "<41" is displayed for speeds too small to measure (under 2000 RPM).	
Threshold	This field displays the minimum speed at which a normal fan should work.	
Voltage(V)	The power supply for each voltage has a sensor that is capable of detecting and reporting if the voltage falls out of the tolerance range.	
Status	<b>Nomal</b> indicates that the voltage is within an acceptable operating range at this point; otherwise <b>Enor</b> is displayed.	

IABEL	DESC RIPIIO N
Current	This is the current voltage reading.
MAX	This field displays the maximum voltage measured at this point.
MIN	This field displays the minimum voltage measured at this point.
Threshold	This field displays the percentage tolerance of the voltage with which the Switch still works.

Table 48 MONITOR > System Information (continued)

# C HAPTER 18 System Log

#### 18.1 System Log Overview

A log message stores the system history information for viewing.

#### 18.2 System Log

Click **MONITOR** > **System Log** in the navigation panel to open this screen. Use this screen to check current system logs.

Note: When a log reaches the maximum number of log messages, new log messages automatically overwrite existing log messages, starting with the oldest existing log message first.

Figure 104 MONITOR > System Log

System Log
1 2022 02 22702:13:065 WR interfaces goet 15 hink speed and doplen mode automorphistic = 2 202-02-02012:13:15:06 www.interfaces point 22 10:06 speed and doplen mode automorphistic # 2022 02 22702:11:405 WR interfaces point 25 link speed and doplen mode automorphistic 5 2025-02-0210:11:405 WR interfaces point 25 link speed and doplen mode automorphistic 5 2025-02-0210:2011:405 WR interfaces point 25 link speed and doplen mode automorphistic 5 2025-02-0210:2011:405 WR interfaces point 25 link speed and doplen mode automorphistic 5 2025-02-0210:2011:405 WR interfaces point 25 link speed and doplen mode automorphistic 5 2025-02-0210:2011:405 WR interfaces point 25 link speed and doplen mode automorphistic 0 2020 02 22702:00:365 DN systems Save system configuration 0 2025-02-22702:00:365 DN systems Save system configuration 1 2022 02 22702:00:365 DN systems Save system configuration 1 2022 02 22702:00:365 DN systems Save system configuration 1 2022 02 22702:00:365 DN systems Save system configuration 1 2022 02 22702:00:365 DN systems Save system configuration 1 2022 02 22702:00:365 DN systems Save system configuration 1 2022 02 22702:00:365 DN systems Save system configuration 1 2022 02 22702:00:365 DN systems Save system configuration 1 2022 02 22702:00:365 DN systems Save system configuration 1 2022 02 22702:00:365 DN systems Save system configuration
10 2022 02 22102:02:03:500 we interfaced port 20 link speed and droler mode automorphistic 2 2022-02-02102:03:500 we interfaced port 20 link speed and droler mode automorphistic 2 2022 02 22702:04 228 We interfaced port 20 link speed and droler mode automorphistic 14 2002-02-02102:03:10 we interfaced port 20 link speed and droler mode automorphistic 2 2022 02 22702:04:03:03 We interfaced port 20 link speed and droler mode automorphistic 14 2002-02-02102:03:10 we interfaced port 20 link speed and droler mode automorphistic 15 2022 02 22702:04:03 We interfaced port 20 link speed and droler mode automorphistic 16 2022 02 22702:04:05 We interfaced port 20 link speed and droler mode automorphistic 17 2002-02-02102:04:05 We interfaced port 20 link speed and droler mode automorphistic 20 2022 02 22702:04:05 We interfaced port 20 link speed and droler mode automorphistic 20 2022 02 22702:04:05 We interfaced port 20 link speed and droler mode automorphistic 2 2022-02-02-02012:04:05 We interfaced port 20 link speed and droler mode automorphistic 2 2022-02-02012:04:05 We interfaced port 20 link speed and droler mode automorphistic
<pre>15 2022 02 22F02:02:425 WR interfaces peri 15 link speed and duplem mode interceptiatie 20 2005-02-02:02:02:00:00 a anthermidiation: univ(s) user which inter [ k address 182.1 21 2022 02 22F02:01:45 UN subscription: UEDP(c) user admit intercent state state 20 2005-02-02:02:01:45 UN subscription: UEDP(c) user admit logic 12F values = 102.1 20 2005-02-02:02:01:45 UN subscription: UEDP(c) user admit logic 12F values = 102.1 20 2005-02-02:02:02 US No interfaces over 20 10:00 pp. 2000 24 2000 02 22F01:40 d 2 DB obscription: 20 10:00 pp. 2000 25 2022 02 22F01:50:00 BB obscription: 20 10 link up 100F 26 2022 02 22F01:50:00 BB interfaces Cost 10 link up 100F 26 2022 02 22F01:50:00 W system: 2000F Admit 20 00 (2000 Lyd200 minutes 100)<sup>0</sup> 20 2002 02 22F01:50:00 M system: 10:00 F PyV scient V1 20 (2000 Lyd200 minutes 100)<sup>0</sup> 20 2002 02 22F01:50:00 M system: 10:00 F PyV scient V1 20 (2000 Lyd200 minutes 100)<sup>0</sup> 20 20 20 22F01:50:00 M system: 2000 minutes cost 10 Link up 100F</pre>
Mafanala Chana Dasandanal

The summary table shows the time the log message was recorded and the reason the log message was generated. Click **Refresh** to update this screen. Click **Clear** to clear the whole log, regardless of what is currently displayed on the screen. Click **Download** to save the log to your computer.

# C HAPTER 19 SYSTEM

The following chapters introduces the configurations of the links under the SYSTEM navigation panel.

Quick links to chapters:

- Cloud Management
- General Setup
- Hardware Monitor Setup
- Interface Setup
- IP Setup
- IPv6
- Logins
- SNMP
- Switch Setup
- Syslog Setup
- Time Range

# CHAPTER 20 Cloud Management

# 20.1 Cloud Management Overview

The Zyxel Nebula Control Center (NCC) is a cloud-based network management system that allows you to remotely manage and monitor Zyxel Nebula APs, Ethernet switches and security gateways.

The Switch is managed and provisioned automatically by the NCC (Nebula Control Center) when:

- It is connected to the Internet.
- The Nebula Control Center (NCC) Discovery feature is enabled.
- It has been registered in the NCC.

# 20.2 Nebula Center Control Discovery

Click **SYSTEM** > Cloud Management to display this screen.



Figure 105 SYSTEM > Cloud Management

IABEL	DESC RIPTIO N
Nebula Control	Enable the switch button to turn on Nebula Control Center (NCC) discovery on the Switch.
Center (NCC) Discovery	This field displays:
	<ul> <li>The Switch Internet connection status.</li> <li>The connection status between the Switch and NCC.</li> <li>The Switch registration status on NCC.</li> </ul>
	To pass your Switch management to NCC, first make sure your Switch is connected to the Internet. Then go to NCC and register your Switch.
	1. Internet
	Green – The Switch is connected to the Internet.
	Orange – The Switch is not connected to the Internet.
	2. Ne bula
	Green – The Switch is connected to NCC.
	Orange – The Switch is not connected to NCC.
	3. Registration
	Green – The Switch is registered on NCC.
	Gray – The Switch is not registered on NCC.
	Note: All circles will gray out if you disable Nebula Discovery.
Connection Status	This table displays the NCC connection status information.
510105	Use the status logs in the $Intemet$ , $Nebula$ , and $Registration$ fields for connection troubleshooting.

Table 49 SYSTEM > Cloud Management

#### Cloud Management Mode

Enable the switch button to turn on NCC discovery on the Switch. If the Switch has Internet access and has been registered on the NCC, it will automatically go into cloud management mode. Follow the steps to register your Switch on NCC:

1 Download the Nebula Mobile App

First, download the app from the Google Play store for Android devices or the App Store for iOS devices and create an organization and site.

You can scan an app store QR code to open the app installation page on the app store.

2 Scan the Device QR code

The **Register Device** QR code in this screen contains the Switch's serial number and the registration MAC address for handy NCC registration of the Switch using the Nebula Mobile app.

Follow the wizard in the Nebula Mobile app to scan the QR code to register the Switch on NCC and add the Switch into a site.

If **Nebula Control Center (NCC) Discovery** is disabled, the Switch will NOT discover the NCC and remain in Standalone mode.

# C HAPTER 21 General Setup

## 21.1 General Setup

Use this screen to configure general settings such as the system name and time. Click **SYSTEM** > **General Setup** in the navigation panel to display the screen as shown.

Figure 106 SYSTEM > General Setup

Ceneralisetop	
S yelene bi a es	20.012
Correctinesch's Hame	
use the several-enucolog	$\mathbb{P}(\mathbb{P}^{n}), \ \mathbb{P}(\mathbb{P}(M_{n})) = \mathbb{P}\left[$
time server in eddiest	Lpool imploig
$\log m > 2$ a var $2$ , $m$ , $\log h > \infty$ .	1499 - renador
Carson Denne	10
new ine channels)	
Carenel Date	2.07 (7. 01
is the Euler (gray) matrix $\{\mathbf{x}\}$	2022 02 02
$T=\infty + 2 n = n$	10°. v
$(2\pi_{1})_{1}^{1}$ , $(2\pi_{2})_{2}^{1}$ , $(2\pi_{2}$	CAR CO
vian para	. First in surface in $ $ of Lemmary in $ $ an axe in $ $
The Cheville	Finite we can be a set of the se

Note: The input string of any field in this screen should not contain [?], [|], ['], ["], or [,].

LABEL	DESC RIPIIO N	
System Name	Choose a descriptive name for identification purposes. This name consists of up to 64 printable ASCII characters; spaces are allowed.	
Location	Enter the geographic location of your Switch. You can use up to 128 printable ASCII characters; spaces are allowed.	
Contact Person's Name	Enter the name of the person in charge of this Switch. You can use up to 32 printable ASCII characters; spaces are allowed.	

Table 50 SYSTEM > General Setup

LABEL	DESC RIPTIO N
Use Time Server when Bootup	Enter the time service protocol that your time server uses. Not all time servers support all protocols, so you may have to use trial and error to find a protocol that works. The main differences between them are the time format.
	When you select the <b>Daytime</b> ( <b>RFC-867</b> ) format, the Switch displays the day, month, year and time with no time zone adjustment. When you use this format it is recommended that you use a Daytime timeserver within your geographical time zone.
	Time (RFC-868) format displays a 4-byte integer giving the total number of seconds since 1970/ $1/1$ at 00:00:00.
	NTP (RFC-1305) is similar to Time (RFC-868).
	<b>None</b> is the default value. Enter the time manually. Each time you turn on the Switch, the time and date will be reset to 2022-01-01 00:00:00.
Time Server IP Address	Enter the IP address or domain name of your timeserver. The Switch searches for the timeserver for up to 60 seconds.
Time Server Sync Interval	Enter the period in minutes between each time server synchronization. The Switch checks the time server after every synchronization interval.
Current Time	This field displays the time you open this menu (or refresh the menu).
New Time (hh:mm:ss)	Enter the new time in hour, minute and second format. The new time then appears in the $Cument$ Time field after you click Apply.
Current Date	This field displays the date you open this menu.
New Date (yyyy- mm-dd)	Enter the new date in year, month and day format. The new date then appears in the Cument Date field after you click Apply.
Time Zone	Select the time difference between UTC (Universal Time Coordinated, formerly known as GMT, Greenwich Mean Time) and your time zone from the drop-down list box.
Daylight Saving Time	Daylight saving is a period from late spring to early fall when many countries set their clocks ahead of normal local time by one hour to give more daytime light in the evening.
	Enable the switch button if you use Daylight Saving Time.
Start Date	Configure the day and time when Daylight Saving Time starts if you selected <b>Daylight Saving</b> <b>Time</b> . The time is displayed in the 24 hour format. Here are a couple of examples:
	Daylight Saving Time starts in most parts of the United States on the second Sunday of March. Each time zone in the United States starts using Daylight Saving Time at 2 A.M. local time. So in the United States you would select <b>Second</b> , <b>Sunday</b> , <b>March</b> and <b>2:00</b> .
	Daylight Saving Time starts in the European Union on the last Sunday of March. All of the time zones in the European Union start using Daylight Saving Time at the same moment (1 A.M. GMT or UTC). So in the European Union you would select <b>Last</b> , <b>Sunday</b> , <b>March</b> and the last field depends on your time zone. In Germany for instance, you would select <b>2:00</b> because Germany's time zone is one hour ahead of GMT or UTC (GMT+1).
End Date	Configure the day and time when Daylight Saving Time ends if you selected <b>Daylight Saving</b> <b>Time</b> . The time field uses the 24 hour format. Here are a couple of examples:
	Daylight Saving Time ends in the United States on the first Sunday of November. Each time zone in the United States stops using Daylight Saving Time at 2 A.M. local time. So in the United States you would select <b>First</b> , <b>Sunday</b> , <b>November</b> and <b>2:00</b> .
	Daylight Saving Time ends in the European Union on the last Sunday of October. All of the time zones in the European Union stop using Daylight Saving Time at the same moment (1 A.M. GMT or UTC). So in the European Union you would select <b>Last</b> , <b>Sunday</b> , <b>October</b> and the last field depends on your time zone. In Germany for instance, you would select <b>2:00</b> because Germany's time zone is one hour ahead of GMT or UTC (GMT+1).

Table 50 SYSTEM > General Setup (continued)

IABEL	DESC RIPTIO N
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 50 SYSTEM > General Setup (continued)

## 21.2 Hardware Monitor Setup

This section introduces Fan Control for the temperature of the SFP transceiver inserted in the Switch.

When the SFP transceiver temperature exceeds the temperature threshold (see your transceiver documentation), the Switch automatically turns on the fans with maximum fan speed to cool down the system.

The fans do not automatically turn off after the SFP transceiver temperature returns below threshold. To turn off the fans, you have to temporarily disable **SFP De te c t** or reboot the Switch.

Click SYSTEM > Hardware Monitor Setup to display the screen as shown below.

Note: The **SFP De te c t** feature only functions if at least one of your SFP transceiver(s) support DDMI (Digital Diagnostic Monitoring Interface). See the transceiver documentation.

Figure 107 SYSTEM > Hardware Monitor Setup

Hardware Monilor Selup	
Fan Control	
SL/ Delect	0
	_
Am	ply Concel

LABEL	DESC RIPTIO N
Fan Control	
SFP Detect	Enable the switch button to enable $\mathbf{SFP} \operatorname{Detect}$ on the Switch.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 51 SYSTEM > Hardware Monitor Setup

You will see SFP warning icons next to the **FAN**s in the **MONITOR** > **System Information** screen when **SFP Detect** has triggered the fans.

Figure 108 Hardware Monitor: SFP Module Temperature Warning

rdwore Monifor						
					contribution .	NO 01 10
terreerelare (c)	status		canart	MA1	ANN	thathald
eros:	storrent		39.6	28.0	32.0	Test
87470	Stormal )		38.7	36.0	30.0	mas
9-40	( harmon )		-19/2	10.00	25500	and a
Fan Speed (EFM)	Status		Canaet	MAX	MIN.	Threshold
6491	Normal )	100	(1962	11925	6195	600
e cita	( Internet )	100 1	010635	11000	a 24,-	101
C460	teerreal 1	547 1	(1423)	Fiss2	22.65	500

# C HAPTER 22 Interface Setup

### 22.1 Interface Setup Overview

This chapter shows you how to create virtual interfaces for interface-based configurations. An IPv6 address is configured on a per-interface basis. The interface can be a physical interface (for example, an Ethernet port) or a virtual interface (for example, a VLAN).

#### 22.2 Interface Setup

Use this screen to view and set IPv6 interfaces on which you can configure an IPv6 address to access and manage the Switch.

The interfaces you create here will only take effect after you configure them in the **SYSTEM** > IPv6 screens.

Click SYSTEM > Interface Setup in the navigation panel to display the configuration screen.

Interface Ser	tup			
			0.44	id/Edit 🍵 Dolato
	in dex	Interface Type	Interface ID	Interface
	1	VLAN	t	VLANI

Figure 109 SYSTEM > Interface Setup

Table 52	SYSTEM > Interface Setup
----------	--------------------------

IABEL	DESC RIPHO N	
Index	This field displays the index number of an entry.	
Interface Type	This field displays the type of interface.	
Interface ID	This field displays the identification number of the interface.	
Interface	This field displays the interface's descriptive name which is generated automatically by the Switch. The name is from a combination of the interface type and ID number.	
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.	
Add/Edit	Click Add/Edit to add a new interface or edit a selected one.	
Delete	Click <b>Delete</b> to remove the selected interfaces.	

#### 22.2.1 Add/Edit Interfaces

Click Add/Edit, or select an entry and click Add/Edit in the SYSTEM > Interface Setup screen to display the configuration screen.

Figure 110 SYSTEM > Interface Setup > Add/Edit

lahadasa 1795 Interimentik	alaa M	
Analo	Circo Concel	

Table 53 SYSTEM > Interface Setup > Add/Edit

LABEL	DESC RIPTIO N
Interface Type	Select the type of IPv6 interface for which you want to configure. The Switch supports the VLAN interface type for IPv6 at the time of writing.
Interface ID	Specify a unique identification number (from 1 to 4094) for the interface.
	To have IPv6 function properly, you should configure a static VLAN with the same ID number in the <b>SWTICHING</b> $>$ <b>VLAN</b> screens.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click <b>Clear</b> to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

# C HAPTER 23 IP Se tup

## 23.1 IP Setup Overview

This chapter shows you how to configure IP settings and set up IP interfaces on the Switch using the **IP Setup** screens.

#### 23.1.1 What You Can Do

- Use the IP Status screen (Section 23.2 on page 164) to view the current IP interfaces and DNS server settings on the Switch.
- Use the IP Setup screen (Section 23.3 on page 166) to configure the default gateway device, the default domain name server and add IP domains.
- Use the **Network Proxy Configuration** screen (Section 23.4 on page 168) to configure network proxy configurations.

#### 23.1.2 IP Interfaces

The Switch needs an IP address for it to be managed over the network. When the Switch (in Standalone mode) fails to obtain an IP address from a DHCP server, the default static IP address 192.168.1.1 will be automatically added and used as the Switch's management IP address. The subnet mask specifies the network number portion of an IP address. The factory default subnet mask is 255.255.255.0.

On the Switch, an IP address is not bound to any physical ports. Since each IP address on the Switch must be in a separate subnet, the configured IP address is also known as IP interface (or routing domain). In addition, this allows routing between subnets based on the IP address without additional routers.

You can configure multiple routing domains on the same VLAN as long as the IP address ranges for the domains do not overlap. To change the IP address of the Switch in a routing domain, simply add a new routing domain entry with a different IP address in the same subnet.

You can configure up to 128 IP domains which are used to access and manage the Switch from the ports belonging to the pre-defined VLANs.

Note: You must configure a VLAN first. Each VLAN can have multiple management IP addresses, and you can log into the Switch through different management IP addresses simultaneously.

### 23.2 IP Status

Click SYSTEM > IP Setup > IP Status to display the screen as shown.

#### Figure 111 SYSTEM > IP Setup > IP Status

IP Status	IP Setup Netw	ork Proxy Configuratio	n			
Domain N	Domain Name Server					
	Domain Name 8	erver		Source		
	1/2.21.10.1			DECPV4		
IP Interfac	æ					
Index	IP Address	IP Subnet Mask	VID	Туре	àction	
1	192, 188, 2, 115	255.255.255.0	100	Stellie		
2	17221-4022	288.286.285.20	1.1	DECE	Hence Release	

The following table describes the labels in this screen.

#### Table 54 SYSTEM > IP Setup > IP Status

IABEL	DESC RIPTIO N
Domain Name Se	rver
Domain Name Server	This field displays the IP address of the DNS server.
Source	This field displays whether the DNS server address is configured manually ( <b>Static</b> ) or obtained automatically using <b>DHC Pv4</b> .
IP Interface	
Index	This field displays the index number of an entry.
IP Address	This field displays the IP address of the Switch in the IP domain.
IP Subnet Mask	This field displays the subnet mask of the Switch in the IP domain.
VID	This field displays the VLAN identification number of the IP domain on the Switch.
Туре	This shows whether this IP address is dynamically assigned from a DHCP server $(DHCP)$ or manually assigned (Static).
Renew	Click this to renew the dynamic IP address.
Release	Click this to release the dynamic IP address.

#### 23.2.1 IP Status Details

Use this screen to view IP status details. Click a number in the Index column in the SYSTEM > IP Setup > IP Status screen to display the screen as shown next.

Figure 112	SYSTEM > IP Setup > IP Status > IP Status Details: Static
------------	---

IP Status	IP Selup	Network Proxy Configuration
IP S Polos 3	> P Stehes D	elonik
IP Status D	etals	
Table		Statin.
×1.2		100
IF Adapts		199 145 9 115
Product M	kah.	200.155(200.0

Table 55 SYSTEM > IP Setup > IP Status > IP Status Details: Static

LABEL	DESC RIPTIO N
Туре	This shows the IP address is manually assigned (Static).
VID	This is the VLAN identification number to which an IP routing domain belongs.
IP Address	This is the IP address of your Switch in dotted decimal notation for example 192.168.1.1.
IP Subnet Mask	This is the IP subnet mask of your Switch in dotted decimal notation for example 255.255.255.0.

#### Figure 113 SYSTEM > IP Setup > IP Status > IP Status Details: DHCP

P Status	P Selop	Nelwork Proxy Configuration
IP Status (>	P Of thus De	stols
IP Storius Def	alis	
1994		DECE
MD .		I. State of the second s
If Address		172 01140 00
If Submellivics		255.255257.0
couse time		88400 seconds
denew line		-01400 kee on da
retard time		70600 secondo
eccel Proe Sko	ri -	2022401-01/00/00:50
Louise Time the		2022 01 02 00 00:00
Defort Colea	ev.	17201701054
JMS Jenner		172 21:10.1
1983 and ver		172213.1

The following table describes the labels in this screen.

Table 56 SYSTEM > IP Setup > IP Status > IP Status Details: DHCP

LABEL	DESC RIPIIO N
Туре	This shows the IP address is dynamically assigned from a DHCP server (DHCP).
VID	This is the VLAN identification number to which an IP routing domain belongs.
IP Address	This is the IP address of your Switch in dotted decimal notation for example 192.168.1.1.
IP Subnet Mask	This is the IP subnet mask of your Switch in dotted decimal notation for example 255.255.255.0.

XGS2220 Series User's Guide

IABEL	DESC RIPTIO N
Lease Time	This displays the length of time in seconds that this interface can use the current dynamic IP address from the DHCP server.
Renew Time	This displays the length of time from the lease start that the Switch will request to renew its current dynamic IP address from the DHCP server.
Rebind Time	This displays the length of time from the lease start that the Switch will request to get any dynamic IP address from the DHCP server.
Lease Time Start	This displays the date and time that the current dynamic IP address assignment from the DHCP server began. You should configure date and time in <b>SYSTEM</b> > <b>General Setup</b> .
Lease Time End	This displays the date and time that the current dynamic IP address assignment from the DHCP server will end. You should configure date and time in <b>SYSIEM</b> > <b>General Setup</b> .
Default Gateway	This displays the IP address of the default gateway assigned by the DHCP server. 0.0.0.0 means no gateway is assigned.
DNS Server	This displays the IP address of the primary and secondary DNS servers assigned by the DHCP server. 0.0.0.0 means no DNS server is assigned.

Table 56 SYSTEM > IP Setup > IP Status > IP Status Details: DHCP (continued)

#### 23.3 IP Se tup

Use this screen to configure the default gateway device, the default domain name server and add IP domains. Click **SYSTEM** > **IP** Se tup > **IP** Se tup in the navigation panel to display the screen as shown.

Note: The Switch allows you to set a static IP interface in the same subnet that already has a DHCP-assigned IP interface on the Switch. The Switch will use the static IP you set and the DHCP-assigned IP will be set to 0.0.0.0.

Figure 114 SYSTEM > IP Setup > IP Setup

e Santa qui					
uhan Daharang	<u>far ar</u>				
enderstense sed					
e an its eith.					
			April - second		
hieluse					
hiebez			a the state of the		0 ++++ #
nintus: G	trans	· Zationa	(* labor i Donk	#X-	Garry & Error

IABEL	DESC RIPIIO N
IP Setup	
Default Gateway	Type the IP address of the default outgoing gateway in dotted decimal notation, for example 192.168.1.254.
Domain Name Server 1/2	Enter a domain name server IPv4 address in order to be able to use a domain name instead of an IP address.

Table 57 SYSTEM > IP Setup > IP Setup

Table 57 SYSTEM > IP Setup > IP Setup (continued)	Table 57	SYSTEM > IF	Setup > IP Setup	etup (continued)
---	----------	-------------	------------------	------------------

IABEL	DESC RIPIIO N	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Cancel	Click Cancel to reset the fields to your previous configuration.	
IP Interface		
Use this section to	view and configure IP routing domains on the Switch.	
Index	This field displays the index number of an entry.	
IP Address	This field displays the IP address of the Switch in the IP domain.	
IP Subnet Mask	This field displays the subnet mask of the Switch in the IP domain.	
VID	This field displays the VLAN identification number of the IP domain on the Switch.	
Туре	This field displays the type of IP address status. Static or DHCP.	
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.	
Add/Edit	Click Add/Edit to add a new IP interface or edit a selected one.	
Delete	Click <b>Delete</b> to remove the selected IP interfaces.	

#### 23.3.1 Add/Edit IP Interfaces

Use this screen to add or edit IP interfaces. Click Add/Edit, or select an entry and click Add/Edit in the SYSTEM > IP Setup > IP Setup screen to display this screen.

O CHOF Clont	
Option 80	•
Closef C	Zero Corporation
O Skilk P Addres	
th Acches	1
17 Subject Mask	
40	
1.000	200 - 12
Auch	Clear Carnee

Figure 115 SYSTEM > IP Setup > IP Setup > Add/Edit


Table 58	SYSTEM > IP Setup > IP Setup > Add/Edit
10010-00	

IABEL	DESC RIPTIO N	
DHCP Client	Select this option if you have a DHCP server that can assign the Switch an IP address, subnet mask, a default gateway IP address and a domain name server IP address automatically.	
Option-60	DHCP Option 60 is used by the Switch for identification to the DHCP server using the VCI (Vendor Class Identifier) on the DHCP server. The Switch adds it in the initial DHCP discovery message that a DHCP client broadcasts in search of an IP address. The DHCP server can assi different IP addresses or options to clients with the specific VCI or reject the request from clie without the specific VCI.	
	Select this and enter the device identity you want the Switch to add in the DHCP discovery frames that go to the DHCP server. This allows the Switch to identify itself to the DHCP server.	
Class-ID	Enter a string of up to 32 printable ASCII characters to identify this Switch to the DHCP server. For example, Zyxel-TW. The string should not contain [?], [   ], [ '], [ "], or [,].	
Static IP Address	Select this option if you do not have a DHCP server or if you wish to assign static IP address information to the Switch. You need to fill in the following fields when you select this option.	
IP Address	Enter the IP address of your Switch in dotted decimal notation, for example, 192.168.1.1. This is the IP address of the Switch in an IP routing domain.	
IP Subnet Mask	Enter the IP subnet mask of an IP routing domain in dotted decimal notation, for example, 255.255.255.0.	
VID	Enter the VLAN identification number to which an IP routing domain belongs.	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Clear	Click Clear to clear the fields to the factory defaults.	
Cancel	Click <b>Cancel</b> to not save the configuration you make and return to the last screen.	

# 23.4 Network Proxy Configuration


The proxy server of an organization may prohibit communication between the Switch and NCC (Nebula Control Center) (See Section 20.1 on page 153). Use this screen to enable communication between the Switch and NCC through the proxy server.

Figure 116 Network Proxy Configuration Application



As of this writing, this setting only allows communication between the Switch and the NCC.

In status	If Setup	Network Froxy Configuration
Active		() arr
Server		
Port		
Authenticat	on	- CHF
Username		]
Password		
	δq	aly Cancel



LABEL	DESC RIPTIO N	
Active	Enable the switch button to enable communication between the Switch and NCC through a proxy server.	
Server	Enter the IP address (dotted decimal notation) or host name of the proxy server. When entering the host name, up to 128 alphanumeric characters are allowed for the <b>Server</b> except [?], [   ], ['], or ["].	
Port	Enter the port number of the proxy server (1 – 65535).	
Authentication	Enable the switch button to enable proxy server authentication using a Usemame and Password.	
Username	Enter a login user name from the proxy server administrator. Up to 32 alphanumeric characters are allowed for the <b>Usemame</b> except [?], [ ], ['], or ["].	
Password	Enter a login password from the proxy server administrator. Up to 32 alphanumeric characters are allowed for the <b>Password</b> except [?], [ ], ['], or ["].	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Cancel	Click Cancel to reset the fields to your previous configuration.	

Table 59	SYSTEM >	IP Setup > Network Pr	oxy Configuration
----------	----------	-----------------------	-------------------

# C HAPTER 24 IPv6

### 24.1 IPv6 Overview

This chapter introduces the IPv6 screens.

#### 24.1.1 What You Can Do

- Use the IPv6 Status screen (Section 24.2 on page 170) to view the IPv6 table and DNS server information.
- Use the IPv6 Global Setup screen (Section 24.3 on page 173) to configure the global IPv6 settings.
- Use the IPv6 Interface Setup screen (Section 24.4 on page 174) to view and configure IPv6 interfaces.
- Use the IPv6 Iink-Iocal Address Setup screen (Section 24.5 on page 175) to view and configure IPv6 link-local addresses.
- Use the IPv6 Global Address Setup screen (Section 24.6 on page 177) to view and configure IPv6 global addresses.
- Use the **IPv6 Neighbor Discovery Setup** screen (Section 24.7 on page 178) to view and configure neighbor discovery settings on each interface.
- Use the IPv6 Router Discovery Setup screen (Section 24.8 on page 180) to view and configure router discovery settings on each interface.
- Use the IPv6 Prefix Setup screen (Section 24.9 on page 182) to configure the Switch's IPv6 prefix list for each interface.
- Use the **IPv6 Neighbor Setup** screen (Section 24.10 on page 183) to configure static IPv6 neighbor entries in the Switch's IPv6 neighbor table.
- Use the DHC Pv6 Client Setup screen (Section 24.11 on page 184) to configure the Switch's DHCP settings when it is acting as a DHCPv6 client.

### 24.2 IPv6 Status

Click SYSTEM > IPv6 > IPv6 Status in the navigation panel to display the IPv6 status screen as shown next.

Figure 118	SYSTEM > IPv6 > IPv6 Status
------------	-----------------------------

Invé Status		
Domein Name Serve	r	
	-	
Domain Nar	the Server	Source
ifvé Table		
Index	Interfaced	Avires
1	VLAN1	C CN

Table 60 SYSTEM > IPv6 > IPv6 Status

IABEL	DESC RIPTIO N
Domain Name S	ierver
Domain Name Server	This field displays the IP address of the DNS server.
Source	This field displays whether the DNS server address is configured manually ( <b>Sta tic</b> ) or obtained automatically using <b>DHC Pv6</b> .
IPv6 Table	
Index	This field displays the index number of an IPv6 interface. Click on an index number to view more interface details.
Interface	This is the name of the IPv6 interface you created.
Active	This field displays whether the IPv6 interface is activated or not.

#### 24.2.1 IPv6 Interface Status Details

Use this screen to view a specific IPv6 interface status and detailed information. Click an interface index number in the **SYSTEM** > IPv6 > IPv

Figure 119	SYSTEM > IPv6 > IPv6 Status > IPv6 Interface	• Details
------------	--	-----------

wá Status			
Pváštolus > IPvá Interfece (	Details		
interface: VLAN1			
Static IPvi Active 04		DBCPv6 Clent Active 🦲 ON	
KITU Size	1500	Identity Association	
CIVP+8 Rote Limit Bucket Size	100	lA iyoe	[A-1] A
CiviPet for Elimit From Interval	10003	MD	11
ND DAD Aprilyo			0
Number of DAD Altempts			•
NS-Interval (millise cand)	1000	F2	D
ND Reachable Time (millikecond).	30200	State	
Init-Factal Address	WORKSAM HERBERCHAR	3D	
	[preferred]	Autometers a	
Clobal Unicast Address	1112 - 2	Professed Lifetime	0
Iolineed Carolys Address	102:02 101:::1 1102::1	Valid Diotimo	0
	102: bitecbb19	DNS	
		Domain Isl	
		Restart Bill GRyb Client	Restort

Table 61 SY	YSTEM > IPv6 >	IPv6 Status > IF	Pv6 Interface Details
-------------	----------------	------------------	-----------------------

IABEL	DESC RIPTIO N
Static IPv6 Activ	e
This field displays	s whether the IPv6 interface is activated or not.
MTU Size	This field displays the Maximum Transmission Unit (MTU) size for IPv6 packets on this interface.
ICMPv6 Rate Limit Bucket Size	This field displays the maximum number of ICMPv6 error messages which are allowed to transmit in a given time interval. If the bucket is full, subsequent error messages are suppressed.
ICMPv6 Rate Limit Error Interval	This field displays the time period (in milliseconds) during which ICMPv6 error messages of up to the bucket size can be transmitted. 0 means no limit.
ND DAD Active	This field displays whether Neighbor Discovery (ND) Duplicate Address Detection (DAD) is enabled on the interface.
Number of DAD Attempts	This field displays the number of consecutive neighbor solicitations the Switch sends for this interface.
NS-Interval (millisecon d)	This field displays the time interval (in milliseconds) at which neighbor solicitations are re-sent for this interface.
ND Reachable Time (millisecon d)	This field displays how long (in milliseconds) a neighbor is considered reachable for this interface.
Link-Local Address	This field displays the Switch's link-local IP address and prefix generated by the interface. It also shows whether the IP address is preferred, which means it is a valid address and can be used as a sender or receiver address.

XGS2220 Series User's Guide

IABEL	DESC RIPHO N		
Global Unicast Address	This field displays the Switch's global unicast address to identify this interface.		
Joined Group Address	This field displays the IPv6 multicast addresses of groups the Switch's interface joins.		
DHCPv6 Client	Active		
This field display	s whether the Switch acts as a DHCPv6 client to get an IPv6 address from a DHCPv6 server.		
Identity Associa	tion		
,	ciation (IA) is a collection of addresses assigned to a DHCP client, through which the server and age a set of related IP addresses. Each IA must be associated with exactly one interface.		
ІА Туре	The IA type is the type of address in the IA. Each IA holds one type of address. <b>IA_NA</b> means an identity association for non-temporary addresses and <b>IA_TA</b> is an identity association for temporary addresses.		
IAID	Each IA consists of a unique IAID and associated IP information.		
TI	This field displays the DHCPv6 T1 timer. After T1, the Switch sends the DHCPv6 server a Renew message.		
	An IA_NA option contains the T1 and T2 fields, but an IA_TA option does not. The DHCPv6 server uses T1 and T2 to control the time at which the client contacts with the server to extend the lifetimes on any addresses in the IA_NA before the lifetimes expire.		
T2	This field displays the DHCPv6 T2 timer. If the time T2 is reached and the server does not respond, the Switch sends a Rebind message to any available server.		
State	This field displays the state of the TA. It shows		
	Active when the Switch obtains addresses from a DHCpv6 server and the TA is created.		
	$\mathbf{Re}\mathbf{ne}\mathbf{w}$ when the TA's address lifetime expires and the Switch sends out a Renew message.		
	<b>Re bind</b> when the Switch does not receive a response from the original DHCPv6 server and sends out a Rebind message to another DHCPv6 server.		
SID	This field displays the DHCPv6 server's unique ID.		
Address	This field displays the Switch's global address which is assigned by the DHCPv6 server.		
Preferred Lifetime	This field displays how long (in seconds) that the global address remains preferred.		
Valid Lifetime	This field displays how long (in seconds) that the global address is valid.		
DNS	This field displays the DNS server address assigned by the DHCPv6 server.		
Domain List	This field displays the address record when the Switch queries the DNS server to resolve domain names.		
Restart DHCPv6 Client	Click <b>Re start</b> to send a new DHCP request to the DHCPv6 server and update the IPv6 address and DNS information for this interface.		

Table 61	SYSTEM > IPv6 >	IPv6 Status > IPv6 Interface Details	(continued)
	0.0.2		

# 24.3 IPv6 Global Setup

Use this screen to configure the global IPv6 settings. Click SYSTEM > IPv6 > IPv6 Global Setup to display the screen as shown next.

Figure 120 SYSTEM > IPv6 > IPv6 Global Setup

IPv4 Global Selop		
1956 Hoo Limit 1979 Mys Ketty anni due oct Size	64 100	
1078Pv8 Kelle tamil Environmetervel	1000 milisee	onds
Apply Co	nosi Cleor	

The following table describes the labels in this screen.

Table 62 SYSTEM > IPv6 > IPv6 Global Setup

LABEL	DESC RIPTIO N
IPv6 Hop Limit	Specify the maximum number of hops (from 1 to 255) in router advertisements. This is the maximum number of hops on which an IPv6 packet is allowed to transmit before it is discarded by an IPv6 router, which is similar to the TTL field in IPv4.
ICMPv6 Rate Limit Bucket Size	Specify the maximum number of ICMPv6 error messages (from 1 to 200) which are allowed to transmit in a given time interval. If the bucket is full, subsequent error messages are suppressed.
ICMPv6 Rate Limit Error Interval	Specify the time period (from 0 to 2147483647 milliseconds) during which ICMPv6 error messages of up to the bucket size can be transmitted. 0 means no limit.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.
Clear	Click Clear to reset the fields to the factory defaults.

# 24.4 IPv6 Interface Setup

Use this screen to view and configure an IPv6 interface you create in the **SYSTEM** > **Interface Setup** screen. Click **SYSTEM** > **IPv6** > **IPv6** Interface Setup to display the screen as shown next.

Figure 121 SYSTEM > IPv6 > IPv6 Interface Setup

IPv8 Interface	Setup		
			🖉 Lak
	Index.	Interface	Active
	I	VEANT	<b>1</b> 11

LABEL	DESC RIPHO N	
Index	This is the interface index number.	
Interface	This is the name of the IPv6 interface you created.	
Active	This field displays whether the IPv6 interface is activated or not.	
	Select an entry's check box to select a specific entry.	
Edit	Click Edit to edit the selected interface.	

Table 63 SYSTEM > IPv6 > IPv6 Interface Setup

#### 24.4.1 Edit an IPv6 Interface

Use this screen to turn on or off an IPv6 interface you create in the **SYSTEM** > **Interface Setup** screen. Select an entry and click **Edit** in the **SYSTEM** > **IPv6** > **IPv6 Interface Setup** screen to display the screen as shown next.

Figure 122 SYSTEM > IPv6 > IPv6 Interface Setup > Edit

interface.		VEANE 🗸
Mahar		(ON ())
Apply	Clear	Cancel

The following table describes the labels in this screen.

LABEL	DESC RIPTIO N
Interface	Select the IPv6 interface you want to configure.
Active	Enable the switch button to enable the interface.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click <b>Clear</b> to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

Table 64 SYSTEM > IPv6 > IPv6 Interface Setup > Edit

### 24.5 IPv6 Link-Local Address Setup

A link-local address uniquely identifies a device on the local network (the LAN). It is similar to a "private IP address" in IPv4. You can have the same link-local address on multiple interfaces on a device. A link-local unicast address has a predefined prefix of fe80::/10.

Use this screen to view and configure the interface's link-local address and default gateway. Click **SYSTEM** > **IPv6** Addressing > **IPv6** Link-Local Address Setup to display the screen as shown next.

Note: You should first create an IPv6 interface in the SYSTEM > Interface Setup screen.

Figure 123 SYSTEM > IPv6 > IPv6 Addressing > IPv6 Link-Local Address Setup

IPvé link-tocol Address Setup		IPv& Global Address Setup		
				📕 bát
	index	interlace	IPv8 Link-Loc of Address	ifvé Delaoti Galeway
	1	VIA01		

IABEL	DESC RIPHO N	
Index	This is the interface index number.	
Interface	This is the name of the IPv6 interface you created.	
IPv6 Link-Local Address	This is the static IPv6 link-local address for the interface.	
IPv6 Default Gateway	This is the default gateway IPv6 address for the interface.	
	Select an entry's check box to select a specific entry.	
Edit	Click Edit to edit the selected entry.	

Table 65 SYSTEM > IPv6 > IPv6 Addressing > IPv6 Link-Local Address Setup

#### 24.5.1 Edit an IPv6 Link-Local Address

Use this screen to configure the link-local address and default gateway of an IPv6 interface you create in the **SYSTEM** > **Interface Setup** screen. Select an entry and click **Edit** in the **SYSTEM** > **IPv6** > **IPv6 Addressing** > **IPv6 link-local Address Setup** screen to display this screen.

Figure 124 SYSTEM > IPv6 > IPv6 Addressing > IPv6 Link-Local Address Setup > Edit

VEAGE 🛩		
Apply	Clour	Cence

The following table describes the labels in this screen.

Table 66 SYSTEM > IPv6 > IPv6 Addressing > IPv6 Link-Local Address Setup > Edit

LABEL	DESC RIPTIO N
Interface	Select the IPv6 interface you want to configure.
Link-Local Address	Manually configure a static IPv6 link-local address for the interface.
Default Gateway	Set the default gateway IPv6 address for the interface. When an interface cannot find a routing information for a frame's destination, it forwards the packet to the default gateway.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.

XGS2220 Series User's Guide

Table 66	SVSTEM > IPV4 > IPV4	Addressing > IPv61	ink-Local Address Setur	> Edit (continued)
	3131E/VI / IF VO / IF VO	Addressing – ir vo L	INK-LOCAI AAAIess seid	

LABEL	DESC RIPIIO N
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

# 24.6 IPv6 Global Address Setup

Use this screen to view and configure the interface's IPv6 global address. Click **SYSTEM** > **IPv6** Addressing > **IPv6** Global Address Setup to display the screen as shown next.

Figure 125 SYSTEM > IPv6 > IPv6 Addressing > IPv6 Global Address Setup

IPv6 Link-Local Address Selup	Ifvé Global Address Selup		
IPvé Domain Name Server			
Domain Namo Sorver 1			
Comolo Nome Server 2			
IPvé Global Address Setup	Apply Control		
		🗘 Add/Edit	
index Inter	ioce IPv5 Global Address/Pret	ts Length EUI-64	

Table 67 SYSTEM > IPv6 > IPv6 Addressing > IPv6 Global Address Setup

IABEL	DESC RIPTIO N			
IPv6 Domain Na	me Server			
Domain Name Server 1/2	Enter a domain name server IPv6 address in order to be able to use a domain name instead of an IP address.			
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.			
Cancel	Click this to reset the <b>Domain Name Server</b> values in this screen to their last-saved values.			
IPv6 Global Ada	Iress Setup			
Index	This is the interface index number.			
Interface	This is the name of the IPv6 interface you created.			
IPv6 Global Address/Prefix Length	This field displays the IPv6 global address and prefix length for the interface.			
EUI-64	This shows whether the interface ID of the global address is generated using the EUI-64 format.			
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.			

Table 67 SYSTEM > IPv6 > IPv6 Addressing > IPv6 Global Address Setup (continued)

LABEL	DESC RIPIIO N
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.
Delete	Click <b>Delete</b> to remove the selected entries.

#### 24.6.1 Add/Edit an IPv6 Global Address

Use this screen to configure the interface's IPv6 global address. Click Add/Edit, or select an entry and click Add/Edit in the SYSTEM > IPv6 Addressing > IPv6 Global Address Setup screen to display this screen.

Figure 126 SYSTEM > IPv6 > IPv6 Addressing > IPv6 Global Address Setup > Add/Edit

Interface The AC-Clean Address	MANIX		I	10.34
- who being the			·	
		Apply	Glean	Geneel

The following table describes the labels in this screen.

Table 68	SYSTEM > IPv6 >	IPv6 Addressing > IPv6 C	Global Address Setup > Add/Edit
	0.0.5		

IABEL	DESC RIPTIO N
Interface	Select the IPv6 interface you want to configure.
IPv6 Global Address	Manually configure a static IPv6 global address for the interface.
Prefix Length	Specify an IPv6 prefix length that specifies how many most significant bits (start from the left) in the address compose the network address.
EUI-64	Select this option to have the interface ID be generated automatically using the EUI-64 format.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click <b>Clear</b> to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

### 24.7 IPv6 Neighbor Discovery Setup

Use this screen to configure neighbor discovery settings for each interface. Click **SYSTEM** > **IPv6** > **IPv6 Neighbor Discovery** > **IPv6 Neighbor Discovery Setup** to display the screen as shown next.

IPv6 Neigh	hbor Discov	ery Setup	IPvé Router Discover	y Setup	IPv6 Prefix Setup
					🖉 Edit
	Index	Interloce	DAD Attempts	NS Interval	Reachable Time
	1	VLANI	1	1000	30000
	2	VLANG	1	1000	30000

Figure 127 SYSTEM > IPv6 > IPv6 Neighbor Discovery > IPv6 Neighbor Discovery Setup

Table 69	SYSTEM > IPV6 >	IPv6 Neighbor Discover	y > IPv6 Neighbor Discovery Setup

IABEL	DESC RIPTIO N
Index	This is the interface index number.
Interface	This is the name of the IPv6 interface you created.
DAD Attempts	This field displays the number of consecutive neighbor solicitations the Switch sends for this interface.
NS Interval	This field displays the time interval (in milliseconds) at which neighbor solicitations are re-sent for this interface.
Reachable Time	This field displays how long (in milliseconds) a neighbor is considered reachable for this interface.
	Select an entry's check box to select a specific entry.
Edit	Click Edit to edit the selected entry.

#### 24.7.1 Edit an IPv6 Neighbor Discovery

Use this screen to configure neighbor discovery settings for each interface. Select an entry and click **Edit** in the **SYSTEM** > **IPv6** > **IPv6** Neighbor Discovery > **IPv6** Neighbor Discovery Setup screen to display this screen.

Figure 128 SYSTEM > IPv6 > IPv6 Neighbor Discovery > IPv6 Neighbor Discovery Setup > Edit

hlerioce	ATV01 ->	
040 attempts	1	
93 hierod	1005	mili socionale
veret stole 1 me	30000	ndlike conda
	Apply Size	ar Concel

The following table describes the labels in this screen.

Table 70 SYSTEM > IPv6 > IPv6 Neighbor Discovery > IPv6 Neighbor Discovery Setup > Edit

LABEL	DESC RIPTIO N
Interface	Select the IPv6 interface you want to configure.
DAD Attempts	The Switch uses Duplicate Address Detection (DAD) with neighbor solicitation and advertisement messages to check whether an IPv6 address is already in use before assigning it to an interface.
	Specify the number of consecutive neighbor solicitations (from 0 to 600) the Switch sends for this interface. Enter 0 to turn off DAD.

XGS2220 Series User's Guide

IABEL	DESC RIPHO N
NS Interval	Specify the time interval (from 1000 to 3600000 milliseconds) at which neighbor solicitations are re- sent for this interface.
Reachable Time	Specify how long (from 1000 to 3600000 milliseconds) a neighbor is considered reachable for this interface.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click <b>Clear</b> to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

Table 70 SYSTEM > IPv6 > IPv6 Neighbor Discovery > IPv6 Neighbor Discovery Setup > Edit (continued)

# 24.8 IPv6 Router Discovery Setup

Use this screen to configure router discovery settings for each interface. Click SYSTEM > IPv6 > IPv6 Ne ig hbor Discovery > IPv6 Router Discovery Setup to display the screen as shown next.

ws Neigh	bor Discovery Sehip	IPv& Router Discovery Setup	IPvo Prefix Selup
----------	---------------------	-----------------------------	-------------------

SYSTEM > IPV6 > IPV6 Neighbor Discovery > IPV6 Pouter Discovery Setup

							E5.95
	index .	Interface	Flogs	Winimom Intervet	Maximum Interval	(betma)	Suppress
EV.	( <b>1</b> )	25.4681	150	1500	3031	1000	(3)1
11	4	V 4765		14(0)	5007	19210	1111

Table 71 SYSTEM > IPv6 > IPv6 Neighbor Discovery > IPv6 Router Discovery Setup

LABEL	DESC RIPTIO N
Index	This is the interface index number.
Interface	This is the name of the IPv6 interface you created.
Flags	This field displays whether IPv6 hosts use DHCPv6 to obtain IPv6 stateful addresses ( $\mathbf{M}$ ) and/or additional configuration settings ( $\mathbf{O}$ ).
Minimum Interval	This field displays the minimum time interval at which the Switch sends router advertisements for this interface.
Maximum Interval	This field displays the maximum time interval at which the Switch sends router advertisements for this interface.
Lifetime	This field displays how long the router in router advertisements can be used as a default router for this interface.
Suppress	This field displays whether the Switch sends router advertisements and responses to router solicitations on this interface ( <b>ON</b> ) or not ( <b>OFF</b> ).
	Select an entry's check box to select a specific entry.
Edit	Click Edit to edit the selected entry.

#### 24.8.1 Edit IPv6 Router Discovery

Use this screen to configure router discovery settings for each interface. Select an entry and click **Edit** in the **SYSTEM** > **IPv6** > **IPv6** Neighbor Discovery > **IPv6** Router Discovery Setup screen to display the screen as shown next.




Figure 130 SYSTEM > IPv6 > IPv6 Neighbor Discovery > IPv6 Router Discovery Setup > Edit

Table 70	SVSTENA S IDV/ S IDV/ Niciahhar Diag	avan ( > ID) / Dautar Disaavan (Satur > Edit
		overy > IPv6 Router Discovery Setup > Edit

LABEL	DESC RIPTIO N	
Interface	Select the IPv6 interface you want to configure.	
Flags	Select the <b>Managed Config Flag</b> option to have the Switch set the "managed address configuration" flag (the M flag) to 1 in IPv6 router advertisements, which means IPv6 hosts use DHCPv6 to obtain IPv6 stateful addresses. De-select the option to set the flag to 0 and the host will not use DHCPv6 to obtain IPv6 stateful addresses.	
	Select the <b>OtherConfig Flag</b> option to have the Switch set the "Other stateful configuration" flag (the O flag) to 1 in IPv6 router advertisements, which means IPv6 hosts use DHCPv6 to obtain additional configuration settings, such as DNS information. De-select the option to set the flag to 0 and the host will not use DHCPv6 to obtain additional configuration settings.	
Minimum Interval	Specify the minimum time interval (from 3 to 1350 seconds) at which the Switch sends router advertisements for this interface.	
	Note: The minimum time interval cannot be greater than three-quarters of the maximum time interval.	
Maximum Interval	Specify the maximum time interval (from 4 to 1800 seconds) at which the Switch sends router advertisements for this interface.	
Lifetime	Specify how long (from 0 to 9000 seconds) the router in router advertisements can be used as a default router for this interface.	
Suppress	Enable the switch button to set the Switch to not send router advertisements and responses to router solicitations on this interface.	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Clear	Click Clear to clear the fields to the factory defaults.	
Cancel	Click Cancel to not save the configuration you make and return to the last screen.	

## 24.9 IPv6 Pre fix Se tup

Use this screen to configure the Switch's IPv6 prefix list for each interface. Click **SYSTEM** > **IPv6** > **IPv6 Ne ig hb or Disc overy** > **IPv6 Pre fix Se tup** to display the screen as shown next.

Figure 131 SYSTEM > IPv6 > IPv6 Neighbor Discovery > IPv6 Prefix Setup

IPv6 Neigh	bor Discov	ery Selup	IFv6 Router Discovery 3	ielup	irvé t	refix Selup
					T-11	C. Parta la
_				O Add	Volid	Eviste Freferred
	Index	Interface	Prefix	L.	Petme	Ulatime

The following table describes the labels in this screen.

LABEL	DESC RIPTIO N
Index	This is the interface index number.
Interface	This is the name of the IPv6 interface you created.
Prefix	This field displays the IPv6 prefix and prefix length that the Switch includes in router advertisements for this interface.
Valid Lifetime	This field displays the IPv6 prefix valid lifetime.
Preferred Lifetime	This field displays the preferred lifetime of an IPv6 address generated from the prefix.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.
Delete	Click <b>De le te</b> to remove the selected entries.

#### 24.9.1 Add/Edit IPv6 Pre fix

Use this screen to configure the Switch's IPv6 prefix list for each interface. Click Add/Edit, or select an entry and click Add/Edit in the SYSTEM > IPv6 > IPv6 Neighbor Discovery > IPv6 Prefix Setup screen to display this screen.

Figure 132 SYSTEM > IPv6 > IPv6 Neighbor Discovery > IPv6 Prefix Setup > Add/Edit

Interface.	VIAN' V
Prelo.	
Profix longth	I
Void Deline	se canada
Preferred Lite inne	2402000 (K
Па де	<ul> <li>□ iuo kutooonig Flag</li> <li>□ iuo Gelick Flag</li> <li>□ iuo setvatisa Flag</li> </ul>
	Apply Oleon Concel

The following table describes the labels in this screen.

LABEL	DESC RIPIIO N	
Interface	Select the IPv6 interface you want to configure.	
Prefix	Set the IPv6 prefix that the Switch includes in router advertisements for this interface.	
Prefix Length	Set the prefix length that the Switch includes in router advertisements for this interface.	
Valid Lifetime	Specify how long (from 0 to 4294967295 seconds) the prefix is valid for on-link determination.	
Preferred Lifetime	Specify how long (from 0 to 4294967295 seconds) that addresses generated from the prefix remain preferred.	
	The preferred lifetime cannot exceed the valid lifetime.	
Flags	Select No-Autoconfig Flag to not allow IPv6 hosts to use this prefix.	
	Select No-Onlink Flag to not allow the specified prefix to be used for on-link determination.	
	Select <b>No-Advertise Flag</b> to set the Switch to not include the specified IPv6 prefix, prefix length in router advertisements for this interface.	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Clear	Click Clear to clear the fields to the factory defaults.	
Cancel	Click Cancel to not save the configuration you make and return to the last screen.	

Table 74 SYSTEM > IPv6 > IPv6 Neighbor Discovery > IPv6 Prefix Setup > Add/Edit

## 24.10 IPv6 Neighbor Setup

Use this screen to view and configure static IPv6 neighbor entries in the Switch's IPv6 neighbor table to store the neighbor information permanently. Click **SYSTEM** > IPv6 > IPv6 Ne ighbor Setup to display the screen as shown next.

Figure 133	SYSTEM > $IPv6$ > $IPv6$ Neighbor Setup
Inguito 100	ererent in ver in vertieigniser eerep

IF	'vé Neighi	bor Setup			
_					
					😋 Add/Edit 🛛 🍵 Delete
		Index	Interface	<b>Neighbor Address</b>	MAC

The following table describes the labels in this screen.

Tal	ole 75	SYSTEM > IPv6 > IPv6 Neigh	bor Setup

LABEL	DESC RIPTIO N
Index	This is the interface index number.
Interface	This is the name of the IPv6 interface you created.
Neighbor Address	This field displays the IPv6 address of the neighboring device which can be reached through the interface.
MAC	This field displays the MAC address of the neighboring device which can be reached through the interface.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.

XGS2220 Series User's Guide

Table 75 SYSTEM > IPv6 > IPv6 Neighbor Setup (continued)

IABEL	DESC RIPIIO N
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.
Delete	Click <b>Delete</b> to remove the selected entries.

### 24.10.1 Add/Edit IPv6 Neighbor

Use this screen to create a static IPv6 neighbor entry. Click Add/Edit, or select an entry and click Add/ Edit in the SYSTEM > IPv6 > IPv6 Neighbor Setup screen to display this screen.

Figure 134	SYSTEM > IPv6 > IPv6 Neighbor Setup > Add/Edit	
Figure 134	STSTEM > IPV6 > IPV6 IVEIGNDOL SETUD > Add/t	zan

Interfacio	$\forall (\Delta X, \nabla)$		
Interface ID			
Neighber Address			
M4C			
	Apply	Clear	Concel

The following table describes the labels in this screen.

Table 76 SYSTEM > IPv6 > IPv6 Neighbor Setup > Add/Edit

IABEL	DESC RIPTIO N
Interface	Select the type of IPv6 interface for which you want to configure. The Switch supports the VLAN interface type for IPv6 at the time of writing.
Interface ID	Specify a unique identification number (from 1 to 4094) for the interface.
	A static IPv6 neighbor entry displays in the <b>MONITOR</b> > <b>IPv6</b> Neighbor Table screen only when the interface ID is also created in the <b>SYSTEM</b> > Interface Setup screen.
	To have IPv6 function properly, you should configure a static VLAN with the same ID number in the $\mathbf{SWTICHING} > \mathbf{VLAN}$ screens.
Neighbor Address	Specify the IPv6 address of the neighboring device which can be reached through the interface.
MAC	Specify the MAC address of the neighboring device which can be reached through the interface.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

## 24.11 DHC Pv6 Client Setup

Use this screen to configure the Switch's DHCP settings when it is acting as a DHCPv6 client. Click **SYSTEM** > **IPv6** > **DHCPv6** Client Setup to display the screen as shown next.

IPvő DH	ICPv6 Cile	nt Setup		·			
							📝 Edit
	Index.	Interloce	IA-NA	Rapid. Commit	DINS	Dominin-List	Information Befresh Minimum
	ī	VLANI	ON D	09	OFF )	Off	86400
	2	VEANS	07		CEF	OFF	66400

The following table describes the labels in this screen.

Table 77	SYSTEM > IPv6 > DHCPv6 Client Setup

IABEL	DESC RIPIIO N
Index	This is the interface index number.
Interface	This is the name of the IPv6 interface you created.
IA-NA	This field displays whether the Switch obtains a non-temporary IP address from the DHCPv6 server.
Rapid-Commit	This field displays whether the Switch obtains information from the DHCPv6 server by a rapid two- message exchange.
DNS	This field displays whether the Switch obtains DNS server IPv6 addresses from the DHCPv6 server.
Domain-List	This field displays whether the Switch obtains a list of domain names from the DHCP server.
Information Refresh Minimum	This field displays the time interval (in seconds) at which the Switch exchanges other configuration information with a DHCPv6 server again.
	Select an entry's check box to select a specific entry.
Edit	Click Edit to edit the selected entry.

#### 24.11.1 Edit DHC Pv6 Client

Use this screen to configure the Switch's DHCP settings when it is acting as a DHCPv6 client. Select an entry and click **Edit** in the **SYSTEM** > **IPv6** > **DHCPv6 Client Setup** screen to display this screen.

Interface.	VLANT V
LA Type	🛃 IA-NA 🔄 Ropic - Commit
Colona	<ul> <li>Diss</li> <li>Dismoin Ust</li> </ul>
internation Reinerti Minimum	86400 socionds
A	aply Clean Cancel

IABEL	DESC RIPIIO N
Interface	Select the IPv6 interface you want to configure.
ІА Туре	Select IA-NA to set the Switch to get a non-temporary IP address from the DHCPv6 server for this interface.
	Optionally, you can also select <b>Rapid-Commit</b> to have the Switch send its DHCPv6 Solicit message with a Rapid Commit option to obtain information from the DHCPv6 server by a rapid two- message exchange. The Switch discards any Reply messages that do not include a Rapid Commit option. The DHCPv6 server should also support the Rapid Commit option to have it work well.
Options	Select <b>DNS</b> to have the Switch obtain DNS server IPv6 addresses and/or select <b>Domain-List</b> to have the Switch obtain a list of domain names from the DHCP server.
Information Refresh Minimum	Specify the time interval (from 600 to 4294967295 seconds) at which the Switch exchanges other configuration information with a DHCPv6 server again.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

Table 78 SYSTEM > IPv6 > DHCPv6 Client Setup > Edit

# C HAPTER 25 Logins

## 25.1 Set Up Login Accounts

Up to five people (one administrator and four non-administrators) may access the Switch through Web Configurator at any one time.

• An administrator is someone who can both view and configure Switch changes. The user name for the Administrator is always **admin**. The default administrator password is **1234**.

Note: It is highly recommended that you change the default administrator password (1234).

• A non-administrator (user name is something other than **admin**) is someone who can view and/or configure Switch settings. The configuration right varies depending on the user's privilege level.

Click **SYSTEM**> **Logins** to view the screen as shown.

dministrator -				
2011-000-000-000				
Sel Passened		() ()		
leve Peterschill				
Satuad la comini	-	1		
		is a new possiveral when we	eryddichange II. Bretestern with	eek vaa oo Hi
	a state of the order of the test of the			
with the second second		chemication and sectored		AAN 68.53 5.47
dit Logins				
dif Logins Jogin			Setype to confirm	Faktlege
	An indian pada	chan your consistent.		
login	An indian pada	chan your consistent.		
login !	An indian pada	chan your consistent.		
E.	An indian pada	chan your consistent.		

Figure 137 SYSTEM > Logins

Note: The input string in any field of this screen should not contain [?], [|], ['], ["] or [,]. In the **Password** fields, [space] is also not allowed.

IABEL	DESC RIPTIO N		
Administrator	•		
This is the default ad user name.	Iministrator account with the "admin" user name. You cannot change the default administrato		
Old Password	Type the existing system password (1234 is the default password when shipped).		
New Password	Enter your new system password. You can enter up to 32 printable ASCII characters.		
Retype to confirm	Retype your new system password for confirmation. You can enter up to 32 printable ASCII characters.		
Edit Logins			
give users higher pri	passwords for up to four users. These users can have read-only or read/write access. You can vileges through the Web Configurator or the CLI. For more information on assigning privileges the Ethernet Switch CLI Reference Guide.		
Login	This is the index of an user account.		
User Name	Set a user name (up to 32 printable ASCII characters except [?], [ ], ['], or [,]).		
Password	Enter your new system password.		
Retype to confirm	Retype your new system password for confirmation.		
Privilege	<ul> <li>Type the privilege level for this user. At the time of writing, users may have a privilege level of 0 3, 13, or 14 representing different configuration rights as shown below.</li> <li>0 – Display basic system information.</li> <li>3 – Display configuration or status.</li> <li>13 – Configure features except for login accounts, SNMP user accounts, the authentication method sequence and authorization settings, multiple logins, administrato and enable passwords, and configuration information.</li> <li>14 – Configure login accounts, SNMP user accounts, the authentication method sequence and authorization display.</li> <li>14 – Configure login accounts, snultiple logins, and administrator and enable passwords, and configuration information.</li> <li>Users can run command lines if the session's privilege level is greater than or equal to the command's privilege level. The session privilege initially comes from the privilege of the login account. For example, if the user has a privilege of 5, he or she can run commands that requires privilege level of 5 or less but not more.</li> </ul>		
Apply	Click Apply to save your changes to the Switch's run-time memory. The Switch loses these		
	changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.		

# C HAPTER 26 SNMP

## 26.1 SNMPOverview

This chapter introduces the SNMP screens and shows you how to setup SNMP settings for management.

#### 26.1.1 What You Can Do

- Use the **SNMP** screen (Section 26.2 on page 189) to configure general SNMP settings.
- Use the **SNMP User** screen (Section 26.3 on page 191) to create SNMP users for authentication with managers using SNMP v3 and associate them to SNMP groups.
- Use the **SNMP Trap Group** screen (Section 26.4 on page 193) to specify the types of SNMP traps that should be sent to each SNMP manager.
- Use the SNMP Thap Port screen (Section 26.5 on page 194) to enable/disable sending SNMP traps on a port.

## 26.2 Configure SNMP

Use this screen to configure your SNMP settings.

Click **SYSTEM** > **SNMP** to view the screen as shown.

thereas see	tting			
- 1675)	Ŷ			
(Corror)	17. To	bits.	10	
Corners	iy a	4.6cc		
e Comino	ols 2	- sile		
p Destin	alion			
Index	Version	P	fot	Usemanne
T	[125 v]	0.0.0.0	162	
25	200 m	(0000)	162	
3	22.0	0.000	102	
	[v:t:w]	landa	14.	

#### Figure 138 SYSTEM > SNMP

Note: The string of any field in this screen should not contain [?], [|], ['], ["] or [,].

The following table describes the labels in this screen.

LABEL	DESC RIPTIO N
General Setting	
Use this section to sp	pecify the SNMP version and community (password) values.
Version	Select the SNMP version for the Switch. The SNMP version on the Switch must match the version on the SNMP manager. Choose SNMP version 2c $(v2c)$ , SNMP version 3 $(v3)$ or both $(v3v2c)$ .
	SNMP version 2c is backwards compatible with SNMP version 1.
Get Community	Enter the <b>GetCommunity</b> string, which is the password for the incoming Get- and GetNext-requests from the management station.
	The GetCommunity string is only used by SNMP managers using SNMP version 2c or lower.
Set Community	Enter the <b>Set Community</b> string, which is the password for incoming Set- requests from the management station.
	The Set Community string is only used by SNMP managers using SNMP version 2c or lower.
Trap Community	Enter the <b>Thap Community</b> string, which is the password sent with each trap to the SNMP manager.
	The Thap Community string is only used by SNMP managers using SNMP version 2c or lower.
Trap Destination	
Use this section to c	onfigure where to send SNMP traps from the Switch.
Index	This is the index of a trap destination.
Version	Specify the version of the SNMP trap messages.
IP	Enter the IP addresses of up to four managers to send your SNMP traps to.

#### Table 80 SYSTEM > SNMP

XGS2220 Series User's Guide

IABEL	DESC RIPTIO N
Port	Enter the port number upon which the manager listens for SNMP traps.
Username	Enter the user name to be sent to the SNMP manager along with the SNMP v3 trap. This user name must match an existing account on the Switch (configured in the <b>SYSTEM</b> > $SNMP Use r$ screen).
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 80 SYSTEM > SNMP (continued)

## 26.3 Configure SNMP User

Use this screen to create SNMP users for authentication with managers using SNMP v3 and associate them to SNMP groups. An SNMP user is an SNMP manager. Click **SYSTEM** > **SNMP** > **SNMP** User to view the screen as shown.

Figure 139 SYSTEM > SNMP > SNMP Us	Figure 139	SYSTEM > SNMP > SNMP Use
------------------------------------	------------	--------------------------

SHMP	SNMP (Isor	SN/AP Trop	Group	SNMP Trap Fort		
					C Actribut	The state of the s
	Index	livemotive	Security Devel	Authentication	hivady	Group

The following table describes the labels in this screen.

LABEL	DESC RIPTIO N
Index	This is a read-only number identifying a login account on the Switch.
Username	This field displays the user name of a login account on the Switch.
Security Level	This field displays whether you want to implement authentication and/or encryption for SNMP communication with this user.
Authentication	This field displays the authentication algorithm used for SNMP communication with this user.
Privacy	This field displays the encryption method used for SNMP communication with this user.
Group	This field displays the SNMP group to which this user belongs.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.
Delete	Click <b>Delete</b> to remove the selected entries.

Table 81 SYSTEM > SNMP > SNMP User

#### 26.3.1 Add/Edit SNMP User

Use this screen to create SNMP users for authentication with managers using SNMP v3 and associate them to SNMP groups. An SNMP user is an SNMP manager. Click **Add/Edit**, or select an entry and click **Add/Edit** in the **SYSTEM > SNMP > SNMP User** screen to view the screen.

Note: Use the user name and password of the login accounts you specify in this screen to create accounts on the SNMP v3 manager.

Figure 140	SYSTEM > SNMP > SNMP User > Add/Edit
------------	--------------------------------------

Usemanie				
Secondly Level	no culh v			
Automicolian	MDS	Posword		
Pfivolog	DES 👳	Fassword		
Group	odmin v			
		Apply	Clear	Concel

LABEL	DESC RIPTIO N
Username	Specify the user name (up to 32 printable ASCII characters) of a login account on the Switch. The string should not contain [?], [   ], [ ' ], [ "] or [,].
Security Level	Select whether you want to implement authentication and/or encryption for SNMP communication from this user. Choose:
	<ul> <li>no auth – to use the user name as the password string to send to the SNMP manager. This is equivalent to the Get, Set and Trap Community in SNMP v2c. This is the lowest security level.</li> </ul>
	• <b>auth</b> – to implement an authentication algorithm for SNMP messages sent by this user.
	• <b>priv</b> – to implement authentication and encryption for SNMP messages sent by this user. This is the highest security level.
	Note: The settings on the SNMP manager must be set at the same security level or higher than the security level settings on the Switch.
Authentication	Select an authentication algorithm. <b>MD5</b> (Message Digest 5) and <b>SHA</b> (Secure Hash Algorithm) are hash algorithms used to authenticate SNMP data. SHA authentication is generally considered stronger than MD5, but is slower.
Password	Enter the password of up to 32 printable ASCII characters (except [?], [ ], ['], ["], [space], or [,]) for SNMP user authentication.
Privacy	Specify the encryption method for SNMP communication from this user. You can choose one of the following:
	<ul> <li>DES – Data Encryption Standard is a widely used (but breakable) method of data encryption. It applies a 56-bit key to each 64-bit block of data.</li> </ul>
	<ul> <li>AES – Advanced Encryption Standard is another method for data encryption that also uses a secret key. AES applies a 128-bit key to 128-bit blocks of data.</li> </ul>
Password	Enter the password of up to 32 printable ASCII characters (except [?], [ ], ['], ["], [space], or [,]) for encrypting SNMP packets.
Group	SNMP v3 adopts the concept of View-based Access Control Model (VACM) group. SNMP managers in one group are assigned common access rights to MIBs. Specify in which SNMP group this user is.
	a dmin – Members of this group can perform all types of system configuration, including the management of administrator accounts.
	<b>re a d-write</b> – Members of this group have read and write rights, meaning that the user can create and edit the MIBs on the Switch, except the user account and AAA configuration.
	$\mathbf{re}  \mathbf{a}  \mathbf{d} \cdot \mathbf{o}  \mathbf{n} \mathbf{l} \mathbf{y}$ – Members of this group have read rights only, meaning the user can collect information from the Switch.

IABEL	DESC RIPTIO N
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

Table 82 SYSTEM > SNMP > SNMP User > Add/Edit (continued)

# 26.4 Configure SNMP Trap Group

Use this screen to specify the types of SNMP traps that should be sent to each SNMP manager. Click **SYSTEM > SNMP > SNMP Tiap Group** to view the screen as shown.

Figure 141 SYSTEM > SNMP > SNMP Trap Group

SNMP SNMP User	SNWP frop Group	SNMP Trap Port			
Trap Dectination I ?					
🔲 system			L miertace		
<ul> <li>colditert</li> <li>temperature</li> <li>Innergale</li> <li>cont</li> </ul>	vernstert    velloge    koopgraat    koopgraat	Compared Co	<ul> <li>Inkup</li> <li>Indravelakev.ddm</li> <li>Incented.</li> </ul>	⊡ linbdown ⊟ storre-coniko	☐ Idp □ a/d
			AAA     Duthenilogitar	Reuterication	🗌 accounting
			🗆 Svilah		
i eko	hoospute		i nip i o colfrer	_ wacisble	i war
			Apple Gancel		

Table 83	SYSTEM >	SNMP	> SNMP	Trap Group
----------	----------	------	--------	------------

IABEL	DESC RIPTIO N
Trap Destination IP	Select one of your configured trap destination IP addresses. These are the IP addresses of the SNMP managers. You must first configure a trap destination IP address in the <b>SYSTEM</b> > <b>SNMP</b> screen.
	Use the rest of the screen to select which traps the Switch sends to that SNMP manager.
	Select the individual SNMP traps that the Switch is to send to the SNMP station. The traps are grouped by category. Selecting a category in the heading row automatically selects all of the SNMP traps under that category. Clear the check boxes for individual traps that you do not want the Switch to send to the SNMP station. Clearing a category's check box automatically clears all of the category's trap check boxes (the Switch only sends traps from selected categories).
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

## 26.5 Enable or Disable Sending of SNMP Traps on a Port

Click **SYSTEM** > **SNMP** > **SNMP** Thap Port to view the screen as shown. Use this screen to set whether a trap received on the ports would be sent to the SNMP manager.

Figure 142 SYSTEM > SNMP > SNMP Trap Port

SNMP	SNMP User	SNMP Trap Group	SNMP Trop Port
Collers	mau <mark>e</mark> cco]		
	Port	Activ	e
	1.1		
		5	
	12		
	14	8	
	Â.	8	
	2.4	8	
	8		
	1	5	
	$\sim$		$\sim$
		~ ~ ~	
	1	Apply General	

The following table describes the labels in this screen.

Table 84	SYSTEM > SNMP > SN	MP Trap Port
----------	--------------------	--------------

IABEL	DESC RIPIIO N
Options	Select the trap type you want to configure here.
Port	This field displays a port number.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some of the settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Changes in this row are copied to all the ports as soon as you make them.
Active	Select this check box to enable the trap type of SNMP traps on this port. The Switch sends the related traps received on this port to the SNMP manager.
	Clear this check box to disable the sending of SNMP traps on this port.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.


## 26.6 Technical Reference

This section provides technical background information on the topics discussed in this chapter.

#### 26.6.1 About SNMP

Simple Network Management Protocol (SNMP) is an application layer protocol used to manage and monitor TCP/IP-based devices. SNMP is used to exchange management information between the network management system (NMS) and a network element (NE). A manager station can manage and monitor the Switch through the network through SNMP version 1 (SNMPv1), SNMP version 2c or SNMP version 3. The next figure illustrates an SNMP management operation. SNMP is only available if TCP/IP is configured.





An SNMP managed network consists of two main components: agents and a manager.

An agent is a management software module that resides in a managed Switch (the Switch). An agent translates the local management information from the managed Switch into a form compatible with SNMP. The manager is the console through which network administrators perform network management functions. It executes applications that control and monitor managed devices.

The managed devices contain object variables or managed objects that define each piece of information to be collected about a Switch. Examples of variables include number of packets received, node port status, and so on. A Management Information Base (MIB) is a collection of managed objects. SNMP allows a manager and agents to communicate for the purpose of accessing these objects.

SNMP itself is a simple request or response protocol based on the manager or agent model. The manager issues a request and the agent returns responses using the following protocol operations:

IABEL	DESC RIPTIO N
Get	Allows the manager to retrieve an object variable from the agent.
GetNext	Allows the manager to retrieve the next object variable from a table or list within an agent. In SNMPv1, when a manager wants to retrieve all elements of a table from an agent, it initiates a Get operation, followed by a series of GetNext operations.
Set	Allows the manager to set values for object variables within an agent.
Trap	Used by the agent to inform the manager of some events.

Table 85 SNMP Commands

#### $SNMP\,v3$ and $Se\,c\,urity$

SNMP v3 enhances security for SNMP management. SNMP managers can be required to authenticate with agents before conducting SNMP management sessions.

Security can be further enhanced by encrypting the SNMP messages sent from the managers.

Encryption protects the contents of the SNMP messages. When the contents of the SNMP messages are encrypted, only the intended recipients can read them.

#### Supported MIBs

A MIB is a collection of managed objects that is organized according to hierarchy. The objects define the attributes of the managed device, which includes the names, status, access rights, and data types. Each object can be addressed through an object identifier (OID).

MIBs let administrators collect statistics and monitor status and performance. The Switch uses standard public (RFC-defined) MIBs for standard functionality, and private MIBs that support additional Switch functionality. Private MIBs contain Switch specific managed objects.

To view a list of standard MIBs supported by your Switch, see the product datasheet at www.zyxel.com (Support > Download Library > Datasheet).

To get the private MIBs supported by your Switch, download (and unzip) the correct model MIB from www.zyxel.com (Support > Download Library > MIB File).

#### SNMP Traps

The Switch sends traps to an SNMP manager when an event occurs. The following tables outline the SNMP traps by category.

O PIIO N	O BJEC T LA BEL	O BJEC TID	DESC RIPTIO N
coldstart	coldStart	1.3.6.1.6.3.1.1.5.1	This trap is sent when the Switch is turned on.
warmstart	warmStart	1.3.6.1.6.3.1.1.5.2	This trap is sent when the Switch restarts.
	pethPsePortOnOffNotification	1.3.6.1.2.1.105.0.1	This trap is sent when the PoE port delivers power or delivers no power to a PD.
(For PoE models only)	pethMainPowerUsageOnNo tification	1.3.6.1.2.1.105.0.2	This trap is sent when the usage power is above the usage indication threshold.
	pethMainPowerUsageOffNo tification	1.3.6.1.2.1.105.0.3	This trap is sent when the usage power is below the usage indication threshold.

Table 86 SNMP System Traps

Table 87 SNMP Interface Traps

O PIIO N	O BJEC TIABEL	O BJEC TID	DESC RIPTIO N
linkup	linkUp	1.3.6.1.6.3.1.1.5.4	This trap is sent when the Ethernet link is up.
linkdown	linkDown	1.3.6.1.6.3.1.1.5.3	This trap is sent when the Ethernet link is down.
lldp	lldpRemTablesChange	1.0.8802.1.1.2.0.0.1	The trap is sent when entries in the remote database have any updates. Link Layer Discovery Protocol (LLDP), defined as IEEE 802.1ab, enables LAN devices that support LLDP to exchange their configured settings. This helps eliminate configuration mismatch issues.

Table 89 SNMP IP Traps

OPIION	OBJECTLABEL	OBJECTID	DESC RIPTIO N
ping	pingProbeFailed	1.3.6.1.2.1.80.0.1	This trap is sent when a single ping probe fails.
	pingTestFailed	1.3.6.1.2.1.80.0.2	This trap is sent when a ping test (consisting of a series of ping probes) fails.
	pingTestCompleted	1.3.6.1.2.1.80.0.3	This trap is sent when a ping test is completed.
traceroute	traceRouteTestFailed	1.3.6.1.2.1.81.0.2	This trap is sent when a traceroute test fails.
	traceRouteTestCompleted	1.3.6.1.2.1.81.0.3	This trap is sent when a traceroute test is completed.

Table 90 SNMP Switch Traps

O PIIO N	OBJECTLABEL	OBJECTID	DESC RIPTIO N
rmon	RmonRisingAlarm	1.3.6.1.2.1.16.0.1	This trap is sent when a variable goes over the RMON "rising" threshold.
	RmonFallingAlarm	1.3.6.1.2.1.16.0.2	This trap is sent when the variable falls below the RMON "falling" threshold.

# C HA PTER 27 Switch Setup

## 27.1 Switch Setup Overview

Use this screen to do the Switch's basic setup configuration, for example, VLAN (Virtual Local Area Network) type, enabling switching protocols, and MAC learning aging time setup.

### 27.1.1 Introduction to VIANs

A VLAN (Virtual Local Area Network) allows a physical network to be partitioned into multiple logical networks. Devices on a logical network belong to one group. A device can belong to more than one group. With VLAN, a device cannot directly talk to or hear from devices that are not in the same groups; the traffic must first go through a router.

In MTU (Multi-Tenant Unit) applications, VLAN is vital in providing isolation and security among the subscribers. When properly configured, VLAN prevents one subscriber from accessing the network resources of another on the same LAN, thus a user will NOT see the printers and hard disks of another user in the same building.

VLAN also increases network performance by limiting broadcasts to a smaller and more manageable logical broadcast domain. In traditional switched environments, all broadcast packets go to each and every individual port. With VLAN, all broadcasts are confined to a specific broadcast domain.

Note: VLAN is unidirectional; it only governs outgoing traffic.

### 27.2 Switch Setup

Click **SYSTEM** > **Switch Setup** in the navigation panel to display the screen as shown. The VLAN setup screens change depending on whether you choose **802.1Q** or **Port Based** in the **VLAN Type** field in this screen.

Switch Selup				
M AN Type Bridge Central Proto-	ol Transporency		O Parl Rowd	
MAC Address Lear	ning			
Aging time		300	seconds	
AR7 Aging Time				
Aging Time		300	seponds	
GARP Timer				
Join finner		200	millseconds	
Leave Timer		000	miliseconds	
Leave All firmer		10000	millseconds	
-	Apply	Con	o#I	

Figure 144 SYSTEM > Switch Setup

LABEL	DESC RIPTIO N			
VLAN Type	Choose 802.1Q or Port Based. The SWIICHING > VIAN link and its sub-links only appears when you choose 802.1Q VLAN type in this screen.			
Bridge Control Protocol Transparency	Enable the <b>ON/OFF</b> switch to allow the Switch to handle bridging control protocols (STP, for example). You also need to define how to treat a BPDU in the <b>PORT</b> > <b>Port Setup</b> screen.			
MAC Address Lec	irning			
MAC address lea must be active.	rning reduces outgoing traffic broadcasts. For MAC address learning to occur on a port, the port			
Aging Time	Enter a time from 10 to 1000000 seconds. This is how long all dynamically learned MAC addresses remain in the MAC address table before they age out (and must be relearned).			
ARP Aging Time	·			
Aging Time	Enter a time from 60 to 1000000 seconds. This is how long dynamically learned ARP entries remain in the ARP table before they age out (and must be relearned). The setting here applie to ARP entries which are newly added in the ARP table after you click <b>Apply</b> .			
GARP. Declaratio	ches join VLANs by making a declaration. A declaration is made by issuing a <b>Join</b> message using ns are withdrawn by issuing a <b>Leave</b> message. A <b>Leave All</b> message terminates all registrations. leclaration timeout values. See the chapter on VLAN setup for more background information.			
Join Timer	Join Timersets the duration of the Join Period timer for GVRP in milliseconds. Each port has a Join Period timer. The allowed Join Time range is between 100 and 65535 milliseconds; the default is 200 milliseconds. See the chapter on VLAN setup for more background information.			
Leave Timer	<b>Leave Timer</b> sets the duration of the <b>Leave Period</b> timer for GVRP in milliseconds. Each port has a single <b>Leave Period</b> timer. <b>Leave Time</b> must be two times larger than <b>Join Timer</b> ; the default is 600 milliseconds.			
Leave All Timer	Leave All Timersets the duration of the Leave All Period timer for GVRP in milliseconds. Each port has a single Leave All Period timer. Leave All Timer must be larger than Leave Timer.			

IABEL	DESC RIPIIO N
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 91 SYSTEM > Switch Setup (continued)

# C HAPTER 28 Syslog Setup

## 28.1 Syslog Overview

This chapter explains the  $\mathbf{Syslog}$  screens.

The syslog protocol allows devices to send event notification messages across an IP network to syslog servers that collect the event messages. A syslog-enabled device can generate a syslog message and send it to a syslog server.

Syslog is defined in RFC 3164. The RFC defines the packet format, content and system log related information of syslog messages. Each syslog message has a facility and severity level. The syslog facility identifies a file in the syslog server. Refer to the documentation of your syslog program for details. The following table describes the syslog severity levels.

CODE	SEVERITY
0	Emergency: The system is unusable.
1	Alert: Action must be taken immediately.
2	Critical: The system condition is critical.
3	Error: There is an error condition on the system.
4	Warning: There is a warning condition on the system.
5	Notice: There is a normal but significant condition on the system.
6	Informational: The syslog contains an informational message.
7	Debug: The message is intended for debug-level purposes.

#### Table 92 Syslog Severity Levels

#### 28.1.1 What You Can Do

Use the **Syslog Setup** screen (Section 28.2 on page 201) to configure the device's system logging settings and configure a list of external syslog servers.

## 28.2 Syslog Setup

The syslog feature sends logs to an external syslog server. Use this screen to configure the device's system logging settings and configure a list of external syslog servers.

Click SYSTEM > Syslog Setup in the navigation panel to display this screen.

Syslog Setup				
Syslog Setup				
Active 🔵 orr	•			
Logging Type		Active	Fool	Hγ
System			local us	e 0 M
Infortacio			local or	e 0 M
Switch			local or	₩ 0 ¥
74A			local or	N C W
P			keed or	e U M
		Apply Concel		
Syslog Server Setup				
			O Andrian	Bolete
Index	Active	IP Address	UDP Port	Log bevel

Figure 145 SYSTEM > Syslog Setup

LABEL	DESC RIPIIO N		
Syslog Setup			
Active	Enable the switch button to turn on syslog (system logging) and then configure the syslog setting.		
Logging Type	This column displays the names of the categories of logs that the device can generate.		
Active	Select this option to set the device to generate logs for the corresponding category.		
Facility	The log facility allows you to send logs to different files in the syslog server. Refer to the documentation of your syslog program for more details.		
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.		
Cancel	Click Cancel to begin configuring this screen afresh.		
Syslog Server Setup	·		
Index	This is the index number of a syslog server entry.		
Active	This field displays if the device is activated to send logs to the syslog server.		
IP Address	This field displays the IP address of the syslog server.		
UDP Port	This field displays the port of the syslog server.		
Log Level	This field displays the severity level of the logs that the device is to send to this syslog server.		
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.		
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.		
Delete	Click <b>Delete</b> to remove the selected entries.		

Table 93 SYSTEM > Syslog Setup

#### 28.2.1 Add/Edit a Syslog Server

Use this screen to configure an external syslog server.

Click Add/Edit, or select an entry and click Add/Edit in the SYSTEM > Syslog Setup screen to display this screen.

Figure 146 SYSTEM > Syslog Setup > Add/Edit

Server Aderess		
UDC Port	214	
log Leve	leve () i m	

Table 94 SYSTEM > Syslog Setup > Add/Edit			
IABEL	DESC RIPIIO N		
Active	Enable the switch button to have the device send logs to this syslog server. Clear the check box if you want to create a syslog server entry but not have the device send logs to it (you can edit the entry later).		
Server Address	Enter the IPv4 or IPv6 address of the syslog server.		
UDP Port	The default syslog server port is 514. If your syslog server uses a different port, configure the one it uses here.		
Log Level	Select the severity levels of the logs that you want the device to send to this syslog server. The lower the number, the more critical the logs are.		
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.		
Clear	Click Clear to clear the fields to the factory defaults.		
Cancel	Click Cancel to not save the configuration you make and return to the last screen.		

# CHAPTER 29 Time Range

## 29.1 Time Range Overview

You can set a time range for time-oriented features such as Classifier ACL (Access Control List) rule which categorizes data packets into different network traffic flow. The advantage of the time range feature is that it allows you to schedule the active time of configurations.

The time range can be configured in two ways – Absolute and Periodic. Absolute is a fixed time range with a start and end time. Periodic is recurrence of a time range and does not have an end time.

#### 29.1.1 What You Can Do

Use the Time Range screen (Section 29.2 on page 204) to view or define a schedule on the Switch.

## 29.2 Configuring Time Range

Click SYSTEM > Time Range in the navigation panel to display the screen as shown.

igure 1	47 SYSTE	M > Time Range		
Time Ri	ange			
				🗘 Add/Bdit. 🍵 Delete
	Index	Name	Type	Range
	1	$a$ the state _4-14	Absolute	siter 2009/04/14 06/05 end 2009/05/04 00300
	2	scheck.ie_tepeor	Periodic	Monday (0000) to Prices (1700)

LABEL	DESC RIPTIO N
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Index	This field displays the index number of the rule.
Name	This field displays the descriptive name for this rule. This is for identification purpose only. You can enter up to 32 printable ASCII characters except [?], [   ], [ ' ], [ '' ] or [, ].

IABEL	DESC RIPTIO N
Туре	This displays the schedule type of the time range rule.
	Absolute
	An one-time schedule. One-time schedules begin on a specific start date and time and end on a specific stop date and time. One-time schedules are useful for long holidays and vacation periods.
	Pe rio d ic
	A recurring schedule. Recurring schedules begin at a specific start time and end at a specific stop time on selected days of the week (Sunday, Monday, Tuesday, Wednesday, Thursday, Friday, and Saturday). Recurring schedules are useful for defining the workday and off-work hours.
Range	This field displays the time periods to which this schedule applies.
Add/Edit	Click Add/Edit to add a new schedule rule or edit a selected one.
Delete	Click <b>De le te</b> to remove the selected rules.

Table 95 SYSTEM > Time Range (continued)

#### 29.2.1 Add/Edit Time Range

This screen allows you to create a new time range or edit an existing one.

To access this screen, click the Add/Edit button or select an entry from the list and click the Add/Edit button.

Figure 148 SYSTEM > Time Range > Add/Edit

5pe	O Attrobile
2014/07/21	
	Biof 2022 + 02 + 23 + 00 + 100 + Biof 2022 + 02 + 23 + 00 + 00 +
	C1 Periodo
	O Mercine ~ 00 ~ 00 ~ 10 Monolog ~ 00 ~ 100 ~
	目 Non 目 No 目 Wed 目 Pu 目 M 目 Azt 目 Aun 目 Meekaces 目 Meekana 部 Daty
	0 × (0) × (0) × (0) 00 ×

The following table describes the labels in this screen.

LABEL	DESC RIPTIO N				
Name	Enter a descriptive name for this rule for identifying purposes. The string should not contain [ ? ], [   ], ['], ["] or [,].				
Туре	Select <b>Ab solute</b> to create a one-time schedule. One-time schedules begin on a specific start date and time and end on a specific stop date and time. One-time schedules are useful for long holidays and vacation periods.				
	Alternatively, select <b>Periodic</b> to create a recurring schedule. Recurring schedules begin at a specific start time and end at a specific stop time on selected days of the week (Sunday, Monday, Tuesday, Wednesday, Thursday, Friday, and Saturday). Recurring schedules are useful for defining the workday and off-work hours.				

Table 96 SYSTEM > Time Range > Add/Edit

XGS2220 Series User's Guide

LABEL	DESC RIPTIO N
Absolute	This section is available only when you set Type to Absolute.
Start	Specify the year, month, day, hour and minute when the schedule begins.
End	Specify the year, month, day, hour and minute when the schedule ends.
Periodic	This section is available only when you set $\mathbf{Type}$ to $\mathbf{Periodic}$ .
	Select the first option if you want to define a recurring schedule for a consecutive time period. You then select the day of the week, hour and minute when the schedule begins and ends respectively.
	Select the second option if you want to define a recurring schedule for multiple non- consecutive time periods. You need to select each day of the week the recurring schedule is effective. You also need to specify the hour and minute when the schedule begins and ends each day. The schedule begins and ends in the same day.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

Table 96 SYSTEM > Time Range > Add/Edit (continued)

# C HAPTER 30 PORT

The following chapters introduces the configurations of the links under the **PORT** navigation panel.

Quick links to chapters:

- Auto PD Recovery (for PoE models only)
- Flex Link
- Green Ethernet
- Link Aggregation
- Link Layer Discovery Protocol (LLDP)
- OAM
- PoE Setup (for PoE models only)
- Port Setup
- ZULD

# C HAPTER 31 Auto PD Recovery

# 31.1 Auto PD Recovery (for PoE models only) Overview

Things can go wrong with any network devices. A PD (for example, IP camera) may slow down or freeze and need to be restarted if it is overworked or a bug causes a memory leak. When a connected PD ceases to respond, Automatic PD Recovery allows the Switch to restart the PD by turning it off and on without the need for on-site troubleshooting.


### 31.1.1 What You Can Do

Use the Auto PD Recovery screen (Section 31.2 on page 208) to enable and configure automatic PD recovery on the Switch.

## 31.2 Auto PD Recovery

This screen lets you turn on automatic PD recovery on the Switch and its Ethernet ports. You can configure whether the Switch uses LLDP or ping to check the current status of a connected PD.

The ping is sent through the Switch's default management IP address to the designated port. To ping the PD, the port must share the same VLAN as the Switch's management VLAN.





The PD may stop responding to the Switch's detection overping or LLDP during firm ware upgrade. Disable the Auto PD Recovery function to prevent damage to the PD caused by a power cutoff during firm ware upgrade.

Note: The following screens are available for the PoE models only.

To open this screen, click **PORT**> **Auto PD Recovery**.

998 1998	100	-							
i.e	in the	Aure	and a first state of the second state of the s	the gradent in	Polary Literati Servic	Polecy Date	1000	Sector Sales Marca Sector	10 Notices General ()
211		$\{u, u, v\}$		1.53			Report View Y		
12	12	1000	2240000 C			1. 1.	Name Charles	$[\alpha ]$	$\left\  f_{n} \right\ _{1}$
4		$\{u_{i},v_{i}\}$	1252.02	623	100	1000	Sebast view view	28.0	
с.	120	[11:00 W]		(C.)	1.5		Address Alexand	(in 11)	1
Щ.,		$[0.07, \mathbf{v}]$		623	32.23		Notice Lines is	135	0.00
10		u <sub>47</sub> ×		12.3	1.4	11_1	99977 (1011) ef	12	1
3	Ε.				2012		A LOS ALASSA	37	Cent
		just v [					second in M	(200 ····)	
1	1	( <u>((), (), ()</u> )			10.11	(b. 1)	Name Annews	[ar ]	IE-1
101		$\{uv,v\}$		123		17-16	orbeen views v	1000	$\square$

Figure 150	PORT > Auto PD Recovery
------------	-------------------------

IABEL	DESC RIPTIO N					
Active	Select this option to enable Auto PD Recovery on the Switch.					
Port	This field displays the index number of a port on the Switch.					
*	Settings in this row apply to all ports.					
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.					
	Changes in this row are copied to all the ports as soon as you make them.					
Active	Select Active to enable Auto PD Recovery on the ports.					
Mode	Select <b>IIDP</b> to have the Switch passively monitor current status of the connected PD by reading LLDP packets from the PD on the port. The Switch also sends out LLDP packets to the PD to update the <b>Switch Neighbor</b> table on the PD.					
	Select <b>Ping</b> to have the Switch ping the IP address of the connected PD to test whether the PD is reachable or not.					
Neighbor Name	If <b>Mode</b> is set to <b>IIDP</b> , the system name of the connected PD displays automatically.					
Neighbor IP	If <b>Mode</b> is set to <b>Ping</b> and the PD supports LLDP, the connected PD's IPv4 or IPv6 address to which the Switch sends ping requests will display automatically. If not, enter the IP address manually.					
Polling Interval (sec)	Specify the number of seconds the Switch waits for a response before sending another ping request.					
	For example, the Switch will try to detect the PD status by performing ping requests every 20 seconds.					

Table 97 PORT > Auto PD Recovery

IABEL	DESC RIPIIO N
Polling Count	Specify how many times the Switch is to resend a ping request before considering the PD unreachable.
	For example, If there is no ping reply from the PD after the <b>Polling Interval (sec)</b> has elapsed, <b>Polling Count</b> starts from 1. After <b>Polling Count</b> reaches 3, the <b>PD Health</b> status LED will turn to red in the <b>MONITOR</b> > <b>Neighbor</b> screen. The Switch will then perform your choice in the <b>Action</b> field.
Action	Set the action to take when the connected PD has stopped responding.
	Select <b>Reboot</b> -Alam to have the Switch turn OFF the power of the connected PD (the connecting port is detected as link-down) and turn it back ON again to restart the PD after sending an SNMP trap and generating a log message.
	When restarting, the PD entry disappears from the Switch's LLDP table and the <b>PD He a lth</b> status LED will turn to yellow in the <b>MONTIOR &gt; Ne ig hbor</b> screen.
	Select $\operatorname{Alam}$ to have the Switch send an SNMP trap and generate a log message.
Resume Polling Interval (sec)	Specify the number of seconds the Switch waits before monitoring the PD status again after it restarts the PD on the port.
PD Reboot Count	Specify how many times the Switch attempts to restart the PD on the port.
	The PD Reboot Count will reset
	as soon as a ping is successful,
	<ul> <li>or when any modification to the Auto PD Recovery screen is applied,</li> <li>or after restarting the Switch.</li> </ul>
Resume Power Interval (sec)	Specify the number of seconds the Switch waits before supplying power to the connected PD again after it restarts the PD on the port.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click this to reset the values in this screen to their last-saved values.

Table 97 PORT > Auto PD Recovery (continued)

### 31.2.1 Activate the Automatic PD Recovery

Follow the steps below to activate the automatic PD recovery.

1 In the **PORT**> **Auto PD Recovery** screen, activate the feature.

ŝ.	ir to	Aurole	- Colorisation	the spinish in		Policy Libertal Service	Polery Care	1000	Sector failing March Sector	na Senara Generi ()
10		(Julie v)			123			abotolom v.		
i i	5	(F-1)-		12210.539	1.5	22	W 1.	No. of the second	- (ar - 1	[F. ]
4	1.1	juur vi	1284 (0)		1221			Staarwight vi	20.	
	R.	1 a		124101562	185	123	lend.	244 and Alexand	42	b1
а.	E.	[000 v]			6235	10.00	1000	State Alter V	[A. ]	1
8	150	щя v			123	12	4.11	electrology 41	1.2	1
8. T	E.	(1170 v)			127	20.17	1	Nation Marson	17	(Card)
	1	june of t			123	1000		secondom v	2.0.	(F

Figure 151 Auto PD Recovery (Ping Mode)

9.9	1000	<b>6</b> .								
i.se	1.44	nante	a electrone interior	the spin or		PolicyLiteral June	Polerý Duve	244	Secondality Interveloped ()	16 Selate General (
$\mathcal{M}_{\mathcal{T}}$		(June 9)			1.77.3			Reportation (c)		
	5	(une -)		1111-123	.005	1	18 14	The second states of the second secon	(cr. )	16.1
4	10	June vi	1242.05		123		1	albertalers v	500.0	S(1,2)
4 6 4	E	[10:# *]		1000	011	1.2.2.1		Address Albert 1973	(em )	b
÷.,	8	[ (the set	11568		CON	32.23	1000	$\mathcal{D}(\mathbf{r}_{1}, \mathbf{r}_{2}, \mathbf{r}_{3}, \mathbf{r}_{4}, \mathbf{r}_{5}, \mathbf{r}_{5})$	[2 <sup>2</sup> ]	1000
$\phi^{(1)}$		u <sub>4</sub> = ×			102	12-1	1-10	debury debury of	12	1
100	=	(iine v)			- 623	100.00		A REAL MARKS	3	1000
		June of			- 123		(E)(	HOCENHOM Y	(as 11)	

2 Select the desired ports in the Active column.

#### 3 Select the Mode.

When you select **Ping**, the connected PD's IPv4 or IPv6 address to which the Switch sends ping requests will display automatically if the PD supports LLDP. If not, enter the IP address of the PDs in the **Ne ighbor IP** field.

The default setting for **Polling Interval (sec)** (20 secs) and **Polling Count** (3 times) will cause the Switch to ping the PD status every 20 seconds. If there is no ping reply from the PD, **Polling Count** starts to count from 1. Once **Polling Count** reaches 3, the Switch will cause a **Reboot-Alam** on the PD as selected in **Action**.

When you select **ILDP**, the Switch monitors the PD status by checking incoming LLDP packets every 30 seconds from the PD (default value of transmit interval for LLDP feature).

Likewise, the Switch sends out LLDP packets to the PD every 30 seconds to update the MONITOR > Neighbor screen.

Once the LLDP table's counter reaches the default 120 seconds, the Switch will cause a **Reboot-Alam** on the PD as selected in **Action**.

4 After sending an SNMP trap and generating a log message, the connected PD will restart (the connecting port is detected as link-down).

When restarting, the PD entry disappears from the Switch's LLDP table and the **PD** He a lth status LED will turn to yellow in the **MONITOR** > Ne ighbor screen.

After the PD is powered on, the Switch resumes detection of the PD status by performing ping requests or checking the LLDP table based on your value for **Resume Polling Interval**.

When the **PD Reboot Count** value is reached, the Switch will no longer perform the PD recovery process. The **PD Health** status LED will turn to red in the **MONITOR** > **Neighbor** screen.

- 5 Click **Apply** to save your changes back to the run-time memory.
- 6 Click the Save link in the upper right corner of the Web Configurator to save your configuration permanently.
  - Note: In the event of a PD performing firmware upgrade, the PD may stop responding to ping or fail to provide LLDP packets for an extended period of time. When the Switch resets power to the PD before firmware upgrade is finished, it may permanently damage the PD or require a hard reset to recover it. It is strongly advised to disable the Switch's Auto PD Recovery function before upgrading the PD's firmware. This will prevent damage caused by a power cutoff.

# C HA PTER 32 Fle x Link

This chapter introduces how to set up a backup link for a primary link using Flex Links.

### 32.1 Flex Link Overview

A flex link pair consists of a primary link and a backup link on a layer-2 interface. A primary link runs on a **Prim ary Port**; a backup link runs on a **Backup Port**. The ports have two states: FORWARDING and BLOCKING. When one link is up and running (port state: FORWARDING), the other link is in down or in standby mode (port state: BLOCKING). Only one port is forwarding traffic (FORWARDING) at a time.

When the primary link goes down, the backup link automatically goes up and is able to forward traffic.

#### Pre e m p tio n

Enable **Preemption** to have the Switch automatically return the primary port to FORWARDING state after the connection from the primary port resumes, and the backup port return to BLOCKING. The Switch will wait for the specified **Preemption Delay Time** before changing the primary port state to FORWARDING and backup port state to BLOCKING. See Table 100 on page 215 for more information.

#### 32.1.1 What You Can Do

- Use the Flex Link Status screen (Section 32.2 on page 213) to view the flex link status on the Switch.
- Use the **Flex Link Setup** screen (Section 32.3 on page 214) to configure flex links for back up links on the Switch.

## 32.2 Flex Link Status

Click PORT > Flex Link > Flex Link Status to display this screen.

Figure 153 PORT > Flex Link > Flex Link Status

Flex Link Status	Flex Unk Se	tup	
Ind ex	Primary Port	Bockup Fort	Sicle
1.00	I.	2	Finnery Down / Society Down
7	м	26	Plinary Down / Nochop Up

The following table describes the labels in this screen.

LABEL	DESC RIPTIO N			
Index	This displays the index number of a flex link pair.			
Primary Port	This displays the port number of the primary link.			
Backup Port	This displays the port number of the backup link.			
State	This displays the link status of the <b>Primary</b> port and <b>Backup</b> port.			
	Down – The link is down.			
	Up – The link is up and the port state is FORWARDING.			
	Standby – The link is up and the port state is BLOCKING.			
	Note: Only one port can be up in a flex link pair.			

Table 98 PORT > Flex Link > Flex Link Status

### 32.3 Flex Link Setup

Click PORT > Flex Link > Flex Link Setup to display this screen.

Note: The Flex Link (**PORT**> **Flex Link**), STP (**SWIICHING** > **Spanning Thee Protocol**), Loop Guard (**SWIICHING** > **Loop Guard**) and Link Aggregation (**PORT**> **Link Aggregation**) features cannot be configured together on the same port. When one of the above functions is enabled, the Switch will not let you enable the others.

Note: You can configure up to five pairs of flex links.

8			1		
Flex Link S	tatus P	lex Link Setup			
	Index	Primary Port	Backup Perl	Freemption	Add/Edit 📲 Delete Preemption Delay Time
	a contra co	transa para a	in a second provide the second	ris singusi	the state provide state of the second
	1	1	2	Yez 🚽	30
	2	24	26	No	30

Figure 154 PORT > Flex Link > Flex Link Setup

IABEL	DESC RIPTIO N
Index	This displays the index number of an entry.
Primary Port	This displays the port number of the primary link.
Backup Port	This displays the port number of the backup link.
Preemption	This displays if <b>Preemption</b> is enabled on the flex link pair. If <b>Preemption</b> is enabled, when the primary port comes back up, the backup port will go into BLOCKING state and the primary port will go into FORWARDING state after the <b>Preemption Delay Time</b> interval.
Preemption Delay Time	This displays the preemption delay time configured for this flex link pair.

Table 99 PORT > Flex Link > Flex Link Setup

LABEL	DESC RIPTIO N	
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.	
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.	
Delete	Click <b>Delete</b> to remove the selected entry.	

Table 99 PORT > Flex Link > Flex Link Setup (continued)

#### 32.3.1 Add/Edit Flex Link

To access this screen, click the Add/Edit button or select an entry from the list and click the Add/Edit button.

Note: A port can only be in one flex link pair. If a port has already been set as a flex link pair's primary/backup port, the port can not be used by other flex links. Check the **PORT**> **Hex Link > Flex Link Setup** screen to see what ports are already in other flex link pairs.

Figure 155 PORT > Flex Link > Flex Link Setup > Add/Edit

Princey Part			
Rockup Port			
Presmption			
Reempton Deby Tree		30	
Apply	Close		Concel

IABEL	DESC RIPTIO N
Primary Port	Enter a port number to be the primary port.
Backup Port	Enter a port number to be the backup port.
Preemption	Select this to enable the $\operatorname{Preemption}$ mode on the flex link pair.
	If <b>Preemption</b> is disabled, if the primary port is down, then comes back up, it will remain in the BLOCKING state even after the <b>Preemption Delay Time</b> .
Preemption Delay Time	Enter the delay time (in seconds) which you want the primary port to wait before changing back to FORWARDING state (when available). The range is 1 – 300 seconds.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click <b>Clear</b> to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

Table 100 PORT > Flex Link > Flex Link Setup > Add/Edit

# CHAPTER 33 Green Ethernet

This chapter shows you how to configure the Switch to reduce the power consumed by switch ports.

## 33.1 Green Ethernet Overview

Green Ethernet reduces switch port power consumption in the following ways.

#### IEEE 802.3a z Energy Efficient Ethernet (EEE)

If EEE is enabled, both sides of a link support EEE and there is no traffic, the port enters Low Power Idle (LPI) mode. LPI mode turns off some functions of the physical layer (becomes quiet) to save power. Periodically the port transmits a REFRESH signal to allow the link partner to keep the link alive. When there is traffic to be sent, a WAKE signal is sent to the link partner to return the link to active mode.

#### Auto PowerDown

Auto Power Down turns off almost all functions of the port's physical layer functions when the link is down, so the port only uses power to check for a link up pulse from the link partner. After the link up pulse is detected, the port wakes up from Auto Power Down and operates normally.

#### Short Reach

Traditional Ethernet transmits all data with enough power to reach the maximum cable length. Shorter cables lose less power, so **Short Reach** saves power by adjusting the transmit power of each port according to the length of cable attached to that port.

## 33.2 Configuring Green Ethernet

Click **PORT** > **Green Ethemet** in the navigation panel to display the screen as shown.

Note: This feature is only available on copper ports. Check boxes of SFP ports are grayed out and cannot be selected.

Note: EEE, Auto Power Down and Short Reach are NOT supported on an uplink port.

Green Bhernet			
11 <b>1</b> 23	07		
é a la manérer d'atro	107		
Statel Keesch	() BH		
for	m	Auto Power Down	Short Seach
	Ð	Ū.	E1
Ϋ́	10	10	11
<u> (</u>	B		E
	10	-0	10
4	12	0	10
7	10	10	17
5			
- 1/			
.16			<u></u>
Ϋ́ν	-	Ū.	
28	(C)	<b>H</b>	<u>C1</u>

Figure 156	PORT > Green Etherne	et.
------------	----------------------	-----

	Table 101	PORT > Green Ethernet
--	-----------	-----------------------

IABEL	DESC RIPTIO N
EEE	Enable the switch button to activate Energy Efficient Ethernet globally.
Auto Power Down	Enable the switch button to activate Auto Power Down globally.
Short Reach	Enable the switch button to activate Short Reach globally.
Port	This field displays the port number.
*	Use this row to make the setting the same for all ports. Use this row first and then make adjustments to each port if necessary.
	Changes in this row are copied to all the ports as soon as you make them.
EEE	Select this to activate Energy Efficient Ethernet on this port.
Auto Power Down	Select this to activate Auto Power Down on this port.
Short Reach	Select this to activate Short Reach on this port.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

# C HAPTER 34 Link Aggregation

# 34.1 Link Aggregation Overview

This chapter shows you how to logically aggregate physical links to form one logical, higher-bandwidth link.

Link aggregation (trunking) is the grouping of physical ports into one logical higher-capacity link. You may want to trunk ports if for example, it is cheaper to use multiple lower-speed links than to under-utilize a high-speed, but more costly, single-port link. However, the more ports you aggregate then the fewer available ports you have. A trunk group is one logical link containing multiple ports.

The beginning port of each trunk group must be physically connected to form a trunk group.

### 34.1.1 What You Can Do

- Use the **Link Aggregation Status** screen (Section 34.2 on page 219) to view ports you have configured to be in the trunk group, ports that are currently transmitting data as one logical link in the trunk group and so on.
- Use the Link Aggregation Setting screen (Section 34.3 on page 221) to configure static link aggregation.
- Use the Link Aggregation Control Protocol screen (Section 34.4 on page 222) to enable Link Aggregation Control Protocol (LACP).

#### 34.1.2 What You Need to Know

The Switch supports both static and dynamic link aggregation.

Note: In a properly planned network, it is recommended to implement static link aggregation only. This ensures increased network stability and control over the trunk groups on your Switch.

See Section 34.5.1 on page 224 for a static port trunking example.

#### Dynamic Link Aggregation

The Switch adheres to the IEEE 802.3ad standard for static and dynamic (LACP) port trunking.

The IEEE 802.3ad standard describes the Link Aggregation Control Protocol (LACP) for dynamically creating and managing trunk groups.

When you enable LACP link aggregation on a port, the port can automatically negotiate with the ports at the remote end of a link to establish trunk groups. LACP also allows port redundancy, that is, if an

operational port fails, then one of the "standby" ports become operational without user intervention. Please note that:

- You must connect all ports point-to-point to the same Ethernet switch and configure the ports for LACP trunking.
- LACP only works on full-duplex links.
- All ports in the same trunk group must have the same media type, speed, duplex mode and flow control settings.

Configure trunk groups or LACP before you connect the Ethernet switch to avoid causing network topology loops.

#### Link Aggregation ID

LACP aggregation ID consists of the following information<sup>1</sup>:

Table 102 Link Aggregation ID: Local Switch

SYSTEM PRIO RITY	MAC ADDRESS	KEY	PO RT PRIO RITY	PORTNUMBER
0000	00-00-00-00-00	0000	00	0000

Table 103 Link Aggregation ID: Peer Switch

SYSTEM PRIO RITY	MAC ADDRESS	KEY	PO RT PRIO RITY	PORTNUMBER
0000	00-00-00-00-00	0000	00	0000

#### Traffic Distribution Criteria

The Switch supports both unicast and non-unicast traffic (broadcast and multicast) network load sharing over link aggregation. Load sharing works by statically splitting the traffic based on source or destination IP/MAC address, and then distributing the load across multiple paths. In link aggregation, this allows the trunk group (ports) to transmit data as one logical link to a single or group of hosts on the network.

Unicast and non-unicast traffic network load sharing over link aggregation (trunking) is enabled by default.

## 34.2 Link Aggregation Status

Click **PORT**> **Link Aggregation** > **Link Aggregation** Status in the navigation panel to display the screen as shown. See Section 34.1 on page 218 for more information.

<sup>1.</sup> Port Priority and Port Number are 0 as it is the aggregator ID for the trunk group, not the individual port.

tink Aggree	galian Shalus	Tink Aggrag	alian Selling	tink Aggregation C	ontrol Protoco
Group ID	<b>Drobled Ports</b>	Synchroniaed Poits	Aggregator 10	Criteria	Status
П	-	-	•	accessionale	-
T?				sts det mind	
T.				ve, del maio	
14				are del marc	
12				are definition	
16	-	-		ac-d-lenar	
LZ	-	-		a::	<u>``</u> _
				d. Com.l.	~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~

Figure 157 PORT > Link Aggregation > Link Aggregation Status

IABEL	DESC RIPTIO N
Group ID	This field displays the group ID to identify a trunk group, that is, one logical link containing multiple ports.
Enabled Ports	These are the ports you have configured in the <b>Link Aggregation Setting</b> screen to be in the trunk group.
	The port numbers displays only when this trunk group is activated and there is a port belonging to this group.
Synchronized Ports	These are the ports that are currently transmitting data as one logical link in this trunk group.
Aggregator ID	Link Aggregator ID consists of the following: system priority, MAC address, key, port priority and port number.
	The ID displays only when there is a port belonging to this trunk group and LACP is also enabled for this group.
Criteria	This shows the outgoing traffic distribution algorithm used in this trunk group. Packets from the same source and/or to the same destination are sent over the same link within the trunk.
	$\operatorname{src}$ - $\operatorname{mac}$ means the Switch distributes traffic based on the packet's source MAC address.
	dst mac means the Switch distributes traffic based on the packet's destination MAC address.
	src - dst - mac means the Switch distributes traffic based on a combination of the packet's source and destination MAC addresses.
	${f src}$ - ${f ip}$ means the Switch distributes traffic based on the packet's source IP address.
	$\mathbf{dst}$ - $\mathbf{ip}$ means the Switch distributes traffic based on the packet's destination IP address.
	<b>src</b> - <b>d</b> st- <b>ip</b> means the Switch distributes traffic based on a combination of the packet's source and destination IP addresses.
Status	This field displays how these ports were added to the trunk group. It displays:
	<ul> <li>Static – if the ports are configured as static members of a trunk group.</li> <li>IACP – if the ports are configured to join a trunk group through LACP.</li> </ul>

Table 104 PORT > Link Aggregation > Link Aggregation Status

# 34.3 Link Aggregation Setting

Click **PORT**> **Link Aggregation** > **Link Aggregation Setting** to display the screen shown next. See Section 34.1 on page 218 for more information on link aggregation.

Unk Aggregano	n Setting	Unk Aggregati
Active		Citterio
2		-dstance -v
<u>i</u>	1	del marci v
		driver v
0	<u>.</u>	det max +
Ū	10	dst mod ×
0	33	dist maio 🗸
. 8		dsl med v
Î	Personal and	
	Nore v Nore v Nore v Nore v	

Figure 158 PORT > Link Aggregation > Link Aggregation Setting

 Table 105
 PORT > Link Aggregation > Link Aggregation Setting

LABEL	DESC RIPIIO N
This is the only so	creen you need to configure to enable static link aggregation.
Group ID	The field identifies the link aggregation group, that is, one logical link containing multiple ports.
Active	Select this to activate a trunk group.

IABEL	DESC RIPIIO N
Criteria	Select the outgoing traffic distribution type. Packets from the same source and/or to the same destination are sent over the same link within the trunk. By default, the Switch uses the smc-dst-mac distribution type. If the Switch is behind a router, the packet's destination or source MAC address will be changed. In this case, set the Switch to distribute traffic based on its IP address to make sure port trunking can work properly.
	Select $\mathbf{src}$ - $\mathbf{mac}$ to distribute traffic based on the packet's source MAC address.
	Select $dst-mac$ to distribute traffic based on the packet's destination MAC address.
	Select <b>sre-dst-mac</b> to distribute traffic based on a combination of the packet's source and destination MAC addresses.
	Select $\mathbf{src}$ - $\mathbf{ip}$ to distribute traffic based on the packet's source IP address.
	Select <b>dst-ip</b> to distribute traffic based on the packet's destination IP address.
	Select <b>sre-dst-ip</b> to distribute traffic based on a combination of the packet's source and destination IP addresses.
Port	This field displays the port number.
Group	Select the trunk group to which a port belongs.
	Note: When you enable the port security feature on the Switch and configure port security settings for a port, you cannot include the port in an active trunk group.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

 Table 105
 PORT > Link Aggregation > Link Aggregation Setting (continued)

# 34.4 Link Aggregation Control Protocol

Click **PORT**> **Link Aggregation** > **Link Aggregation Control Protocol** to display the screen shown next. See Dynamic Link Aggregation on page 218 for more information on dynamic link aggregation.

Note: Do NOT configure this screen unless you want to enable dynamic link aggregation.

Storius L	ink Aggregation Setting	Unk Aggregation Control Protocol
702102		
Soutempt	entre labore	
	Group ID	LACP Active
	H	C3
	1	
	5	0
	(4)	G
	-3	- [2]
	(5)	
		LLCF Timeout
	Г?  Тот 	LACE Timeoun ()) v Juny Carlle
		LLCF Timeout
	Г?  Тот 	LACE Timeoun ()) v Juny Carlle
	12 70 1	LECF Rmean (3) v arcords (3) v arcords
	12 70T 1 2	LACE Timesul 30 v Second 30 v Second 30 v Second 30 v Second
	12 1 2 3	LSCP Timeout ()) v Jerocrati ()) v Jerocrati ()) v Jerocrati ()) v Jerocratic ()) v Jerocratic
	12 7or 1 2 3 4	LSCR Timesuri 30 v Jeconde 30 v Jeconde 30 v Jeconde 30 v Jeconde 30 v Jeconde 30 v Jeconde
	Tar - - - - - - - - - - - - -	LECE Time can 30 v are consta 30 v are

Figure 159 PORT > Link Aggregation > Link Aggregation Control Protocol

The following table describes the labels in this screen.

LABEL	DESC RIPTIO N
Active	Enable the switch button to enable Link Aggregation Control Protocol (LACP).
System Priority	LACP system priority is a number between 1 and 65535. The switch with the lowest system priority (and lowest port number if system priority is the same) becomes the LACP "server". The LACP "server" controls the operation of LACP setup. Enter a number to set the priority of an active port using Link Aggregation Control Protocol (LACP). The smaller the number, the higher the priority level.
Use this section t	o enable LACP on trunks.
Group ID	The field identifies the link aggregation group, that is, one logical link containing multiple ports.
LACP Active	Select this option to enable LACP for a trunk.
Use this section t	o configure LACP timeout on ports.
Port	This field displays the port number.

XGS2220 Series User's Guide

IABEL	DESC RIPTIO N
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
LACP Timeout	Timeout is the time interval between the individual port exchanges of LACP packets in order to check that the peer port in the trunk group is still up. If a port does not respond after three tries, then it is deemed to be "down" and is removed from the trunk. Set a short timeout (1 second) for busy trunked links to ensure that disabled ports are removed from the trunk group as soon as possible.
	Select either 1 second or 30 seconds.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

 Table 106
 PORT > Link Aggregation > Link Aggregation Control Protocol (continued)

## 34.5 Technical Reference

This section provides technical background information on the topics discussed in this chapter.

### 34.5.1 Static Trunking Example

This example shows you how to create a static port trunk group for ports 2 – 5.

1 Make your physical connections – make sure that the ports that you want to belong to the trunk group are connected to the same destination. The following figure shows ports 2 – 5 on switch A connected to switch B.



Figure 160 Trunking Example – Physical Connections

2 Configure static trunking – Click PORT> Link Aggregation > Link Aggregation Setting. In this screen activate trunk group **TI**, select the traffic distribution algorithm used by this group and select the ports that should belong to this group as shown in the figure below. Click **Apply** when you are done.

Group ID	Active	Cólcrio
(T)		sie dat mee 🗸
12	0	so del medio
13	(C)	such have y
14	121	steahl-may w
15		standbler and w
14	101	seedal-more w
123	CI	size <b>b</b> [-mass w]
Perl		Citoth
Ped		
Peil		No a v
Peril		[Na = *]
-		[Na u v]
1		Nors +     +     +     +
-		
		Nore v
-		

Figure 161 Trunking Example – Configuration Screen

Your trunk group 1 ( ${f n}$ ) configuration is now complete.

# C HAPTER 35 Link Layer Discovery Protocol (LIDP)

## 35.1 IIDP Overview

The LLDP (Link Layer Discovery Protocol) is a layer 2 protocol. It allows a network device to advertise its identity and capabilities on the local network. It also allows the device to maintain and store information from adjacent devices which are directly connected to the network device. This helps an administrator discover network changes and perform necessary network reconfiguration and management. The device information is encapsulated in the LLDPDUs (LLDP data units) in the form of TLV (Type, Length, Value). Device information carried in the received LLDPDUs is stored in the standard MIB.

The Switch supports these basic management TLVs.

- End of LLDPDU (mandatory)
- Chassis ID (mandatory)
- Port ID (mandatory)
- Time to Live (mandatory)
- Port Description (optional)
- System Name (optional)
- System Description (optional)
- System Capabilities (optional)
- Management Address (optional)

The Switch also supports the IEEE 802.1 and IEEE 802.3 organizationally-specific TLVs.

IEEE 802.1 specific TLVs:


- Port VLAN ID TLV (optional)
- Port and Protocol VLAN ID TLV (optional)

IEEE 802.3 specific TLVs:

- MAC/PHY Configuration/Status TLV (optional)
- Power via MDI TLV (optional, For PoE models only)
- Link Aggregation TLV (optional)
- Maximum Frame Size TLV (optional)

The optional TLVs are inserted between the Time To Live TLV and the End of LLDPDU TLV.

The next figure demonstrates that the network devices Switches and Routers (S and R) transmit and receive device information through LLDPDU and the network manager can query the information using Simple Network Management Protocol (SNMP).



## 35.2 LIDP-MED Overview


LLDP-MED (Link Layer Discovery Protocol for Media Endpoint Devices) is an extension to the standard LLDP developed by the Telecommunications Industry Association (TIA) TR-41.4 subcommittee which defines the enhanced discovery capabilities, such as VoIP applications, to enable network administrators manage their network topology application more efficiently. Unlike the traditional LLDP, which has some limitations when handling multiple application devices, the LLDP-MED offers display of accurate physical topology, interoperability of devices, and easy trouble shooting for mis-configured IP addresses. There are three classes of endpoint devices that the LLDP-MED supports:

Class I: IP Communications Controllers or other communication related servers

Class II: Voice Gateways, Conference Bridges or Media Servers

Class III: IP-Phones, PC-based Softphones, End user Communication Appliances supporting IP Media

The following figure shows that with the LLDP-MED, network connectivity devices (NCD) like Switches and Routers will transmit LLDP TLV to endpoint device (ED) like IP Phone first (1), to get its device type and capabilities information, then it will receive that information in LLDP-MED TLV back from endpoint devices (2), after that the network connectivity devices will transmit LLDP-MED TLV (3) to provision the endpoint device to such that the endpoint device's network policy and location identification information is updated. Since LLDPDU updates status and configuration information periodically, network managers may check the result of provision through remote status. The remote status is updated by receiving LLDP-MED TLVs from endpoint devices.



### 35.2.1 What You Can Do - LLDP

- Use the IIDP Local Status screen (Section 35.3 on page 228) to view the Switch's LLDP information.
- Use the **IIDP Remote Status** screen (Section 35.4 on page 233) to view LLDP information from the neighboring devices.
- Use the IIDP Setup screen (Section 35.5 on page 238) to configure LLDP on the Switch.
- Use the **Basic TLV Setting** screen (Section 35.6 on page 240) to configure basic TLV settings on each port.
- Use the Org-specific TLV Setting screen (Section 35.7 on page 241) to configure organization-specific TLV settings on each port.

## 35.2.2 What You Can Do - LLDP MED

- Use the **IIDP-MED** Setup screen (Section 35.8 on page 242) to configure LLDP-MED (Link Layer Discovery Protocol for Media Endpoint Devices) parameters.
- Use the **IIDP-MED Network Policy** screen (Section 35.9 on page 243) to configure LLDP-MED (Link Layer Discovery Protocol for Media Endpoint Devices) network policy parameters.
- Use the **IIDP-MED Location** screen (Section 35.10 on page 245) to configure LLDP-MED (Link Layer Discovery Protocol for Media Endpoint Devices) location parameters.

## 35.3 LLDP Local Status

This screen displays a summary of LLDP status on this Switch. Click PORT > IIDP > IIDP > IIDP Iocal Status to display the screen as shown next.

	U.CF Remote Stolus 1107	Setup Scale IDV Sette	g Org-specific TV Setting	
ode NV				
of earliest ins			Letter serve to	
Charge Columbia	voc admin		Land and	+ 3x5200
cient c	Contracticution)		Linkin and fellen in	
			Served and a	Na Angel Sati Albert ( A2,1 (2009)
toy make a lingue state of a	n=		Access analysis and the set of a	
Inderest Ages Inc.	adate Mittal		the open distance of the second	L e A J el MS
within capital Meril	notied Adapt		Mercoe vanberskoryce	OPD4
			feerose haniper	1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1. 1
			Stand American	
		ist to		red acceptor
LD * Politiniormalia	ai	estrite:		ed accesso
LDF Folk Informatio	al Forfic antige	eon as I		nd activation
	All Booff at califyings Doctor-official wat	1 1 2		- education
LDP Port Informativ Locative	Al Politic antitype DCS-CELQ-MC Politic antitype	3		- extraction
LDF Folk Informatio	Al Portis and type DCS-CELQ-MS Port 1 No. 1 No. 1 No. 1	i i		- extraction
LDP Point informatio Local not L L L L L L L L L L L L L L L L L L L	Al Politic Statype Dis-Charles Politic Statype Politic Statype Politi	i i		winestern
LDF Folk Internatio	All For the sectors For the sectors F	- - - -		winestan

Table 107 PORT > LLDP > LLDP > LLDP Local Status

IABEL	DESC RIPTIO N
Basic TLV	
Chassis ID TLV	<ul> <li>This displays the chassis ID of the local Switch, that is the Switch you are configuring. The chassis ID is identified by the chassis ID subtype.</li> <li>Chassis ID Subtype – This displays how the chassis of the Switch is identified.</li> <li>Chassis ID – This displays the chassis ID of the local Switch.</li> </ul>
System Name TLV	System Name – This shows the host name of the Switch.
System Description TLV	System Description – This shows the firmware version of the Switch.
System Capabilities TLV	<ul> <li>This shows the System Capabilities enabled and supported on the local Switch.</li> <li>System Capabilities Supported – Bridge</li> <li>System Capabilities Enabled – Bridge</li> </ul>
Management Address TLV	The Management Address TLV identifies an address associated with the local LLDP agent that may be used to reach higher layer entities to assist discovery by network management. The TLV may also include the system interface number and an object identifier (OID) that are associated with this management address. This field displays the Management Address settings on the specified ports.
	<ul> <li>Management Address Subtype - ipv4 or all-802</li> <li>Interface Number Subtype - Unknown</li> <li>Interface Number - 0 (not supported)</li> <li>Object Identifier - 0 (not supported)</li> </ul>
LLDP Port Information	י ז
This displays the loca	l port information.

LABEL	DESC RIPTIO N
Local Port	This displays the number of the Switch port which receives the LLDPDU from the remote device. Click a port number to view the detailed LLDP status on this port in the <b>LLDP Local Port Status De tail</b> screen.
Port ID Subtype	This indicates how the port ID field is identified.
Port ID	This is an alpha-numeric string that contains the specific identifier for the port from which this LLDPDU was transmitted.
Port Description	This shows the port description that the Switch will advertise from this port.

Table 107 PORT > LLDP > LLDP > LLDP Local Status (continued)

## 35.3.1 LLDP Local Port Status Detail

This screen displays detailed LLDP status for each port on this Switch. Click PORT > ILDP > ILDP > ILDPI ocal Status and then, click a port number, for example 1 in the local port column to display the screen as shown next.

LLDP Local Status	LLDP Remote Status	LLDP Setup Basic TL	V Setting
HDPTocalStatus >	HDP Local Part Status Da	atol	
Local Port 1			
Basic TLV			
Port ID TLV		Fort Description TUV	
Port ID Subtype	local assigned	Port Description	
Port ID	1		
Doll TLV			
Port VLAN ID TLV		Fort-Protocol VLAN ID TL	v
Port MUXINID	1	Perf Protocol VLAN ID	
N . 45 W131			
Dot3 TLV			
MAC 20Y Configurat	ion & Stotus 11V	link Aggregation TLV	
AN Supported	Y ex	Apprepation Copability	Yea
ANTrobled	No	Approximition Stokes	No
AN Advertised Copo	do ili y	Aggregated PathD	0
Oper MAU Type	36	Max Frame Size ILV	
		Max Frame Size	1518
MED TLV			
Copobilities R.V		Network Policy TLV	
Network fields:	й ех	Volce	
Lessel kom	Үнэ	Molece-Signicalings	
Edend Power via MD	DI PSE NO	Quest Voice	
Edend Pewervie MI	CI PD NO	Suest Voice Signaling	
Inventory Managem	ont No	Sofphone-Voice	
		Video-Conferencing	
		Streaming-Middea	
		Midece//kgindling	
Device Type TCV		Location Identification I	LV
Device Type	Network Connectivity	Coordinate-base LCI	
	such the citrary	CM: LCI	
		EUN	

Figure 165 PORT > LLDP > LLDP Local Status > LLDP Local Port Status Detail

T I I 100		
Table 108	PORT > LLDP > LLDP > LLDP Local Status > LLDP Local Port Statu	is Detail

IABEL	DESC RIPTIO N
Local Port	This displays the number of the Switch's port.
Basic TLV	•
These are the Basic T	LV flags
Port ID TLV	The port ID TLV identifies the specific port that transmitted the LLDP frame.
	<ul> <li>Port ID Sub type – This shows how the port is identified.</li> <li>Port ID – This is the ID of the port.</li> </ul>
Port Description TLV	Port Description – This displays the local port description.
Dot1 TLV	
Port VLAN ID TLV	Port VIAN ID – This displays the VLAN ID sent by the IEEE 802.1 Port VLAN ID TLV.
Port-Protocol VLAN ID TLV	<b>Port-Protocol VIAN ID</b> – This displays the IEEE 802.1 Port Protocol VLAN ID TLVs, which indicates whether the VLAN is enabled and supported.
Dot3 TLV	
MAC PHY Configuration & Status TLV	The MAC/PHY Configuration/Status TLV advertises the bit-rate and duplex capability of the sending 802.3 node. It also advertises the current duplex and bit-rating of the sending node. Lastly, it advertises whether these setting were the result of auto-negotiation during link initiation or manual override.
	<ul> <li>AN Supported – Displays if the port supports or does not support auto-negotiation.</li> <li>AN Enabled – The current auto-negotiation status of the port.</li> <li>AN Advertised Capability – The auto-negotiation capabilities of the port.</li> <li>Oper MAU Type – The current Medium Attachment Unit (MAU) type of the port.</li> </ul>
Link Aggregation TLV	<ul> <li>The Link Aggregation TLV indicates whether the link is capable of being aggregated, whether the link is currently in an aggregation, and if in an aggregation, the port identification of the aggregation.</li> <li>Aggregation Capability – The current aggregation capability of the port.</li> <li>Aggregation Status – The current aggregation status of the port.</li> <li>Aggregation Port ID – The aggregation ID of the current port.</li> </ul>
Max Frame Size TLV	This displays the maximum supported frame size in octets.
MED TLV	
LLDP Media Endpoin media endpoint dev	t Discovery (MED) is an extension of LLDP that provides additional capabilities to support ices. MED enables advertisement and discovery of network policies, device location discovery ocation databases, and information for troubleshooting.
Capabilities TLV	This field displays which LLDP-MED TLV are capable to transmit on the Switch.
	<ul> <li>Network Policy</li> <li>Location</li> <li>Extend Powervia MDI PSE</li> <li>Extend Powervia MDI PD</li> <li>Inventory Management</li> </ul>

DESC RIPTIO N	
This displays a network policy for the specified application.	
• Voice	
• Voic e - Sig na ling	
• Guest Voice	
• Guest-Voice-Signaling	
Softphone-Voice	
• Vide o - C onferencing	
• Streaming-Video	
• Vide o - Sig na ling	
Device Type – This is the LLDP-MED device class.	
The Zyxel Switch device type is:	
Network Connectivity	
This shows the location information of a caller by its ELIN (Emergency Location Identifier Number) or the IETF Geopriv Civic Address based Location Configuration Information (Civic Address LCI).	
Coordinate-based ICI – Latitude, longitude and altitude coordinates of the location     Configuration Information (LCI)	
Civic ICI-IETF Geopriv Civic Address based Location Configuration Information	
EIIN – (Emergency Location Identifier Number)	

T . I. I 100			
1 able 1 08	PORI > LLDP > LLDP >	<ul> <li>LLDP Local Status &gt; LLDP Local Port Status Detail (a)</li> </ul>	continuea)

## 35.4 LLDP Remote Status

This screen displays a summary of LLDP status for each LLDP connection to a neighboring Switch. Click **PORT**> **ILDP** > **ILDP** > **ILDP** Remote Status to display the screen as shown next.

Figure 166 PORT > LLDP > LLDP > LLDP Remote Status

Index         Local Port         Chossis ID         Fort ID         Fort Description         System Name         Management Address           1         10         AD 31 vol 31         edvat rubbindott         Address         Address	LLDP Loc	al Status	LLDP Remote Sta	tus ILDP Set	up Basic TLY S	Setting Org spi	ecific TLV Setting
	Index	local Pad	Chosely ID	FortID	For Description	System Karne	
	I.	10	AD SIMPRIAD SI	$(100)^{10} (100)^{10} (100)^{10}$			
2 26 04.04.04.04 37 IZ/S 54 04.04.04	2	25	044.04.04.04.04	*		12/13/04	04.04.04.04.04.04

The following table describes the labels in this screen.

Table 109	PORT > LLDP > LLDP > LLDP Remo	te Status
-----------	--------------------------------	-----------

IABEL	DESC RIPIIO N
Index	The index number shows the number of remote devices that are connected to the Switch. Click on an index number to view the detailed LLDP status for this remote device in the <b>IIDP</b> <b>Remote Port Status Detail</b> screen.
Local Port	This is the number of the Switch's port that received LLDPDU from the remote device.
Chassis ID	This displays the chassis ID of the remote device associated with the transmitting LLDP agent. The chassis ID is identified by the chassis ID subtype. For example, the MAC address of the remote device.
Port ID	This is an alpha-numeric string that contains the specific identifier for the port from which this LLDPDU was transmitted. The port ID is identified by the port ID subtype.

XGS2220 Series User's Guide

LABEL	DESC RIPTIO N
Port Description	This displays a description for the port from which this LLDPDU was transmitted.
System Name	This displays the system name of the remote device.
Management Address	This displays the management address of the remote device. It could be the MAC address or IP address.

Table 109 PORT > LLDP > LLDP > LLDP Remote Status (continued)

### 35.4.1 LLDP Remote Port Status Detail

This screen displays detailed LLDP status of the remote device connected to the Switch. Click **PORT**> **IIDP** > **IIDP** > **IIDP** Remote Status and then click an index number, for example 1, in the **Index** column in the **IIDP** Remote Status screen to display the screen as shown next.

Figure 167 PORT > LLDP > LLDP Remote Status > LLDP Remote Port Status Detail (Basic TLV)

LDP Local Status	P Remote Status	LLDP Scrup Basic	TLV Setting	
HTTP: Renoble Stotus, D. I	110 'Renoble IVan Sv	dus Deizal		
Local Part. 28				
Dasia ILV				
Chards ID 11V		Port ID TLY		
Check Darwyn	max addir	e: Epit ID S. Migra	letent of	(gri sel
Chevile D	od 16april 2	aesi 8 - Eed D	37	
Time To Live TV		Port Description	ΠV	
Inviet se	120	Pat Devention		
System Name IUV		System Description	on IIV	
Sedem Nome	1983-54	Redem Devol(d)	an (W. 50)4. 2,12000 167,5020	230
System Copicibilities 1.V		Monogement A	idnes: 11V	
System Copycellities Suppl	stori bridgo	Management A	idios Vilstyra — All 500	
System Coprobines enabl	ed bruge	Management A	Juliens e4.18.04	a Reed 1
		Interface Nomb	a Sub yper	a
		Isterbooe Norob	e 0	
		Object identifier		

The following table describes the labels in Basic TLV part of the screen.

Table 110	PORT > LLDP :	> LLDP > LLDP Remote	e Status > LLDP Remote	e Port Status Detail (Basic TLV)
-----------	---------------	----------------------	------------------------	----------------------------------

IABEL	DESC RIPIIO N
Local Port	This displays the number of the Switch's port to which the remote device is connected.
Basic TLV	
Chassis ID TLV	<ul> <li>Chassis ID Subtype – This displays how the chassis of the remote device is identified.</li> <li>Chassis ID – This displays the chassis ID of the remote device. The chassis ID is identified by the chassis ID subtype.</li> </ul>

	Table 110	PORT > LLDP :	> LLDP > LLDP Remote Status	> LLDP Remote Port Status Detail (Basic TLV	)
--	-----------	---------------	-----------------------------	---	---

IABEL	DESC RIPTIO N
Port ID TLV	<ul> <li>Port ID Sub type – This displays how the port of the remote device is identified.</li> <li>Port ID – This displays the port ID of the remote device. The port ID is identified by the port ID subtype.</li> </ul>
Time To Live TLV	<b>Time To Live</b> – This displays the time-to-live (TTL) multiplier of LLDP frames. The device information on the neighboring devices ages out and is discarded when its corresponding TTL expires. The TTL value is to multiply the TTL multiplier by the LLDP frames transmitting interval.
Port Description TLV	Port Description – This displays the remote port description.
System Name TLV	System Name – This displays the system name of the remote device.
System Description TLV	System $\operatorname{Desciption}$ – This displays the system description of the remote device.
System Capabilities TLV	This displays whether the system capabilities are enabled and supported on the remote device.
	<ul> <li>System Capabilities Supported</li> <li>System Capabilities Enabled</li> </ul>

Figure 168 PORT > LLDP > LLDP Remote Status > LLDP Remote Port Status Detail (Dot1 and Dot3 TLV)

Port VIAN ID TIV		Mon Nome TIV
Port VEAN ID	2040	VLAN D
		M AN Norme
Protocol Identity 11V		Port-Protocol VLAN IB 11V
Protocial D		Fort Extended VERNIER
		Fort Erstonol VI SN ERGuppion of
		Fort Fruitscol MLAN (Desirabled
Dolt II V		
MAC FH1 Configuration & Status ID	r	Mox frame size IIV
AN Supported	Yes	Most rome Mee
AN Incides:	Yes	Unk Apprepation TV
AN Advartised Closed By	10hoso1 10hoso170 100hoso12 100hoso1210 100hoso1210	Ageing attes Coperbility
		Angung mice Arel is
		Aggrogated Per-D
Option MAL types	30	Forect Via MD11LV
		feat Close
		M 1 Supported
		MD Drahlad
		Tale Controlle Mo
		Hat Newer Yers
		naro ya fuliwa s

The following table describes the labels in the Dot1 and Dot3 parts of the screen.

Table 111	PORT > LLDP > LLDP Remote Status > LLDP Remote Port Status Detail (Dot1 and Dot3
TL∨)	

IABEL	DESC RIPTIO N		
Dot1 TLV			
Port VLAN ID TLV	Port VIAN ID – This displays the VLAN ID of this port on the remote device.		
Vlan Name TLV	This shows the VLAN ID and name for remote device port.		
	<ul><li>VIAN ID</li><li>VIAN Name</li></ul>		
Protocol Identity TLV	Protocol ID – The Protocol Identity TLV allows the Switch to advertise the particular protocols that are accessible through its port.		
Port-Protocol VLAN ID TLV	This displays the IEEE 802.1 Port Protocol VLAN ID TLV, which indicates whether the VLAN ID and whether it is enabled and supported on the port of remote Switch which sent the LLDPDU.		
	Port-Protocol VIAN ID		
	Port-Protocol VIAN ID Supported     Port-Protocol VIAN ID Enabled		
	• Port-Protocol VIAN ID Enabled		
Dot3 TLV			
MAC PHY Configuration & Status TLV	The MAC/PHY Configuration/Status TLV advertises the bit-rate and duplex capability of the sending 802.3 node. It also advertises the current duplex and bit-rating of the sending node. Lastly, it advertises whether these setting were the result of auto-negotiation during link initiation or manual override.		
	<ul> <li>AN Supported – Displays if the port supports or does not support auto-negotiation.</li> <li>AN Enabled – The current auto-negotiation status of the port.</li> </ul>		
	<ul> <li>AN Advertised Capability – The auto-negotiation capabilities of the port.</li> <li>Oper MAU Type – The current Medium Attachment Unit (MAU) type of the port.</li> </ul>		
Max Frame Size TLV	Max Frame Size – This displays the maximum supported frame size in octets.		
Link Aggregation TLV	The Link Aggregation TLV indicates whether the link is capable of being aggregated, whether the link is currently in an aggregation, and if in an aggregation, the port identification of the aggregation.		
	<ul> <li>Aggregation Capability – The current aggregation capability of the port.</li> <li>Aggregation Status – The current aggregation status of the port.</li> <li>Aggregated Port ID – The aggregation ID of the current port.</li> </ul>		
Power Via MDI TLV	The Power Via MDI TLV allows network management to advertise and discover the MDI power support capabilities of the sending port on the remote device.		
	• Port Class		
	MDI Supported		
	MDI Ena ble d     De in Constan lle ble		
	Pair Controllable     PSE Power Pairs		
	PowerClass		

Copobilities 1.V	Device Type TV
Network Falley	Tenedo na Tegan
Location	Location Mentification 11V
Edend Fower - a MD1 F05	Counting of a base 101
Estend Tower VolMDTTD	0046100
Inventory Monopercent	IN
Colonded Power vio MDI 119	Network Folloy 1.V
Prevent Type:	Valea
Power Source	Valeo Signaling
Puwer Prenty	Cause Marce
Power Wolfer	Crues - Volkoe-Cignoling
	Soliphone-Wolce
	Minico Condensing
	Among video
	video à graine
Inventory IIV	
Licycle one Revision	
Sol ware Residen	
Firstworp Rovision	
wiedel Name	
Alamakae tahar	
Senial Number	
Asset IIC	

Figure 169 PORT > LLDP > LLDP Remote Status > LLDP Remote Port Status Detail (MED TLV)

The following table describes the labels in the MED TLV part of the screen.

Table 112	PORT > II DP >	> II DP > II DP Romoto	Status > LLDP Remote	Port Status Detail I	
			JIGIOS / LEDI KOIHOIO	T OFF STUTOS DOTUT	

LABEL	DESC RIPIIO N		
MED TLV			
media endpoint devi	t Discovery (MED) is an extension of LLDP that provides additional capabilities to support ices. MED enables advertisement and discovery of network policies, device location discovery ocation databases, and information for troubleshooting.		
Capabilities TLV	This displays the MED capabilities the remote port supports.		
	<ul> <li>Network Policy</li> <li>Location</li> <li>Extend Power via MDI PSE</li> <li>Extend Power via MDI PD</li> <li>Inventory Management</li> </ul>		
Device Type TLV	LLDP-MED endpoint device classes:  Endpoint Class I  Endpoint Class II  Network Connectivity		

IABEL	DESC RIPTIO N
Location Identification	This shows the location information of a caller by its:
TLV	Coordinate-base ICI – Latitude and longitude coordinates of the Location Configuration Information (LCI)
	<ul> <li>Civic ICI – IETF Geopriv Civic Address based Location Configuration Information</li> <li>ELIN – (Emergency Location Identifier Number)</li> </ul>
Extended Power via MDI TLV	Extended Power Via MDI Discovery enables detailed power information to be advertised by Media Endpoints, such as IP phones and Network Connectivity Devices such as the Switch.
	<ul> <li>Power Type – Whether it is currently operating from primary power or is on backup power (backup power may indicate to the Endpoint Device that it should move to a power conservation mode).</li> </ul>
	<ul> <li>Power Source – Whether or not the Endpoint is currently operating from an external power source.</li> </ul>
	<ul> <li>Power Priority – The Endpoint Device's power priority (which the Network Connectivity Device may use to prioritize which devices will remain in service during power shortages).</li> </ul>
	• <b>PowerValue</b> – Power requirement, in fractions of Watts, in current configuration.
Network Policy TLV	This displays a network policy for the specified application.
	• Voice
	Voice-Signaling
	Guest-Voice
	• Guest-Voice-Signaling
	Softphone-Voice
	Vide o-Conferencing
	<ul> <li>Streaming-Video</li> <li>Video-Signaling</li> </ul>
Inventory TLV	The majority of IP Phones lack support of management protocols such as SNMP, so LLDP-MED inventory TLVs are used to provide their inventory information to the Network Connectivity Devices such as the Switch. The Inventory TLV may contain the following information.
	• Hardware Revision
	• Software Revision
	• Firm wa re Revisio n
	• ModelName
	• Manufacturer
	• Serial Number
	• Asset ID

Table 110 DODTS		toth to > 11 DD Down at a Dowt Cto	
	· LLDP > LLDP > LLDP Remote \$	10108 > 110P Remote Port Sic	

# 35.5 IIDP Setup

Use this screen to configure global LLDP settings on the Switch. Click **PORT**> **ILDP** > **ILDP** > **ILDP** Setup to display the screen as shown next.

LIDP Local Status	LLDP Romote Status	LUDP Setup	Rosic TLV Setting
(cho	CON CO		
For smille the solu-	30 secores		
Transmit Hold	4 fines		
Present Delay	3 seconds		
Rectable Celay	(c)		
Pari -	Admin Status <u>TCR: ×</u>		Achillen .
	TX FX		
<b>8</b> 5	TX RX M		
3	To Ball M		17
4	Tx Rx 🛩		É.
<u>8</u> .)	$Tx_i Rx \equiv \mathcal{M}_i$		
8	Is-Ra V		
1	Is Ka w	<u>^</u>	Ö.
	Apply 12	1000	

#### Figure 170 PORT > LLDP > LLDP > LLDP Setup

The following table describes the labels in this screen.

#### Table 113 PORT > LLDP > LLDP > LLDP Setup

IABEL	DESC RIPTIO N	
Active	Select to enable LLDP on the Switch. It is enabled by default.	
Transmit Interval	Enter how many seconds the Switch waits before sending LLDP packets.	
Transmit Hold	Enter the time-to-live (TTL) multiplier of LLDP frames. The device information on the neighboring devices ages out and is discarded when its corresponding TTL expires. The TTL value is to multiply the TTL multiplier by the LLDP packets transmitting interval.	
Transmit Delay	Enter the delay (in seconds) between successive LLDPDU transmissions initiated by value or status changes in the Switch MIB.	
Reinitialize Delay	Enter the number of seconds for LLDP to wait before initializing on a port.	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Cancel	Click Cancel to begin configuring this screen afresh.	
Port	This displays the Switch's port number. * means all ports.	
*	Use this row to make the setting the same for all ports. Use this row first and then make adjustments to each port if necessary.	
	Changes in this row are copied to all the ports as soon as you make them.	

LABEL	DESC RIPTIO N	
Admin Status	<ul> <li>Select whether LLDP transmission and/or reception is allowed on this port.</li> <li>Disable – not allowed</li> <li>Tk-Only – transmit only</li> <li>Rx-Only – receive only</li> <li>Tk-Rx – transmit and receive</li> </ul>	
Notification	Select whether LLDP notification is enabled on this port.	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Cancel	Click Cancel to begin configuring this screen afresh.	

Table 113 PORT > LLDP > LLDP > LLDP Setup (continued)

## 35.6 Basic TLV Setting

Use this screen to configure Basic TLV settings. Click **PORT** > **IIDP** > **IIDP** > **Basic TLV Setting** to display the screen as shown next.

LDP Local	Status LLDP Re	mote Status U	DP Setup	Basic TLV Setting	
hart	Acidopement Address	Port Description	System Copablities	System Description	System Kons
1.2	12	0	- 01	<b>D</b> _1	(C)
***	5	2	2	8	12
2	8	2	1	22	22
3	5	2			8
+	5	12	23		12
÷	8	53	10	53	52
E.	2	22	2	2	2
7	83	2	8		
		Austy	Garee		

Figure 171 PORT > LLDP > LLDP > Basic TLV Setting

The following table describes the labels in this screen.

IABEL	DESC RIPTIO N	
Port	This displays the Switch's port number.	
*	Use this row to make the setting the same for all ports. Use this row first and then make adjustments to each port if necessary. Changes in this row are copied to all the ports as soon as you make them.	
Management Address	Select the check boxes to enable or disable the sending of Management Address TLVs on the ports.	
Port Description	Select the check boxes to enable or disable the sending of Port Description TLVs on the ports.	

Table 114 PORT > LLDP > LLDP > Basic TLV Setting

XGS2220 Series User's Guide

<sup>240</sup> 

Table 114	PORT > LLDP > LLDP	> Basic TLV Setting (continued)
-----------	--------------------	---------------------------------

IABEL	DESC RIPTIO N
System Capabilities	Select the check boxes to enable or to disable the sending of System Capabilities TLVs on the ports.
System Description	Select the check boxes to enable or to disable the sending of System Description TLVs on the ports.
System Name	Select the check boxes to enable or to disable the sending of System Name TLVs on the ports.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click <b>Cancel</b> to begin configuring this screen afresh.

# 35.7 Org-specific TLV Setting

Use this screen to configure organization-specific TLV settings. Click PORT > ILDP > ILDP > Org-specificTLV Setting to display the screen as shown next.

LLDP Local Status	LLDP Remote Status	LLDP Setup B	osic TLV Setting	Org-specif	ic TLV Setting
	Don	LILY.		Dor3 TLV	
Port	Port-Protociol VLAN ID	Port VLAN ID	Link Aggregation	MAC/PHY	Woz frome Stor
1		2			
2		<b>a</b>		<i></i>	
3		1		e' .	
4		2		£.,	
9		<b>a</b>			
٥		×	0		0
7		<u></u>		J.	
		Apply Comp			
		Apply Care	CT .		

Figure 172 PORT > LLDP > LLDP > Org-specific TLV Setting

LABEL	DESC RIPTIO N	
Port	This displays the Switch's port number.	
*	Use this row to make the setting the same for all ports. Use this row first and then make adjustments to each port if necessary.	
	Changes in this row are copied to all the ports as soon as you make them.	
Dot1 TLV		

LABEL	DESC RIPTIO N
Port-Protocol VLAN ID	Select the check boxes to enable or disable the sending of IEEE 802.1 Port and Protocol VLAN ID TLVs on the ports.
Port VLAN ID	Select the check boxes to enable or disable the sending of IEEE 802.1 Port VLAN ID TLVs on the ports. All check boxes in this column are enabled by default.
Dot3 TLV	
Link Select the check boxes to enable or disable the sending of IEEE 802.3 Link Aggregation on the ports.	
MAC/PHY	Select the check boxes to enable or disable the sending of IEEE 802.3 MAC/PHY Configuration/Status TLVs on the ports. All check boxes in this column are enabled by default.
Max Frame Size	Select the check boxes to enable or disable the sending of IEEE 802.3 Max Frame Size TLVs on the ports.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 115 PORT > LLDP > Drg-specific TLV Setting (continued)

## 35.8 LIDP-MED Setup

Click PORT> IIDP > IIDP MED > IIDP-MED Setup to display the screen as shown next.

Figure 173 PORT > LLDP > LLDP MED > LLDP-MED Setup

LLDP-MED Setup	LIDP-MED Network	e Policy — III	P-MED Location
Port	Notification	MED	ILV setting
	Topology Change	Location	Network Folloy
-			
1			
2			
3			
4			
5			
5			
7		~ !~	
	Apply	Cancel	

The following table describes the labels in this screen.

T. I. I. 11/	
1 able 1 1 6	PORT > LLDP > LLDP > LLDP-MED Setup

IABEL	DESC RIPTIO N			
Port	This displays the Switch's port number. Select * to configure all ports simultaneously.			
*	Use this row to make the setting the same for all ports. Use this row first and then make adjustments to each port if necessary.			
	Changes in this row are copied to all the ports as soon as you make them.			
Notification	•			
Topology Change	Select to enable LLDP-MED topology change traps on this port.			
MED TLV Setting	•			
Location Select to enable transmitting LLDP-MED location TLV.				
Network Policy	Select to enable transmitting LLDP-MED Network Policy TLV.			
Apply	Click <b>Apply</b> to save the changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the Save link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.			
Cancel	Click Cancel to begin configuring this screen afresh.			

## 35.9 LLDP-MED Network Policy

Click PORT> IIDP > IIDP MED > IIDP-MED Network Policy to display the screen as shown next.

LIDP-MED Sahup		LLOF-MED Network Policy		LLDP-MED Location			
					Q ALL	eva 1	C LANNE
0	lidex.	Port	Application Type	tog	YLAN	OSCE	tight
0	1.1	1	voice	teened	1	1.00	0

Figure 174 PORT > LLDP > LLDP MED > LLDP-MED Network Policy

Table 117 PORT > LLDP > LLDP MED > LLDP-MED Network Policy


IABEL	DESC RIPTIO N
Index	This field displays the of index number of the network policy. Click an index number to edit the rule.
Port	This field displays the port number of the network policy.
Application Type This field displays the application type of the network policy.	
Tag	This field displays the Tag Status of the network policy.
VLAN	This field displays the VLAN ID of the network policy.
DSCP This field displays the DSCP value of the network policy.	
Priority	This field displays the priority value of the network policy.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.

	L DESC RIPTIO N	
Add/Edit	Click Add/Edit to add a new schedule rule or edit a selected one.	
Delete	Select the rules that you want to remove, then click $\mathbf{De}\mathbf{le}\mathbf{te}.$	

Table 117 PORT > LLDP > LLDP MED > LLDP-MED Network Policy (continued)

### 35.9.1 Add/Edit LLDP-MED Ne two rk Policy

To access this screen, click the Add/Edit button or select an entry from the list and click the Add/Edit button.






Table 118	PORT > LLDP >	> LLDP MED >	LLDP-MED	Network Policy > Add/Edit
-----------	---------------	--------------	----------	---------------------------

IABEL	DESC RIPTIO N	
Port	Enter the port number to set up the LLDP-MED network policy. You can enter multiple ports separated by (no space) comma (",") or hyphen ("-") for a range. For example, enter "3-5" for ports 3, 4, and 5. Enter "3,5,7" for ports 3, 5, and 7.	
Application Type	Select the type of application used in the network policy.  voice voice-signaling guest-voice guest-voice-signaling softphone-voice video-conferencing streaming-video video-signaling	
Tag	<ul><li>Select to tag or untag in the network policy.</li><li>tagged</li><li>untagged</li></ul>	
VLAN	Enter the VLAN ID number. It should be from 1 to 4094. For priority tagged frames, enter "0".	
DSCP	Enter the DSCP value of the network policy. The value is defined from 0 through 63 with the 0 representing use of the default DSCP value.	
Priority	Enter the priority value for the network policy.	

IABEL	DESC RIPIIO N
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

Table 118 PORT > LLDP > LLDP MED > LLDP-MED Network Policy > Add/Edit (continued)

## 35.10 LLDP-MED Location

Click PORT> ILDP > ILDP MED > ILDP-MED Location to display the screen as shown next.

LLDP-MED Salup		UDP-2	MED Network Policy	LLDP-MED Location	
				O Advite	R 🛙 Ostate
0	Index.	Port	location Coordinates	Civic Addies	ELIN Number

The following table describes the labels in this screen.

Table 119 PORT > LLDP > LLDP MED > LLDP-MED Location

LABEL	DESC RIPTIO N
Index	This lists the index number of the location configuration. Click an index number to view or edit the location.
Port	This lists the port number of the location configuration.
Location Coordinates	This field displays the location configuration information based on geographical coordinates that includes longitude, latitude, altitude and datum.
Civic Address	This field displays the Civic Address for the remote device using information such as Country, State, County, City, Street, Number, ZIP code and additional information.
ELIN Number	This field shows the Emergency Location Identification Number (ELIN), which is used to identify endpoint devices when they issue emergency call services. The valid length is form 10 to 25 characters.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to add a new location or edit a selected one.
Delete	Select the locations that you want to remove, then click $\mathbf{De}  \mathbf{le}  \mathbf{te}$ .

## 35.10.1 Add/Edit IIDP-MED Location

To access this screen, click the Add/Edit button or select an entry from the list and click the Add/Edit button.

calan Coordina			
alli Ade	[ north w]		
obult gric	watal 🐱		
Alitzen	[masses v.]		
Ngium :	NN 2893 😽		
Civic Address			
County		2030	
County	Ĩ	CIN	
Disiden.			
Shoef		Loading Street Direction	
Strawel Softing	Γ	Transport web Santh	
Protee-No. (1894)		Poise-Number-	
l ar adarca b		Additionel- Losoffen	
Nation		/ip-faide	
Dulicing	Ê.	Unit	
Fice		Reconstruction	
Race type		Footo Currincinty N/ms	
Poel-Office-Tox	le	Additions (Secie	
EUN			
EUN NUMBER			

#### Figure 177 PORT > LLDP > LLDP MED > LLDP-MED Location > Add/Edit

Table 120 PC	ORT > LLDP >	LLDP MED >	LLDP-MED	Location >	Add/Edit
--------------	--------------	------------	----------	------------	----------

LABEL	DESC RIPTIO N			
Port	nter the port number you want to set up the location within the LLDP-MED network.			
Location Coordinate	S			
device. Geographic	eographical coordinates and Civic Address to set the location information of the remote al based coordinates includes latitude, longitude, altitude and datum. Civic Address includes ty, City, Street and other related information.			
Latitude	Enter the latitude information. The value should be from 0° to 90°.			
	<ul><li>north</li><li>south</li></ul>			

IABEL	DESC RIPIIO N			
Longitude	Enter the longitude information. The value should be from 0° to 180°.			
	• west			
	• east			
Altitude	Enter the altitude information. The value should be from –2097151 to 2097151 in meters or in floors.			
	• meters			
	• floor			
Datum	Select the appropriate geodetic datum used by GPS.			
	• WG \$84			
	• NAD83-NAVD88			
	• NAD83-MILW			
Civic Address	Enter the Civic Address by providing information such as Country, State, County, City, Street, Number, ZIP code and other additional information. Enter at least 2 fields in this configuration including the Country. The valid length of the Country field is 2 characters and all other fields are up to 32 characters.			
	• Country			
	• State			
	• County			
	• City			
	• Division			
	<ul> <li>Neighbor</li> <li>Street</li> </ul>			
	Le a ding - Stree t-Direction			
	Street Suffix			
	Tia iling - Stree t- Suffix			
	• House-Number			
	• House - Number Suffix			
	• Landmark			
	• Additional-Location			
	• Name			
	• Zip-Code			
	• Building			
	• Unit			
	• Floor			
	Room-Number			
	<ul> <li>Place-Type</li> <li>Postal-Community-Name</li> </ul>			
	Post-Office-Box			
	Additional-Code			
ELIN Number	Enter a numerical digit string, corresponding to the ELIN identifier which is used during emergency call setup to a traditional CAMA or ISDN trunk-based PSAP. The valid length is from 10 to 25 characters.			
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.			
Clear	Click Clear to clear the fields to the factory defaults.			
	Click <b>Cancel</b> to not save the configuration you make and return to the last screen.			

#### Table 120 PORT > LLDP MED > LLDP-MED Location > Add/Edit (continued)

# C HAPTER 36 OAM

## 36.1 OAM Overview

Link layer Ethernet OAM (Operations, Administration and Maintenance) as described in IEEE 802.3ah is a link monitoring protocol. It utilizes OAM Protocol Data Units or OAM PDUs to transmit link status information between directly connected Ethernet devices. Both devices must support IEEE 802.3ah. Because link layer Ethernet OAM operates at layer two of the OSI (Open Systems Interconnection Basic Reference) model, neither IP or SNMP are necessary to monitor or troubleshoot network connection problems.

The Switch supports the following IEEE 802.3ah features:

- Discovery this identifies the devices on each end of the Ethernet link and their OAM configuration.
- Remote Loopback this can initiate a loopback test between Ethernet devices.

#### 36.1.1 What You Can Do

- Use the **OAM Status** screen (Section 36.2 on page 248) to view the configuration of ports on which Ethernet OAM is enabled.
- Use the OAM Setup screen (Section 36.3 on page 253) to enable Ethernet OAM on the Switch.
- Use the OAM Remote Loopback screen (Section 36.4 on page 254) to perform remote-loopback tests.

## 36.2 OAM Status

Use this screen to view the configuration of ports on which Ethernet OAM is enabled. Click **PORT** > **OAM** > **OAM** Status in the navigation panel.

Figure 178	PORT > OAM > OAM Status
------------	-------------------------

OAM Skilov	OAM Selop	OAM Kemple	<ul> <li>toopback</li> </ul>		
OAM is discl	bed				
U	ocal		Kvn	nole	
Rod	Mode	Mod Address	000	Mode	Corrig
1					
2					
5					
4					
2					
<u>é</u>					
7		$\sim$		$\sim$	~~~
			$\sim$		$\tilde{}$

The following table describes the fields in the above screen.

<b>T</b>	
Table 121	PORT > OAM > OAM Status

LABEL	DESC RIPTIO N		
Local			
This section displays information about the ports on the Switch.			
Port	This field displays the port number.		
Mode	This field displays the operational state of the port when OAM is enabled on the port.		
	$\mathbf{Active}$ – Allows the port to issue and respond to Ethernet OAM commands.		
	$\mathbf{Passive}$ – Allows the port to respond to Ethernet OAM commands.		
Remote			
This section displays information about the remote device.			
Mac Address	This field displays the MAC address of the remote device.		
OUI	This field displays the OUI (first 3 bytes of the MAC address) of the remote device.		
Mode	This field displays the operational state of the port when OAM is enabled on the port.		
	$\mathbf{Active}$ – Allows the port to issue and respond to Ethernet OAM commands.		
	$\mathbf{Passive}$ – Allows the port to respond to Ethernet OAM commands.		
Config	This field displays the capabilities of the Switch and remote device.		

## 36.2.1 OAM Details

Use this screen to view OAM configuration details and operational status of a specific port. Click an number in the **Port** column in the **PORT** > **OAM** > **OAM** Status screen to display the screen as shown next.

249

OAM Sigius	OAM Selup	OAM Remote Loopback			
		·			
OAM Stolus 2	- OAM De Miz				
cost and as a					
Port No: 1					
Discovery					
Annual Chinese Pro-	-	Remote Client			
Local Client Setup Mode		NAC odders			
Wate Unividentional		Venderfoul)			
Semate loopback					
Nometo ideo poteix Hink eventa		Remote Client Setup			
Voolotele vehievool		No de Unicipación d			
Max, OAMPOU size		Articilio chiorità Merricile loscolocolo			
		link events			
		Vojable refievel			
		Mox CV/APDU size			
	peration al Status	Remote Client Operational Status			
Unk status		Info revision			
hito, revikion Porser kiole					
Discovery shot					
		Statistics			
Information O	AMPDU 18				
Information O	AMPOL R:				
Eveni Notinca	for CAMPDU Is				
Event Notines	Ion CAMPDU IX.				
Loopback Co	ntrol-OAMPOUTx				
Loopback Co	ntrol OAMPOU Rx				
Variable Perg	est OAMPOUIs				
Variable Reg.	est CAMPOLIEs				
Variable Resp	erse OAMPDU 1a				
-	orse CAMPDURA				
Unsupported	OVAMPENU TA				
Unsupported	oww.peu rx				

Figure 179 PORT > OAM > OAM Status > OAM Details

The following table describes the fields in the above screen.

 Table 122
 PORT > OAM > OAM Status > OAM Details

LABEL	DESC RIPIIO N	
Port No	This field displays the port number.	
Discovery		
This section displays OAM configuration details and operational status of the port on the Switch and/or the remote device.		

LABEL	DESC RIPTIO N		
Local Client/Remote Client Setup			
Mode	This field displays the OAM mode. The device in active mode (typically the service provider's device) controls the device in passive mode (typically the subscriber's device).		
	Ac tive : The port initiates OAM discovery; sends information PDUs; and may send event notification PDUs, variable request/response PDUs, or loopback control PDUs.		
	<b>Passive</b> : The port waits for the remote device to initiate OAM discovery; sends information PDUs; may send event notification PDUs; and may respond to variable request PDUs or loopback control PDUs.		
	The Switch might not support some types of PDUs, as indicated in the fields below.		
Unidirectional	This field indicates whether or not the port can send information PDUs to transmit fault information when the receive path is non-operational.		
Remote loopback	This field indicates whether or not the port can use loopback control PDUs to put the remote device into loopback mode.		
Link events	This field indicates whether or not the port can interpret link events, such as link fault and dying gasp. Link events are sent in event notification PDUs and indicate when the number of errors in a given interval (time, number of frames, number of symbols, or number of error frame seconds) exceeds a specified threshold. Organizations may create organization-specific link event TLVs as well.		
Variable retrieval	This field indicates whether or not the port can respond to requests for more information, such as requests for Ethernet counters and statistics, about link events.		
Max. OAMPDU size	This field displays the maximum size of PDU for receipt and delivery.		
Local Client/Remote C	lient Operational status		
Link status	This field indicates that the link between the Switch port and a connected IEEE 802.3ah- enabled remote Ethernet device is up or down.		
Info. revision	This field displays the current version of local state and configuration. This two-octet value starts at zero and increments every time the local state or configuration changes.		
Parser state	This field indicates the current state of the parser.		
	Forward: The port is forwarding packets normally.		
	Loopback: The port is in loopback mode.		
	<b>Disc a rd</b> : The port is discarding non-OAM PDUs because it is trying to or has put the remote device into loopback mode.		

Table 122 PORT > OAM > OAM Status > OAM Details (continued)

LABEL	DESC RIPHO N		
Discovery state	This field indicates the state in the OAM discovery process. OAM-enabled devices use this process to detect each other and to exchange information about their OAM configuration and capabilities. OAM discovery is a handshake protocol.		
	Fault: One of the devices is transmitting OAM PDUs with link fault information, or the interface is not operational.		
	Active Send Local: The port is in active mode and is trying to see if the remote device supports OAM.		
	<b>Passive Wait</b> : The port is in passive mode and is waiting for the remote device to begin OAM discovery.		
	Send Local Remote: This state occurs in the following circumstances.		
	• The port has discovered the remote device but has not accepted or rejected the connection yet.		
	• The port has discovered the remote device and rejected the connection.		
	Send Local Remote OK: The port has discovered the remote device and has accepted the connection. In addition, the remote device has not accepted or rejected the connection yet, or the remote device has rejected the connected.		
	Send Any: The port and the remote device have accepted the connection. This is the operating state for OAM links that are fully operational.		
Remote Client			
MAC Address	This field displays the MAC address of the IEEE 802.3ah-enabled remote Ethernet device that is connected to the Switch.		
Vendor(oui)	This field displays the Organizationally Unique Identifiers (OUI) representing the vendor of the IEEE 802.3ah-enabled remote Ethernet device that is connected to the Switch.		
Statistics			
This section displays the	e number of OAM packets transferred on the port of the Switch.		
Information OAMPDU Tx	This field displays the number of OAM PDUs sent on the port.		
Information OAMPDU Rx	This field displays the number of OAM PDUs received on the port.		
Event Notification OAMPDU Tx	This field displays the number of unique or duplicate OAM event notification PDUs sent on the port.		
Event Notification OAMPDU Rx	This field displays the number of unique or duplicate OAM event notification PDUs received on the port.		
Loopback Control OAMPDU Tx	This field displays the number of loopback control OAM PDUs sent on the port.		
Loopback Control OAMPDU Rx	This field displays the number of loopback control OAM PDUs received on the port.		
Variable Request OAMPDU Tx	This field displays the number of OAM PDUs sent to request MIB objects on the remote device.		
Variable Request OAMPDU Rx	This field displays the number of OAM PDUs received requesting MIB objects on the Switch.		
Variable Response OAMPDU Tx	This field displays the number of OAM PDUs sent by the Switch in response to requests.		
Variable Response OAMPDU Rx	This field displays the number of OAM PDUs sent by the remote device in response to requests.		

Table 122 PORT > OAM > OAM Status > OAM Details (continued)

IABEL DESCRIPTION			
Unsupported OAMPDU Tx	This field displays the number of unsupported OAM PDUs sent on the port.		
Unsupported OAMPDU Rx	This field displays the number of unsupported OAM PDUs received on the port.		

## 36.3 OAM Setup

Use this screen to turn on Ethernet OAM on the Switch and ports and configure the related settings.

Click **PORT** > **OAM** > **OAM** Setup to display the configuration screen as shown.

OAM Status, OAM Remote Loopback. OAM Setup 2.2164 ( NEE) Remote Loopbeeck Kemele Leopbeck Active Node Port-Supported. ignore-tri ē. ACTOR Y anthe M action m E  $\tilde{e}_{i}$ actio M ż C. active m 12  $\mathbf{b}$ nothing re-63 67 D Active M. 21 Active Y -17. Y Faincel **Apply** 

Figure 180 PORT > OAM > OAM Setup

The following table describes the fields in the above screen.

IABEL	DESC RIPTIO N			
Active	Enable the switch button to enable Ethernet OAM on the Switch.			
Port	This field displays the port number.			
*	Settings in this row apply to all ports.			
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.			
	Note: Changes in this row are copied to all the ports as soon as you make them.			

Table 123 PORT > OAM > OAM Setup

LABEL	DESC RIPTIO N
Active	Select this check box to enable Ethernet OAM on this port.
	Clear this check box to disable Ethernet OAM on the port.
Mode	Specify the OAM mode on the port.
	Select $\mathbf{Active}$ to allow the port to issue and respond to Ethernet OAM commands.
	Select $\mathbf{Passive}$ to allow the port to respond to Ethernet OAM commands.
Remote Loopback Supported	Select this check box to enable the remote loopback feature on the port. Otherwise, clear the check box to disable it.
Remote Loopback Ignore-Rx	Select this check box to set the Switch to process loopback commands received on the port. Otherwise, clear the check box to have the Switch ignore loopback commands received on the port.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

# 36.4 OAM Remote Loopback

Use this screen to perform a remote loopback test. Click **PORT** > **OAM Remote Loopback** to display the screen as shown.

Figure 181 PORT > OAM > OAM Remote Loopback

OAM Status	OAM Selup	OAM Remole Loopback	
Infe			
Remote Loopi	bock leat		
Port			
Number of Po	skot		
Pocket Ste			
Tool			
Remote Loop	back Mode		
Port	]		
Start Stop	l		

The following table describes the fields in the above screen.

Table 124	PORT > C	> MAC	OAM	Remote	Loopback
		//////	0/ 11/1	Kernole	LOOPDOCK

IABEL	DESC RIPIIO N
Remote Loopback Test	
Port	Enter the number of the port from which the Switch performs a remote-loopback test.
Number of Packet	Define the allowable packet number of the loopback test frames.
Packet Size	Define the allowable packet size of the loopback test frames.
Test	Click Tlest to begin the test.
Remote Loopback Mod	de
Port	Enter the number of the port from which the Switch sends loopback control PDUs to initiate or terminate a remote-loopback test.
Start	Click <b>Start</b> to initiate a remote-loopback test from the specified port by sending Enable Loopback Control PDUs to the remote device.
Stop	Click $\mathbf{Stop}$ to terminate a remote-loopback test from the specified port by sending Disable Loopback Control PDUs to the remote device.

# C HAPTER 37 PoESetup

# **37.1** PoE Status (for PoE models only)


Note: The following screens are available for the PoE models only.

The PoE models supports the IEEE 802.3bt High Power over Ethernet (PoE) standard.

A powered device (PD) is a device such as an access point or a switch, that supports PoE (Power over Ethernet) so that it can receive power from another device through an Ethernet port.

In the figure below, the IP camera and IP phone get their power directly from the Switch. Aside from minimizing the need for cables and wires, PoE removes the hassle of trying to find a nearby electric outlet to power up devices.

Figure 182 Powered Device Examples



You can also set priorities so that the Switch is able to reserve and allocate power to certain PDs.

Note: The PoE (Power over Ethernet) devices that supply or receive power and their connected Ethernet cables must all be completely indoors.

256

Figure 183	PORT > PoE Setup > PoE Status
------------	-------------------------------

of Burks	PotSchitz	Pot One Res	nge tëtai				
en et Garden		$(2, \alpha) \in (\alpha, \beta, \beta, \beta, \alpha) \in (0, 1, 2, 2, 2, 2, 2, 2, 2, 2, 2, 2, 2, 2, 2,$					
dilate the second	22	124 C					
Part and get		8.7					
	2.412 (2.01 (A)	19. 2.2					
	and when the						
	2500 107	3. A.					
apsing	204 34	263					
( M	326	56.0	Search -	N/4548	Contracting Porter (%)	Pais Portel (N)	States and a state of
1.1	1	2	.2%	904.18°	22	( <del>.</del> .	+
33	(India)	3	·~	P10.0 1	- A4 -		
- 90	1		189	0.02.57	302	12	21
	(Index			1923	1.2		
10	A setter 1		.79	102.57	9.97	1.2	15
12	1.1.444	1		140.5 s	1.1		
	I tooks .		792	100.00	10		4
	1 init				$\sim$		
			_	400 2.4	$\sim$		

Table 125 PORT > PoE Setup > PoE Status

IABEL	DESC RIPTIO N
PoE Mode	This field displays the power management mode used by the Switch, whether it is in <b>Classific a tion</b> or <b>Consumption</b> mode.
Total Power (W)	This field displays the total power the Switch can provide to the connected PoE-enabled devices on the PoE ports.
PoE Usage (%)	This field displays the amount of power currently being supplied to connected PoE devices (PDs) as a percentage of the total PoE power the Switch can supply.
	When PoE usage reaches 100%, the Switch will shut down PDs one-by-one according to the PD priority which you configured in $PORT > PoESe tup > PoESe tup$ .
PoE Usage Threshold (%)	This field displays the percentage of PoE usage. The Switch will generate a trap and/or a log when the usage exceeds the specified threshold.
Consuming Power (W)	This field displays the amount of power the Switch is currently supplying to the connected PoE- enabled devices.
Allocated Power (W)	This field displays the total amount of power the Switch (in classification mode) has reserved for PoE after negotiating with the connected PoE devices. It shows <b>NA</b> when the Switch is in consumption mode.
	Consuming Power(W) can be less than or equal but not more than the Allocated Power(W).
Remaining Power (W)	This field displays the amount of power the Switch can still provide for PoE.
Port	This is the port index number.
State	This field shows which ports can receive power from the Switch.
	<ul> <li>Disable – The PD connected to this port cannot get power supply.</li> <li>Enable – The PD connected to this port can receive power.</li> </ul>

IABEL	DESC RIPIIO N			
Class	This shows the power classification of the PD. Each PD has a spunder one of the classes			

Class	This shows the power classification of the PD. Each PD has a specified maximum power that fall
	under one of the classes.
	The $C \ln ss$ is a number from 0 to 6, where each value represents the range of power that the Switch provides to the PD. The power ranges in PoE standards are as follows.
	<ul> <li>Class 0 - default: 0.44 W to 15.4 W.</li> <li>Class 1 - default: 0.44 W to 4 W.</li> <li>Class 2 - default: 0.44 W to 7 W.</li> <li>Class 3 - default: 0.44 W to 15.4 W.</li> <li>Class 4 - default: 0.44 W to 30 W.</li> <li>Class 5 - default: 0.44 W to 45 W.</li> <li>Class 6 - default: 0.44 W to 60 W.</li> <li>Note: You can extend or set a limit on the maximum power the connected PD can use on a port in PORT&gt; PoESe tup &gt; PoESe tup.</li> </ul>
Priority	When the total power requested by the PDs exceeds the total PoE power budget on the Switch, you can set the priority to allow the Switch to provide power to ports with higher priority first.
	<ul> <li>Critic al has the highest priority.</li> <li>High has the Switch assign power to the port after all critical priority ports are served.</li> <li>Low has the Switch assign power to the port after all critical and high priority ports are served.</li> </ul>
Power-Up	This field displays the PoE standard the Switch uses to provide power on this port.
Consuming Power (W)	This field displays the current amount of power consumed by the PD from the Switch on this port.
Max Power (W)	This field displays the maximum amount of power the PD could use from the Switch on this port. This field displays "" if the maximum power is not specified in <b>Basic Setting</b> > <b>PoE Setup</b> > <b>PoE</b> <b>Setup</b> .
Time-Range State	This field shows whether or not the port currently receives power from the Switch according to its schedule.
	<ul> <li>It shows "<b>In</b>" followed by the time range name if PoE is currently enabled on the port.</li> <li>It shows "<b>Out</b>" if PoE is currently disabled on the port.</li> <li>It shows "-" if no schedule is applied to the port. PoE is enabled by default.</li> </ul>

## 37.2 PoESetup

Use this screen to set the PoE power management mode, priority levels, power-up mode and the maximum amount of power for the connected PDs.

Click the PoESetup tab in the PORT > PoESetup screen. The following screen opens.

of General Part Colog	I for their being	e tokja -			
in 1999 German Pol	(129	Q			
d the based of the	1000				
-	-	1001	a (mystage	Non-angelog	1.0 week rough
	2	- HOUSE	a finite set an an an		
		100.00	Kiler -		1.0
41	6	114 41	(BRENT 200)		6
	The second secon	100	10.000		
4.5	6	De Al	15159		6
		100 -1	10.000		5 (F
		12m (A)	Lines of		ä
10		14 11	Distant X		10
- E	100	den et al.	Kither -	14	
	.0	(Sec. 9)	1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.		. 5
	-	320.00	1000 v		
71	5	14.14	16.564		5
¥.,		Arts 191	16424		
14.1	6	(Terring)	10000		# 5
14		100.23	0.21		
-	_	and the second			$\sim$
					$\sim$
				- ~	

Figure 184 PORT > PoE Setup > PoE Setup

The following table describes the labels in this screen.

#### Table 126 PORT > PoE Setup > PoE Setup

IABEL	DESC RIPTIO N
PoE Mode	Select the power management mode you want the Switch to use.
	• <b>Classification</b> – Select this if you want the Switch to reserve the maximum power for each PD according to the PD's power class and priority level. If the total power supply runs out, PDs with lower priority do not get power to function. In this mode, the maximum power is reserved based on what you configure in <b>Max Power</b> or the standard power limit for each class.
	<ul> <li>Consumption – Select this if you want the Switch to supply the actual power that the PD needs. The Switch also allocates power based on a port's Max Power and the PD's power class and priority level. The Switch puts a limit on the maximum amount of power the PD can request and use. In this mode, the default maximum power that can be delivered to the PD is 30 W (IEEE 802.3at Class 4) or 22 W (IEEE 802.3at Classes 0 to 3).</li> </ul>
Continuous PoE	Select <b>ON</b> to guarantee continuous power supply to the connected PDs while the Switch is restarting after a warm reboot. The Switch will NOT perform a power cycle on the connected PDs.
	If you do a cold reboot, the Switch also restarts the connected PDs.

LABEL	DESC RIPHO N				
MIB Trap	The Switch sends traps (monitoring event notification) to an SNMP (Simple Network Management Protocol) manager when an event occurs. See Section 26.6.1 on page 195 for more information on SNMP, MIB (Management Information Base), and SNMP traps.				
	Select $\mathbf{ON}$ to allow sending of MIB Trap when the following situations occur:				
	<ul> <li>Situation 1 – Trap sent whenever a PoE port status change occurs (PoE port delivers power or delivers no power to a PD (powered device)</li> <li>Situation 2 – Trap sent in cases where the total power usage exceeds the PoE usage threshold</li> <li>Situation 3 – Trap sent if total usage power decreases below the PoE usage threshold (only if previous total power usage exceeded the PoE usage threshold and a trap was sent).</li> </ul>				
	Note: If the <b>MIB</b> Thap is <b>ON</b> , you must also configure:				
	<ul> <li>SNMP trap destination (SYSTEM &gt; SNMP &gt; SNMP), SNMP trap group (SYSTEM &gt; SNMP &gt; SNMP Thap Group) and SNMP trap port (SYSTEM &gt; SNMP &gt; SNMP Thap Port) for Situation 1</li> <li>SNMP trap destination and SNMP trap group for Situation 2 and Situation 3.</li> </ul>				
	See Section 26.2 on page 189 for more information on configuring SNMP.				
PoE Usage Threshold (%)	Enter a number ranging from 1 to 99 to set the threshold. The Switch will generate a trap and/or log when the actual PoE usage is higher than the specified threshold.				
Port	This is the port index number.				
*	Settings in this row apply to all ports.				
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.				
	Changes in this row are copied to all the ports as soon as you make them.				
Active	Select this to provide power to a PD connected to the port.				
	If left unchecked, the PD connected to the port cannot receive power from the Switch.				
Priority	When the total power requested by the PDs exceeds the total PoE power budget on the Switch, you can set the PD priority to allow the Switch to provide power to ports with higher priority.				
	Select <b>C ritic a I</b> to give the highest PD priority on the port.				
	Select <b>High</b> to set the Switch to assign the remaining power to the port after all critical priority ports are served.				
	Select $\mathbf{Low}$ to set the Switch to assign the remaining power to the port after all critical and high priority ports are served.				

Table 126	PORT > PoE Setup >	PoF Setun	(continued)
	1 OKI > 1 OF 2610b >	I OL SEIUP	(connined)

LABEL	DESC RIPTIO N
Power-Up	Set how the Switch provides power to a connected PD at power-up.
	802.3af – the Switch follows the IEEE 802.3af Power over Ethernet standard to supply power to the connected PDs during power-up.
	$\mathbf{Legacy}$ – the Switch can provide power to the connected PDs that require high inrush currents at power-up. Inrush current is the maximum, instantaneous input current drawn by the PD when first turned on.
	<b>Pre</b> - <b>802.3a t</b> – the Switch initially offers power on the port according to the IEEE 802.3af standard, and then switches to support the IEEE 802.3at standard within 75 milliseconds after a PD is connected to the port. Select this option if the Switch is performing 2-event Layer-1 classification (PoE+ hardware classification) or the connected PD is NOT performing Layer 2 power classification using Link Layer Discovery Protocol (LLDP).
	802.3at – the Switch supports the IEEE 802.3at High Power over Ethernet standard and can supply power of up to 30 W per Ethernet port. IEEE 802.3at is also known as PoE+ or PoE Plus. An IEEE 802.3at compatible device is referred to as Type 2. Power Class 4 (High Power) can only be used by Type 2 devices. If the connected PD requires a Class 4 current when it is turned on, it will be powered up in this mode.
	For $e-802.3at$ – the Switch offers power of up to 33 W on the port without performing PoE hardware classification. Select this option if the connected PD does not comply with any PoE standard and requests power higher than a standard power limit.
	<b>Pre-802.3bt</b> – the Switch offers power on the port according to the IEEE 802.3bt standard. Select this option if the connected PD was developed before the IEEE 802.3bt standard is implemented but requires power between 33 W and 60 W. IEEE 802.3bt is also known as PoE++ or PoE Plus Plus.
	802.3bt – the Switch supports the IEEE 802.3bt standard and can supply power of up to 60 W per Ethernet port to the connected PDs at power-up.
Max Power (mW)	Specify the maximum amount of power the PD could use from the Switch on this port. If you leave this field blank, the Switch refers to the standard or default maximum power for each class.
	Note: The setting you enter here will NOT take effect when the power-up mode is set to <b>802.3b t</b> .
LLDP Power Via MDI	Select this to have the Switch negotiate PoE power with the PD connected to the port by transmitting LLDP Power Via MDI TLV frames. This helps the Switch allocate less power to the PD on this port. The connected PD must be able to request PoE power through LLDP.
	The Power Via MDI TLV allows PoE devices to advertise and discover the MDI power support capabilities of the sending port on the remote device.
	<ul> <li>Port Class</li> <li>MDI Supported</li> <li>MDI Enabled</li> <li>Pair Controllable</li> <li>PSE Power Pairs</li> <li>Power Class</li> </ul>
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

## 37.3 PoETime Range Setup

Use this screen to apply a schedule to the ports on the Switch. You must first configure a schedule in the SYSTEM > Time Range screen.

Figure 185 PORT > PoE Setup > PoE Time Range Setup

Publicius	Pot Sciop	Poë Time Kunge Selup		
				Qinamuti 🔮 balar
		Part -	Term Bange Failles	
		1		
		2	•	
		1		
		4		
		5		
		1.1	•	
		1		$\sim$
			$\sim$	
			$\checkmark$	~ ~

The following table describes the labels in this screen.

Table 127	PORT > PoE Setu	o > PoE Time	Ranae Setup

IABEL	DESC RIPIIO N
Port	This field displays the index number of the port. Click a port number to change the schedule settings.
Time Range	This field displays the name of the schedule which is applied to the port.
Profiles	PoE is enabled at the specified time or date.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to add a new rule or edit a selected one.
Delete	Check the rules that you want to remove and then click the $\mathbf{De}  \mathbf{le}  \mathbf{te}$ button.

### 37.3.1 Add/Edit PoETime Range

To access this screen, click the Add/Edit button or select an entry from the list and click the Add/Edit button.

Figure 186 PORT > PoE Setup > PoE Time Range Setup > Add/Edit

+od	1		
Time Songe			-
			-
	Anply	Clear	Concel

Table 128	PORT > PoE Setup > PoE Time Range Setup > Add/Edit
10010 120	

IABEL	DESC RIPTIO N
Port	Enter the number of the port to which you want to apply a schedule.
Time Range	This field displays the name of the schedule that you have created using the <b>SYSTEM</b> > <b>Time</b> <b>Range</b> screen. Select a pre-defined schedule to control when the Switch enables PoE to provide power on the port. To select more than one schedule, press [SHIFT] and select the choices at the same time.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click <b>Clear</b> to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

# C HAPTER 38 Port Se tup

## 38.1 Port Setup

Use this screen to configure Switch port settings. Click **PORT** > **Port Setup** in the navigation panel to display the configuration screen.

201	Actsy	Nate	Special C	obies.	Now Control	- 900.00 Proof	89.003.01	Made 1886
35	a (		2.16	21	Evaple M	0.2	Pear	1911 N
			- A.15		Example w	0.9	Press and	g++ v
$\frac{1}{2}$	a (		Acio	<u></u>	Evande M	0 v	Yve: v	arr v
13	<b>a</b> (		>.lo	×.	Could ve	. Q 💌	<u>PVat</u>	8++ ×
${\mathfrak X}_{\mathbb C}$	0		<u></u>	~	Disable w	<u>. U x </u>	No. Y	814
8	2		144	<u> </u>	$1.72M_{\odot} \sim$	<u> </u>	No. x	g-++ v
÷			0.00		$[0,\infty] [v,v]$	<u>0 ×</u>	$\underline{\mathbf{N}}_{\mathbf{x}}^{(i)} = \mathbf{v}_{\mathbf{x}}^{(i)}$	Serve a
+			<u>A.b</u>	1		U.v.	. Po:	d+++ +
				<u> </u>		1.+		1.0

Figure 187 PORT > Port Setup

The following table describes the labels in this screen.

	Table 129	PORT > Port Setup
--	-----------	-------------------

IABEL	DESC RIPTIO N
Port	This is the port index number.
*	Settings in this row apply to all ports. Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis. Note: Changes in this row are copied to all the ports as soon as you make them.
Active	Select this check box to enable a port. The factory default for all ports is enabled. A port must be enabled for data transmission to occur.
Name	Type a descriptive name that identifies this port. You can enter up to 128 printable ASCII characters except [?], [   ], ['] or ["].         Note: Due to space limitations, the port name may be truncated in some Web Configurator screens.

XGS2220 Series User's Guide

LABEL	DESC RIPHO N
Speed/Duplex	Select the speed and the duplex mode of the Ethernet connection on this port. Choices are Auto, Auto-1G, 10-an (10M/auto-negotiation), 10M/Full Duplex, 100-an (100M/auto- negotiation), 100M/Full Duplex, 1G/Full Duplex, 2.5G/Full Duplex, 5G/Full Duplex, and 10G/Full Duplex (Gigabit connections only).
	Selecting <b>Auto-1G</b> or <b>Auto</b> (auto-negotiation) allows one port to negotiate with a peer port automatically to obtain the connection speed and duplex mode that both ends support. When auto-negotiation is turned on, a port on the Switch negotiates with the peer automatically to determine the connection speed and duplex mode. If the peer port does not support auto- negotiation or turns off this feature, the Switch determines the connection speed by detecting the signal on the cable and using half duplex mode. When the Switch's auto-negotiation is turned off, a port uses the pre-configured speed and duplex mode when making a connection, thus requiring you to make sure that the settings of the peer port are the same in order to connect.
Flow Control	A concentration of traffic on a port decreases port bandwidth and overflows buffer memory causing packet discards and frame losses. Flow Control is used to regulate transmission of signals to match the bandwidth of the receiving port.
	The Switch uses IEEE 802.3x flow control in full duplex mode and backpressure flow control in half duplex mode.
	IEEE 802.3x flow control is used in full duplex mode to send a pause signal to the sending port, causing it to temporarily stop sending signals when the receiving port memory buffers fill.
	Back Pressure flow control is typically used in half duplex mode to send a "collision" signal to the sending port (mimicking a state of packet collision) causing the sending port to temporarily stop sending signals and resend later.
	Select <b>Tx Rx</b> to allow the Switch port to send pause signal to the connected device, and for the connected device to send a pause signal to the Switch. The Switch will temporarily stop sending signals after receiving pause signal.
	Select $\mathbf{T}_{\mathbf{X}}$ to allow the Switch port to send pause signal to the connected device.
	Select $\mathbf{R}_{\mathbf{x}}$ to allow the connected device to send a pause signal to the Switch. The Switch will temporarily stop sending signals.
	Otherwise, select <b>Disable</b> .
802.1p Priority	This priority value is added to incoming frames without a (802.1p) tag.
BPDU Ctrl	Configure the way to treat BPDUs received on this port. You must activate <b>Bridging Control</b> <b>Protocol Transparency</b> in the <b>SYSTEM</b> > <b>Switch Setup</b> screen first.
	Select $\mathbf{Peer}$ to process any BPDU (Bridge Protocol Data Units) received on this port.
	Select Tunnel to forward BPDUs received on this port.
	Select <b>Disc a rd</b> to drop any BPDU received on this port.
	Select <b>Network</b> to process a BPDU with no VLAN tag and forward a tagged BPDU.
Media Type	You can insert either an SFP+ transceiver or an SFP+ Direct Attach Copper (DAC) cable into the 10 Gigabit interface of the Switch.
	Select the media type (SFP+ or DAC10G) of the SFP+ module that is attached to the 10 Gigabit interface.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.


Table 129 PORT > Port Setup (continued)

# C HAPTER 39

## 39.1 ZUID Overview

A unidirectional link is a connection where the link is up on both ends, but only one end can receive packets. This may happen if OAM was initially enabled but then disabled, there are mis-configured transmitting or receiving lines or the hardware is malfunctioning. Zyxel Unidirectional Link Detection (ZULD) is a layer-2 protocol that can detect and disable these physical one-way links before they cause loops or communication malfunction.

In the figure below, S1-A is a bidirectional link as both ends can send packets to each other. S1-B is unidirectional as B cannot send packets to \$1 (although the \$1-B link is up). Similarly, \$2-\$1 is unidirectional as \$1 cannot send packets to \$2 (although the \$1-\$2 link is up).



### Figure 188 ZULD Overview

### 39.1.1 What You Can Do

- Use the ZUID Status screen (Section 39.2 on page 267) to see details on ZULD.
- Use the ZULD Setup screen (Section 39.3 on page 268) to enable ZULD on a port, configure a mode and set the probe time.

### 39.1.2 What You Need to Know

- ZULD must be enabled on the Switch and the ports in order to detect unidirectional links by monitoring OAMPDUs.
- Ports advertise their unidirectional link detection capability using OAMPDUs, so all connected devices must support OAM as well as ZUID. You need to enable OAM on the Switch by going to PORT > OAM > OAM Setup and enable the switch in the Active field. OAM must be enabled on other connected

devices too. If OAM is not enabled initially, **ZULD** will not work.

- If OAM is enabled initially and later disabled on one end of a link, the link will be unidirectional as that end cannot send OAMPDUs.
- OAM discovery, the sending of OAMPDUs to other ports, is initiated by an active port.
- When **ZUID** detects a unidirectional link, it sends a syslog and SNMP trap and may shut down the affected port (**Aggressive Mode**).
- If a port on the Switch is shut down by ZULD, and you want to recover it, then do one of the following:
  - Go to PORT > Port Setup. Clear Active and click Apply. Then select Active and click Apply again.
  - Go to SEC URITY > End is a ble > End is a ble Recovery and set the interval for ZULD. After the interval expires, the closed ports will become active and start receiving packets again.
  - Use the command port no inactive.
- Refer to the ZULD logs to see when a unidirectional link is detected and when it is recovered to a bidirectional link.

## **39.2 ZULD Status**

Use this screen to see details of unidirectional and bidirectional links discovered by **ZULD**. To open this screen, click **PORT** > **ZULD** > **ZULD** Status.

ZULD Sh	atus 2010	Setup							
ZULDI	ZULD is discribed								
Port	Active	Node	Frobe Inne	Hole Storie	Remote Operation	Remote MAC Adds	Female Ful		
1	( ar )	Normal							
2		Normal							
π.	044	Normal							
4	044	Normal							
5	01	Number							
۰.	( 01 )	Plannal							
	- <i>30</i>	Normal	$\sim$	$\sim$			$\sim$		
					$\sim$				

Figure 189 PORT > ZULD > ZULD Status

The following table describes the fields in the above screen.

IABEL	DESC RIPIIO N
ZULD is	This shows whether <b>ZULD</b> is enabled or disabled on the Switch.
Port	This field displays the port number.
Active	This field displays whether ZULD is enabled on the port or not. ZULD must be enabled to detect an unidirectional link by monitoring OAMPDUs.

Table 130 PORT > ZULD > ZULD Status

LABEL	DESC RIPIIO N
Mode	This field indicates what <b>ZUID</b> will do when a unidirectional link is detected. In <b>Nomal</b> mode, <b>ZUID</b> only sends a syslog and trap when it detects a unidirectional link. In <b>Aggressive</b> mode, <b>ZUID</b> shuts down the port (puts it into an <b>ErDisable</b> state) as well as sends a syslog and trap when it detects a unidirectional link.
Probe Time	Probe time is the length of time that <b>ZULD</b> waits before declaring that a link is unidirectional. When the probe time expires, and one port (either on the Switch or the connected device) still has not received an OAMPDU, then <b>ZULD</b> declares that the link is unidirectional.
Link State	This field shows the following link states:
	• <b>Linkdown</b> : This is an initialization state, where the port is not yet up.
	• <b>Probe</b> : This indicates that <b>ZULD</b> is discovering the connected device on this link.
	<ul> <li>Bid ire c tional: Traffic sent by the Switch is received by the connected device on this link, and traffic from the connected device on this link is received by the Switch.</li> </ul>
	<ul> <li>Unidire c tional: The state of the link between the port and its connected port cannot be determined either because no ZULD message was received, or one port is not capable of sending traffic.</li> </ul>
	• <b>Shutdown</b> : The port has been shut down because its link with the connected device is unidirectional and <b>ZUID</b> is in <b>Aggressive</b> mode.
Remote Operation	This field displays whether ZULD is enabled or disabled on the connected device on this link. ZULD must be enabled on the connected device and on the port that is connecting to the Switch.
Remote MAC Addr	This is the MAC address of the port on the connected device to which the port of the Switch is connected.
Remote Port	This is the port number of the port on the connected device to which the port of the Switch is connected.

Table 130 PORT > ZULD > ZULD Status (continued)

## 39.3 ZUID Setup

Use this screen to enable ZULD on a port, configure a mode and set the probe time. To open this screen, click **PORT** > **ZULD** >

ILD Status ZULC	Setup		
(He ) () :	Ð		
Port	Active	Mode	Probe Time
1		Normal M	C
1	E.	Normal M	5
	<u>E1</u>		
3	E	Namu Y	3
S0		Hermal M	5
s.ŧ	0	Manual 👻	5
¢	17	Hermal 🗠	15
		Number V	

Figure 190 PORT > ZULD > ZULD Setup

The following table describes the fields in the above screen.

Table 131 PORT > ZULD > ZULD Setup

LABEL	DESC RIPIIO N
Active	Enable the switch button to enable <b>ZULD</b> on the Switch.
Port	This field displays the port number.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
Active	Select this to enable <b>ZUID</b> on the port. ZULD must be enabled to detect an unidirectional link by monitoring OAMPDUs.
Mode	Select <b>Nomal</b> or <b>Aggressive</b> . In <b>Nomal</b> mode, ZULD only sends a syslog and trap when it detects a unidirectional link. In <b>Aggressive</b> mode, ZULD shuts down the port (puts it into an <b>ErrDisable</b> state) as well as sends a syslog and trap when it detects a unidirectional link.
Probe Time	Type the length of time that <b>ZULD</b> waits before declaring that a link is unidirectional. When the probe time expires, and one port (either on the Switch or the connected device) still has not received an OAMPDU, then <b>ZULD</b> declares that the link is unidirectional.
	The allowed time range is from 5 – 65535 seconds.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click this to reset the values in this screen to their last-saved values.

# C HAPTER 40 SWIICHING

The following chapters introduces the configurations of the links under the SWTICHING navigation panel.

Quick links to chapters:

- Layer 2 Protocol Tunneling
- Loop Guard
- MAC Pinning
- Mirroring
- Multicast
- Static Multicast Forwarding
- PPPoE
- Differentiated Services
- Queuing Method
- Priority Queue
- Bandwidth Control
- sFlow
- Spanning Tree Protocol
- Static MAC Filtering
- Static MAC Forwarding
- VLAN
- VLAN Isolation
- VLAN Mapping
- VLAN Stacking

# C HAPTER 41 Layer 2 Protocol Tunne ling

# 41.1 Layer 2 Protocol Tunneling Overview

This chapter shows you how to configure layer 2 protocol tunneling on the Switch.

## 41.1.1 What You Can Do

Use the **Layer 2 Protocol Tunneling** screen (Section 41.2 on page 272) to enable layer 2 protocol tunneling on the Switch and specify a MAC address with which the Switch uses to encapsulate the layer 2 protocol packets by replacing the destination MAC address in the packets.

### 41.1.2 What You Need to Know

Layer 2 protocol tunneling (L2PT) is used on the service provider's edge devices.

L2PT allows edge switches (1 and 2 in the following figure) to tunnel layer 2 STP (Spanning Tree Protocol), CDP (Cisco Discovery Protocol) and VTP (VLAN Trunking Protocol) packets between customer switches (A, B and C in the following figure) connected through the service provider's network. The edge switch encapsulates layer 2 protocol packets with a specific MAC address before sending them across the service provider's network to other edge switches.





Figure 191 Layer 2 Protocol Tunneling Network Scenario

In the following example, if you enable L2PT for STP, you can have switches A, B, C and D in the same

spanning tree, even though switch **A** is not directly connected to switches **B**, **C** and **D**. Topology change information can be propagated throughout the service provider's network.

To emulate a point-to-point topology between two customer switches at different sites, such as **A** and **B**, you can enable protocol tunneling on edge switches **1** and **2** for PAgP (Port Aggregation Protocol), LACP or UDLD (Uni-Directional Link Detection).





### 41.1.2.1 Layer 2 Protocol Tunneling Mode

Each port can have two layer 2 protocol tunneling modes, Access and Tunnel.

- The Access port is an ingress port on the service provider's edge device (1 or 2 in Figure 192 on page 272) and connected to a customer switch (A or B). Incoming layer 2 protocol packets received on an access port are encapsulated and forwarded to the tunnel ports.
- The **Timel** port is an egress port at the edge of the service provider's network and connected to another service provider's switch. Incoming encapsulated layer 2 protocol packets received on a tunnel port are decapsulated and sent to an access port.

# 41.2 Configuring Layer 2 Protocol Tunneling

Click SWIICHING > Layer 2 Protocol Tunneling in the navigation panel to display the screen as shown.

ayer 2 Prois	acol Tunne	ling						
Active Doct notion M	AC Address		• 🙆 xx x x x x x x x x	30				
Port	COP	ЯР	VIE	LLDP	PLOP	Point to LACP	Point Doto	Mode
談	0		2 <b>0</b> 10	19 <b>1</b> 18	0	10 I	0	ACC23.1
142	12	10	TT-	10	0	-10	10	Access
12		Ū.		0	121	n	-	Access
12	10	0	(E)	10	10	-13	13	Accessiv
i.	- C1	Ω.	121	6211	-C1	13	101	Augusta v
1	CI CI	EI.		107	10	11	10	ALCOM: N
<u>a</u> .	10		-13	. 13	-111		C3	Access
1. A	jui -	11	11	<u></u>	<u>C1</u>			
					$\sim$			
	_		App	D D D D D D D D D D D D D D D D D D D	stark []]			

Figure 193	SWITCHING > Layer 2 Protocol Tunneling

LABEL	DESC RIPTIO N
Active	Enable the switch button to enable layer 2 protocol tunneling on the Switch.
Destination MAC Address	Specify a MAC address with which the Switch uses to encapsulate the layer 2 protocol packets by replacing the destination MAC address in the packets.
	Note: The MAC address can be either a unicast MAC address or multicast MAC address. If you use a unicast MAC address, make sure the MAC address does not exist in the address table of a switch on the service provider's network.
	Note: All the edge switches in the service provider's network should be set to use the same MAC address for encapsulation.
Port	This field displays the port number. * means all ports.
*	Use this row to make the setting the same for all ports. Use this row first and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
CDP	Select this option to have the Switch tunnel CDP (Cisco Discovery Protocol) packets so that other Cisco devices can be discovered through the service provider's network.
STP	Select this option to have the Switch tunnel STP (Spanning Tree Protocol) packets so that STP can run properly across the service provider's network and spanning trees can be set up based on bridge information from all (local and remote) networks.
VTP	Select this option to have the Switch tunnel VTP (VLAN Trunking Protocol) packets so that all customer switches can use consistent VLAN configuration through the service provider's network.

LABEL	DESC RIPIIO N
LLDP	Select this option to have the Switch tunnel LLDP (Link Layer Discovery Protocol) packets so that all network devices can advertise its identity and capabilities through the service provider's network.
Point to Point	The Switch supports PAgP (Port Aggregation Protocol), LACP (Link Aggregation Control Protocol) and UDLD (UniDirectional Link Detection) tunneling for a point-to-point topology.
	Both PAgP and UDLD are Cisco's proprietary data link layer protocols. PAgP is similar to LACP and used to set up a logical aggregation of Ethernet ports automatically. UDLD is to determine the link's physical status and detect a unidirectional link.
PAGP	Select this option to have the Switch send PAgP packets to a peer to automatically negotiate and build a logical port aggregation.
LACP	Select this option to have the Switch send LACP packets to a peer to dynamically create and manage trunk groups.
UDLD	Select this option to have the Switch send UDLD packets to a peer's port it connected to monitor the physical status of a link.
Mode	Select Access to have the Switch encapsulate the incoming layer 2 protocol packets and forward them to the tunnel ports. Select Access for ingress ports at the edge of the service provider's network.
	Note: You can enable L2PT services for STP, LACP, VTP, CDP, UDLD, PAgP, and LLDP on the access ports only.
	Select <b>Timmel</b> for egress ports at the edge of the service provider's network. The Switch decapsulates the encapsulated layer 2 protocol packets received on a tunnel port by changing the destination MAC address to the original one, and then forward them to an access port. If the services is not enabled on an access port, the protocol packets are dropped.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.


 Table 132
 SWITCHING > Layer 2 Protocol Tunneling (continued)

# CHAPTER 42 Loop Guard

# 42.1 Loop Guard Overview

This chapter shows you how to configure the Switch to guard against loops on the edge of your network.

Loop guard allows you to configure the Switch to shut down a port if it detects that packets sent out on that port loop back to the Switch. While you can use Spanning Tree Protocol (STP) to prevent loops in the core of your network. STP cannot prevent loops that occur on the edge of your network.



Refer to Section 42.1.2 on page 275 for more information.

## 42.1.1 What You Can Do

Use the **Loop Guard** screen (Section 42.2 on page 277) to enable loop guard on the Switch and in specific ports.


### 42.1.2 What You Need to Know

Loop guard is designed to handle loop problems on the edge of your network. This can occur when a port is connected to a Switch that is in a loop state. Loop state occurs as a result of human error. It happens when two ports on a switch are connected with the same cable. When a switch in loop state sends out broadcast messages the messages loop back to the switch and are re-broadcast again and again causing a broadcast storm.

If a switch (not in loop state) connects to a switch in loop state, then it will be affected by the switch in loop state in the following way:

- The switch (not in loop state) will receive broadcast messages sent out from the switch in loop state.
- The switch (not in loop state) will receive its own broadcast messages that it sends out as they loop back. It will then re-broadcast those messages again.


The following figure shows port  $\mathbf{N}$  on switch  $\mathbf{A}$  connected to switch  $\mathbf{B}$ . Switch  $\mathbf{B}$  has two ports,  $\mathbf{x}$  and  $\mathbf{y}$ , mistakenly connected to each other. It forms a loop. When broadcast or multicast packets leave port  $\mathbf{N}$  and reach switch  $\mathbf{B}$ , they are sent back to port  $\mathbf{N}$  on  $\mathbf{A}$  as they are rebroadcast from  $\mathbf{B}$ .



The loop guard feature checks to see if a loop guard enabled port is connected to a Switch in loop state. This is accomplished by periodically sending a probe packet and seeing if the packet returns on the same port. If this is the case, the Switch will shut down the port connected to the switch in loop state.

Loop guard can be enabled on both Ethernet ports. The following figure shows a loop guard enabled port **N** on switch **A** sending a probe packet **P** to switch **B**. Since switch **B** is in loop state, the probe packet **P** returns to port **N** on **A**. The Switch then shuts down port **N** to ensure that the rest of the network is not affected by the switch in loop state.






The Switch also shuts down port  $\mathbf{N}$  if the probe packet returns to switch  $\mathbf{A}$  on any other port. In other words loop guard also protects against standard network loops.

The following figure illustrates three switches forming a loop. A sample path of the loop guard probe packet is also shown. In this example, the probe packet is sent from port  $\mathbf{N}$  and returns on another port. As long as loop guard is enabled on port  $\mathbf{N}$ . The Switch will shut down port  $\mathbf{N}$  if it detects that the probe packet has returned to the Switch.





Note: After resolving the loop problem on your network you can re-activate the disabled port through the Web Configurator or through commands (See the CLI Reference Guide).

## 42.2 Loop Guard Setup

Click SWIICHING > Loop Guard in the navigation panel to display the screen as shown.

Note: The loop guard feature cannot be enabled on the ports that have Spanning Tree Protocol (RSTP, MRSTP or MSTP) enabled.

Figure 198 SWITCHING > Loop Guard

Loop Guard	
Active	<b>्र</b> वन
Port	Active
1	
2	
3	
4	
đ	
7	
	Apply Carrol

IABEL	DESC RIPTIO N
Active	Enable the switch button to activate loop guard function on the Switch.
	The Switch generates syslog, internal log messages as well as SNMP traps when it shuts down a port through the loop guard feature.
Port	This field displays the port number.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
Active	Select this check box to enable the loop guard feature on this port. The Switch sends broadcast and multicast probe packets from this port to check if the switch it is connected to is in loop state. If the switch that this port is connected is in loop state the Switch will shut down this port. Clear this check box to disable the loop guard feature.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

# C HAPTER 43 MAC Pinning


This chapter shows you how to configure MAC pinning on the Switch.

## 43.1 MAC Pinning Overview

When the Switch obtains a connected device's MAC address, it adds an entry in the MAC address forwarding table and uses the table to determine how to forward frames. In addition to the source MAC address of a received frame, the Switch also learns the VLAN to which the device belongs and the port on which the frame is received. If the Switch learns the same MAC address and same VLAN ID on another port, it updates the MAC address table immediately.

MAC pinning allows you to set a port or multiple ports to have priority over other ports in MAC address learning. That means when a MAC address (and VLAN ID) is learned on a MAC-pinning-enabled port, the MAC address will not be learned on any other port until the aging time for the dynamically learned MAC address in the table expires.

This helps enhance security. For example, when an attacker (A) sends packets to all connected clients by spoofing the source MAC address of a server (B) connected to one of the Switch's ports, on which MAC pinning is enabled, the responses from clients will still be forwarded to the server according to the Switch's MAC forwarding table.



## 43.2 MAC Pinning Configuration

Use this screen to enable MAC pinning on the Switch and on specific ports. Click **SWIIC HING** > **MAC Pinning** in the navigation panel to open the following screen.

MAC Pinning	
Active	() (H)
Port	Δcive
	D
t.	
2	
3	
4	
5	
6	0
7	
~	~ ~ ~
	Apply Concel

Figure 199 SWITCHING > MAC Pinning

Table 134	SWITCHING > MAC Pinning

IABEL	DESC RIPTIO N
Active	Enable the switch button to turn on the MAC pinning function on the Switch.
Port	This field displays the port number.
*	Settings in this row apply to all ports. Use this row only if you want to make some settings the same for all ports. Use this row first to set
	the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
Active	Select this check box to enable MAC pinning on this port. The port then has priority over other ports in MAC address learning.
	Clear this check box to disable MAC pinning.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

# C HAPTER 44 Mirroring

## 44.1 Minoring Overview

This chapter discusses port mirroring setup screens.


Port mirroring allows you to copy a traffic flow to a monitor port (the port you copy the traffic to) in order that you can examine the traffic from the monitor port without interference.

### 44.1.1 What You Need to Know

Read on for concepts on Mirroring that can help you configure the screens in this chapter.

The Switch supports both local port mirroring and remote port mirroring.

In local port mirroring, the mirroring ports (through which traffic you copy passes) and the monitor port are on the same device.



## 44.2 Local Port Mirroring

Click **SWIIC HING** > **Minoring** > **Minoring** in the navigation panel to display the **Minoring** screen. Use this screen to select a monitor port and specify the traffic flow to be copied to the monitor port.

280

н (	20 <del>1</del>	
okerPot		
Patt	Mercored	Devention
200 C		Liber A.
33	E.	ingers w
		In provide the
100		ingos e
S <b>1</b> .5		Incros M
.*	10	Fgps Y
5	1	Ingroa M
1000		

Figure 200 SWITCHING > Mirroring > Mirroring

Table 135 SWITCHING > Mirroring	>	Mirroring
---------------------------------	---	-----------

IABEL	DESC RIPTIO N
Active	Enable the switch button to activate port mirroring on the Switch. Disable the switch to disable the feature.
Monitor Port	The monitor port is the port you copy the traffic to in order to examine it in more detail without interfering with the traffic flow on the original ports. Enter the port number of the monitor port.
Port	This field displays the port number.
*	Settings in this row apply to all ports. Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis. Note: Changes in this row are copied to all the ports as soon as you make them.
Mirrored	Select this option to mirror the traffic on a port.
Direction	Specify the direction of the traffic to mirror by selecting from the drop-down list box. Choices are <b>Egress</b> (outgoing), <b>Ingress</b> (incoming) and <b>Both</b> .
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to reset the fields.

# C HAPTER 45 Multic a st

## 45.1 Multic a st Overvie w

This chapter shows you how to configure various multicast features.

Traditionally, IP packets are transmitted in one of either two ways – Unicast (one sender to one recipient) or Broadcast (one sender to everybody on the network). Multicast delivers IP packets to just a group of hosts on the network.

IGMP (Internet Group Management Protocol) is a network-layer protocol used to establish membership in a multicast group – it is not used to carry user data. Refer to RFC 1112, RFC 2236 and RFC 3376 for information on IGMP versions 1, 2 and 3 respectively.

The Multicast Listener Discovery (MLD) protocol (defined in RFC 2710) is derived from IPv4's Internet Group Management Protocol version 2 (IGMPv2). MLD uses ICMPv6 message types, rather than IGMP message types. MLDv1 is similar to IGMPv2 and MLDv2 is similar to IGMPv3. MLD allows an IPv6 switch or router to discover the presence of MLD listeners who wish to receive multicast packets and the IP addresses of multicast groups the hosts want to join on its network.

MLD snooping and MLD proxy are analogous to IGMP snooping and IGMP proxy in IPv4. MLD filtering controls which multicast groups a port can join.

## 45.1.1 What You Can Do - IPv4 Multicast

- Use the IPv4 Multic a st Status screen (Section 45.2 on page 286) to view IPv4 multicast group information.
- Use the IGMP Snooping screen (Section 45.3 on page 287) to enable IGMP snooping to forward group multicast traffic only to ports that are members of that group.
- Use the IGMP Snooping VIAN screen (Section 45.4 on page 290) to perform IGMP snooping on VLANs.
- Use the IGMP Filtering Profile (Section 45.5 on page 292) to specify a range of multicast groups that clients connected to the Switch are able to join.

### 45.1.2 What You Can Do - IPv6 Multicast

- Use the IPv6 Multic a st Status screen (Section 45.6 on page 294) to view IPv6 multicast group information.
- Use the **MID Snooping-proxy** screen (Section 45.7 on page 295) to enable the upstream port to report group changes to a connected multicast router and forward MLD messages to other upstream ports.
- Use the **MID Snooping-proxy VIAN** screen (Section 45.8 on page 295) to enable and configure MLD snooping-proxy settings on the VLANs you specified.

- Use the **MID Snooping-proxy Port Role Setting** screen (Section 45.9 on page 298) to assign MLD snooping-proxy port roles and configure Leave settings for each port.
- Use the **MID Snooping-proxy Filtering** screen (Section 45.10 on page 299) to enable and configure MLD snooping-proxy filtering.
- Use the **MID Snooping-proxy Filtering Profile** screen (Section 45.11 on page 301) to create/edit MLD snooping-proxy filtering profiles.

### 45.1.3 What You Can Do - MVR

• Use the **MVR** screens (Section 45.12 on page 303) to create multicast VLANs and select the receiver ports and a source port for each multicast VLAN.

### 45.1.4 What You Need to Know

Read on for concepts on Multicasting that can help you configure the screens in this chapter.

### IP Multic a st Addresses

In IPv4, a multicast address allows a device to send packets to a specific group of hosts (multicast group) in a different subnetwork. A multicast IP address represents a traffic receiving group, not individual receiving devices. IP addresses in the Class D range (224.0.0.0 to 239.255.255.255) are used for IP multicasting. Certain IP multicast numbers are reserved by IANA for special purposes (see the IANA website for more information).

In IPv6, multicast addresses provide the same functionality as IPv4 broadcast addresses. Broadcasting is not supported in IPv6. A multicast address allows a host to send packets to all hosts in a multicast group. Multicast scope allows you to determine the size of the multicast group. A multicast address has a predefined prefix of ff00::/8.

### IG MP Filte ring

With the IGMP filtering feature, you can control which IGMP groups a subscriber on a port can join. This allows you to control the distribution of multicast services (such as content information distribution) based on service plans and types of subscription.

You can set the Switch to filter the multicast group join reports on a per-port basis by configuring an IGMP filtering profile and associating the profile to a port.

### IG MP Snooping

A Switch can passively snoop on IGMP packets transferred between IP multicast routers or switches and IP multicast hosts to learn the IP multicast group membership. It checks IGMP packets passing through it, picks out the group registration information, and configures multicasting accordingly. IGMP snooping allows the Switch to learn multicast groups without you having to manually configure them.

The Switch forwards multicast traffic destined for multicast groups (that it has learned from IGMP snooping or that you have manually configured) to ports that are members of that group. IGMP snooping generates no additional network traffic, allowing you to significantly reduce multicast traffic passing through your Switch.

### IGMP Snooping and VIANs


The Switch can perform IGMP snooping on up to 16 VLANs. You can configure the Switch to automatically learn multicast group membership of any VLANs. The Switch then performs IGMP snooping on the first 16 VLANs that send IGMP packets. This is referred to as auto mode. Alternatively, you can specify the VLANs that IGMP snooping should be performed on. This is referred to as fixed mode. In fixed mode the Switch does not learn multicast group membership of any VLANs other than those explicitly added as an IGMP snooping VLAN.

### MID Snooping-proxy

MLD snooping-proxy is a Zyxel-proprietary feature. IPv6 MLD proxy allows only one upstream interface on a switch, while MLD snooping-proxy supports more than one upstream port on a switch. The upstream port in MLD snooping-proxy can report group changes to a connected multicast router and forward MLD messages to other upstream ports. This helps especially when you want to have a network that uses STP to provide backup links between switches and also performs MLD snooping and proxy functions. MLD snooping-proxy, like MLD proxy, can minimize MLD control messages and allow better network performance.

In MLD snooping-proxy, if one upstream port is learned through snooping, all other upstream ports on the same device will be added to the same group. If one upstream port requests to leave a group, all other upstream ports on the same device will also be removed from the group.

In the following MLD snooping-proxy example, all connected upstream ports (1 - 7) are treated as one interface. The connection between ports 8 and 9 is blocked by STP to break the loop. If there is one query from a router (**x**) or MLD Done or Report message from any upstream port, it will be broadcast to all connected upstream ports.



#### MID Messages

A multicast router or switch periodically sends general queries to MLD hosts to update the multicast forwarding table. When an MLD host wants to join a multicast group, it sends an MLD Report message for that address.

An MLD Done message is similar to an IGMP Leave message. When an MLD host wants to leave a multicast group, it can send a Done message to the router or switch. If the leave mode is not set to **Immediate**, the router or switch sends a group-specific query to the port on which the Done message is received to determine if other devices connected to this port should remain in the group.

### MVR Overvie w

Multicast VLAN Registration (MVR) is designed for applications (such as Media-on-Demand (MoD)) that use multicast traffic across an Ethernet ring-based service provider network.

MVR allows one single multicast VLAN to be shared among different subscriber VLANs on the network. While isolated in different subscriber VLANs, connected devices can subscribe to and unsubscribe from the multicast stream in the multicast VLAN. This improves bandwidth utilization with reduced multicast traffic in the subscriber VLANs and simplifies multicast group management.

MVR only responds to IGMP join and leave control messages from multicast groups that are configured under MVR. Join and leave reports from other multicast groups are managed by IGMP snooping.

The following figure shows a network example. The subscriber VLAN (1, 2 and 3) information is hidden from the streaming media server, **S**. In addition, the multicast VLAN information is only visible to the Switch and **S**.



Figure 201 MVR Network Example

### Types of MVR Ports

In MVR, a source port is a port on the Switch that can send and receive multicast traffic in a multicast VLAN while a receiver port can only receive multicast traffic. Once configured, the Switch maintains a forwarding table that matches the multicast stream to the associated multicast group.

### MVR Modes

You can set your Switch to operate in either dynamic or compatible mode.

In dynamic mode, the Switch sends IGMP leave and join reports to the other multicast devices (such as multicast routers or servers) in the multicast VLAN. This allows the multicast devices to update the multicast forwarding table to forward or not forward multicast traffic to the receiver ports.

In compatible mode, the Switch does not send any IGMP reports. In this case, you must manually configure the forwarding settings on the multicast devices in the multicast VLAN.

#### How MVR Works

The following figure shows a multicast television example where a subscriber device (such as a computer) in VLAN 1 receives multicast traffic from the streaming media server, **s**, through the Switch. Multiple subscriber devices can connect through a port configured as the receiver on the Switch.

When the subscriber selects a television channel, computer **A** sends an IGMP report to the Switch to join the appropriate multicast group. If the IGMP report matches one of the configured MVR multicast group addresses on the Switch, an entry is created in the forwarding table on the Switch. This maps the subscriber VLAN to the list of forwarding destinations for the specified multicast traffic.

When the subscriber changes the channel or turns off the computer, an IGMP leave message is sent to the Switch to leave the multicast group. The Switch sends a query to VLAN 1 on the receiver port (in this case, an uplink port on the Switch). If there is another subscriber device connected to this port in the same subscriber VLAN, the receiving port will still be on the list of forwarding destination for the multicast traffic. Otherwise, the Switch removes the receiver port from the forwarding table.



Figure 202 MVR Multicast Television Example

## 45.2 IPv4 Multic a st Sta tus

Click SWIIC HING > Multic ast > IPv4 Multic ast > IPv4 Multic ast Status to display the screen as shown. This screen shows the IPv4 multicast group information. See Section 45.1 on page 282 for more information on multicasting.

Figure 203	SWITCHING > Multicast > IPv4 Multicast > IPv4 Multicast S	tatus
Inguit 200		10105

If v4 Multicost Status	IGMP Snooping	IGMP Snooping VLAN	
Index	VID	Pat	Noticent Group
	I.	18	224.000201
2	I.	10	224300252
1	I	10	232.2xx,255.2x4)

The following table describes the labels in this screen.

Table 136	SWITCHING > Multicast >	IPVA Multicast	IPvA Multicast Status
		r if va indilicust /	IF V4 MUNICUST STUTUS

LABEL	DESC RIPIIO N
Index	This is the index number of the entry.
VID	This field displays the multicast VLAN ID.
Port	This field displays the port number that belongs to the multicast group.
Multicast Group	This field displays IP multicast group addresses.

# 45.3 IGMP Snooping

Click SWIIC HING > Multic ast > IPv4 Multic ast > IGMP Snooping to display the screen as shown. See Section 45.1 on page 282 for more information on multicasting.

Figure 204 SWITCHING > Multicast > IPv4 Multicast > IGMP Snooping

IPv4 Wutt	locist Stotus	IGMP Sho	oping IGMP	Snooping	VLAN 3	GWP Filtering	Profile		
ictic									
300.00			13						
Dietero 3	ender-		WI -	파					
630,004,0	197		123	197					
- 907 Dec./	(d)		260	(#12273	db.				
302.00.094	act e		De la vige	é.					
OUR HIS	A ALSO		100						
$\mathcal{O}(\mathcal{A})/\mathcal{O}(\mathcal{A})$	ride given at th	sant artsa	0.04						
Distance:	ka il cost frate	ò	O hear of	Clark .	0	2159 VO V.AM			
and see	Nutries have	e la Goria Pal	O Com	Oteres	ialių 🗇	oreganding Careta	765		
<b>Depended</b>	Nutrat See	6	O Francisco de	0.0%5					
Port	Immediate Leigre	Normal Leave	Foot Secree	Group United	Max Group Stamble	Throtting	IGME Film Fradia	TP :	IGVE Guerler Node
3	0	0	8 <u></u> 1			Dec. v	(Delay)	<u>.</u>	ALISTY
35	0	0 400	0 28	0	3	Deres	Detsort	~	Acres w.
- W	0	0 2/2	0 20	Ħ		<u>Bernin</u>	(Beloci	6	AUR V
	00	0.30	0.00	1.1	1	Det - V	(Defect)	+	Auto v
4	0	0 4.	0 72 1	- 11	+	Dec. v	<u> </u> Éstèch	-1	A.No. 9
- 36. -	-0-	0.800	1 285 1	101	2	De	(20)001	-	2010-9
	0	0 200	0.25		- 18 - L	Uc - v	$\{\psi_{ij}(\omega_{i})\}$		Ada v
	01	0 400	87. L	~	3 1	U. y	(C.full	-	2.17.4
				$\sim$		~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~~			ALIST
				ANDY	Caster-				

Table for entremite memoral in tritlemeast fermi encepting	Table 137	SWITCHING > Multicast > IPv4 Multicast > IGMP Snoopin	g
--	-----------	---	---

LABEL	DESC RIPIIO N				
Active	Enable the switch button to enable IGMP Snooping to forward group multicast traffic only to ports that are members of that group.				
Querier	Select this to allow the Switch to send IGMP General Query messages to the VLANs with the multicast hosts attached.				
Querier Version	IGMP snooping query works only when both host and Switch support the same IGMP version.				
	Select $\mathbf{v2}$ to allow the Switch to send IGMPv2 queries only.				
	Select $\mathbf{v3}$ to allow the Switch to send IGMPv3 queries only.				
Report Proxy	Select this to allow the Switch to act as the IGMP report proxy and leave proxy. It will report group changes to a connected multicast router.				
	The Switch not only checks IGMP packets between multicast routers or switches and multicast hosts to learn the multicast group membership, but also replaces the source MAC address in an IGMP v1/v2 report with its own MAC address before forwarding to the multicast router or switch. When the Switch receives more than one IGMP v1/v2 join report that requests to join the same multicast group, it only sends a new join report with its MAC address. This helps reduce the number of multicast join reports passed to the multicast router or switch.				
	The Switch sends a leave message with its MAC address to the multicast router or switch only when it receives the leave message from the last host in a multicast group.				
Host Timeout	Specify the time (from 1 to 16711450) in seconds that elapses before the Switch removes an IGMP group membership entry if it does not receive report messages from the port.				
802.1p Priority	Select a priority level $(0 - 7)$ to which the Switch changes the priority in outgoing IGMP control packets. Otherwise, select <b>No-Change</b> to not replace the priority.				
IGMP Filtering Active	Enable the switch button to enable IGMP filtering to control which IGMP groups a subscriber on a port can join.				
	If you enable IGMP filtering, you must create and assign IGMP filtering profiles for the ports that you want to allow to join multicast groups.				
IGMP Snooping Smart Forward Active	Enable the switch button to enable sending of multicast frame to querier port and IGMP subscriber groups. Otherwise, the querier port forwards the frames only when it receives a join report and it belongs to the IGMP group.				
Unknown Multicast	Specify the action to perform when the Switch receives an unknown multicast frame.				
Frame	<ul> <li>Select Flooding to send the frames to all ports.</li> <li>Select Drop to discard the frames.</li> <li>Select Drop on VLAN and enter the VLAN ID numbers to discard the frames on the specified VLANs. Use a dash to specify consecutive VLANs and a comma (no spaces) to specify non-consecutive VLANs. For example, 51–53 includes 51, 52 and 53, but 51,53 does not include 52.</li> </ul>				
Unknown Multicast	Specify the action to perform when Unknown Multicast Frame is set to Drop.				
Frame to Querier Port	<ul> <li>Select Drop to discard the frames.</li> <li>Select Forwarding to send the frames to all querier ports.</li> <li>Select Forwarding on VIAN and enter the VLAN ID numbers to send the frames to the ports which are used as an IGMP query port on the specified VLANs. Use a dash to specify consecutive VLANs and a comma (no spaces) to specify non-consecutive VLANs. For</li> </ul>				

LABEL	DESC RIPTIO N
Reserved Multicast Group	The IP address range of 224.0.0.0 to 224.0.0.255 are reserved for multicasting on the local network only. For example, 224.0.0.1 is for all hosts on a local network segment and 224.0.0.9 is used to send RIP routing information to all RIP v2 routers on the same network segment. A multicast router will not forward a packet with the destination IP address within this range to other networks. See the IANA web site for more information.
	The layer-2 multicast MAC addresses used by Cisco layer-2 protocols, 01:00:0C:CC:CC:CC and 01:00:0C:CC:CC:CD, are also included in this group.
	Specify the action to perform when the Switch receives a frame with a reserved multicast address.
	<ul> <li>Select Flooding to send the frames to all ports.</li> <li>Select Drop to discard the frames.</li> </ul>
Use this section to c	onfigure IGMP Snooping on each port.
Port	This field displays the port number.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Changes in this row are copied to all the ports as soon as you make them.
Immediate Leave	Select this to set the Switch to remove this port from the multicast tree when an IGMP version 2 leave message is received on this port.
	Select this option if there is only one host connected to this port.
Normal Leave	Enter an IGMP normal leave timeout value (from 200 to 6348800) in miliseconds. Select this option to have the Switch use this timeout to update the forwarding table for the port.
	In normal leave mode, when the Switch receives an IGMP leave message from a host on a port, it forwards the message to the multicast router. The multicast router then sends out an IGMP Group-Specific Query (GSQ) message to determine whether other hosts connected to the port should remain in the specific multicast group. The Switch forwards the query message to all hosts connected to the port and waits for IGMP reports from hosts to update the forwarding table.
	This defines how many seconds the Switch waits for an IGMP report before removing an IGMP snooping membership entry when an IGMP leave message is received on this port from a host.
Fast Leave	Enter an IGMP fast leave timeout value (from 200 to 6348800) in miliseconds. Select this option to have the Switch use this timeout to update the forwarding table for the port.
	In fast leave mode, right after receiving an IGMP leave message from a host on a port, the Switch itself sends out an IGMP Group-Specific Query (GSQ) message to determine whether other hosts connected to the port should remain in the specific multicast group. This helps speed up the leave process.
	This defines how many seconds the Switch waits for an IGMP report before removing an IGMP snooping membership entry when an IGMP leave message is received on this port from a host.
Group Limited	Select this option to limit the number of multicast groups this port is allowed to join.
Max Group Number	Enter the number of multicast groups this port is allowed to join. Once a port is registered in the specified number of multicast groups, any new IGMP join report frames is dropped on this port.

Table 137 SWITCHING > Multicast > IPv4 Multicast > IGMP Snooping (continued)

LABEL	DESC RIPTIO N
Throttling	IGMP throttling controls how the Switch deals with the IGMP reports when the maximum number of the IGMP groups a port can join is reached.
	Select <b>Deny</b> to drop any new IGMP join report received on this port until an existing multicast forwarding table entry is aged out.
	Select $\operatorname{Replace}$ to replace an existing entry in the multicast forwarding table with the new IGMP reports received on this port.
IGMP Filtering Profile	Select the name of the IGMP filtering profile to use for this port. Otherwise, select $De fault$ to prohibit the port from joining any multicast group.
	You can create IGMP filtering profiles in the SWIIC HING > Multic ast > IPv4 Multic ast > IGMP Filtering Profile screen.
IGMP Querier Mode	The Switch treats an IGMP query port as being connected to an IGMP multicast router (or server). The Switch forwards IGMP join or leave packets to an IGMP query port.
	Select ${\bf Auto}$ to have the Switch use the port as an IGMP query port if the port receives IGMP query packets.
	Select $\mathbf{Fixed}$ to have the Switch always use the port as an IGMP query port. Select this when you connect an IGMP multicast server to the port.
	Select <b>Edge</b> to stop the Switch from using the port as an IGMP query port. The Switch will not keep any record of an IGMP router being connected to this port. The Switch does not forward IGMP join or leave packets to this port.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 137	SWITCHING > Multicast >	<ul> <li>IPv4 Multicast &gt; IGM</li> </ul>	P Snooping (continued)
-----------	-------------------------	---	------------------------

# 45.4 IGMP Snooping VIAN

Click SWIIC HING > Multic ast > IPv4 Multic ast > IGMP Snooping VIAN to display the screen as shown. See IGMP Snooping and VLANs on page 284 for more information on IGMP Snooping VLAN.

Note: You can perform IGMP snooping on up to 16 VLANs.

Figure 205 SWITCHING > Multicast > IPv4 Multicast > IGMP Snooping VLAN

1Pv4 Mullic	asl Status	IGMP Snooping	IGMP Shooping VLAN	IGMT Filler	ing trofile
IGMP Snor	oping VLAN				
Made	<b>Q</b> 3.60	() thus	only Course		
VLAN		0.00			
				O Assoluti	The section of the se
0	locker.	Neros	VIU		
		Wi-tain	10		

XGS2220 Series User's Guide

Table 138 SWITCHING > Multicast > IPv4 Multicast > IGMP Snooping VLAN

LABEL	DESC RIPIIO N
IGMP Snooping	J VLAN
Mode	Select <b>auto</b> to have the Switch learn multicast group membership information of any VLANs automatically.
	Select <b>fixed</b> to have the Switch only learn multicast group membership information of the VLANs that you specify below.
	In either <b>auto</b> or <b>fixed</b> mode, the Switch can learn up to 16 VLANs (including up to five VLANs you configured in the <b>MVR</b> screen). For example, if you have configured one multicast VLAN in the <b>SWIICHING</b> > <b>Multicast</b> > <b>MVR</b> screen, you can only specify up to 15 VLANs in this screen.
	The Switch drops any IGMP control messages which do not belong to these 16 VLANs.
	You must also enable IGMP snooping in the <b>SWTIC HING</b> > <b>Multic a st</b> > <b>IPv4 Multic a st</b> > <b>IGMP</b> <b>Snooping</b> screen first.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click <b>Cancel</b> to begin configuring this screen afresh.
VLAN	
Use this section	of the screen to add VLANs on which the Switch is to perform IGMP snooping.
Index	This is the index number of the IGMP snooping VLAN entry in the table.
Name	This field displays the descriptive name for this VLAN group.
VID	This field displays the ID number of the VLAN group.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to create a new entry or edit a selected one.
Delete	Click <b>De le te</b> to remove the selected entries.

#### 45.4.1 Add/Edit IGMP Snooping VIANs

This screen allows you to add an IGMP snooping VLAN or edit an existing one.

To access this screen, click the Add/Edit button or select an entry from the list and click the Add/Edit button.

Figure 206 SWITCHING > Multicast > IPv4 Multicast > IGMP Snooping VLAN > Add/Edit

Namo		
VD		
Apply	Gloca	Gancel

IABEL	DESC RIPTIO N
Name	Enter the descriptive name of the VLAN for identification purposes. You can enter up to 32 printable ASCII characters except [?], [   ], [ ' ], [ " ] or [ , ].
VID	Enter the ID of a static VLAN; the valid range is between 1 and 4094. Note: You cannot configure the same VLAN ID as in the <b>SWIIC HING</b> > <b>Multic a st</b> > <b>MVR</b> screen.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

Table 139 SWITCHING > Multicast > IPv4 Multicast > IGMP Snooping VLAN > Add/Edit

## 45.5 IG MP Filtering Profile

An IGMP filtering profile specifies a range of multicast groups that clients connected to the Switch are able to join. A profile contains a range of multicast IP addresses which you want clients to be able to join. Profiles are assigned to ports (in the SWITC HING > Multicast > IPv4 Multicast > IGMP Snooping screen). Clients connected to those ports are then able to join the multicast groups specified in the profile. Each port can be assigned a single profile. A profile can be assigned to multiple ports.

Click SWIIC HING > Multic a st > IPv4 Multic a st > IGMP Filte ring Profile link to display the screen as shown.

Figure 207 SWITCHING > Multicast > IPv4 Multicast > IGMP Filtering Profile

'v4 Molfica	st Status	IGMP Sneoping	IGMP Snooping VLAN	IGMP Filte	ring Profile
			O Acio Profila	O Arto Bulk	Criteri
U	Frofile (	lame	Stort Address	End	Address
	Option 2	x1			
			0.0.0		0.0 <mark>0</mark>
(1)	000	<b>0</b> <sup>1</sup>			(1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.
17			22/ 0.00	22	1000
<u></u>			\$28,0000	170	228.00

The following table describes the labels in this screen.

Table 140	SWITCHING >	Multicast >	IPv4 Multicast >	> IGMF	Profile
		111011100001		10111	i monnig i romo

IABEL	DESC RIPTIO N
Profile Name	This field displays the descriptive name of the profile.
Start Address	This field displays the start of the multicast address range.
End Address	This field displays the end of the multicast address range.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add Profile	Click this to add a new IGMP filtering profile.

XGS2220 Series User's Guide

<sup>292</sup> 

IABEL	DESC RIPTIO N
Add Rule	Click Add Rule to add a new rule and specify the profile it belongs to in the Add Rule screen.
	You can also select a profile entry and click <b>Add Rule</b> to add an additional rule for the selected profile.
Delete	Select a profile and click $\mathbf{De}  \mathbf{le}  \mathbf{te}$ to remove the selected profile and the accompanying rules.
	Select a rule from a profile and click $\mathbf{De}  \mathbf{le}  \mathbf{te}$ to remove the selected rule.

Table 140 SWITCHING > Multicast > IPv4 Multicast > IGMP Filtering Profile (continued)

## 45.5.1 Add IGMP Filtering Profile

To access this screen, click the Add Profile button in the SWIIC HING > Multic ast > IPv4 Multic ast > IGMP Filtering Profile screen.

Figure 208 SWITCHING > Multicast > IPv4 Multicast > IGMP Filtering Profile > Add Profile

Short Address	924.030	0
and Address	224.0.0.	0
Add/FdB	Clear	Concel

The following table describes the labels in this screen.

IABEL	DESC RIPIIO N
Profile Name	Enter a descriptive name for the profile for identification purposes. You can enter up to 32 printable ASCII characters except [?], [   ], [ ' ], [ "] or [, ].
Start Address	Type the starting multicast IP address for a range of multicast IP addresses that you want to belong to the IGMP filter profile.
End Address	Type the ending multicast IP address for a range of IP addresses that you want to belong to the IGMP filter profile. If you want to add a single multicast IP address, enter it in both the <b>Start Address</b> and <b>End Address</b> fields.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

## 45.5.2 Add IGMP Filtering Rule

Click Add Rule in the SWIIC HING > Multic ast > IPv4 Multic ast > IGMP Filtering Profile screen to access this screen.

Figure 209 SWITCHING > Multicast > IPv4 Multicast > IGMP Filtering Profile > Add Rule

Profile Nome	no <mark>le</mark> t	~
Short Address	224.0.00	)
Ind Address	994-0403	1
Add/Edit	Olour	Cencel

The following table describes the labels in this screen.

Table 142	SWITCHING >	Multicast > I	Pv4 Multicast >	IGMP Filtering Profi	e > Add Rule
		111011100051			

IABEL	DESC RIPTIO N
Profile Name	Select a profile from the drop-down list to add a additional rule for the existing profile.
Start Address	Type the starting multicast IP address for a range of multicast IP addresses that you want to belong to the IGMP filter profile.
End Address	Type the ending multicast IP address for a range of IP addresses that you want to belong to the IGMP filter profile. If you want to add a single multicast IP address, enter it in both the <b>Start Address</b> and <b>End Address</b> fields.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

## 45.6 IPv6 Multic a st Sta tus

Click SWIIC HING > Multic ast > IPv6 Multic ast > IPv6 Multic ast Status to display the screen as shown. This screen shows the IPv6 multicast group information. See Section 45.1 on page 282 for more information on multicasting.

Figure 210 SWITCHING > Multicast > IPv6 Multicast > IPv6 Multicast Status

If vé Multicast 9	latus	MLD Snooping proxy	VLAN	Fort Role Setting	g Filtering
Index	VID	Port	Nuticasi	Group	Group Rinout
1	1	<b>39</b>	H02-000	10003	595

The following table describes the fields in the above screen.

Table 143	SWITCHING >	> Multicast >	IPv6 Multicast >	> IPv6 Multicast Status
-----------	-------------	---------------	------------------	-------------------------

LABEL	DESC RIPIIO N
Index	This is the index number of the entry.
VID	This field displays the multicast VLAN ID.
Port	This field displays the port number that belongs to the multicast group.

XGS2220 Series User's Guide

Tailala 142		A Audition and A	ID. ( ) A ultiments	ID. ( ) A luit a grat Startura	(a a lation , a al)
10010143	20011CHING >	MUIIICASI >	· IPV6 MUIIICASI >	· IPv6 Multicast Status	(coninuea)

IABEL	DESC RIPHO N
Multicast Group	This field displays IP multicast group addresses.
Group Timeout	This field displays the time (in seconds) that elapses before the Switch removes a MLD group membership entry if it does not receive report messages from the port.

## 45.7 MLD Snooping-proxy

Click SWIIC HING > Multic ast > IPv6 Multic ast > MID Snooping-proxy to display the screen as shown. See Section 45.1 on page 282 for more information on multicasting.

Figure 211 SWITCHING > Multicast > IPv6 Multicast > MLD Snooping-proxy

IPv& Multicost Status	MLD Shooping-proxy VLAN
MID Scorping provi	Active (* 2001) 2021: Frank (* 2004)
	Apply Cancel

The following table describes the fields in the above screen.

Table 144 SWITCHING > Multicast > IPv6 Multicast > MLD Snooping-prox	Table 144	SWITCHING >	> Multicast >	IPv6 Multicast >	MLD Snooping-proxy
--	-----------	-------------	---------------	------------------	--------------------

IABEL	DESC RIPTIO N					
MLD Snooping-proxy	MLD Snooping-proxy					
Use these settings to con	Use these settings to configure MLD snooping-proxy.					
Active	Enable the switch button to enable MLD snooping-proxy on the Switch to minimize MLD control messages and allow better network performance.					
802.1p Priority	Select a priority level (0 – 7) to which the Switch changes the priority in outgoing MLD messages.					
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.					
Cancel	Click <b>Cancel</b> to begin configuring this screen afresh.					

## 45.8 MID Snooping-proxy VIAN

Click SWIIC HING > Multic ast > IPv6 Multic ast > VIAN screen to display the screen as shown. See Section 45.1 on page 282 for more information on multicasting.

0				1 0	. ,
Irvs Mullico	rst Skalus	MLD Snooping-proxy	VLAN	rod Role Selling	Fillering
MID Snoop	ing-proxy	VIAN			
				O Adm/Edit	Tridletk
J.T.	Index	W0			
0	1	14			
10	2	105			

Figure 212 SWITCHING > Multicast > IPv6 Multicast > VLAN: MLD Snooping-proxy VLAN

The following table describes the fields in the above screen.

Table 145 SWITCHING > Multicast > IPv6 Multicast > VLAN: MLD Snooping-proxy VLAN

LABEL	DESC RIPHO N			
MLD Snooping-proxy VL	AN			
Index	This is the index number of the MLD snooping-proxy VLAN entry in the table.			
VID	This field displays the ID number of the VLAN group.			
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.			
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.			
Delete	Click <b>Delete</b> to remove the selected entry.			

### 45.8.1 Add/Edit MLD Snooping-proxy VIAN

The screen allows you to enable and configure MLD Snooping-proxy settings on a VLAN you specified.

Click Add/Edit in the SWIICHING > Multic ast > IPv6 Multic ast > VIAN screen to display this screen.

Figure 213 SWITCHING > Multicast > IPv6 Multicast > VLAN > Add/Edit

via		
Upshoum		
Oues intead	121000	milkessenes
Matamorn Response Deley	10000)	millecones
Dy austrines Variaty a	4	
ligd Member Weery Interval	1000	milles serves
Downsheam		
Guery Interval	125000	milleconvex
Maximum Rospanse Roldv	0000	miliseivenies
	Apply Class	Conned.

The following table describes the fields in the above screen.

Table 146	SWITCHING > Multi	cast > IPv6 Multicast	> VLAN > Add/Edit
101010 110			

LABEL	DESC RIPTIO N				
VID	Enter the ID number of the VLAN on which you want to enable MLD snooping-proxy and configure related settings.				
Upstream					
Query Interval	Enter the amount of time (in miliseconds) between general query messages sent by the router connected to the upstream port. This value should be exactly the same as what is configured in the connected multicast router.				
	This value is used to calculate the amount of time an MLD snooping membership entry (learned only on the upstream port) can remain in the forwarding table.				
	When an MLD Report message is received, the Switch sets the timeout period of the entry to be $T = (QI*RV) + MRD$ , where $T = T$ imeout, $QI = Query$ Interval, $RV = R$ obustness Variable and MRD = Maximum Response Delay.				
Maximum Response Delay	Enter the amount of time (in miliseconds) the router connected to the upstream port waits for a response to an MLD general query message. This value should be exactly the same as what is configured in the connected multicast router.				
	This value is used to calculate the amount of time an MLD snooping membership entry (learned only on the upstream port) can remain in the forwarding table.				
	When an MLD Report message is received, the Switch sets the timeout period of the entry to be $T = (Q*RV) + MRD$ , where $T = T$ imeout, $QI = Query$ Interval, $RV = R$ obustness Variable and MRD = Maximum Response Delay.				
	When an MLD Done message is received, the Switch sets the entry's lifetime to be the product of <b>Iast Member Query Interval</b> and <b>Robustness Variable</b> .				
Robustness Variable	Enter the number of queries. A multicast address entry (learned only on an upstream por by snooping) is removed from the forwarding table when there is no response to the configured number of queries sent by the router connected to the upstream port. This value should be exactly the same as what's configured in the connected multicast router.				
	This value is used to calculate the amount of time an MLD snooping membership entry (learned only on the upstream port) can remain in the forwarding table.				
Last Member Query Interval	Enter the amount of time (in miliseconds) between the MLD group-specific queries sent by an upstream port when an MLD Done message is received. This value should be exactly the same as what's configured in the connected multicast router.				
	This value is used to calculate the amount of time an MLD snooping membership entry (learned only on the upstream port) can remain in the forwarding table after a Done message is received.				
	When an MLD Done message is received, the Switch sets the entry's lifetime to be the product of <b>Last Member Query Interval</b> and <b>Robustness Variable</b> .				
Downstream	· · · · · · · · · · · · · · · · · · ·				
Query Interval	Enter the amount of time (in miliseconds) between general query messages sent by the downstream port.				
Maximum Response Delay	Enter the maximum time (in miliseconds) that the Switch waits for a response to a general query message sent by the downstream port.				
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.				
Clear	Click <b>Clear</b> to clear the fields to the factory defaults.				
Cancel	Click Cancel to not save the configuration you make and return to the last screen.				

## 45.9 MLD Snooping-proxy Port Role Setting

Click SWIIC HING > Multic ast > IPv6 Multic ast > Port Role Setting to display the screen as shown. See Section 45.1 on page 282 for more information on multicasting.

Figure 214 SWITCHING > Multicast > IPv6 Multicast > Port Role Setting

	ping proxy Port Ro Persponsive Abrid	4 4		
Fort	FotFole	Leove Mode	Leove Timeour	Fost Leave Timeout
1	Hora y	transcipte w		
Ť	Nora 🗸	anneda e ×	0	28
2	Liona v	minerate w	6.00	500
3	Nore v	miacius v	100	300
80	Horn S	transforme w	+00	110
3	Nor 2	nimechie v	1228	- 200
4	[Nona v	mineritie e	15.070	311
÷.	Nore v	m nectore v	ene no	$\sim$

The following table describes the fields in the above screen.

Table 147 SWITCHING > Multicast > IPv6 Multicast > Port Role Setting

LABEL	DESC RIPIIO N
MLD Snooping-proxy Pc	rt Role Setting
MLD Snooping-proxy VLAN ID	Select the VLAN ID for which you want to configure a port's MLD snooping-proxy settings.
Port	This field displays the port number.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Changes in this row are copied to all the ports as soon as you make them.
Port Role	A port on the Switch can be either a <b>Downstre am</b> port or <b>Upstre am</b> port in MLD. A downstream port connects to MLD hosts and acts as a multicast router to send MLD queries and listen to the MLD host's Report and Done messages. An upstream port connects to a multicast router and works as a host to send Report or Done messages when receiving queries from a multicast router.
	Otherwise, select $None$ if the port is not joining a multicast group or does not belong to this VLAN.

LABEL	DESC RIPTIO N
Leave Mode	This is configurable only when you select <b>Downstream</b> in the previous <b>Port Role</b> field.
	Select the leave mode for the specified downstream ports in this VLAN.
	This specifies whether the Switch removes an MLD snooping membership entry (learned on a downstream port) immediately ( <b>Immediate</b> ) or wait for an MLD report before the leave timeout ( <b>Nomal</b> ) or fast leave timeout ( <b>Fast</b> ) when an MLD leave message is received on this port from a host.
Leave Timeout	Enter the MLD snooping normal leave timeout (in milliseconds) the Switch uses to update the forwarding table for the specified downstream ports.
	This defines how many seconds the Switch waits for an MLD report before removing an MLD snooping membership entry (learned on a downstream port) when an MLD Done message is received on this port from a host.
Fast Leave Timeout	Enter the fast leave timeout (in milliseconds) for the specified downstream ports.
	This defines how many seconds the Switch waits for an MLD report before removing an MLD snooping membership entry (learned on a downstream port) when an MLD Done message is received on this port from a host.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to reset the fields to your previous configuration.

Table 147 SWITCHING > Multicast > IPv6 Multicast > Port Role Setting (continued)

## 45.10 MLD Snooping-proxy Filtering

Use this screen to configure the Switch's MLD filtering settings. Click the SWITC HING > Multic a st > IPv6 Multic a st > Filtering screen to display the screen as shown.

Pva Muttice	ist Status MLC	i Sacaping-proxy VI	AN Port Role Setting	Filtering
MLD Snoop	ing-proxy <mark>F</mark> ilterin	a		
Aut-u				
Pod	Group Limit	Max Group Number	MLD Shooping-proxy Filte	rhig Profile
- 16			Detcul	
- 33	5	1	[0=6ail	$[\omega]$
2		· · · · ·	Detaul	e e
3	19	i	Default	v
i i	2	1	Detout	•
58	8	1	Default	•
	53	3	Detcut	×
*		1	- beel	
		$\sim$		

Figure 215 SWITCHING > Multicast > IPv6 Multicast > Filtering

The following table describes the fields in the above screen.

IABEL	DESC RIPTIO N			
MLD Snooping-proxy F	iltering			
Active	Enable the switch button to enable MLD filtering on the Switch.			
Port	This field displays the port number.			
*	Settings in this row apply to all ports.			
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.			
	Changes in this row are copied to all the ports as soon as you make them.			
Group Limit	Select this option to limit the number of multicast groups this port is allowed to join.			
Max Group Number	Enter the number of multicast groups this port is allowed to join. Once a port is registered in the specified number of multicast groups, any new MLD Report message is dropped on this port.			
MLD Snooping-proxy Filtering Profile	Select the name of the MLD filtering profile to use for this port. Otherwise, select <b>De fa ult</b> to prohibit the port from joining any multicast group.			
	You can create MLD filtering profiles in the SWTIC HING > Multic ast > IPv6 Multic ast > Filtering Profile screen.			
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.			
Cancel	Click Cancel to reset the fields to your previous configuration.			

Table 148	SWITCHING >	Multicast >	IPv6 Multicast	> Filtering
-----------	-------------	-------------	----------------	-------------

# 45.11 MLD Snooping-proxy Filtering Profile

Use this screen to view and create MLD filtering profiles.

Click SWIICHING > Multic ast > IPv6 Multic ast > Filtering Profile to display the screen as shown.

Figure 216 SWITCHING > Multicast > IPv6 Multicast > Filtering Profil	le
--	----

Py& Mullicest Slah	the second se		ort hale setting	Fillering	Filtering Profile
MLD Snooping-pn	oxy Filtering Profile				
			O Actalinofile	O Add Role	1 Denie
0	Profile Name	Starl Address			Address
	Detpull				
		00000000		0000	00000
	promet				
- O		HODE: I		1	1::00
0		1012-12		3	02:5

The following table describes the fields in the above screen.

IABEL	DESC RIPTIO N
MLD Snooping-pro	xy Filtering Profile
Profile Name	This field displays the descriptive name of the profile.
Start Address	This field displays the start of the multicast IPv6 address range.
End Address	This field displays the end of the multicast IPv6 address range.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add Profile	Click this to add a new MLD Snooping-proxy filtering profile.
Add Rule	Click Add Rule to add a new rule and specify the profile it belongs to in the Add Rule screen.
	You can also select a profile entry and click <b>Add Rule</b> to add an additional rule for the selected profile.
Delete	Select a profile and click $\mathbf{De}  \mathbf{le}  \mathbf{te}$ to remove the selected profile and the accompanying rules.
	Select a rule from a profile and click <b>Delete</b> to remove the selected rule.

Table 149 SWITCHING > Multicast > IPv6 Multicast > Filtering Profile

## 45.11.1 Add MLD Snooping-proxy Filtering Profile

Use this screen to create an MLD filtering profile and set the range of the multicast addresses.

Click Add Profile in the SWIICHING > Multic ast > IPv6 Multic ast > Filtering Profile to display the screen as shown.

Figure 217 SWITCHING > Multicast > IPv6 Multicast > Filtering Profile > Add Profile

Profile Name			
Stort Address			
Ind Address			
	Apply	Gleen	Geneel

The following table describes the fields in the above screen.

Table 150	SWITCHING >	Multicast >	· IPv6 Multicast >	> Filtering Profile > Add Profile
-----------	-------------	-------------	--------------------	-----------------------------------

LABEL	DESC RIPTIO N
Profile Name	Enter a descriptive name (up to 32 printable ASCII characters except [?], [1], ['], ["], [,]) for the profile for identification purposes.
	To configure additional rules for a profile that you have already added, enter the profile name and specify a different IP multicast address range.
Start Address	Type the starting multicast IPv6 address for a range of multicast IPv6 addresses that you want to belong to the MLD filtering profile.
End Address	Type the ending multicast IPv6 address for a range of IPv6 addresses that you want to belong to the MLD filtering profile.
	If you want to add a single multicast IPv6 address, enter it in both the <b>Start Address</b> and <b>End Address</b> fields.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

#### 45.11.2 Add MID Snooping-proxy Filtering Rule

Use this screen to create a multicast addresses range rule of the MLD filtering profile.

Click Add Rule in the SWIICHING > Multic ast > IPv6 Multic ast > Filtering Profile to display this screen.

Figure 218 SWITCHING > Multicast > IPv6 Multicast > Filtering Profile > Add Rule

noble Nome	E.	8	1
Start Avaid das	14		
NY ARTING	Ċ.		
		-	

The following table describes the fields in the above screen.

Table 151	SWITCHING >	Multicast > IPv6	Multicast >	> Filtering Profile > Add Rule	
-----------	-------------	------------------	-------------	--------------------------------	--

IABEL	DESC RIPTIO N
Profile Name	Select a profile from the drop-down list to add a additional rule for the existing profile.
Start Address	Type the starting multicast IPv6 address for a range of multicast IPv6 addresses that you want to belong to the MLD filtering profile.
End Address	Type the ending multicast IPv6 address for a range of IPv6 addresses that you want to belong to the MLD filtering profile.
	If you want to add a single multicast IPv6 address, enter it in both the <b>Start Address</b> and <b>End Address</b> fields.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click <b>Clear</b> to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

## 45.12 General MVR Configuration

Use this screen to view and create multicast VLANs.

Click SWITC HING > Multic a st > MVR to display the screen as shown next.

Note: You can create up to five multicast VLANs and up to 256 multicast rules on the Switch.

Note: Your Switch automatically creates a static VLAN (with the same VID) when you create a multicast VLAN in this screen.

Figure 219	SWITCHING >	Multicast > MVR
------------	-------------	-----------------

MVR	Group Sa	elup					
						O Ada/Edit	🝵 Delete
	VLAN	Active	Nome	Mode	Source Port	Receiver Port	802.1p Priority
	5	01	GroupEcompte	Dynomie			0

The following table describes the related labels in this screen.

IABEL	DESC RIPTIO N		
VLAN	This field displays the multicast VLAN ID.		
Active	field displays whether the multicast group is enabled or not.		
Name	This field displays the descriptive name for this setting.		
Mode	This field displays the MVR mode.		
Source Port	This field displays the source port numbers.		
Receiver Port	This field displays the receiver port numbers.		
802.1p Priority	This field displays the priority level.		

XGS2220 Series User's Guide

LABEL	DESC RIPTIO N
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to add a new multicast VLAN or edit a selected one.
Delete	Select the entries that you want to remove, then click $\mathbf{De}  \mathbf{le}  \mathbf{te}$ to delete multicast VLANs.

#### 45.12.1 Add/Edit MVR

Use this screen to create or edit multicast VLANs and select the receiver ports and a source port for each multicast VLAN.

To access this screen, click Add/Edit or select an existing entry and click Add/Edit in the SWIIC HING > Multic a st > MVR screen.

Figure 220 SWITCHING > Multicast > MVR > Add/Edit

aten (		07			
incup Ne	201 <b>H</b>				
Uticosi	VLAN D	-			
C20 p P4	offy	0.			
And=		O Dimanto	O Con	cicitos	
		1.			
rital	Source Fort	Receiver	Port	Нопе	lagging
8		- Store	¥.		Ū.
10	0	0		0	1.1
2.	0	0		0	
2.	0.	0		0	
4	Ċ.	0		0	D.
ъ.	0	0		0	
$\delta = -$	Ó.	Ð		0	-
7	20	2	~~	0	
- 191					$\sim$

The following table describes the related labels in this screen.

Table 153 SWITCHING > Multicast > MVR > Add/Edit

IABEL	DESC RIPTIO N
Active	Enable the switch button to enable MVR to allow one single multicast VLAN to be shared among different subscriber VLANs on the network.
Group Name	Enter a descriptive name (up to 32 printable ASCII characters except [ ? ], [   ], [ ' ], [ " ], or [ , ]) for identification purposes.
Multicast VLAN ID	Enter the VLAN ID (1 to 4094) of the multicast VLAN.

IABEL	DESC RIPIIO N				
802.1p Priority	Select a priority level $(0 - 7)$ with which the Switch replaces the priority in outgoing IGMP or MLD control packets (belonging to this multicast VLAN).				
Mode	Specify the MVR mode on the Switch. Choices are <b>Dynamic</b> and <b>Compatible</b> .				
	Select <b>Dynamic</b> to send IGMP reports or MLD messages to all MVR source ports in the multicast VLAN.				
	Select Compatible to set the Switch not to send IGMP reports or MLD messages.				
Use this section to	configure MVR settings on each port.				
Port	This field displays the port number on the Switch.				
*	Settings in this row apply to all ports.				
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.				
	Changes in this row are copied to all the ports as soon as you make them.				
Source Port	Select this option to set this port as the MVR source port that sends and receives multicast traffic. All source ports must belong to a single multicast VLAN.				
Receiver Port	Select this option to set this port as a receiver port that only receives multicast traffic.				
None	Select this option to set the port not to participate in MVR. No MVR multicast traffic is sent or received on this port.				
Tagging	Select this check box if you want the port to tag the VLAN ID in all outgoing frames transmitted.				
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.				
Clear	Click Clear to clear the fields to the factory defaults.				
Cancel	Click Cancel to not save the configuration you make and return to the last screen.				

Table 153	SWITCHING > Multicast > MVR > Add/Edit (continue	Ч
	3 MILCHING - MULICUSI - MVK - AUU/EUI (COLIIIIUE	u)

## 45.13 MVR Group Setup

All source ports and receiver ports belonging to a multicast group can receive multicast data sent to this multicast group.

Use this screen to view and configure MVR IP multicast group settings. Click SWIIC HING > Multic a st > MVR > Group Se tup to access this screen.

Note: A port can belong to more than one multicast VLAN. However, IP multicast group addresses in different multicast VLANs cannot overlap.

VR (	Group Setup				
				Q Add/Tatt	E Datada
C1-	ANY DAM	Group Name	Stori Addrese		Address
	5	descent of			
0		Securi	722.000	22	1002
- 63		198-re-0	10933	<u> </u>	6950)
12	4				
1 (C)		1 <mark>3/2017</mark> 9	102 <mark>2</mark>	្មា	02:2

Figure 221 SWITCHING > Multicast > MVR > Group Setup

Table 154	SWITCHING > Multicast > MVR > Group Setup
-----------	---

IABEL	DESC RIPTIO N
MVLAN	This field displays the multicast VLAN ID.
Group Name	This field displays the descriptive name for this setting.
Start Address	This field displays the starting IP address of the multicast group.
End Address	This field displays the ending IP address of the multicast group.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to add a new multicast group or edit a selected one.
Delete	Select the group entries that you want to remove, then click <b>Delete</b> to delete the selected multicast groups.
	If you delete a multicast VLAN, all multicast groups in this VLAN will also be removed.

## 45.13.1 Add/Edit MVR Group

Use this screen to configure MVR IP multicast group addresses. To access this screen, click the Add/Edit button or select an entry from the list and click the Add/Edit button.

Figure 222	SWITCHING >	Multicast > MVR >	Group Setup >	Add/Edit
------------	-------------	-------------------	---------------	----------

Multipost VLAN ID	×
Group Name	
Skal Address	
End Address	
	Apply Clear Cancel
	silelerk second second

Talala 155	CNALL C > NAULTING > AND C Crown Coture > A dd/ ( dit
	SWITCHING > Multicast > MVR > Group Setup > Add/Edit

IABEL	DESC RIPTIO N			
Multicast VLAN ID	Select a multicast VLAN ID (that you configured in the $\mathbf{MVR}$ screen) from the drop-down list box.			
Group Name	Enter a descriptive name for identification purposes. You can enter up to 32 printable ASCII characters except [?], [   ], ['], ["] or [, ].			
Start Address	Enter the starting IP multicast address of the multicast group in dotted decimal notation.			
End Address	Enter the ending IP multicast address of the multicast group in dotted decimal notation.			
	Enter the same IP address as the <b>Start Address</b> field if you want to configure only one IP address for a multicast group.			
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.			
Clear	Click Clear to clear the fields to the factory defaults.			
Cancel	Click Cancel to not save the configuration you make and return to the last screen.			

#### 45.13.2 MVRConfiguration Example

The following figure shows a network example where ports 1, 2 and 3 on the Switch belong to VLAN 1. In addition, port 7 belongs to the multicast group with VID 200 to receive multicast traffic (the **News** and **Movie** channels) from the remote streaming media server, **S**. Computers A, B and C in VLAN 1 are able to receive the traffic.





To configure the MVR settings on the Switch, click the Add/Edit button in the SWIIC HING > Multic ast > MVR screen. Create a multicast VLAN and set the receiver and source ports.

au toust v 02 lip îre		hanian   200   noj		
iceo		Obytemic Odespetts	)	
fot	Source Port	Repetver Port	None	logging
3		Report of Part w		D
1	0	0	0	
2	0	0	0	
Y	0	0	0	
1	0	Ó	0	
ā.	0	0	0	D
×	0	0	0	11
(*	0	0	(ÚT)	
8	Ċ.	9	0 ~	~0 ~

Figure 224 MVR Configuration Example

To set the Switch to forward the multicast group traffic to the subscribers, click Add/Edit in the SWIIC HING > Multicast > MVR > Group Setup screen and configure multicast group settings. The following figure shows an example where two IPv4 multicast groups (News and Movie) are configured for the multicast VLAN 200.

Multioast VLAN ID	200 w
Group Name	Missie
Silceri Actioness	200.1.2.50
End Address	280.1.2.60
	Apply Clear Cancel

Figure 225 MVR Group Configuration Example – Add

WVR	Group Setu				
				G Act/bat	T optim
	WYLAN	Group Name	Start Address	End	Address
THE ST	200		05014010040100	4,000	
11		Altori-	28(1.3.9)	202	in two
		NCis 3	224,7,4,10	226	3.4.31

Figure 226 MVR Group Configuration Example – View

# C HAPTER 46 Static Multic ast Forwarding

# 46.1 Static Multicast Forwarding Overview

This chapter discusses how to configure static multicast forwarding rules based on multicast MAC addresses or multicast IPv4 addresses.

Use these screens to configure static multicast address forwarding by defining the ports and VLANs that multicast traffic can pass through the Switch. If a subscriber is on a different port or VLAN, then the subscriber will not get the multicast.

## 46.1.1 What You Can Do

Use the **Static Multic ast Forwarding By MAC** screen (Section 46.2 on page 311) to configure rules to forward specific multicast frames, such as streaming or control frames, to specific ports.

## 46.1.2 What You Need To Know


A multicast MAC address or multicast IP address is the MAC address or IP address of a multicast group, and not a receiving device.

A static multicast address is a multicast MAC address or multicast IPv4 address that has been manually entered in the multicast table. This identifies the destination of the multicast content. Multicast IPv4 addresses uses the Class D IP addresses range 224.0.0.0 to 239.255.255.255. Multicast MAC addresses have a "1" as the last binary bit of the first octet pair (for example, 01:00:5e:00:00:0A). Static multicast addresses do not age out. See IP Multicast Addresses on page 283 for more information on IP multicast addresses.

Note: Static (manual) multicast forwarding allows you (the administrator) to forward multicast frames to a member without the member having to join the group first.

If a multicast group has no members, then the Switch cannot forward to specific ports unless you configure static (manual) multicast entries. The Switch will either flood the multicast frames to all ports (default) or drop them. Figure 227 on page 311 shows such unknown multicast frames flooded to all ports. With static multicast forwarding, you can forward these multicasts to ports within a VLAN group.





## 46.2 Static Multicast Forwarding By MAC

Use this screen to view and configure static multicast MAC addresses for ports to receive the multicast stream. Click **SWIICHING** > **Multicast** > **Static Multicast Forwarding By MAC** to display the screen as shown next.

Figure 228 SWITCHING > Multicast > Static Multicast Forwarding By MAC

static Multic	asl Forward	ing by MAC				
				C	Add/Edit	💡 Deleba
	Index	Active	Name	MAC Address	VID	Pori
	1	ON D	ha emple	01.d00exec00800877	1	5

The following table describes the labels in this screen.

LABEL	DESC RIPTIO N
Index	This is the index number of the static multicast MAC address rule.
Active	This field displays whether a static multicast MAC address forwarding rule is active or not. You may temporarily deactivate a rule without deleting it.
Name	This field displays the descriptive name for identification purposes for a static multicast MAC address-forwarding rule.
MAC Address	This field displays the multicast MAC address that identifies a multicast group.
VID	This field displays the ID number of a VLAN group to which frames containing the specified multicast MAC address will be forwarded.
Port	This field displays the ports within an identified VLAN group to which frames containing the specified multicast MAC address will be forwarded.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to add a new rule or edit a selected one.
Delete	Click <b>Delete</b> to remove the selected rules.

Table 156 SWITCHING > Multicast > Static Multicast Forwarding By MAC

#### 46.2.1 Add/Edit Static Multicast Forwarding By MAC

Use this screen to add a static multicast MAC address rule for ports to receive the multicast stream.

Click Add/Edit, or select an entry and click Add/Edit in the SWIIC HING > Multicast > Static Multicast Forwarding By MAC to display this screen.

Figure 229	SWITCHING >	> Multicast >	Static Multicast	Forwarding By MA	C > Add/Edit
------------	-------------	---------------	------------------	------------------	--------------

Active	() OFF (		
Name			
$M \wedge C_{\rm c} \wedge {\rm christen}$			
VII)			
that i			
	- Apply	Clear	Concel

The following table describes the labels in this screen.

IABEL	DESC RIPTIO N
Active	Enable the switch button to activate your rule. You may temporarily deactivate a rule without deleting it by disabling the switch.
Name	Enter a descriptive name (up to 32 printable ASCII characters except [?], [ ], ['], ["] or [,]) for this static multicast MAC address forwarding rule. This is for identification only.
MAC Address	Enter a multicast MAC address which identifies the multicast group. The last binary bit of the first octet pair in a multicast MAC address must be 1. For example, the first octet pair 00000001 is 01 in hexadecimal, so 01:00:5e:00:00:0A and 01:00:5e:00:00:27 are valid multicast MAC addresses.
VID	You can forward frames with matching destination multicast MAC address to ports within a VLAN group. Enter the ID that identifies the VLAN group here. If you do NOT have a specific target VLAN, enter 1.
Port	Enter the ports where frames with destination multicast MAC address that matched the entry above are forwarded. You can enter multiple ports separated by (no space) comma (,) or hyphen (-). For example, enter "3-5" for ports 3, 4, and 5. Enter "3,5,7" for ports 3, 5, and 7.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click <b>Cancel</b> to not save the configuration you make and return to the last screen.

Table 157 SWITCHING > Multicast > Static Multicast Forwarding By MAC > Add/Edit

# 46.3 Configure a Static Multicast IPv4 Address

Use this screen to configure static multicast IPv4 addresses for ports to receive the multicast stream. Click **SWIIC HING** > **Multic a st** > **Static Multic a st Forwarding By IP** to display the screen as shown next.

Figure 230	SWITCHING >	Static Multicast	Forwarding By IP
	0	0.0.0.0	

ing are not officially a				
Static Multico & Forwarding Ry 12				
				O kodňuba 📑 pelete
index.	Name	E destroyers	WD.	Peril.

Table 158 SWIT	CHING > Static	Multicast	Forwardina	Bv IP
----------------	----------------	-----------	------------	-------

IABEL	DESC RIPTIO N
Index	This is the index number of the static multicast IP address rule.
Name	This field displays the descriptive name for identification purposes for a static multicast IP address- forwarding rule.
IP Address	This field displays the multicast IP address that identifies a multicast group.
VID	This field displays the ID number of a VLAN group to which frames containing the specified multicast IP address will be forwarded.
Port	This field displays the ports within an identified VLAN group to which frames containing the specified multicast IP address will be forwarded.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to add a new rule or edit a selected one.
Delete	Click <b>Delete</b> to remove the selected rules.

#### 46.3.1 Add/Edit a Static Multic ast Address By IP

Use this screen to configure ports and VLAN to receive the multicast stream with this multicast IPv4 address.

Click Add/Edit, or select an entry and click Add/Edit in the SWIICHING > Static Multic ast Forwarding By IP to display this screen.

Name		
IP Address		
VD		
Port		
Apply	Clear	Cancel
Аррау	O.Cor	Canca

Figure 231 SWITCHING > Static Multicast Forwarding By IP > Add/Edit

The following table describes the labels in this screen.

Table 159 SWITCHING > Static Multicast Forwarding By IP > Add/Edit

IABEL	DESC RIPTIO N
Name	Enter a descriptive name (up to 32 printable ASCII characters except [ $?$ ], [ $ $ ], [ $'$ ], [ $'$ ] or [,]) for this static multicast IPv4 address forwarding rule. This is for identification only.
IP Address	Enter a multicast IPv4 address (224.0.0.0 – 239.255.255.255) which identifies the multicast group.

IABEL	DESC RIPIIO N
VID	You can forward frames with matching destination multicast IPv4 address to ports within a VLAN group. Enter the ID that identifies the VLAN group here. If you do NOT have a specific target VLAN, enter 1.
Port	Enter the ports where frames with destination multicast IPv4 address that matched the entry above are forwarded. You can enter multiple ports separated by (no space) comma (,) or hyphen (-). For example, enter "3-5" for ports 3, 4, and 5. Enter "3,5,7" for ports 3, 5, and 7.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

Table 150		Statio Multioad	Ferryarding By ID >	Add/Edit (continued)
1001010107		• 510110 ////////////////////////////////	FOIWOIOINO DV   F >	Add/Edit (continued)
	0	010110 1110 1110 0101		

# C HAPTER 47 PPPoE

## 47.1 PPPoE Intermediate Agent Overview

This chapter describes how the Switch gives a PPPoE termination server additional information that the server can use to identify and authenticate a PPPoE client.

A PPPoE Intermediate Agent (PPPoE IA) is deployed between a PPPoE server and PPPoE clients. It helps the PPPoE server identify and authenticate clients by adding subscriber line specific information to PPPoE discovery packets from clients on a per-port or per-port-per-VLAN basis before forwarding them to the PPPoE server.



#### 47.1.1 What You Can Do

- Use the **PPPoEIntermediate Agent** screen (Section 47.2 on page 317) to enable the PPPoE Intermediate Agent on the Switch.
- Use the **PPPoEIA Port** screen (Section 47.3 on page 319) to set the port state and configure PPPoE intermediate agent sub-options on a per-port basis.
- Use the **PPPoEIA Port VIAN** screen (Section 47.4 on page 320) to configure PPPoEIA settings that apply to a specific VLAN on a port.
- Use the **PPPoEIA VIAN** (Section 47.5 on page 322) to enable the PPPoE Intermediate Agent on a VLAN.

#### 47.1.2 What You Need to Know

Read on for concepts on ARP that can help you configure the screen in this chapter.

#### 47.1.2.1 PPPoE Intermediate Agent Tag Format

If the PPPoE Intermediate Agent is enabled, the Switch adds a vendor-specific tag to PADI (PPPoE Active Discovery Initialization) and PADR (PPPoE Active Discovery Request) packets from PPPoE clients.

This tag is defined in RFC 2516 and has the following format for this feature.

Table 160 PPPoE	Intermediate Age	ent Vendor-specifie	c Tag Format	
Tag_Type	Tag_Len	Value	il	i2
(0x0105)				

The Tag\_Type is 0x0105 for vendor-specific tags, as defined in RFC 2516. The Tag\_Len indicates the length of Value, i1 and i2. The Value is the 32-bit number 0x00000DE9, which stands for the "ADSL Forum" IANA entry. i1 and i2 are PPPoE intermediate agent sub-options, which contain additional information about the PPPoE client.

#### 47.1.2.2 Sub-Option Format

There are two types of sub-option: "Agent Circuit ID Sub-option" and "Agent Remote ID Sub-option". They have the following formats.

#### Table 161 PPPoE IA Circuit ID Sub-option Format: User-defined String

SubOpt	Length	Value
0x01	Ν	String
(1 byte)	(1 byte)	(63 bytes)
Table 162	PPPoE IA R	emote ID Sub-option Format
SubOpt	Length	Value
0x02	Ν	MAC Address or String
(1 byte)	(1 byte)	(63 bytes)

The 1 in the first field identifies this as an Agent Circuit ID sub-option and 2 identifies this as an Agent Remote ID sub-option. The next field specifies the length of the field. The Switch takes the Circuit ID string you manually configure for a VLAN on a port as the highest priority and the Circuit ID string for a port as the second priority. In addition, the Switch puts the PPPoE client's MAC address into the Agent Remote ID Sub-option if you do not specify any user-defined string.

#### Flexible Circuit ID Syntax with Identifier String and Variables

If you do not configure a Circuit ID string for a VLAN on a specific port or for a specific port, the Switch adds the user-defined identifier string and variables into the Agent Circuit ID Sub-option. The variables can be the slot ID of the PPPoE client, the port number of the PPPoE client and/or the VLAN ID on the PPPoE packet.

The identifier-string, slot ID, port number and VLAN ID are separated from each other by a pound key (#), semi-colon (;), period (.), comma (,), forward slash (/) or space. An Agent Circuit ID Sub-option example is "Switch/07/0123" and indicates the PPPoE packets come from a PPPoE client which is connected to the Switch's port 7 and belong to VLAN 123.

 Table 163
 PPPoE IA Circuit ID Sub-option Format: Using Identifier String and Variables

 SubOpt
 Length

 Value

3000pi	Longin				Value			
0x01	Ν	Identifier	delimiter	Slot ID	delimiter	Port No	delimiter	VLAN ID
(1 byte)	(1 byte)	String (53 byte)	(1 byte)	(1 byte)	(1 byte)	(2 byte)	(1 byte)	(4 bytes)

#### WT-101 De fault Circuit ID Syntax

If you do not configure a Circuit ID string for a specific VLAN on a port or for a specific port, and disable the flexible Circuit ID syntax in the **PPPoE** > **Intermediate Agent** screen, the Switch automatically generates a Circuit ID string according to the default Circuit ID syntax which is defined in the DSL Forum Working Text (WT)-101. The default access node identifier is the host name of the PPPoE intermediate agent and the eth indicates "Ethernet".

Table 164 PPPoE IA Circuit ID Sub-option Format: Defined in WT-101

SubOpt	Length	Value								
0x01	Ν	Access	Space	eth	Space	Slot ID	/	Port No	:	VLAN ID
(1 byte)	(1 byte)	Node Identifier (20 byte)	(1 byte)	(3 byte)	(1 byte)	(1 byte)	(1 byte)	(2 byte)	(1 byte)	(4 bytes)

#### 47.1.2.3 Port State

Every port is either a trusted port or an untrusted port for the PPPoE intermediate agent. This setting is independent of the trusted or untrusted setting for DHCP snooping or ARP inspection. You can also specify the agent sub-options (circuit ID and remote ID) that the Switch adds to PADI and PADR packets from PPPoE clients.

Trusted ports are connected to PPPoE servers.

- If a PADO (PPPoE Active Discovery Offer), PADS (PPPoE Active Discovery Session-confirmation), or PADT (PPPoE Active Discovery Terminate) packet is sent from a PPPoE server and received on a trusted port, the Switch forwards it to all other ports.
- If a PADI or PADR packet is sent from a PPPoE client but received on a trusted port, the Switch forwards it to other trusted ports.

Note: The Switch will drop all PPPoE discovery packets if you enable the PPPoE intermediate agent and there are no trusted ports.

Untrusted ports are connected to subscribers.

- If a PADI, PADR, or PADT packet is sent from a PPPoE client and received on an untrusted port, the Switch adds a vendor-specific tag to the packet and then forwards it to the trusted ports.
- The Switch discards PADO and PADS packets which are sent from a PPPoE server but received on an untrusted port.

## 47.2 PPPoEIntermediate Agent

Use this screen to configure the Switch to give a PPPoE termination server additional subscriber information that the server can use to identify and authenticate a PPPoE client.

Click SWIICHING > PPPoE Intermediate Agent to display the screen as shown.

Figure 232	SWITCHING > PPPoE Inte	ermediate Aaent
ing unc aua		innoaiaio / goin

PPPoE Intermediate	Agent	PPPOE IA Port	PPPOE LA PORT Y LAN	PPPOE 14 VEAN
PPPoE Intermediate				
Active Les andre de Learning		о че		
Circuit-ID				
Section.	COT (			
de 15, 2007 Splite	- Terror			
Peride	<u>×</u> ×	1		
		Acoty C	aw	

IABEL	DESC RIPTIO N
PPPoE Intermedi	ate Agent
Active	Enable the switch button to enable the PPPoE intermediate agent globally on the Switch.
Access- Node- Identifier	Enter up to 20 ASCII printable characters (except [?], [   ], ['], or [,]) to identify the PPPoE intermediate agent. Hyphens (-) and spaces are also allowed. The default is the Switch's host name.
Circuit-ID	
Use this section t	o configure the Circuit ID field in the PADI and PADR packets.
screen) or for a s screen) has prior	u configure for a specific port (in the <b>SWIICHING</b> > <b>PPPoE Intermediate Agent</b> > <b>PPPoEIA Port</b> specific VLAN on a port (in the <b>SWIICHING</b> > <b>PPPoEIntermediate Agent</b> > <b>PPPoEIA Port VIAN</b> ity over this. That means, if you also want to configure PPPoEIA Per-Port or Per-Port Per-VLAN e fields here empty and configure circuit-id and remote-id in the Per-Port or Per-Port Per-VLAN
Active	Enable the switch button to have the Switch add the user-defined identifier string and variables (specified in the <b>Option</b> field) to PADI or PADR packets from PPPoE clients.
	If you leave this option unselected and do not configure any Circuit ID string (using CLI commands) on the Switch, the Switch will use the string specified in the Access-Node-Identifier field.
Identifier- String	Specify a string that the Switch adds in the Agent Circuit ID sub-option. You can enter up to 53 printable ASCII characters (except [?], [   ], [ ' ], or [, ]). Spaces are allowed.
Option	Select the variables that you want the Switch to generate and add in the Agent Circuit ID sub- option. The variable options include <b>sp</b> , <b>sv</b> , <b>pv</b> and <b>spv</b> which indicate combinations of slot-port, slot-VLAN, port-VLAN and slot-port-VLAN respectively. The Switch enters a zero into the PADI and PADR packets for the slot value.
Delimiter	Select a delimiter to separate the identifier-string, slot ID, port number and/or VLAN ID from each other. You can use a pound key (#), semi-colon (;), period (.), comma (,), forward slash (/) or space.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

 Table 165
 SWITCHING > PPPoE Intermediate Agent

## 47.3 PPPoEIA Port

Use this screen to specify whether individual ports are trusted or untrusted ports and have the Switch add extra information to PPPoE discovery packets from PPPoE clients on a per-port basis.

Note: The Switch will drop all PPPoE packets if you enable the PPPoE Intermediate Agent on the Switch and there are no trusted ports.

Click the SWIIC HING > PPPoE Intermediate Agent > PPPoEIA Port screen to display the screen as shown.

Port	Server Tupled State	Circuil-ID	Remote-10
93 <del>3</del>	University	l	
1	Luinven v		
2	Unitation v	l	
26	Etrin.dec.w		
8 <b>2</b>	Unfusice -		
35. 25	tinh. dec v		
1	Unitatice -		
4	Enhand y		$\sim$
		$\sim$	$\sim$

Figure 233 SWITCHING > PPPoE Intermediate Agent > PPPoE IA Port

The following table describes the labels in this screen.

IABEL	DESC RIPTIO N
Port	This field displays the port number. * means all ports.
*	Use this row to make the setting the same for all ports. Use this row first and then make adjustments on a port-by-port basis. Changes in this row are copied to all the ports as soon as you make them.

Table 166 SWITCHING > PPPoE Intermediate Agent > PPPoE IA Port

IABEL	DESC RIPIIO N
Server Trusted	Select whether this port is a trusted port (Trusted) or an untrusted port (Untrusted).
State	Trusted ports are uplink ports connected to PPPoE servers.
	If a PADO (PPPoE Active Discovery Offer), PADS (PPPoE Active Discovery Session-confirmation), or PADT (PPPoE Active Discovery Terminate) packet is sent from a PPPoE server and received on a trusted port, the Switch forwards it to all other ports.
	If a PADI or PADR packet is sent from a PPPoE client but received on a trusted port, the Switch forwards it to other trusted ports.
	Untrusted ports are downlink ports connected to subscribers.
	If a PADI, PADR, or PADT packet is sent from a PPPoE client and received on an untrusted port, the Switch adds a vendor-specific tag to the packet and then forwards it to the trusted ports.
	The Switch discards PADO and PADS packets which are sent from a PPPoE server but received on an untrusted port.
Circuit-ID	Enter a string of up to 63 ASCII characters (except [?], [], ['], or [,]) that the Switch adds into the Agent Circuit ID sub-option for PPPoE discovery packets received on this port. Spaces are allowed.
	The Circuit ID you configure for a specific VLAN on a port (in the <b>SWIIC HING &gt; PPPoE</b> Intermediate Agent > <b>PPPoEIA</b> Port VIAN screen) has the highest priority.
Remote-ID	Enter a string of up to 63 ASCII characters (except [?], [ ], ['], or [,]) that the Switch adds into the Agent Remote ID sub-option for PPPoE discovery packets received on this port. Spaces are allowed.
	If you do not specify a string here or in the $\mathbf{Remote} \cdot \mathbf{ID}$ field for a VLAN on a port, the Switch automatically uses the PPPoE client's MAC address.
	The Remote ID you configure for a specific VLAN on a port (in the <b>SWIICHING &gt; PPPoE</b> Intermediate Agent > PPPoEIA Port VIAN screen) has the highest priority.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

#### Table 166 SWITCHING > PPPoE Intermediate Agent > PPPoE IA Port (continued)

## 47.4 PPPoEIA Port VIAN

Use this screen to configure PPPoE IA settings that apply to a specific VLAN on a port.

Click SWIICHING > PPPoE Intermediate Agent > PPPoEIA Port VIAN to display the screen as shown.

0			0	
PPPoE Interne	adiata Agent	PPPoE IA Port	PPPoE IA Port VLAN	PPPOE IA VIAN
Show Fort Show YuAN	For Sten VID	Dr.d. VIC	Auch	
tat.	VIC	N	Circur-D	(Fage 1 ) of (1 m) Remote-O
				(Rego 1)of 1
		Austr	Ganx	

Table 167	SWITCHING >	PPPoE Intermediate Agent > PPPoE IA Port VLAN	1
	3000 CT III (O )	TH DE INCINCUIDE / GOIN / TH DE I/ TO T + E/ T	

LABEL	DESC RIPTIO N
Show Port	
Port	Enter a port number to show the PPPoE Intermediate Agent settings for the specified VLANs on the port.
Show VLAN	·
Use this section	to specify the VLANs you want to configure in the section below.
Start VID	Enter the lowest VLAN ID you want to configure in the section below.
End VID	Enter the highest VLAN ID you want to configure in the section below.
Apply	Click <b>Apply</b> to display the specified range of VLANs in the section below.
Port:	This field displays the port number specified above.
VID	This field displays the VLAN ID of each VLAN in the range specified above. If you configure the * VLAN, the settings are applied to all VLANs.
*	Use this row to make the setting the same for all VLANs. Use this row first and then make adjustments on a VLAN-by-VLAN basis.
	Changes in this row are copied to all the VLANs as soon as you make them.
Circuit-ID	Enter a string of up to 63 ASCII characters (except [?], [ ], ['], or [,]) that the Switch adds into the Agent Circuit ID sub-option for this VLAN on the specified port. Spaces are allowed.
	The Circuit ID you configure here has the highest priority.
Remote-ID	Enter a string of up to 63 ASCII characters (except [?], [ ], ['], ["], or [,]) that the Switch adds into the Agent Remote ID sub-option for this VLAN on the specified port. Spaces are allowed.
	If you do not specify a string here or in the <b>Remote-ID</b> field for a specific port, the Switch automatically uses the PPPoE client's MAC address.
	The Remote ID you configure here has the highest priority.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

# 47.5 PPPoEIA VIAN

Use this screen to set whether the PPPoE Intermediate Agent is enabled on a VLAN and whether the Switch appends the Circuit ID and/or Remote ID to PPPoE discovery packets from a specific VLAN.

Click SWIICHING > PPPoEIntermediate Agent > PPPoEIA VIAN to display the screen as shown.

Figure 235 SWITCHING > PPPoE Intermediate Agent > PPPoE IA VLAN

PPPoE Interme	diate Agent	PPPoE IA Port	PPPoE IA Port VI	AN	PPPoE IA VIAN
Show VLAN	Sterf VID	End VID	Apply		
				K (P	ge I o D X
VID		Enchled	Circui-ID		Remote-ID
				$\mathbb{R} < \mathbb{P}_{1}$	ge 1 of the R
		Apply	Ocnool		

The following table describes the labels in this screen.

Table 168 SWITCHING > PPPoE Intermediate Agent > PPPoE IA VLAN

LABEL	DESC RIPIIO N
Show VLAN	
Use this section	to specify the VLANs you want to configure in the section below.
Start VID	Enter the lowest VLAN ID you want to configure in the section below.
End VID	Enter the highest VLAN ID you want to configure in the section below.
Apply	Click <b>Apply</b> to display the specified range of VLANs in the section below.
VID	This field displays the VLAN ID of each VLAN in the range specified above. If you configure the * VLAN, the settings are applied to all VLANs.
*	Use this row to make the setting the same for all VLANs. Use this row first and then make adjustments on a VLAN-by-VLAN basis.
	Changes in this row are copied to all the VLANs as soon as you make them.
Enabled	Select this option to turn on the PPPoE Intermediate Agent on a VLAN.
Circuit-ID	Select this option to make the Circuit ID settings for a specific VLAN take effect.
Remote-ID	Select this option to make the Remote ID settings for a specific VLAN take effect.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

# C HAPTER 48 Differentia ted Services

## 48.1 DiffServ Overview

This chapter shows you how to configure Differentiated Services (DiffServ) on the Switch.

Quality of Service (QoS) is used to prioritize source-to-destination traffic flows. All packets in the flow are given the same priority. You can use CoS (class of service) to give different priorities to different packet types.

DiffServ is a class of service (CoS) model that marks packets so that they receive specific per-hop treatment at DiffServ-compliant network devices along the route based on the application types and traffic flow. Packets are marked with DiffServ Code Points (DSCPs) indicating the level of service desired. This allows the intermediary DiffServ-compliant network devices to handle the packets differently depending on the code points without the need to negotiate paths or remember state information for every flow. In addition, applications do not have to request a particular service or give advanced notice of where the traffic is going.

#### 48.1.1 What You Can Do

- Use the **Diffserv** screen (Section 48.2 on page 324) to activate DiffServ to apply marking rules or IEEE 802.1p priority mapping on the Switch.
- Use the DSCP Setting screen (Section 48.3.1 on page 326) to change the DSCP-IEEE 802.1p mapping.

#### 48.1.2 What You Need to Know

Read on for concepts on Differentiated Services that can help you configure the screens in this chapter.

#### DSCP and Per Hop Behavior

DiffServ defines a new DS (Differentiated Services) field to replace the Type of Service (ToS) field in the IP header. The DS field contains a 6-bit DSCP field which can define up to 64 service levels and the remaining 2 bits are defined as currently unused (CU). The following figure illustrates the DS field.

Figure 236 DiffServ: Differentiated Service Field

	DSCP (6 bits) CU (2 bits)
--	---------------------------

DSCP is backward compatible with the three precedence bits in the ToS octet so that non-DiffServ compliant, ToS-enabled network device will not conflict with the DSCP mapping.

The DSCP value determines the PHB (Per-Hop Behavior), that each packet gets as it is forwarded across the DiffServ network. Based on the marking rule different kinds of traffic can be marked for different

priorities of forwarding. Resources can then be allocated according to the DSCP values and the configured policies.

#### DiffServ Network Example

The following figure depicts a DiffServ network consisting of a group of directly connected DiffServcompliant network devices. The boundary node (**A** in Figure 237) in a DiffServ network classifies (marks with a DSCP value) the incoming packets into different traffic flows (**Pla tinum**, **Gold**, **Silver**, **Bronze**) based on the configured marking rules. A network administrator can then apply various traffic policies to the traffic flows. An example traffic policy, is to give higher drop precedence to one traffic flow over others. In our example, packets in the **Bronze** traffic flow are more likely to be dropped when congestion occurs than the packets in the **Pla tinum** traffic flow as they move across the DiffServ network.




Figure 237 DiffServ Network

## 48.2 Activating DiffServ

Activate DiffServ to apply marking rules or IEEE 802.1p priority mapping on the selected ports.

Click SWITC HING  $> Q_0 S > Diffserv$  to display the screen as shown.

Diffserv	DSCP selling	
45.64	() urr	
	Peri	1.ch/w
	257	
	通。	Ū
	3	
	1.1	
	- A	Ľ.
	4	Ċ.
	18	13
	1.2	
	$\sim$	
		pole States

Figure 238	SWITCHING >	QoS > Diffserv
------------	-------------	----------------

#### Table 169 SWITCHING > QoS > Diffserv

IABEL	DESC RIPTIO N
Active	Enable the switch button to enable Diffserv on the Switch.
Port	This field displays the index number of a port on the Switch.
*	Settings in this row apply to all ports. Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis. Changes in this row are copied to all the ports as soon as you make them.
Active	Select Active to enable Diffserv on the port.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

## 48.3 DSC P- to - IEEE 802.1 p Priority Settings

You can configure the DSCP to IEEE 802.1p mapping to allow the Switch to prioritize all traffic based on the incoming DSCP value according to the DiffServ to IEEE 802.1p mapping table.

The following table shows the default DSCP-to-IEEE802.1p mapping.

Table 170 Default DSCP-IEEE 802.1p Mapping

DSCP VALUE	0 – 7	8 – 15	16 – 23	24 – 31	32 – 39	40 – 47	48 – 55	56 - 63
IEEE 802.1p	0	1	2	3	4	5	6	7

### 48.3.1 Configuring DSCP Settings

To change the DSCP-IEEE 802.1p mapping click SWTIC HING >  $Q_0 S$  > Diffse rv > DSC P Se tting to display the screen as shown next.

Figure 239 SWITCHING > QoS> Diffserv > DSCP Setting

	902. I <u>p</u>	o Mappi	ng												
0 0 2	W	1.0	19	2 0	w.	1.0	- 14	4 0	w);	8.0	Э¥.	0.01	т¥ (	7.0	1
11 ( <u>)</u>	$ \psi $	1	- 19	10.[1	$\mathbf{x}$	UL	$(\mathbf{w})$	38 <u> </u>	$\mathbf{w}_{1}^{i}$	10.11	$[\mathbf{w}]$	10 1	$\{\psi_i\}$	時間	3
16 2	$\sim$	17 [2	$\langle \mathcal{H} \rangle$	18 2	$\{\mathbf{y}_i\}$	19 [2]	. w	29 [2	8	11 2	29	92 J	· • )	22 2	2
14 [3	.w.)	15 3	- 4	24 2	$\mathbf{x}_{i}$	1	12	16 1	$\mathbf{v}_{i}$	19 [2	<u>.</u>	30 3	<b>.</b>	31 [2]	-2
33 4	w.	33 4	v	34 4	v)	23 [4]	×	26 4	v.	37 4	۷	-38 4	v	22.4	
40 (§	- 22	40 [5	1	42 5	v	40 5	14	++ 5	w);	41 5	÷.,	45 5	- <b>v</b> -	42 5	1
45 6	4	49.16	$\langle q \rangle$	30.[6	$\hat{\mathbf{v}}$	87 <b>[6</b>	$\langle \psi \rangle$	81.6	$ \psi $	53.16	Ξ¥	34 (4	$\langle \psi \rangle$	38 <b>4</b>	19
Se 755	W)	积47	1.9	-38 7	¥.	28.7	- 9	00 7	$ \psi $	0.17.	<u>.</u>	32.7	w);	43.7	1

IABEL	DESC RIPTIO N
0 63	This is the DSCP classification identification number.
	To set the IEEE 802.1p priority mapping, select the priority level from the drop-down list box.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click <b>Cancel</b> to begin configuring this screen afresh.

# C HAPTER 49 Queuing Method

## 49.1 Queuing Method Overview

This section introduces the queuing methods supported.

Queuing is used to help solve performance degradation when there is network congestion. Use the **Queuing Method** screen to configure queuing algorithms for outgoing traffic. See also **Priority Queue** Assignment in the SWIICHING > QoS > Priority Queue screen and 802.1p Priority in the PORT > Port Setup screen for related information.

#### 49.1.1 What You Can Do

Use the **Queuing Method** screen (Section 49.2 on page 328) to set priorities for the queues of the Switch. This distributes bandwidth across the different traffic queues.

#### 49.1.2 What You Need to Know

Queuing algorithms allow switches to maintain separate queues for packets from each individual source or flow and prevent a source from monopolizing the bandwidth.

#### Stric tly Priority Queuing

Strictly Priority Queuing (SPQ) services queues based on priority only. As traffic comes into the Switch, traffic on the highest priority queue, Q7 is transmitted first. When that queue empties, traffic on the next highest-priority queue, Q6 is transmitted until Q6 empties, and then traffic is transmitted on Q5 and so on. If higher priority queues never empty, then traffic on lower priority queues never gets sent. SPQ does not automatically adapt to changing network requirements.

#### Weighted Fair Queuing

Weighted Fair Queuing is used to guarantee each queue's minimum bandwidth based on its bandwidth weight (portion) (the number you configure in the Weight field) when there is traffic congestion. WFQ is activated only when a port has more traffic than it can handle. Queues with larger weights get more guaranteed bandwidth than queues with smaller weights. This queuing mechanism is highly efficient in that it divides any available bandwidth across the different traffic queues. By default, the weight for Q0 is 1, for Q1 is 2, for Q2 is 3, and so on.

#### Weighted Round Robin Scheduling (WRR)

Round Robin Scheduling services queues on a rotating basis and is activated only when a port has more traffic than it can handle. A queue is given an amount of bandwidth irrespective of the incoming traffic

on that port. This queue then moves to the back of the list. The next queue is given an equal amount of bandwidth, and then moves to the end of the list; and so on, depending on the number of queues being used. This works in a looping fashion until a queue is empty.

Weighted Round Robin Scheduling (WRR) uses the same algorithm as round robin scheduling, but services queues based on their priority and queue weight (the number you configure in the queue **Weight** field) rather than a fixed amount of bandwidth. WRR is activated only when a port has more traffic than it can handle. Queues with larger weights get more service than queues with smaller weights. This queuing mechanism is highly efficient in that it divides any available bandwidth across the different traffic queues and returns to queues that have not yet emptied.

## 49.2 Configuring Queuing

Use this screen to set priorities for the queues of the Switch. This distributes bandwidth across the different traffic queues.

Click SWIICHING > QoS > Queuing Method to display the screen as shown below.

	and the second second					laht				Rybrid-SPC
Pod	Webbe	Qð	- 91	- 92	QS	04	Q.5	96	- 97	Invest-Queix
393	350 4		1		11		11		<u>II</u>	No w
	200	1	12	3.0	4	5	8	(Y)	la -	North M
20	82.0		2	3	4	2	ξ	- T	8	None w
1	2000 M	1	18	0	112	5	16	10	149	Horse M
4	<u>320 v</u>	1	2	3	14	5	1	7	8	None w
•	3.0 9	15	Ц¥.	а	10	- N	i fa	10	-fi	Nonere
- 22	<u> 80 0</u>	1	2	3	}[ <b>4</b>	5	8	7	8	Nore w
16	3-10-10-1	10	28	3.2	][00]	1.	14	5e -	a	Horse a
			4			<u> </u>	~		$\sim$	

Figure 240 SWITCHING > QoS > Queuing Method

Table 172 SWITCHING > QoS > Queuing Method

IABEL	DESC RIPIIO N
Port	This label shows the port you are configuring.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.

IABEL	DESC RIPTIO N
Method	Select <b>SPQ</b> (Strictly Priority Queuing), <b>WFQ</b> (Weighted Fair Queuing) or <b>WRR</b> (Weighted Round Robin).
	Strictly Priority Queuing services queues based on priority only. When the highest priority queue empties, traffic on the next highest-priority queue begins. Q7 has the highest priority and Q0 the lowest.
	Weighted Fair Queuing is used to guarantee each queue's minimum bandwidth based on their bandwidth portion (weight) (the number you configure in the <b>Weight</b> field). Queues with larger weights get more guaranteed bandwidth than queues with smaller weights.
	Weighted Round Robin Scheduling services queues on a rotating basis based on their queue weight (the number you configure in the queue <b>Weight</b> field). Queues with larger weights get more service than queues with smaller weights.
Weight	When you select <b>WFQ</b> or <b>WRR</b> , enter the queue weight here. Bandwidth is divided across the different traffic queues according to their weights.
Hybrid-SPQ	This field is applicable only when you select <b>WFQ</b> or <b>WRR</b> .
Lowest- Queue	Select a queue (Q0 to Q7) to have the Switch use SPQ to service the subsequent queues after and including the specified queue for the port. For example, if you select Q5, the Switch services traffic on Q5, Q6 and Q7 using SPQ.
	Select <b>None</b> to always use <b>WFQ</b> or <b>WRR</b> for the port.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 172 SWITCHING > QoS > Queuing Method (continued)

# C HAPTER 50 Priority Queue

## 50.1 Priority Queue Overview

IEEE 802.1p defines up to eight separate traffic types by inserting a tag into a MAC-layer frame that contains bits to define class of service. Frames without an explicit priority tag are given the default priority of the ingress port. Use this screen to configure the priority level-to-physical queue mapping. The Switch has eight physical queues that you can map to the eight priority levels.

On the Switch, traffic assigned to higher index queues gets through faster while traffic in lower index queues is dropped if the network is congested.

### 50.1.1 What You Can Do

Use the **Priority Queue** screen (Section 50.2 on page 330) to configure the priority level-to-physical queue mapping.

## 50.2 Assign Priority Queue

Use this screen to assign priority level to each queue.

Click SWIICHING > QoS > Priority Queue to open this screen.

Figure 241 SWITCHING > QoS > Priority Queue

Priority Queues	csignment .	
Pricety7	<u>7</u> .v.	
Prioritys	<u> 4 v</u>	
Priority C	2 · • [	
fricitie <sup>2</sup>	4.2	
Prically S	3.4	
Priority 2		
Picat <sub>7</sub> 1	17. •	
Price 1922	7.0	

XGS2220 Series User's Guide

LABEL	DESC RIPTIO N
Priority Queu	le Assignment
	g descriptions are based on the traffic types defined in the IEEE 802.1d standard (which incorporates To map a priority level to a physical queue, select a physical queue from the drop-down menu on the
Priority 7	Typically used for network control traffic such as router configuration messages.
Priority 6	Typically used for voice traffic that is especially sensitive to jitter (jitter is the variations in delay).
Priority 5	Typically used for video that consumes high bandwidth and is sensitive to jitter.
Priority 4	Typically used for controlled load, latency-sensitive traffic such as SNA (Systems Network Architecture) transactions.
Priority 3	Typically used for "excellent effort" or better than best effort and would include important business traffic that can tolerate some delay.
Priority 2	This is for "spare bandwidth".
Priority 1	This is typically used for non-critical "background" traffic such as bulk transfers that are allowed but that should not affect other applications and users.
Priority 0	Typically used for best-effort traffic.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to reset the fields.

#### Table 173 SWITCHING > QoS > Priority Queue

# C HAPTER 51 Bandwidth Control

# 51.1 Bandwidth Control Overview

This chapter shows you how you can cap the maximum bandwidth using the **Bandwidth Control** screen.

Bandwidth control means defining a maximum allowable bandwidth for incoming and/or out-going traffic flows on a port.

### 51.1.1 What You Can Do

Use the **Bandwidth Control** screen (Section 51.2 on page 332) to limit the bandwidth for traffic going through the Switch.

### 51.1.2 CIR and PIR

The Committed Information Rate (CIR) is the guaranteed bandwidth for the incoming traffic flow on a port. The Peak Information Rate (PIR) is the maximum bandwidth allowed for the incoming traffic flow on a port when there is no network congestion.

The CIR and PIR should be set for all ports that use the same uplink bandwidth. If the CIR is reached, packets are sent at the rate up to the PIR. When network congestion occurs, packets through the ingress port exceeding the CIR will be marked for drop.

## 51.2 Bandwidth Control Setup

Click SWIIC HING > QoS > Bandwidth Control in the navigation panel to bring up the screen as shown next.

Note: The CIR should be less than the PIR.

Note: The sum of CIRs cannot be greater than or equal to the uplink bandwidth.

• •		111.42	10000	0.2007		oo kalenda s
Fort	Activo	ingre	ác Role	Active	igro.	an Rola
	( <b>1</b> )		(kayar	13	1.5	Muse
1	11		koy.e	1.1	64	Jun
-	Ξ.	-ia	linges.	<u>1</u>	in a	lines
à		- 14	jither.	i î	64	Marca
×.		34	lizpi	13	64	Max
. *	12	24	luque-	0	64	Jours
.6.	1.1		koy.e.	1.1	64	Juni
1. Contract (1. Contract)	0	44	lates.	101	24	lines
1		$\frown$	line	$\sim$		$\sim$
		- 11	Impr		a	littere

Figure 242 SWITCHING > QoS > Bandwidth Control

IABEL	DESC RIPIIO N
Active	Enable the switch button to enable bandwidth control on the Switch.
Port	This field displays the port number.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
Active	Select this check box to activate ingress rate limits on this port.
Ingress Rate	Specify the maximum bandwidth allowed in kilobits per second (Kbps) for the incoming traffic flow on a port.
	Note: Ingress rate bandwidth control applies to layer 2 traffic only.
Active	Select this check box to activate egress rate limits on this port.
Egress Rate	Specify the maximum bandwidth allowed in kilobits per second (Kbps) for the out-going traffic flow on a port.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to reset the fields.


# C HAPTER 52 sFlow

This chapter shows you how to configure sFlow to have the Switch monitor traffic in a network and send information to an sFlow collector for analysis.

### 52.1 sFlow Overview

sFlow (RFC 3176) is a standard technology for monitoring switched networks. An sFlow agent embedded on a switch or router gets sample data and packet statistics from traffic forwarded through its ports. The sFlow agent then creates sFlow data and sends it to an sFlow collector. The sFlow collector is a server that collects and analyzes sFlow datagram. An sFlow datagram includes packet header, input and output interface, sampling process parameters and forwarding information.

sFlow minimizes impact on CPU load of the Switch as it analyzes sample data only. sFlow can continuously monitor network traffic and create reports for network performance analysis and troubleshooting. For example, you can use it to know which IP address or which type of traffic caused network congestion.



## 52.2 sFlow Port Configuration

Click SWITCHING > sFlow in the navigation panel to display the screen as shown.

r,			
Active	Sample role	Poll Interval	Collector Address
E1			
D	22765	120	<u>1</u>
51	.12 / est	120	T.
CI	32768	120	
Ω.	350 at	190	
	227.66	120	C C
17	Server -	00	1
0	32746	120	
		Active         Sample role           I         I           I	Active         Sample role         Poll Interval           Image: Sample role         Poll Interval         Image: Sample role         Poll Interval           Image: Sample role         Sample role         Poll Interval         Image: Sample role         Poll Interval           Image: Sample role         Sample role         Poll Interval         Image: Sample role         Image: Sample

Figure 244 SWITCHING > sFlow

Table 1	75	SWITCHING > sFlow
	, 0	

IABEL	DESC RIPIIO N
Active	Enable the switch button to enable the sFlow agent on the Switch.
Port	This field displays the port number.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
Active	Select this to allow the Switch to monitor traffic on this port and generate and send sFlow datagram to the specified collector.
Sample-rate	Enter a number (N) from 256 to 65535. The Switch captures every one out of N packets for this port and creates sFlow datagram.
Poll-interval	Specify a time interval (from 20 to 120 in seconds) the Switch waits before sending the sFlow datagram and packet counters for this port to the collector.
Collector Address	Enter the IP address of the sFlow collector.
Address	Note: You must have the sFlow collector already configured in the <b>SWIIC HING</b> > sFlow > Collector screen. The sFlow collector does not need to be in the same subnet as the Switch, but it must be accessible from the Switch.
	Note: Configure UDP port 6343 (the default) on a NAT router to allow port forwarding if the collector is behind a NAT router. Configure a firewall rule for UDP port 6343 (the default) to allow incoming traffic if the collector is behind a firewall.

IABEL	DESC RIPTIO N
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 175 SWITCHING > sFlow (continued)

## 52.3 sFlow Collector Configuration

Click **SWIIHCING** > **sFlow** > **Collector** to display the screen as shown. You may want to configure more than one collector if the traffic load to be monitored is more than one collector can manage.

Note: You can configure up to four sFlow collectors in this screen.

Figure 245 SWITHCING > sFlow > Collector

sFlow	Collector		
		O Aduibalt	The states and the states of t
0	index	Collecter Address	UDP Fort

The following table describes the labels in this screen.

Table 176	SWITHCING > sFlow > Collector

LABEL	DESC RIPTIO N
Index	This field displays the index number of this entry.
Collector Address	This field displays IP address of the sFlow collector.
UDP Port	This field displays port number the Switch uses to send sFlow datagram to the collector.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.
Delete	Click <b>Delete</b> to remove the selected entries.

#### 52.3.1 Add/EditsFlowCollector

Click Add/Edit, or select an entry and click Add/Edit in the SWIIHCING > sFlow > Collector screen to display this screen.

Collector Address	0.0.0	95
ULP Put	A2433	
Audy	Clear	Name

Figure 246 SWITCHING > sFlow > Collector > Add/Edit

IABEL	DESC RIPTIO N
Collector Address	Enter the IP address of the sFlow collector.
UDP Port	Enter a UDP port number the Switch uses to send sFlow datagram to the collector. If you change the port here, make sure you change it on the collector, too. The default port is 6343.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

Table 177 SWITCHING > sFlow > Collector > Add/Edit

# CHAPTER 53 Spanning Tree Protocol

## 53.1 Spanning Tree Protocol Overview

The Switch supports Spanning Tree Protocol (STP), Rapid Spanning Tree Protocol (RSTP) and Multiple Spanning Tree Protocol (MSTP) as defined in the following standards.

- IEEE 802.1D Spanning Tree Protocol
- IEEE 802.1w Rapid Spanning Tree Protocol
- IEEE 802.1s Multiple Spanning Tree Protocol

The Switch also allows you to set up multiple STP configurations (or trees). Ports can then be assigned to the trees.

#### 53.1.1 What You Can Do

- Use the **Spanning Thee Protocol Status** screen (Section 53.2 on page 341) to view the STP status in the different STP modes (RSTP, MRSTP or MSTP) you can configure on the Switch.
- Use the **Spanning Thee Setup** screen (Section 53.3 on page 341) to activate one of the STP modes on the Switch.
- Use the Rapid Spanning Tire Protocol Status screen (Section 53.4 on page 344) to view the RSTP status.
- Use the Rapid Spanning Tire Protocol screen (Section 53.5 on page 346) to configure RSTP settings.
- Use the Multiple Rapid Spanning The Protocol Status screen (Section 53.6 on page 348) to view the MRSTP status.
- Use the Multiple Rapid Spanning The Protocol screen (Section 53.7 on page 350) to configure MRSTP.
- Use the Multiple Spanning The Protocol Status screen (Section 53.8 on page 353) to view the MSTP status.
- Use the Multiple Spanning Thee Protocol screen (Section 53.9 on page 355) to configure MSTP.
- Use the **Multiple Spanning Thee Protocol Port Setup** screen (Section 53.10 on page 358) to configure MSTP ports.

#### 53.1.2 What You Need to Know

Read on for concepts on STP that can help you configure the screens in this chapter.

#### (Rapid) Spanning Tree Protocol

(R)STP detects and breaks network loops and provides backup links between switches, bridges or routers. It allows a switch to interact with other (R)STP-compliant switches in your network to ensure that only one path exists between any two stations on the network.

The Switch uses IEEE 802.1 w RSTP (Rapid Spanning Tree Protocol) that allows faster convergence of the

338

spanning tree than STP (while also being backwards compatible with STP-only aware bridges). In RSTP, topology change information is directly propagated throughout the network from the device that generates the topology change. In STP, a longer delay is required as the device that causes a topology change first notifies the root bridge that then notifies the network. Both RSTP and STP flush unwanted learned addresses from the filtering database. In RSTP, the port states are Discarding, Learning, and Forwarding.

Note: In this user's guide, "STP" refers to both STP and RSTP.

#### SIP Terminology

The root bridge is the base of the spanning tree.

Path cost is the cost of transmitting a frame onto a LAN through that port. The recommended cost is assigned according to the speed of the link to which a port is attached. The slower the media, the higher the cost.

	LINK SPEED	RECOMMENDED VALUE	RECOMMENDED RANGE	ALLO WED RANGE
Path Cost	4 Mbps	250	100 to 1000	1 to 65535
Path Cost	10 Mbps	100	50 to 600	1 to 65535
Path Cost	16 Mbps	62	40 to 400	1 to 65535
Path Cost	100 Mbps	19	10 to 60	1 to 65535
Path Cost	1 Gbps	4	3 to 10	1 to 65535
Path Cost	10 Gbps	2	1 to 5	1 to 65535

Table 178 STP Path Costs

On each bridge, the root port is the port through which this bridge communicates with the root. It is the port on this switch with the lowest path cost to the root (the root path cost). If there is no root port, then this switch has been accepted as the root bridge of the spanning tree network.

For each LAN segment, a designated bridge is selected. This bridge has the lowest cost to the root among the bridges connected to the LAN.

#### How SIP Works

After a bridge determines the lowest cost-spanning tree with STP, it enables the root port and the ports that are the designated ports for connected LANs, and disables all other ports that participate in STP. Network packets are therefore only forwarded between enabled ports, eliminating any possible network loops.

STP-aware switches exchange Bridge Protocol Data Units (BPDUs) periodically. When the bridged LAN topology changes, a new spanning tree is constructed.

Once a stable network topology has been established, all bridges listen for Hello BPDUs (Bridge Protocol Data Units) transmitted from the root bridge. If a bridge does not get a Hello BPDU after a predefined interval (Max Age), the bridge assumes that the link to the root bridge is down. This bridge then initiates negotiations with other bridges to reconfigure the network to re-establish a valid network topology.

#### SIP Port States

STP assigns five port states to eliminate packet looping. A bridge port is not allowed to go directly from

blocking state to forwarding state so as to eliminate transient loops.

PORTSTATE	DESC RIPTIO N	
Disabled	STP is disabled (default).	
Blocking	Only configuration and management BPDUs are received and processed.	
Listening	All BPDUs are received and processed. Note: The listening state does NOT exist in RSTP.	
Learning	All BPDUs are received and processed. Information frames are submitted to the learning process but not forwarded.	
Forwarding	All BPDUs are received and processed. All information frames are received and forwarded.	

Table 179	STP Port States

#### Multiple RSIP


MRSTP (Multiple RSTP) is Zyxel's proprietary feature that is compatible with RSTP and STP. With MRSTP, you can have more than one spanning tree on your Switch and assign ports to each tree. Each spanning tree operates independently with its own bridge information.

In the following example, there are two RSTP instances (MRSTP 1 and MRSTP2) on switch A.

To set up MRSTP, activate MRSTP on the Switch and specify which ports belong to which spanning tree.

Note: Each port can belong to one STP tree only.





#### Multiple SIP

Multiple Spanning Tree Protocol (IEEE 802.1s) is backward compatible with STP/RSTP and addresses the limitations of existing spanning tree protocols (STP and RSTP) in networks to include the following features:

- One Common and Internal Spanning Tree (CIST) that represents the entire network's connectivity.
- Grouping of multiple bridges (or switching devices) into regions that appear as one single bridge on the network.
- A VLAN can be mapped to a specific Multiple Spanning Tree Instance (MSTI). MSTI allows multiple VLANs to use the same spanning tree.
- Load-balancing is possible as traffic from different VLANs can use distinct paths in a region.

## 53.2 Spanning Tree Protocol Status

The Spanning Tree Protocol status screen changes depending on what standard you choose to implement on your network. Click **SWIICHING** > **Spanning Thee Protocol** > **Spanning Thee Protocol** > **Spanning Thee Protocol** Status to see the screen as shown.

Figure 248 SWITCHING > Spanning Tree Protocol > Spanning Tree Protocol Status

Sponning Inee Frol-	acol Slaho				
Spanning Tree Fro	IOCOL RSTP				
	Koel Bridge		Oor Bri	dge	
Sndge 10	2000-00000000000		0000.0		
Hello lime (Secondk)	2		0		
Mos Age (vec onds)	5		0		
Porwarding Delay (seconds)	2		9		
Cost to Rildge	0				
Port ID	2,000				
Topology Changed Times	2				
Time Since Lost Chunge	200.22				
For Port State	ii an bhiadh a	esignated Bridge ID	Designated Part IB	Designated Carl	Kool Courd State

This screen differs depending on which STP mode (RSTP, MRSTP or MSTP) you configure on the Switch. This screen is described in detail in the section (Section 53.4 on page 344, Section 53.6 on page 348, and Section 53.8 on page 353) that follows the configuration section for each STP mode. Use the SWITC HING > Spanning The e Protocol > Spanning The e Setup screen to activate one of the STP standards on the Switch.

## 53.3 Spanning Tree Setup

There are three **Auto path-cost Modes** (see Table 183 on page 343). Choose the **Auto Path-cost Mode** according to the device average link speeds in the STP network.

If most of your devices support high link speed, you should select **Long** or **User defined** mode. The path cost of link speed slower than 10 Mbps can be set to 2000000, and the path cost of link speed faster than 10 Gbps can be set to 200. This way, the path costs can better reflect actual link speeds with a wider range (32 bits) of path cost values. If the link speeds within the system are averagely smaller than 1 Gbps, you should select **Short** mode since **Short** mode have path cost values more detailed defined for link speeds under1 Gbps.

The path cost values are described in the following tables.

The Switch defines the following **Short** mode path costs.

LINK SPEED	AUTO PATH COSTVALLE
Up to 4 Mbps	250
Up to 10 Mbps	100
Up to 16 Mbps	62
Up to 100 Mbps	19
Up to 1 Gbps	4
Up to 10 Gbps	2
More than 10 Gbps	1

Table 180 Auto Path Cost Mode: Short

The Switch defines the following **Long** mode path costs.

#### Table 181 Auto Path Cost Mode: Long

LINK SPEED	AUIO PATH COSTVAILLE
Up to 10 Mbps	2000000
Up to 100 Mbps	200000
Up to 1 Gbps	20000
Up to 2.5 Gbps	8000
Up to 5 Gbps	4000
Up to 10 Gbps	2000
More than 10 Gbps	200

If you do not configure the auto path cost values for **User** defined mode, the Switch uses the following default values.

Table 182 Auto Path Cost Mode: User-defined
---

LINK SPEED	AUTO PATH COSTVALLE
Up to 10 Mbps	2000000
Up to 100 Mbps	200000
Up to 1 Gbps	20000
Up to 2.5 Gbps	8000
Up to 5 Gbps	4000
More than 5 Gbps	2000

Use the this screen to activate one of the STP modes on the Switch. Click SWIICHING > Spanning The e Protocol > Spanning The e Setup to display the screen as shown.

-		
Spanning Tree Setup		
Spanning Tree Mode		
O Ropid Sponning Inee(191P)		
🔵 kiulipie Ropid Spanning Te	w(MRSIP)	
<ul> <li>Multiple spanning Tree/WST</li> </ul>	F)	
Auto Path-cost Mode		
O Short		
O Long		
🔿 Uaersdefinest	106/1 20000000	
	100%/ 200000	
	1G 20000	
	250 800	
	50 4000	
	103 2000	
	Concel	

Figure 249 SWITCHING > Spanning Tree Protocol > Spanning Tree Setup

The following table describes the labels in this screen.

Table 183 SWITCHING > Spanning Tree Protocol > Spanning Tree Setu	Table 183	SWITCHING >	Spanning Tree	Protocol > Sp	panning Tree Setup
---	-----------	-------------	---------------	---------------	--------------------

LABEL	DESC RIPTIO N
Spanning Tree Mode	You can activate one of the STP modes on the Switch. Select Rapid Spanning Tree (RSTP), Multiple Rapid Spanning Tree (MRSTP) or Multiple Spanning
	The e (MSIP).

Auto Path-cost Mode

Auto Path-cost Mode allows you to have the Switch automatically set the path cost for each port according to their link speed. The Switch uses the path costs to determine the best path to the root bridge in a spanning tree. There are three Auto Path-cost Modes that supports different path cost lengths:

- Short (16-bit)
- Long (32-bit)
- Userdefined (32-bit).

The auto path cost values of each mode are described in Section 53.3 on page 341.

Note: It is recommended to use the same Auto Path-cost Mode on all switches within the spanning tree network system.

To use the auto path-cost feature, select the Auto Path-cost mode (Short, Iong, User defined), set a port's Path Cost (in the SWIICHING > Spanning Thee Protocol > RSIP, MRSIP, and MSIP screens) to "0". The Switch will automatically set the port's path cost to the auto path cost value defined by the Auto Path-cost Mode you select.

Short	Select this mode if you want to use the 16-bit auto path cost values the Switch defines.
Long	Select this mode if you want to use the 32-bit auto path cost values the Switch defines.
User-defined	Select this mode to manually set the auto path costs for each link speed. Enter the path cost value for each link speed. The range is from 1 – 2000000. It is recommended to assign this value according to link speeds. The slower the speed, the higher the cost.

LABEL	DESC RIPTIO N
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

 Table 183
 SWITCHING > Spanning Tree Protocol > Spanning Tree Setup (continued)

## 53.4 Rapid Spanning Tree Protocol Status

The Spanning Tree Protocol status screen changes depending on what standard you choose to implement on your network. Click **SWTICHING** > **Spanning Tiee Protocol** > **Spanning Tiee Protocol** > **Spanning Tiee Protocol** > **Status** in the navigation panel to display the status screen as shown next. See Section 53.1 on page 338 for more information on RSTP.

Note: This screen is only available after you activate RSTP on the Switch.

Figure 250	SWITCHING >	Spannina Tree	Protocol > Spanning	Tree Protocol Status: RSTP
Ing and 100		op an in ing in o o	i loloool opaining	

Spanning Tree Protocol Sto	atus				
Spanning Tree Protocol: R	ST#				
	Roof Bridge		Out Bridg	je	
Bridge (D	-6555-bc65555ct	10-666	6555-be	Sééschezől.	
Helle Time (seconds)	2.		2		
Wax Age (seconds)	20		20		
Forwarding Delay (seconds)	13		15		
Cont to Bridge	a.				
FortiD	040000				
Topology Changed Times	2				
Time Since Lost Change	0.01133				
Port Port State	Part Role	Designated Sitslige 10	Designated Port ID	Gesignated Cort	Roof Goard State
1 DISCAROING	Chicoled	2000-00000000000	8-000	0	Torwarding
2 DECARONO	Discelled	0000-00000000000	8+2000	0	Torwarding
3 DECARDINO	Disboled	0000-00000000000	0x0000	0	Forwarding
4 DECASONG	Clustered	0000-00000000000000000	II+0000	. a	Potwarding
5 DECARCINE	Olicitried	0000-000000000000000000	0x0000	a	forwarding
# FORWARDING	Designated	eeee troeseectroese	030012	9	Forwarding
7 DISCARDING	Olicoled	0000-00000000000	0×0000	0	Forwarding
B PORMARDING	Designated	6666 b 106666 b 10666	0+6016	0	Forwarding

Table 184	SWITCHING > Spann	ing Tree Protocol >	> Spannina Tree	Protocol Status: RSTP
		ing neer leteer.		

IABEL	DESC RIPIIO N
Bridge	<b>Root Bridge</b> refers to the base of the spanning tree (the root bridge). <b>Our Bridge</b> is this Switch. This Switch may also be the root bridge.
Bridge ID	This is the unique identifier for this bridge, consisting of bridge priority plus MAC address. This ID is the same for <b>Root Bridge</b> and <b>Our Bridge</b> if the Switch is the root switch.
Hello Time (seconds)	This is the time interval (in seconds) at which the root switch transmits a configuration message. The root bridge determines <b>He llo Time</b> , <b>Max Age</b> and <b>Forwarding Delay</b> .
Max Age (seconds)	This is the maximum time (in seconds) the Switch can wait without receiving a configuration message before attempting to reconfigure.
Forwarding Delay (seconds)	This is the time (in seconds) the root switch will wait before changing states (that is, listening to learning to forwarding).
	Note: The listening state does NOT exist in RSTP.
Cost to Bridge	This is the path cost from the root port on this Switch to the root switch.
Port ID	This is the priority and number of the port on the Switch through which this Switch must communicate with the root of the Spanning Tree.
Topology Changed Times	This is the number of times the spanning tree has been reconfigured.
Time Since Last Change	This is the time since the spanning tree was last reconfigured.
Port	This field displays the number of the port on the Switch.
Port State	This field displays the port state in STP.
	<ul> <li>DISCARDING – The port does not forward or process received frames or learn MAC addresses, but still listens for BPDUs.</li> </ul>
	LEARNING – The port learns MAC addresses and processes BPDUs, but does NOT forward frames yet.
	<ul> <li>FORWARDING – The port is operating normally. It learns MAC addresses, processes BPDUs and forwards received frames.</li> </ul>
Port Role	This field displays the role of the port in STP.
	<ul> <li>Root – A forwarding port on a non-root bridge, which has the lowest path cost and is the best port from the non-root bridge to the root bridge. A root bridge does NOT have a root port.</li> </ul>
	<ul> <li>De sig na te d – A forwarding port on the designated bridge for each connected LAN segment. A designated bridge has the lowest path cost to the root bridge among the bridges connected to the LAN segment. All the ports on a root bridge (root switch) are designated ports.</li> </ul>
	<ul> <li>Altemate – A blocked port, which has a best alternate path to the root bridge. This path is different from using the root port. The port moves to the forwarding state when the designated port for the LAN segment fails.</li> </ul>
	<ul> <li>Backup – A blocked port, which has a backup or redundant path to a LAN segment where a designated port is already connected when a switch has two links to the same LAN segment.</li> </ul>
	• $Disa b le d$ – Not strictly part of STP. The port can be disabled manually.
Designated Bridge ID	This field displays the identifier of the designated bridge to which this port belongs when the port is a designated port. Otherwise, it displays the identifier of the designated bridge for the LAN segment to which this port is connected.
Designated Port ID	This field displays the priority and number of the bridge port (on the designated bridge), through which the designated bridge transmits the stored configuration messages.

LABEL	DESC RIPTIO N
Designated Cost	This field displays the path cost to the LAN segment to which the port is connected when the port is a designated port. Otherwise, it displays the path cost to the root bridge from the designated port for the LAN segment to which this port is connected.
Root Guard State	This field displays the state of the port on which root guard is enabled.
	<ul> <li>Root-inconsistent – the Switch receives superior BPDUs on the port and blocks the port.</li> <li>Forwarding – the Switch unblocks and allows the port to forward frames again.</li> </ul>

Table 184 SWITCHING > Spanning Tree Protocol > Spanning Tree Protocol Status: RSTP (continued)

## 53.5 Configure Rapid Spanning Tree Protocol

Use this screen to configure RSTP settings, see Section 53.1 on page 338 for more information on RSTP. Click SWITCHING > Spanning The Protocol > RSTP in the navigation panel to display the screen as shown.

Rapid Spanning Tree Protocol ()) (CFF) Aclive 32788 ----**Bridge Priority** 2 seconds Help Tree MAXAgo. 20 seconds 15 seconds Forwarding Delay: Root Cound Path Cost Port Active 6dge hiisnity. . 128  $\mathbf{P}$  $\mathbf{2}^{\dagger}$  $\Box$ 128 2 3 178  $\mathbf{Z}$ 128 2 4 5 138 X. 2 6 120 7 128  $\mathbf{2}$ -----1 Apply Concel

Figure 251 SWITCHING > Spanning Tree Protocol > RSTP

<b>T</b>     105 01		
Table 185 SV	WITCHING > Spanning Tree Protocol > RS	SIP

IABEL	DESC RIPTIO N
Active	Enable the switch button to activate RSTP. Disable the switch to disable RSTP.
	Note: You must also activate <b>Rapid Spanning Thee</b> ( <b>RSTP</b> ) in the <b>SWITCHING</b> > <b>Spanning Thee Protocol</b> > <b>Spanning Thee Setup</b> screen to enable RSTP on the Switch.
Bridge Priority	Bridge priority is used in determining the root switch, root port and designated port. The Switch with the highest priority (lowest numeric value) becomes the STP root switch. If all Switches have the same priority, the Switch with the lowest MAC address will then become the root switch. Select a value from the drop-down list box.
	The lower the numeric value you assign, the higher the priority for this bridge.
	Bridge Priority determines the root bridge, which in turn determines <b>Hello Time</b> , <b>Max Age</b> and <b>Forwarding Delay</b> .
Hello Time	This is the time interval in seconds between BPDU (Bridge Protocol Data Units) configuration message generations by the root switch. The allowed range is 1 to 10 seconds.
Max Age	This is the maximum time (in seconds) the Switch can wait without receiving a BPDU before attempting to reconfigure. All Switch ports (except for designated ports) should receive BPDUs at regular intervals. Any port that ages out STP information (provided in the last BPDU) becomes the designated port for the attached LAN. If it is a root port, a new root port is selected from among the Switch ports attached to the network. The allowed range is 6 to 40 seconds.
Forwarding Delay	This is the maximum time (in seconds) the Switch will wait before changing states. This delay is required because every Switch must receive information about topology changes before it starts to forward frames. In addition, each port needs time to listen for conflicting information that would make it return to a blocking state; otherwise, temporary data loops might result. The allowed range is 4 to 30 seconds.
	As a general rule:
	$2 * (Forward Delay - 1) \ge Max Age \ge 2 * (Hello Time + 1)$
Port	This field displays the port number.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
Active	Select this check box to activate RSTP on this port.
Edge	Select this check box to configure a port as an edge port when it is directly attached to a computer. An edge port changes its initial STP port state from blocking state to forwarding state immediately without going through listening and learning states right after the port is configured as an edge port or when its link status changes.
	Note: An edge port becomes a non-edge port as soon as it receives a Bridge Protocol Data Unit (BPDU).
Root Guard	Select this check box to enable root guard on this port in order to prevent the switches attached to the port from becoming the root bridge.
	With root guard enabled, a port is blocked when the Switch receives a superior BPDU on it. The Switch allows traffic to pass through this port again when the switch connected to the port stops to send superior BPDUs.

IABEL	DESC RIPTIO N
Priority	Configure the priority for each port here.
	Priority decides which port should be disabled when more than one port forms a loop in a switch. Ports with a higher priority numeric value are disabled first. The allowed range is between 0 and 255 and the default value is 128.
Path Cost	Path cost is the cost of transmitting a frame on to a LAN through that port. It is recommended to assign this value according to the speed of the bridge. The slower the media, the higher the cost.
	Note: Set the value to 0 to use the auto path cost you set in the <b>SWIICHING</b> > <b>Spanning Thee Protocol</b> > <b>Spanning Thee Setup</b> screen (see Auto Path-cost Mode).
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

 Table 185
 SWITCHING > Spanning Tree Protocol > RSTP (continued)

# 53.6 Multiple Rapid Spanning Tree Protocol Status

Click SWIICHING > Spanning The Protocol > Spanning The Protocol Status in the navigation panel to display the status screen as shown next. See Section 53.6 on page 348 for more information on MRSTP.

Note: This screen is only available after you activate MRSTP on the Switch.

pannin	g Tree Protocol	Status					
Spannir	ng Tree Protocol	E MRSTP					
766]]	w i						
		Root Bridge		Ovr Bridge			
140303	0	Anie boleneoboer	4	Seed-border	Anterial Contents		
Hello Tr	ne (seconds)	£.		2			
Mox Ag	(seconds)	20		- 29	20		
forward (recons	Sing Deloy S()	15		15			
Cost to	bildge	-0.					
Port ID		0-0000					
Topolog	y Changed Times	4					
Time He	ice Last Change	0.02/12					
Part	Port State	Pert Note	Overige divel Bridge 10	Designated Part	Designated Colf	Roof Guara Sich	
1	DISCARDING	Dividated	0000	0×0000	a	Rewarding	
2	POEMARDINO	Delignated	6666- TiccosoCiccoso	058002	0	Forwarding	
38	DISCARDING	Deopled	0000- 0000000000000	0:0000	. Ø	Forwarding	
÷.	PORWARDING	Designated	6555- be565566656	0x8014	6	forwarding	
7	DISCANDING	Dischled	0000-	0.0000		forwarding	

Figure 252	SWITCHING >	Spannina Tree	Protocol > Spannina	Tree Protocol Status: MRSTP
Ing une aua		opanning noo	riorocor, oparining	

#### Table 186 SWITCHING > Spanning Tree Protocol > Spanning Tree Protocol Status: MRSTP

IABEL	DESC RIPIIO N	
Tree	Select which STP tree configuration you want to view.	
Bridge	<b>Root Bridge</b> refers to the base of the spanning tree (the root bridge). <b>Our Bridge</b> is this switch. This Switch may also be the root bridge.	
Bridge ID	This is the unique identifier for this bridge, consisting of bridge priority plus MAC address. This ID is the same for <b>Root Bridge</b> and <b>Our Bridge</b> if the Switch is the root switch.	
Hello Time (seconds)	This is the time interval (in seconds) at which the root switch transmits a configuration message. The root bridge determines <b>He llo Time</b> , <b>Max Age</b> and <b>Forwarding Delay</b> .	
Max Age (seconds)	This is the maximum time (in seconds) the Switch can wait without receiving a configuration message before attempting to reconfigure.	
Forwarding Delay (seconds)	This is the time (in seconds) the root switch will wait before changing states (that is, listening to learning to forwarding).	
	Note: The listening state does not exist in RSTP.	
Cost to Bridge	This is the path cost from the root port on this Switch to the root switch.	
Port ID	This is the priority and number of the port on the Switch through which this Switch must communicate with the root of the Spanning Tree.	
Topology Changed Times	This is the number of times the spanning tree has been reconfigured.	

XGS2220 Series User's Guide

LABEL	DESC RIPTIO N				
Time Since Last Change	This is the time since the spanning tree was last reconfigured.				
Port	This field displays the number of the port on the Switch.				
Port State	This field displays the port state in STP.				
	<ul> <li>DISCARDING – The port does not forward or process received frames or learn MAC addresses, but still listens for BPDUs.</li> </ul>				
	• <b>LEARNING</b> – The port learns MAC addresses and processes BPDUs, but does not forward frames yet.				
	<ul> <li>FORWARDING – The port is operating normally. It learns MAC addresses, processes BPDUs and forwards received frames.</li> </ul>				
Port Role	This field displays the role of the port in STP.				
	<ul> <li>Root – A forwarding port on a non-root bridge, which has the lowest path cost and is the best port from the non-root bridge to the root bridge. A root bridge does not have a root port.</li> </ul>				
	<ul> <li>Designated – A forwarding port on the designated bridge for each connected LAN segment. A designated bridge has the lowest path cost to the root bridge among the bridges connected to the LAN segment. All the ports on a root bridge (root switch) are designated ports.</li> </ul>				
	<ul> <li>Altemate – A blocked port, which has a best alternate path to the root bridge. This path is different from using the root port. The port moves to the forwarding state when the designated port for the LAN segment fails.</li> </ul>				
	<ul> <li>Backup – A blocked port, which has a backup or redundant path to a LAN segment where a designated port is already connected when a switch has two links to the same LAN segment.</li> </ul>				
	• $Disabled$ – Not strictly part of STP. The port can be disabled manually.				
Designated Bridge ID	This field displays the identifier of the designated bridge to which this port belongs when the port is a designated port. Otherwise, it displays the identifier of the designated bridge for the LAN segment to which this port is connected.				
Designated Port ID	This field displays the priority and number of the bridge port (on the designated bridge), through which the designated bridge transmits the stored configuration messages.				
Designated Cost	This field displays the path cost to the LAN segment to which the port is connected when the port is a designated port. Otherwise, it displays the path cost to the root bridge from the designated port for the LAN segment to which this port is connected.				
Root Guard State	This field displays the state of the port on which root guard is enabled.				
	<ul> <li>Root – inconsistent – the Switch receives superior BPDUs on the port and blocks the port.</li> <li>Forwarding – the Switch unblocks and allows the port to forward frames again.</li> </ul>				

## 53.7 Configure Multiple Rapid Spanning Tree Protocol

To configure MRSTP, click SWIICHING > Spanning Tiee Protocol > MRSTP in the navigation panel to display the screen as shown.

(relet)	6:the	Boolgie Frients	Seto 5	me	мах аде	Porvearding Dela
31		32/45 9	2	2020	20 <mark>cebende</mark>	0 seconds
3	-	227.65 4	2, 90	sent c	20 seconds	5 seconds
3	13	_s2/es ₩	2 500	onds -	20 :eponde	S coco ods
4	11		2 - out	anak 👘	20 Referrets	5 Seconds
Fort	Active	Edge	Roat Guard	Priority	Patro	ost free
(t)	121	121	(E)			Li e
1	17	10		120	2	1.
4	11	0	11	128	2	119
3	1	<b>C1</b>		1W	[2	1~
$\mathcal{K}$	306	0	0	(28)	2	[1.9.]
<u>A</u>	1.	(E1)		1240	2	1.
÷.	12	0	0	128	2	li se
1	П	D		120	1	14
$\leq$			$\sim$	$\sim$	$\sim$	$\sim$

Figure 253	SWITCHING > Spanning Tree Protocol > MRSTP

Table 187 SWITCHING > Spanning Tree Protocol > MRSTP

IABEL	DESC RIPIIO N
Tree	This is the index number of the STP trees.
Active	Select this check box to activate an STP tree. Clear this check box to disable an STP tree.
	Note: You must also activate <b>Multiple Rapid Spanning Thee (MRSTP)</b> in the <b>SWITHCING &gt; Spanning Thee Protocol &gt; Spanning Thee Setup</b> screen to enable MRSTP on the Switch.
Bridge Priority	Bridge priority is used in determining the root switch, root port and designated port. The switch with the highest priority (lowest numeric value) becomes the STP root switch. If all switches have the same priority, the switch with the lowest MAC address will then become the root switch. Select a value from the drop-down list box.
	The lower the numeric value you assign, the higher the priority for this bridge.
	Bridge Priority determines the root bridge, which in turn determines <b>Hello Time</b> , <b>Max Age</b> and <b>Forwarding Delay</b> .
Hello Time	This is the time interval in seconds between BPDU (Bridge Protocol Data Units) configuration message generations by the root switch. The allowed range is 1 to 10 seconds.

IABEL	DESC RIPTIO N			
Max Age	This is the maximum time (in seconds) the Switch can wait without receiving a BPDU before attempting to reconfigure. All Switch ports (except for designated ports) should receive BPE at regular intervals. Any port that ages out STP information (provided in the last BPDU) becomes the designated port for the attached LAN. If it is a root port, a new root port is selected from among the Switch ports attached to the network. The allowed range is 6 to 4 seconds.			
Forwarding Delay	This is the maximum time (in seconds) the Switch will wait before changing states. This delay is required because every switch must receive information about topology changes before it starts to forward frames. In addition, each port needs time to listen for conflicting information that would make it return to a blocking state; otherwise, temporary data loops might result. The allowed range is 4 to 30 seconds.			
	As a general rule:			
	2 * (Forward Delay - 1) >= Max Age >= 2 * (Hello Time + 1)			
Port	This field displays the port number.			
*	Settings in this row apply to all ports.			
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.			
	Note: Changes in this row are copied to all the ports as soon as you make them.			
Active	Select this check box to activate STP on this port.			
Edge	Select this check box to configure a port as an edge port when it is directly attached to a computer. An edge port changes its initial STP port state from blocking state to forwarding state immediately without going through listening and learning states right after the port is configured as an edge port or when its link status changes. Note: An edge port becomes a non-edge port as soon as it receives a Bridge			
Root Guard	Protocol Data Unit (BPDU). Select this check box to enable root guard on this port in order to prevent the switch(es)			
	attached to the port from becoming the root bridge.			
	With root guard enabled, a port is blocked when the Switch receives a superior BPDU on it. The Switch allows traffic to pass through this port again when the switch connected to the port stops to send superior BPDUs.			
Priority	Configure the priority for each port here.			
	Priority decides which port should be disabled when more than one port forms a loop in a switch. Ports with a higher priority numeric value are disabled first. The allowed range is between 0 and 255 and the default value is 128.			
Path Cost	Path cost is the cost of transmitting a frame on to a LAN through that port. It is recommended to assign this value according to the speed of the bridge. The slower the media, the higher the cost.			
	Note: Set the value to 0 to use the auto path cost you set in the SWIIC HING > Spanning The Protocol > Spanning The Setup screen (see Auto Path-cost Mode).			
Tree	Select which STP tree configuration this port should participate in.			
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.			
Cancel	Click Cancel to begin configuring this screen afresh.			

Table 187 SWITCHING > Spanning Tree Protocol > MRSTP (continued)

## 53.8 Multiple Spanning Tree Protocol Status

Click SWIIC HING > Spanning Tire Protocol > Spanning Tire Protocol Status in the navigation panel to display the status screen as shown next.

Note: This screen is only available after you activate MSTP on the Switch.

Figure 254 SWITCHING > Spanning Tree Protocol > Spanning Tree Protocol Status: MSTP

Spanning Tree Protocol:	MSTP				
CSI					
	Fool Bridge	Our Bridge			
Gridge ID	ener bussessbeete	6666 (r. 16666), (r. 1666)			
Helio fime (seconds)	2	2			
Max Age (seconds)	50	20			
Forwarding Delay (seconds)	15	15			
Cost to Bridge	2	U			
Pat ID	0#2000	16 0000			
Configuration Name	too shekele oo sa kele				
Reveron Nomber	9				
Configuration Digest	A27881774502550104963621106A6260562				
Topology Chonged Times	D				
Thre Since Lost Change	0.1140				
Instance					
Indonce	VIAN				
0	1-4024				
M911 <u> </u>					
	Regional Bool	Our Bridge			
Bridge ID	2000-2020000000	3001 0000000000			
Internal Cost	2	U			
Pat D	000000	(6,0000			
	a sala Designated Designated Par				
Port Port Marte Po	d Sale Dialgranic Designation for Bridge ID ID	Besignment Cost Root Sured State			

Table 188	SWITCHING >	> Spannina Tree Protocol	I > Spanning Tree Protocol Status: MSTP
101010 100	0		

IABEL	DESC RIPIIO N
CST	
This section describe	es the Common Spanning Tree settings.
Bridge	<b>Root Bridge</b> refers to the base of the spanning tree (the root bridge). <b>Our Bridge</b> is this switch. This Switch may also be the root bridge.
Bridge ID	This is the unique identifier for this bridge, consisting of bridge priority plus MAC address. This ID is the same for <b>Root Bridge</b> and <b>Our Bridge</b> if the Switch is the root switch.
Hello Time (seconds)	This is the time interval (in seconds) at which the root switch transmits a configuration message. The root bridge determines <b>He Ilo Time</b> , <b>Max Age</b> and <b>Forwarding Delay</b> .
Max Age (seconds)	This is the maximum time (in seconds) the Switch can wait without receiving a configuration message before attempting to reconfigure.
Forwarding Delay (seconds)	This is the time (in seconds) the root switch will wait before changing states (that is, listening to learning to forwarding).
Cost to Bridge	This is the path cost from the root port on this Switch to the root switch.
Port ID	This is the priority and number of the port on the Switch through which this Switch must communicate with the root of the Spanning Tree.
Configuration Name	This field displays the configuration name for this MST region.
Revision Number	This field displays the revision number for this MST region.
Configuration	A configuration digest is generated from the VLAN-MSTI mapping information.
Digest	This field displays the 16-octet signature that is included in an MSTP BPDU. This field displays the digest when MSTP is activated on the system.
Topology Changed Times	This is the number of times the spanning tree has been reconfigured.
Time Since Last Change	This is the time since the spanning tree was last reconfigured.
nstance These fields display the MSTI to VLAN mapping. In other words, which VLANs run on e spanning tree instance.	
Instance	·
Instance	This field displays the MSTI ID.
VLAN	This field displays which VLANs are mapped to an MSTI.
MSTI	
MSTI	Select the MST instance settings you want to view.
	<b>Regional Root</b> refers to the base of the MST instance. <b>Our Bridge</b> is this switch. This Switch may also be the root bridge.
Bridge ID	This is the unique identifier for this bridge, consisting of bridge priority plus MAC address. This ID is the same for <b>Regional Root</b> and <b>Our Bridge</b> if the Switch is the root switch.
Internal Cost	This is the path cost from the root port in this MST instance to the regional root switch.
Port ID	This is the priority and number of the port on the Switch through which this Switch must communicate with the root of the MST instance.
Port	This field displays the number of the port on the Switch.

IABEL	DESC RIPIIO N				
Port State	This field displays the port state in STP.				
	<ul> <li>DISCARDING – The port does not forward or process received frames or learn MAC addresses, but still listens for BPDUs.</li> </ul>				
	• <b>LEARNING</b> – The port learns MAC addresses and processes BPDUs, but does not forward frames yet.				
	• FORWARDING – The port is operating normally. It learns MAC addresses, processes BPDUs and forwards received frames.				
Port Role	This field displays the role of the port in STP.				
	<ul> <li>Root – A forwarding port on a non-root bridge, which has the lowest path cost and is the best port from the non-root bridge to the root bridge. A root bridge does not have a root port.</li> </ul>				
	<ul> <li>Designated – A forwarding port on the designated bridge for each connected LAN segment. A designated bridge has the lowest path cost to the root bridge among the bridges connected to the LAN segment. All the ports on a root bridge (root switch) are designated ports.</li> </ul>				
	<ul> <li>Altemate – A blocked port, which has a best alternate path to the root bridge. This path is different from using the root port. The port moves to the forwarding state when the designated port for the LAN segment fails.</li> </ul>				
	<ul> <li>Backup – A blocked port, which has a backup or redundant path to a LAN segment where a designated port is already connected when a switch has two links to the same LAN segment.</li> </ul>				
	• $Disabled$ – Not strictly part of STP. The port can be disabled manually.				
Designated Bridge ID	This field displays the identifier of the designated bridge to which this port belongs when the port is a designated port. Otherwise, it displays the identifier of the designated bridge for the LAN segment to which this port is connected.				
Designated Port ID	This field displays the priority and number of the bridge port (on the designated bridge), through which the designated bridge transmits the stored configuration messages.				
Designated Cost	This field displays the path cost to the LAN segment to which the port is connected when the port is a designated port. Otherwise, it displays the path cost to the root bridge from the designated port for the LAN segment to which this port is connected.				
Root Guard State	This field displays the state of the port on which root guard is enabled.				
	<ul> <li>Root-inconsistent – the Switch receives superior BPDUs on the port and blocks the port.</li> <li>Forwarding – the Switch unblocks and allows the port to forward frames again.</li> </ul>				

Tabla 100	$\sim 2 < 10$ mm m m m m m m m m m m m m m m m m m	anning Trac Drataco	I > Coopping Troo	Protocol Status: MSTP	(continued)
		annina iree Floioca	1 > 3 DOULING LEE		rconnnuear
					1

# 53.9 Configure Multiple Spanning Tree Protocol

To configure MSTP, click SWTIC HING > Spanning The e Protocol > MSTP in the navigation panel to display the screen as shown.

Aulliple Spanning	Tree Protocol MSTP Port Selug	
Bridge		
Adlive	CONC)	
Hele Time	2 seconda	
MAX Age	20 esconds	
Previousing Delay	15 seconda	
Maximum mapi	20	
Configuration Name	bc9931cbc363	
Revolan Normale	Ü.	
	Analy	et
instance		
		O Antrida 🚦 Lineau
initiance	VLAN	Active Port
0	1-4094	-

IABEL	DESC RIPTIO N	
Bridge	·	
Active	Enable the switch button to activate MSTP on the Switch. Disable the switch to disable MSTP on the Switch.	
	Note: You must also activate <b>Multiple Spanning Tree</b> ( <b>MSIP</b> ) in the <b>SWIICHING</b> > <b>Spanning Tree Protocol</b> > <b>Spanning Tree Setup</b> screen to enable MSTP on the Switch.	
Hello Time	This is the time interval in seconds between BPDU (Bridge Protocol Data Units) configuration message generations by the root switch. The allowed range is 1 to 10 seconds.	
Max Age	This is the maximum time (in seconds) a switch can wait without receiving a BPDU before attempting to reconfigure. All switch ports (except for designated ports) should receive BPDUs at regular intervals. Any port that ages out STP information (provided in the last BPDU) becomes the designated port for the attached LAN. If it is a root port, a new root port is selected from among the Switch ports attached to the network. The allowed range is 6 to 40 seconds.	
Forwarding Delay	This is the maximum time (in seconds) a switch will wait before changing states. This delay is required because every switch must receive information about topology changes before it starts to forward frames. In addition, each port needs time to listen for conflicting information that would make it return to a blocking state; otherwise, temporary data loops might result. The allowed range is 4 to 30 seconds. As a general rule: Note: $2 * (Forward Delay - 1) >= Max Age >= 2 * (Hello Time + 1)$	
Maximum hops	Enter the number of hops (between 1 and 255) in an MSTP region before the BPDU is discarded and the port information is aged.	
Configuration Name	Enter a descriptive name (up to 32 printable ASCII characters except [?], [   ], ['], ["], or [, ]) of an MST region.	

Table 189 SWITCHING > Spanning Tree Protocol > MSTP

IABEL	DESC RIPIIO N	
Revision Number	Enter a number to identify a region's configuration. Devices must have the same revision number to belong to the same region.	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Cancel	Click Cancel to begin configuring this screen afresh.	
Instance		
Use this section to c	onfigure MSTI (Multiple Spanning Tree Instance) settings.	
Instance	This field displays the ID of an MST instance.	
VLAN	This field displays the VID (or VID ranges) to which the MST instance is mapped.	
Active Port	This field display the ports configured to participate in the MST instance.	
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.	
Add/Edit	Click Add/Edit to add a new instance or edit a selected one.	
Delete	Click <b>Delete</b> to remove the selected instances.	

Table 189	SWITCHING > Spanning Tree Protocol > MSTP	(continued)
-----------	---	-------------

#### 53.9.1 Add/Edit Multiple Spanning Tree

Click Add/Edit, or select an entry and click Add/Edit in the SWIICHING > Spanning Tire Protocol > MSIP screen to display this screen.

Figure 256	SWITCHING > Spanning	Tree Protocol > I	MSTP > Add/Edit

VI AN (BI		22762 • ]	
fort	Active	Fronty	Fully Cost
¥6			12 11
1	Ξ.	108	2
23		128	2
3	<u><u> </u></u>	i i cose	1
4		129	2
7	Ц.	128	2
0	Ð	122	2
78		122	$\sim$
$\smile$		$\sim$	$\sim \sim \sim$

Table 190	SWITCHING >	Spannina Tree	Protocol > MSTP > Ac	dd/Edit
		spanning nee		

IABEL	DESC RIPTIO N	
Instance	Enter the number you want to use to identify this MST instance on the Switch. The Switch supports instance numbers $0 - 16$ .	
Bridge Priority	Set the priority of the Switch for the specific spanning tree instance. The lower the number, the more likely the Switch will be chosen as the root bridge within the spanning tree instance.	
	Enter priority values between 0 and 61440 in increments of 4096 (thus valid values are 4096, 8192, 12288, 16384, 20480, 24576, 28672, 32768, 36864, 40960, 45056, 49152, 53248, 57344 and 61440).	
VLAN List	Enter the VLAN ID range. You can specify multiple VLAN ID range separated by (no space) comma (,) or hyphen ("-") for a range. For example, enter "1,3,5-7" for VLANs 1, 3, 5, 6, and 7.	
Port	This field displays the port number. * means all ports.	
*	Settings in this row apply to all ports.	
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.	
	Note: Changes in this row are copied to all the ports as soon as you make them.	
Active	Select this check box to add this port to the MST instance.	
Priority	Configure the priority for each port here.	
	Priority decides which port should be disabled when more than one port forms a loop in the Switch. Ports with a higher priority numeric value are disabled first. The allowed range is between 0 and 255 and the default value is 128.	
Path Cost	Path cost is the cost of transmitting a frame on to a LAN through that port. It is recommended to assign this value according to the speed of the bridge. The slower the media, the higher the cost.	
	Note: Set the value to 0 to use the auto path cost you set in the <b>SWIIC HING</b> > <b>Spanning The e Protocol</b> > <b>Spanning The e Setup</b> screen (see Auto Path-cost Mode).	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Clear	Click Clear to clear the fields to the factory defaults.	
Cancel	Click Cancel to not save the configuration you make and return to the last screen.	

# 53.10 Multiple Spanning Tree Protocol Port Setup

Click SWIICHING > Spanning The Protocol > MSIP > MSIP Port Setup to display the screen as shown next.

Auttiple Spannin	g Tree Protocol	MSTP Port Setup
Fort	Edge	Root Guard
1 (M)	<u></u>	CI .
3	10	
2	Ð	0
3		
- W	13	(T)
3	10	
~	11	Ξ.
1	1	
		$\sim\sim\sim$
	~ ~ ~	
	Analy One	

LABEL	DESC RIPIIO N		
Port	This field displays the port number. * means all ports.		
*	Settings in this row apply to all ports.		
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.		
	Note: Changes in this row are copied to all the ports as soon as you make them.		
Edge	Select this check box to configure a port as an edge port when it is directly attached to a computer. An edge port changes its initial STP port state from blocking state to forwarding state immediately without going through listening and learning states right after the port is configured as an edge port or when its link status changes.		
	Note: An edge port becomes a non-edge port as soon as it receives a Bridge Protocol Data Unit (BPDU).		
Root Guard	Select this check box to enable root guard on this port in order to prevent the switches attached to the port from becoming the root bridge.		
	With root guard enabled, a port is blocked when the Switch receives a superior BPDU on it. The Switch allows traffic to pass through this port again when the switch connected to the port stops to send superior BPDUs.		
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.		
Cancel	Click Cancel to begin configuring this screen afresh.		

Tabla 101	C(M/TC) = C(M/TC)	na Tran Dratanal >	MSTP > MSTP Port Setup
	2 MIICHING > 200111	na nee Floiocol 2	


# 53.11 Technical Reference

This section provides technical background information on the topics discussed in this chapter.


### 53.11.1 MSIP Network Example


The following figure shows a network example where two VLANs are configured on the two switches. If the switches are using STP or RSTP, the link for VLAN 2 will be blocked as STP and RSTP allow only one link in the network and block the redundant link.





With MSTP, VLANs 1 and 2 are mapped to different spanning trees in the network. Therefore traffic from the two VLANs travel on different paths. The following figure shows the network example using MSTP.





#### 53.11.2 MSTRegion

An MST region is a logical grouping of multiple network devices that appears as a single device to the rest of the network. Each MSTP-enabled device can only belong to one MST region. When BPDUs enter an MST region, external path cost (of paths outside this region) is increased by one. Internal path cost (of paths within this region) is increased by one when BPDUs traverse the region.

Devices that belong to the same MST region are configured to have the same MSTP configuration identification settings. These include the following parameters:

- Name of the MST region
- Revision level as the unique number for the MST region
- VLAN-to-MST Instance mapping

#### 53.11.3 MSTInstance

An MST Instance (MSTI) is a spanning tree instance. VLANs can be configured to run on a specific MSTI. Each created MSTI is identified by a unique number (known as an MST ID) known internally to a region. Therefore an MSTI does not span across MST regions.

The following figure shows an example where there are two MST regions. Regions 1 and 2 have two spanning tree instances.




Figure 260 MSTIs in Different Regions

#### 53.11.4 Common and Internal Spanning Tree (CIST)

A CIST represents the connectivity of the entire network and it is equivalent to a spanning tree in an STP/ RSTP. The CIST is the default MST instance (MSTID 0). Any VLANs that are not members of an MST instance are members of the CIST. In an MSTP-enabled network, there is only one CIST that runs between MST regions and single spanning tree devices. A network may contain multiple MST regions and other network segments running RSTP.




Figure 261 MSTP and Legacy RSTP Network Example

XGS2220 Series User's Guide

# C HAPTER 54 Static MAC Filtering

## 54.1 Static MAC Filtering Overview

This chapter discusses MAC address port filtering.

Filtering means sifting traffic going through the Switch based on the source and/or destination MAC addresses and VLAN group (ID).

#### 54.1.1 What You Can Do

Use the Static MAC Filtering screen (Section 54.2 on page 362) to create rules for traffic going through the Switch.

## 54.2 Configure a Static MAC Filtering Rule

Use this screen to view and configure rules for traffic going through the Switch. Click SWIICHING > StaticMAC Filtering in the navigation panel to display the screen as shown next.

F	Illering						
						C Add/Edit	📋 Deieta
		Index	Active	Name	MAC Address	V10	Action

IABEL	DESC RIPIIO N		
Index	This field displays the index number of the rule.		
Active	This field displays whether the rule is activated or not.		
Name This field displays the descriptive name for this rule. This is for identification purpose onl			
MAC Address	This field displays the source or destination MAC address with the VLAN identification number to which the MAC address belongs.		
VID This field displays the VLAN group identification number.			
Action	This field displays <b>Discard source</b> , <b>Discard destination</b> , or <b>Discard both</b> depending on what you configured above.		

Table 192 SWITCHING > Static MAC Filtering

IABEL	DESC RIPIIO N			
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.			
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.			
Delete	Click <b>De le te</b> to remove the selected entries.			

Table 192 SWITCHING > Static MAC Filtering (continued)

#### 54.2.1 Add/Edit a Static MAC Filtering Rule

Use this screen to create or edit rules for traffic going through the Switch. Click Add/Edit, or select an entry and click Add/Edit in the SWIICHING > Static MAC Filtering screen to display this screen.



Name	
A stiller.	<ul> <li>Disseri sausto</li> <li>Disseri destination</li> </ul>
0.07 <u>1</u>	
VIT:	

Table 193	SWITCHING > Static MAC Filtering > Add/Edit
-----------	---

DESC RIPTIO N
Enable the switch button to activate your rule. You may temporarily deactivate a rule without deleting it by de-selecting this check box.
Enter a descriptive name (up to 32 printable ASCII characters excluding [?], [ ], ['], ["] or [,]) for this rule. This is for identification only.
Select <b>Disc and source</b> to drop the frames from the source MAC address (specified in the <b>MAC</b> field). The Switch can still send frames to the MAC address.
Select <b>Discard destination</b> to drop the frames to the destination MAC address (specified in the <b>MAC</b> address). The Switch can still receive frames originating from the MAC address.
Select <b>Discard source</b> and <b>Discard destination</b> to block traffic to or from the MAC address specified in the <b>MAC</b> field.
Enter a MAC address in valid MAC address format, that is, six hexadecimal character pairs.
Enter the VLAN group identification number.
Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Click <b>Clear</b> to clear the fields to the factory defaults.
Click Cancel to not save the configuration you make and return to the last screen.

# C HAPTER 55 Static MAC Forwarding

# 55.1 Static MAC Forwarding Overview

This chapter discusses how to configure forwarding rules based on MAC addresses of devices on your network.

Use these screens to configure static MAC address forwarding.

#### 55.1.1 What You Can Do

Use the Static MAC Forwarding screen (Section 55.2 on page 364) to assign static MAC addresses for a port.

## 55.2 Configure Static MAC Forwarding

A static MAC address is an address that has been manually entered in the MAC address table. Static MAC addresses do not age out. When you set up static MAC address rules, you are setting static MAC addresses for a port. This may reduce the need for broadcasting.

Click **SWIIC HING** > **Static MAC Forwarding** in the navigation panel to display the configuration screen as shown.

Figure 264 SWITCHING > Static MAC Forwarding

Static MAC Forwarding						
				🙁 Add/Ed	it	🔮 Delebe
	Indea.	Active	Nome	MAE Address	VID	Port
	1	ON D	Dample	00100050000585.ge	1	17

The following table describes the labels in this screen.

Table 194 SWITCHING > Static MAC Forwarding

LABEL	DESC RIPTIO N		
Index This is the index number of a static MAC address rule.			
Active	This field displays whether this static MAC address forwarding rule is active. You may temporarily deactivate a rule without deleting it.		
Name	This field displays the descriptive name for identification purposes for this static MAC address- forwarding rule.		

XGS2220 Series User's Guide

IABEL	DESC RIPTIO N	
MAC Address This field displays the MAC address that will be forwarded and the VLAN identification nu which the MAC address belongs.		
VID	/ID This field displays the ID number of the VLAN group.	
Port	This field displays the port where the MAC address shown in the next field will be forwarded.	
Select an entry's check box to select a specific entry. Otherwise, select the check box ir heading row to select all entries.		
Add/Edit Click Add/ Edit to add a new rule or edit a selected one.		
Delete Click <b>Delete</b> to remove the selected rules.		

Table 194 SWITCHING > Static MAC Forwarding (continued)

### 55.2.1 Add/Edit Static MAC Forwarding Rules

Click Add/Edit, or select an entry and click Add/Edit in the SWIIC HING > Static MAC Forwarding screen to display this screen.

Figure 265	SWITCHING > Static MAC Forwarding > Add/Edit
------------	--

_			
	Antion	() or	I
	Variat		
	MAC Address		
	412		
	Cot		
	Apply	Older	Concel

IABEL	DESC RIPTIO N
Active	Enable the switch button to activate your rule. You may temporarily deactivate a rule without deleting it by disabling the switch.
Name	Enter a descriptive name for identification purposes for this static MAC address forwarding rule. You can enter up to 32 printable ASCII characters except [?], [ ], ['], ["] or [,].
MAC Address	Enter the MAC address in valid MAC address format, that is, six hexadecimal character pairs.
	Note: Static MAC addresses do NOT age out.
VID	Enter the VLAN identification number.
Port	Enter the port where the MAC address entered in the previous field will be automatically forwarded.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

# C HAPTER 56 VLAN

## 56.1 VLAN Overview

This chapter shows you how to configure 802.1Q tagged and port-based VLANs.

The type of screen you see here depends on the **VIAN Type** you selected in the **SYSTEM** > **Switc h Se tup** screen which is only available in standalone mode. The Switch does not support port-based VLANs in Stacking mode.

#### 56.1.1 What You Can Do

- Use the VIAN Status screen (Section 56.3 on page 369) to view and search all static VLAN groups.
- Use the VIAN Status Details screen (Section 56.3.1 on page 370) to view detailed port settings and status of the static VLAN group.
- Use the Static VIAN Setup screen (Section 56.4 on page 371) to configure a static VLAN for the Switch.
- Use the VIAN Port Setup screen (Section 56.5 on page 373) to configure the static VLAN (IEEE 802.1Q) settings on a port.
- Use the GVRP screen (Section 56.6 on page 375) to enable/disable GVRP on each port.
- Use the **Subnet Based VIAN Setup** screen (Section 56.8 on page 377) to set up VLANs that allow you to group traffic into logical VLANs based on the source IP subnet you specify.
- Use the **Protocol Based VIAN Setup** screen (Section 56.9 on page 378) to set up VLANs that allow you to group traffic into logical VLANs based on the protocol you specify.
- Use the **Voice VIAN Setup** screen (Section 56.11 on page 381) to set up VLANs that allow you to group voice traffic with defined priority and enable the Switch port to carry the voice traffic separately from data traffic to ensure the sound quality does NOT deteriorate.
- Use the MAC Based VIAN Setup screen (Section 56.12 on page 383) to set up VLANs that allow you to group untagged packets into logical VLANs based on the source MAC address of the packet. This eliminates the need to reconfigure the Switch when you change ports. The Switch will forward the packets based on the source MAC address you set up previously.
- Use the **Vendor ID Based VIAN Setup** screen (Section 56.13.1 on page 385) to set up VLANs that allow you to group untagged packets into logical VLANs based on the source MAC address of the packet. You can specify a mask for the MAC address to create a MAC address filter and enter a weight to set the VLAN rule's priority.

#### 56.1.2 What You Need to Know

Read this section to know more about VLAN and how to configure the screens.

366

# 56.2 Introduction to IEEE 802.1Q Tagged VIANs

A tagged VLAN uses an explicit tag (VLAN ID) in the MAC header to identify the VLAN membership of a frame across bridges – they are not confined to the switch on which they were created. The VLANs can be created statically by hand or dynamically through GVRP. The VLAN ID associates a frame with a specific VLAN and provides the information that switches need to process the frame across the network. A tagged frame is 4 bytes longer than an untagged frame and contains 2 bytes of TPID (Tag Protocol Identifier, residing within the type or length field of the Ethernet frame) and 2 bytes of TCI (Tag Control Information, starts after the source address field of the Ethernet frame).

The CFI (Canonical Format Indicator) is a single-bit flag, always set to zero for Ethernet switches. If a frame received at an Ethernet port has a CFI set to 1, then that frame should not be forwarded as it is to an untagged port. The remaining twelve bits define the VLAN ID, giving a possible maximum number of 4096 VLANs. Note that user priority and VLAN ID are independent of each other. A frame with VID (VLAN Identifier) of null (0) is called a priority frame, meaning that only the priority level is significant and the default VID of the ingress port is given as the VID of the frame. Of the 4096 possible VIDs, a VID of 0 is used to identify priority frames and value 4095 (FFF) is reserved, so the maximum possible VLAN configurations are 4094.

TPID	User Priority	CFI	VLAN ID
16 Bits	3 Bits	1 Bit	12 Bits

#### Forwarding Tagged and Untagged Frames

Each port on the Switch is capable of passing tagged or untagged frames. To forward a frame from an 802.1Q VLAN-aware switch to an 802.1Q VLAN-unaware switch, the Switch first decides where to forward the frame and then strips off the VLAN tag. To forward a frame from an 802.1Q VLAN-unaware switch to an 802.1Q VLAN-aware switch, the Switch first decides where to forward the frame, and then inserts a VLAN tag reflecting the ingress port's default VID. The default PVID is VLAN 1 for all ports, but this can be changed.

A broadcast frame (or a multicast frame for a multicast group that is known by the system) is duplicated only on ports that are members of the VID (except the ingress port itself), thus confining the broadcast to a specific domain.

#### 56.2.0.1 Automatic VIAN Registration

GARP and GVRP are the protocols used to automatically register VLAN membership across switches.

#### GARP

GARP (Generic Attribute Registration Protocol) allows network switches to register and de-register attribute values with other GARP participants within a bridged LAN. GARP is a protocol that provides a generic mechanism for protocols that serve a more specific application, for example, GVRP.

#### GARP Timers

Switches join VLANs by making a declaration. A declaration is made by issuing a Join message using GARP. Declarations are withdrawn by issuing a Leave message. A Leave All message terminates all registrations. GARP timers set declaration timeout values.

#### GVRP

GVRP (GARP VLAN Registration Protocol) is a registration protocol that defines a way for switches to register necessary VLAN members on ports across the network. Enable this function to permit VLAN groups beyond the local Switch.

Please refer to the following table for common IEEE 802.1Q VLAN terminology.


VIAN PARAMEIER	TERM	DESC RIPIIO N						
VLAN Type	Permanent VLAN	This is a static VLAN created manually.						
	Dynamic VLAN	This is a VLAN configured by a GVRP registration or de-registration process.						
VLAN Administrative	Registration Fixed	Fixed registration ports are permanent VLAN members.						
Control	Registration Forbidden	Ports with registration forbidden are forbidden to join the specified VLAN.						
	Normal Registration	Ports dynamically join a VLAN using GVRP.						
VLAN Tag Control	Tagged	Ports belonging to the specified VLAN tag all outgoing frames transmitted.						
	Untagged	Ports belonging to the specified VLAN do not tag all outgoing frames transmitted.						
VLAN Port	Port VID	This is the VLAN ID assigned to untagged frames that this port received.						
	Acceptable Frame Type	You may choose to accept both tagged and untagged incoming frames, just tagged incoming frames or just untagged incoming frames on a port.						
	Ingress filtering	If set, the Switch discards incoming frames for VLANs that do not have this port as a member.						

Table 196 IEEE 802.1Q VLAN Terminology

#### 56.2.0.2 Port VIAN Trunking

Enable **VIAN Trunking** on a port to allow frames belonging to unknown VLAN groups to pass through that port. This is useful if you want to set up VLAN groups on end devices without having to configure the same VLAN groups on intermediary devices.

Refer to the following figure. Suppose you want to create VLAN groups 1 and 2 (V1 and V2) on devices A and B. Without **VIAN Trunking**, you must configure VLAN groups 1 and 2 on all intermediary switches C, D and E; otherwise they will drop frames with unknown VLAN group tags. However, with **VIAN Trunking** enabled on ports in each intermediary switch you only need to create VLAN groups in the end devices (A and B). C, D and E automatically allow frames with VLAN group tags 1 and 2 (VLAN groups that are unknown to those switches) to pass through their VLAN trunking ports.



368

#### 56.2.0.3 Select the VIAN Type

Select a VLAN type in the SYSTEM > Switch Setup screen.

Figure 267	SYSTEM > Switch Setup: Select VLAN Type
------------	---

Switch Setup		
(VLAN Type	<b>O</b> 802.10	<ul> <li>Port Based)</li> </ul>
Mage Control Protocol homoporency	() (FF	
MAC Address learning		
Aging Time	900 ·	eccentik
Att Aging Time		
Aging line	300 v	econdik
GAR Timer		
Join fimor	200 n	al live coornada
Leove Umer	N00 N	al iso conds
Loavo All Timer	10000 n	al becometa
Analy	Concel	

#### 802.1Q Static VIAN

Make sure 802.1Q is selected in the SYSTEM > Switch Setup screen.

Use a static VLAN to decide whether an incoming frame on a port should be

- sent to a VLAN group as normal depending on its VLAN tag.
- sent to a group whether it has a VLAN tag or not.
- blocked from a VLAN group regardless of its VLAN tag.

You can also tag all outgoing frames (that were previously untagged) from a port with the specified VID.

## 56.3 VIAN Status

Use this screen to view and search all static VLAN groups. Click **SWIICHING** > **VIAN** > **VIAN** Status from the navigation panel to display the screen as shown next.

SWITCHING > VLA	N > VLAN Status
	WITCHING > VLA

VDAN Stolos						
VIAN2 calify VI2		SHO	ch			
The Number of V	LANES					
						$E \in rage(\underline{1-}of) \in o$
index.	VID	Harne	Teorpy & Post	Listing gov! Deci	Report True	United Sec.
L	1	I.		1 M	2.5871	21 in .
2	100	2042100			0.00.00	sic fic
						$0 \leq 2 \exp(1 -    \cos 1    > 2)$

The following table describes the labels in this screen.

LABEL	DESC RIPTIO N						
VLAN Search by VID	Enter (an) existing VLAN ID numbers (use a comma (,) to separate individual VLANs or a hyphen (-) to indicate a range of VLANs. For example, "3,4" or "3-9") and click <b>Search</b> to display only the specified VLANs in the list below.						
	Leave this field blank and click $\mathbf{Searh}$ to display all VLANs configured on the Switch.						
The Number of VLAN	This is the number of VLANs configured on the Switch.						
The Number of	This is the number of VLANs that match the searching criteria and display in the list below.						
Search Results	This field displays only when you use the $\mathbf{Searc}\mathbf{h}$ button to look for certain VLANs.						
Index	This is the VLAN index number. Click an index number to view more VLAN details.						
VID	This is the VLAN identification number that was configured in the corresponding VLAN configuration screen.						
Name	This fields shows the descriptive name of the VLAN.						
Tagged Port	This field shows the tagged ports that are participating in the VLAN.						
Untagged Port	This field shows the untagged ports that are participating in the VLAN.						
Elapsed Time	This field shows how long it has been since a normal VLAN was registered or a static VLAN was set up.						
Status	This field shows how this VLAN was added to the Switch.						
	<ul> <li>Dynamic – using GVRP</li> <li>Static – added as a permanent VLAN</li> </ul>						

Table 197 SWITCHING > VLAN > VLAN Status

## 56.3.1 VLAN De tails

Use this screen to view detailed port settings and status of the static VLAN group. Click an index number in the **VLAN Status** screen to display VLAN details.

```
Figure 269 SWITCHING > VLAN > VLAN Status > VLAN Status Details
```

VLAF	( blu	lua -																								
<u>VI</u> 2	el So	715	s V	1.AN	Short	с Эн	de a																			
×15					I	3.																				
$ \mathbf{f}  = -$	a a Ch	1.01			0	en de la	с. —																			
viat.	8				Ŷ	tafic.																				
fort	Num	iber																								
																						1 H I	i ka p	p e l	11.	99) 99
<i>P</i> .	4	$\mathbf{A}_{i}$	$\mathcal{A}_{1}$	10	${\bf U}^{\rm p}$	14	$\mathbf{D}_{i}$	<b>15</b>	80	10	84	66	-06	$\lambda \mathbf{i}$	10	3.2	$2\lambda$	30	di î	$_{\rm de}$	- 22	100	18	$\mathcal{I} \mathfrak{A}$	85	8.2
1	а		$\tau$	т	11	12	10	17	$\mathbf{T}$	21	23	24	27	27	32	3.0	3.0	37	37	41	-12	-18	47	48	41	40

The following table describes the labels in this screen.

IABEL	DESC RIPIIO N
VID	This is the VLAN identification number that was configured in the corresponding VLAN configuration screen.
Elapsed Time	This field shows how long it has been since a normal VLAN was registered or a static VLAN was set up.
Status	<ul> <li>This field shows how this VLAN was added to the Switch.</li> <li>Dynamic: using GVRP</li> <li>Static: added as a permanent entry</li> </ul>
Port Number	This section displays the ports that are participating in a VLAN. A tagged port is marked as $\mathbf{T}$ an untagged port is marked as $\mathbf{U}$ and ports not participating in a VLAN are marked as "-".

Table 198 SWITCHING > VLAN > VLAN Status > VLAN Status Details

# 56.4 Configure a Static VIAN

Use this screen to view and configure a static VLAN for the Switch. Click SWIICHING > VIAN > VIAN Setup > Static VIAN to display the screen as shown next.

Figure 270 SWITCHING > VLAN > VLAN Setup > Static VLAN

Static VLAN	VLAN	Port Setup	GVRP	
				🗘 Add/Sdit. 🍵 Delete
	VD	Active	Name	
	1	OH 🔰	1	
	2	ON	2	
	З	ON D	Э	
	100	UN	VLANI00	

The following table describes the related labels in this screen.

IABEL	DESC RIPIIO N
VID	This field displays the ID number of the VLAN group.
Active	This field indicates whether the VLAN settings are enabled or disabled.
Name	This field displays the descriptive name for this VLAN group.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to add a new static VLAN or edit a selected one.
Delete	Click <b>Delete</b> to remove the selected static VLAN.

Table 199	SWITCHING > VLAN	VIAN Setun	> Static VI AN

#### 56.4.1 Add/Edit a Static VLAN

Use this screen to configure a static VLAN for the Switch. Click Add/Edit, or select an entry and click Add/Edit in the SWIICHING > VIAN > VIAN Setup > Static VIAN screen to display this screen.

1271N		-		
4903	00010			
Fort		Control		lojging
1		Marriel W		🛤 In Targeria
1	(Onerma)	C Ford	Chemindee	🛛 in 1099710
2 < 1	O Hearter	Otwood	Diretiday:	🖬 tetogeng
à –	Othenize	Of red 1	Cristonder	📓 te tegy eg
4	OHeme	C freed	() Torbutden	🔯 Triface na
5.	Oriema	D Flowel	C () Someticen	🔯 te Tabaina
Α.	<b>O</b> riental	Dead	() estimation	📓 11 10 39 10
0	Otherse:	Churd	Oncerver	🗱 tetyying
÷.	Otterre	Of and	() Natalades	📓 fellegeng
4	Ø Hama	Total .	Tetet	E In Descrie
070	Qramit			Distanting and
			1. Sec. 1. Sec. 1.	

Figure 271 SWITCHING > VLAN > VLAN Setup > Static VLAN > Add/Edit

Table 200 SWITCHING > VLAN > VLAN Setup > Static VLAN > Add/Edit

LABEL	DESC RIPTIO N
Active	Enable the switch button to activate the VLAN settings.
Name	Enter a descriptive name for the VLAN group for identification purposes. This name consists of up to 64 printable ASCII characters. The string should not contain [?], [   ], [ ' ], [ "] or [,].

IABEL	DESC RIPTIO N
VLAN Group ID	Enter the VLAN ID for this static entry; the valid range is between 1 and 4094.
	Note: Do NOT add a VLAN ID that has been used in the <b>SWIIC HING</b> > <b>VIAN</b> > <b>Voice</b> <b>VIAN Setup</b> .
Port	The port number identifies the port you are configuring.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
Control	Select <b>Nomal</b> for the port to dynamically join this VLAN group using GVRP. This is the default selection.
	Select $\mathbf{Fixed}$ for the port to be a permanent member of this VLAN group.
	Select Forbidden if you want to prohibit the port from joining this VLAN group.
Tagging	Select <b>Tx Tagging</b> if you want the port to tag all outgoing frames transmitted with this VLAN Group ID.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

#### Table 200 SWITCHING > VLAN > VLAN Setup > Static VLAN > Add/Edit (continued)

# 56.5 VLAN Port Setup

Use this screen to configure the static VLAN (IEEE 802.1Q) settings on a port. Click **SWIICHING** > **VIAN** > **VIAN** Setup > VIAN Port Setup to display the screen as shown.

kalie V	LAN V	LAN Fort Selup	GVRP			
Pod	ingrais Chect	9V0	Abcept Frome		VLAN Trunking	Isolation
75	- P.		Al	Y	(E)	а.
-		1	41	<u> </u>	T1	.01
4	13	1	AL	U		
10	-ti (	T	24	<u> </u>	id l	
30	Π.	E	7.1	÷	(D)	<u> </u>
<b>8</b> 2	<b>.</b>	1	(AT)	Υ.		
÷.	- 73	- 1.	74	¥.,	13	- C
1		ī	<u>Ai</u>	~		
				$\sim$		$\sim$
		- Ap	phy 60	entre .		

Figure 272 SWITCHING > VLAN > VLAN Setup > VLAN Port Setup

Table 201	SWITCHING >	VIAN >	VI AN Setup >	VLAN Port Setup

LABEL	DESC RIPTIO N
Port	This field displays the port number.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
Ingress Check	If this check box is selected, the Switch discards incoming frames on a port for VLANs that do not include this port in its member set.
	Clear this check box to disable ingress filtering.
PVID	A PVID (Port VLAN ID) is a tag that adds to incoming untagged frames received on a port so that the frames are forwarded to the VLAN group that the tag defines.
	Enter a number between 1 and 4094 as the port VLAN ID.
Acceptable	Specify the type of frames allowed on a port. Choices are All, Tag Only and Untag Only.
Frame Type	Select All from the drop-down list box to accept all untagged or tagged frames on this port. This is the default setting.
	Select <b>Tag Only</b> to accept only tagged frames on this port. All untagged frames will be dropped.
	Select <b>Untag Only</b> to accept only untagged frames on this port. All tagged frames will be dropped.
VLAN Trunking	Enable <b>VIAN Thunking</b> on ports connected to other switches or routers (but not ports directly connected to end users) to allow frames belonging to unknown VLAN groups to pass through the Switch.
Isolation	Select this to allows this port to communicate only with the CPU management port and the ports on which the isolation feature is NOT enabled.

IABEL	DESC RIPTIO N
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 201 SWITCHING > VLAN > VLAN Setup > VLAN Port Setup (continued)

## 56.6 Configure GVRP

Use this screen to configure GVRP settings on a port. Click **SWIICHING** > **VIAN** > **VIAN** Setup > GVRP to display the screen as shown.

Figure 273	SWITCHING > VLAN > VLAN Setup > GVRP	
------------	--------------------------------------	--

Stotic VLAN	VLAN Port Setup GVRP
CVR <sup>2</sup>	(CF)
Peril	CVIP
	<b>D</b>
	<b>D</b>
24	
	0
-1.0 <sup>6</sup> i	E)
5	D
1	<b>EI</b>
$\sim$	~~~~~
18:13)	
	Apple Carve

1006202 $30010100$ $20100$ $20100$ $2000$ $2000$	Table 202	SWITCHING > VLAN > VLAN Setup > GVRP
--	-----------	--------------------------------------

IABEL	DESC RIPTIO N
GVRP	GVRP (GARP VLAN Registration Protocol) is a registration protocol that defines a way for switches to register necessary VLAN members on ports across the network.
	Enable the switch button to permit VLAN groups beyond the local Switch.
Port	This field displays the port number.
*	Settings in this row apply to all ports. Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis. Note: Changes in this row are copied to all the ports as soon as you make them.
GVRP	Select this check box to allow GVRP on this port.

LABEL	DESC RIPTIO N
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 202 SWITCHING > VLAN > VLAN Setup > GVRP (continued)

# 56.7 Subnet Based VLANs

Subnet based VLANs allow you to group traffic into logical VLANs based on the source IP subnet you specify. When a frame is received on a port, the Switch checks if a tag is added already and the IP subnet it came from. The untagged packets from the same IP subnet are then placed in the same subnet based VLAN. One advantage of using subnet based VLANs is that priority can be assigned to traffic from the same IP subnet.

Note: Subnet based VLAN applies to un-tagged packets and is applicable only when you use IEEE 802.1Q tagged VLAN.

For example, an ISP (Internet Services Provider) may divide different types of services it provides to customers into different IP subnets. Traffic for voice services is designated for IP subnet 172.16.1.0/24, video for 192.168.1.0/24 and data for 10.1.1.0/24. The Switch can then be configured to group incoming traffic based on the source IP subnet of incoming frames.

You configure a subnet based VLAN with priority 6 and VID of 100 for traffic received from IP subnet 172.16.1.0/24 (voice services). You also have a subnet based VLAN with priority 5 and VID of 200 for traffic received from IP subnet 192.168.1.0/24 (video services). Lastly, you configure VLAN with priority 3 and VID of 300 for traffic received from IP subnet 10.1.1.0/24 (data services). All untagged incoming frames will be classified based on their source IP subnet and prioritized accordingly. That is video services receive the highest priority and data the lowest.




Figure 274 Subnet Based VLAN Application Example

# 56.8 Configuring Subnet Based VIAN

Click the SWIICHING > VIAN > Subnet Based VIAN Setup link in the navigation panel to display the configuration screen as shown.

Figure 275 SWITCHING > VLAN > Subnet Based VLAN Setup

obmit Succid M	an:				
a he	-				
NOT IT IN COMM					
		late -	Termi		
				0-0.4	

The following table describes the labels in this screen.

IABEL	DESC RIPTIO N
Active	Enable the switch button to activate this subnet based VLANs on the Switch.
DHCP-VLAN Override	When DHCP snooping is enabled DHCP clients can renew their IP address through the DHCP VLAN or through another DHCP server on the subnet based VLAN.
	Enable the switch button to force the DHCP clients in this IP subnet to obtain their IP addresses through the DHCP VLAN.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.
Index	This is the index number identifying this subnet based VLAN.
Active	This field shows whether the subnet based VLAN is active or not.
Name	This field shows the name the subnet based VLAN.
IP	This field shows the IP address of the subnet for this subnet based VLAN.
Mask-Bits	This field shows the subnet mask in bit number format for this subnet based VLAN.
VID	This field shows the VLAN ID of the frames which belong to this subnet based VLAN.
Priority	This field shows the priority which is assigned to frames belonging to this subnet based VLAN.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.
Delete	Click <b>De le te</b> to remove the selected entry.

Table 203 SWITCHING > VLAN > Subnet Based VLAN Setup

## 56.8.1 Add/Edit Subnet Based VIAN

Click Add/Edit, or select an entry and click Add/Edit in the SWIICHING > VIAN > Subnet Based VIAN Setup screen to display this screen. Figure 276 SWITCHING > VLAN > Subnet Based VLAN Setup > Add/Edit

Active	() (ME)	
Nume		-
17		_
Mask-Silv		
VLAN		
Educity	<u>∩</u> ~	
App dy	- Chan - Canad	

The following table describes the labels in this screen.

LABEL	DESC RIPIIO N
Active	Enable the switch button to activate the IP subnet VLAN you are creating or editing.
Name	Enter up to 32 alphanumeric characters to identify this subnet based VLAN. The string should not contain [?], [   ], [ ' ], [ "] or [, ].
IP	Enter the IP address of the subnet for which you want to configure this subnet based VLAN.
Mask-Bits	Enter the bit number of the subnet mask. To find the bit number, convert the subnet mask to binary format and add all the 1's together. Take "255.255.255.0" for example. 255 converts to eight 1s in binary. There are three 255s, so add three eights together and you get the bit number (24).
VID	Enter the ID of a VLAN with which the untagged frames from the IP subnet specified in this subnet based VLAN are tagged. This must be an existing VLAN which you defined in the <b>SWIICHING &gt; VLAN &gt; VLAN Se tup &gt; Sta tic VLAN</b> screen.
Priority	Select the priority level that the Switch assigns to frames belonging to this VLAN.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

Table 204 SWITCHING > VLAN > Subnet Based VLAN Setup > Add/Edit


# 56.9 Protocol Based VIANs


Protocol based VLANs allow you to group traffic into logical VLANs based on the protocol you specify. When an upstream frame is received on a port (configured for a protocol based VLAN), the Switch checks if a tag is added already and its protocol. The untagged packets of the same protocol are then placed in the same protocol based VLAN. One advantage of using protocol based VLANs is that priority can be assigned to traffic of the same protocol.

Note: Protocol-based VLAN applies to un-tagged packets and is applicable only when you use IEEE 802.1Q tagged VLAN.

For example, port 1, 2, 3 and 4 belong to static VLAN 100, and port 4, 5, 6, 7 belong to static VLAN 120. You configure a protocol based VLAN A with priority 3 for ARP traffic received on port 1, 2 and 3. You also have a protocol based VLAN B with priority 2 for Apple Talk traffic received on port 6 and 7. All

upstream ARP traffic from port 1, 2 and 3 will be grouped together, and all upstream Apple Talk traffic from port 6 and 7 will be in another group and have higher priority than ARP traffic, when they go through the uplink port to a backbone switch C.





## 56.10 Configuring Protocol Based VIAN

Click the SWIIC HING > VIAN > Protocol Based VIAN Setup link in the navigation panel to display the configuration screen as shown.

Figure 278 SWITCHING > VLAN > Protocol Based VLAN Setup

Prolocol Royed VLA	N					
					dyn dd	Talata 🕈
lindex.	Active	Pvri	Nume	kine ne Hype	Y D2	Privatly

IABEL	DESC RIPIIO N
Index	This is the index number identifying this protocol based VLAN. Click any of these numbers to edit an existing protocol based VLAN.
Active	This field shows whether the protocol based VLAN is active or not.
Port	This field shows which port belongs to this protocol based VLAN.
Name	This field shows the name of the protocol based VLAN.
Ethernet-type	This field shows which Ethernet protocol is part of this protocol based VLAN.
VID	This field shows the VLAN ID of the port.
Priority	This field shows the priority which is assigned to frames belonging to this protocol based VLAN.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.
Delete	Click <b>Delete</b> to remove the selected entry.

Table 205 SWITCHING > VLAN > Protocol Based VLAN Setup

#### 56.10.1 Add/Edit a Protocol Based VIAN

Click Add/Edit, or select an entry and click Add/Edit in the SWIIC HING > VIAN > Protocol Based VIAN Setup screen to display this configuration screen.

Active -	() ort
(Polt)	
Source -	
Efforted type	O 10
	C Other (Fixed
9124N	
nadiy.	1966
	6500
EXP	N Charles Courses

Figure 279 SWITCHING > VLAN > Protocol Based VLAN Setup > Add/Edit

The following table describes the labels in this screen.

LABEL	DESC RIPTIO N
Active	Enable the switch button to activate this protocol based VLAN.
Port	Type a port to be included in this protocol based VLAN.
	This port must belong to a static VLAN in order to participate in a protocol based VLAN.
Name	Enter up to 32 alphanumeric characters to identify this protocol based VLAN. The string should not contain [?], [ ], ['], ["] or [, ].
Ethernet-type	Use the drop down list box to select a predefined protocol to be included in this protocol based VLAN or select <b>0 the r</b> and type the protocol number in hexadecimal notation. For example the IP protocol in hexadecimal notation is 0800, and Novell IPX protocol is 8137.
	Note: Protocols in the hexadecimal number range of 0x0000 to 0x05ff are not allowed to be used for protocol based VLANs.
VID	Enter the ID of a VLAN to which the port belongs. This must be an existing VLAN which you defined in the SWIICHING > VIAN > VIAN Se tup > Static VIAN screen.
Priority	Select the priority level that the Switch will assign to frames belonging to this VLAN.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.


#### 56.10.1.1 Create an IP-based VIAN Example

This example shows you how to create an IP VLAN which includes ports 1, 4 and 8. Follow these steps using the screen below:

- **1** Activate this protocol based VLAN.
- 2 Type the port number you want to include in this protocol based VLAN. Type 1.

- **3** Give this protocol-based VLAN a descriptive name. Type **IP-VIAN**.
- 4 Select the protocol. Leave the default value IP.
- 5 Type the VLAN ID of an existing VLAN. In our example we already created a static VLAN with an ID of 5. Type 5.
- 6 Leave the priority set to 0 and click Apply.

Figure 280 Protocol Based VLAN Configuration Example



To add more ports to this protocol based VLAN.

- 1 Click the index number of the protocol based VLAN entry. Click 1.
- 2 Change the value in the **Port** field to the next port you want to add.
- 3 Click Apply.

## 56.11 Voice VIAN

Voice VLAN is a VLAN that is specifically allocated for voice traffic. It ensures that the sound quality of an IP phone is preserved from deteriorating when the data traffic on the Switch ports is high. It groups the voice traffic with defined priority into an assigned VLAN which enables the separation of voice and data traffic coming onto the Switch port.

The Switch can determine whether a received packet is

- an untagged voice packet when the incoming port is a fixed port for voice VLAN.
- a tagged voice packet when the incoming port and VLAN tag belongs to a voice VLAN.

It then checks the source packet's MAC address against an OUI list. If a match is found, the packet is considered as a voice packet.

You can set priority level to the Voice VLAN and add MAC address of IP phones from specific manufacturers by using its ID from the Organizationally Unique Identifiers (OUI).

Click SWIICHING > VIAN > Voice VIAN Setup to display the configuration screen as shown.

Figure 281	SWITCHING > VLAN > Voice VLAN Setup
riguie 201	

Voice VIAN	Selup			
Voice VLAN	Global Setup			
Veloe VLAN Priority	O Disoble			
LINCOLY.	<u>5 v</u>	Apply	Concel	
Voice VLAN	OUI Setup			
				🖸 Add)Edit 🔋 Delete
	in diex	OUI Address	OUI Work	Description

The following table describes the fields in the above screen.

IABEL	DESC RIPTIO N	
Voice VLAN Global S	etup	
Voice VLAN	Click the second radio button if you want to enable the Voice VLAN feature. Type a VLAN ID number in the box next to the radio button that is associated with the Voice VLAN. You also need to create a static VLAN with the same VID in the <b>SWTICHING</b> > <b>VLAN</b> > <b>VLAN Setup</b> > <b>Static VLAN</b> screen, and then connect the IP phone with the specified OUI MAC address to a port that joins the static VLAN.	
	Click <b>Disable</b> radio button if you do not want to enable the Voice VLAN feature.	
Priority	Select the priority level of the voice traffic from 0 to 7. Default setting is 5. The higher the numeric value you assign, the higher the priority for this voice traffic.	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Cancel	Click Cancel to begin configuring this section afresh.	
Voice VLAN OUI Setu	q	
Index	This field displays the index number of the Voice VLAN.	
OUI Address	This field displays the OUI address of the Voice VLAN.	
OUI Mask	This field displays the OUI mask address of the Voice VLAN.	
Description	This field displays the description of the Voice VLAN with OUI address.	
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.	
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.	
Delete	Click <b>Delete</b> to remove the selected entry.	

Table 207	SWITCHING > VLAN > Voice VLAN Setup
-----------	-------------------------------------

## 56.11.1 Add/Edita Voice VIAN

Click Add/Edit, or select an entry and click Add/Edit in the SWIIC HING > VIAN > Voice VIAN Setup screen to display the configuration screen.

Figure 282 SWITCHING > VLAN > Voice VLAN Setup > Add/Edit

O II Addinas	I	I	
D. I.V.ok		1	
Examplen			
	Apply	Clear	Geneel

The following table describes the fields in the above screen.

Table 208 SWITCHING	> VLAN > Voice VLAN Setup > Add	I/Edit
---------------------	---------------------------------	--------

LABEL	DESC RIPTIO N	
OUI Address	Enter the IP phone manufacturer's OUI MAC address. The first 3 bytes is the manufacturer identifier, the last 3 bytes is a unique station ID.	
OUI Mask	Enter the mask for the specified IP phone manufacturer's OUI MAC address to determine which bits a packet's MAC address should match.	
	Enter "f" for each bit of the specified MAC address that the traffic's MAC address should match. Enter "0" for the bits of the matched traffic's MAC address, which can be of any hexadecimal characters. For example, if you set the MAC address to 00:13:49:00:00:00 and the mask to ff:ff:ff:00:00:00, a packet with a MAC address of 00:13:49:12:34:56 matches this criteria.	
Description	Enter a description up to 32 printable ASCII characters except [?], [   ], [ ' ], or ["] for the Voice VLAN device. For example: Siemens.	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Clear	Click <b>Clear</b> to clear the fields to the factory defaults.	
Cancel	Click Cancel to not save the configuration you make and return to the last screen.	

## 56.12 MAC Based VIAN

The MAC-based VLAN feature assigns incoming untagged packets to a VLAN and classifies the traffic based on the source MAC address of the packet. When untagged packets arrive at the Switch, the source MAC address of the packet is looked up in a MAC to VLAN mapping table. If an entry is found, the corresponding VLAN ID is assigned to the packet. The assigned VLAN ID is verified against the VLAN table. If the VLAN is valid, ingress processing on the packet continues; otherwise, the packet is dropped.

This feature allows users to change ports without having to reconfigure the VLAN. You can assign priority to the MAC-based VLAN and define a MAC to VLAN mapping table by entering a specified source MAC address in the MAC-based VLAN setup screen. You can also delete a MAC-based VLAN entry in the same screen.

Click SWIICHING > VIAN > MAC Based VIAN Setup to see the following screen.

Figure 283	SWITCHING > VLAN > MAC Based VLAN Setup
rigure 283	SWITCHING > VLAN > MAC BUSED VLAN SETUP

NAC fused VIAN					
				🙄 Aris Se	a Maria 👋 Danis da s
	Indix	NO INF	www.cr.weddiaeco	710	sticity

XGS2220 Series User's Guide

The following table describes the fields in the above screen.

IABEL	DESC RIPTIO N
Index	This field displays the index number of the MAC-based VLAN entry.
Name	This field displays the name of the MAC-based VLAN entry.
MAC Address	This field displays the source MAC address that is bind to the MAC-based VLAN entry.
VID	This field displays the VLAN ID of the MAC-based VLAN entry.
Priority	This field displays the priority level which is assigned to frames belonging to this MAC-based VLAN entity.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.
Delete	Click <b>De le te</b> to remove the selected entry.

Table 209	SWITCHING >	VLAN > MAC Based VLAN Setup

### 56.12.1 Add/Edit a MAC Based VIAN

Click Add/Edit, or select an entry and click Add/Edit in the SWIICHING > VIAN > MAC Based VIAN Setup screen to see this screen.

None		
MPC Address		
MD.		
Pricily	$0 \ge 1$	
Apply	Clear	Cancel

The following table describes the fields in the above screen.

LABEL	DESC RIPTIO N
Name	Enter a name up to 32 alphanumeric characters except [?], [ ], ['], ["] or [,] for the MAC-based VLAN entry.
MAC Address	Enter a MAC address that is bind to the MAC-based VLAN entry. This is the source MAC address of the data packet that is looked up when untagged packets arrive at the Switch.
VID	Enter an ID (from 1 to 4094) for the VLAN that is associated with the MAC-based VLAN entry.
Priority	Enter a priority (0 to 7) that the Switch assigns to frames belonging to this VLAN. The higher the numeric value you assign, the higher the priority for this MAC-based VLAN entry.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

# 56.13 Vendor ID Based VIAN

The Vendor ID based VLAN feature assigns incoming untagged packets to a VLAN and classifies the traffic based on the source MAC address of the packet. When untagged packets arrive at the switch, the source MAC address of the packet is looked up in a Vendor ID to VLAN mapping table. If an entry is found, the corresponding VLAN ID is assigned to the packet. The assigned VLAN ID is verified against the VLAN table. If the VLAN is valid, ingress processing on the packet continues; otherwise, the packet is dropped.

This feature allows users to change ports without having to reconfigure the VLAN. You can assign a 802.1p priority to the vendor ID based VLAN and define a vendor ID to VLAN mapping table by entering a specified source MAC address and mask in the vendor ID based VLAN setup screen. You can also delete a vendor ID based VLAN entry in the same screen.

For every vendor ID based VLAN rule you set, you can specify a weight number to define the rule's priority level. As rules are processed one after the other, stating a priority order will let you choose which rule has to be applied first and which second.

Click the SWIIC HING > VIAN > Vendor ID Based VIAN Setup to see the following screen.

Vendor	ID Based '	VLAN					
					🗘 Addû	Beit 🚺	Delete
	index.	Nome	MAC Address	Mask	VIAN	Friedly	Weight

The following table describes the fields in the above screen.

IABEL	DESC RIPTIO N
Index	This field displays the index number of the vendor ID based VLAN entry.
Name	This field displays the name of the vendor ID based VLAN entry.
MAC Address	This field displays the source MAC address that is bind to the vendor ID based VLAN entry.
Mask	This field displays the mask for the source MAC address that is bind to the vendor ID based VLAN entry.
VLAN	This field displays the VLAN ID of the vendor ID based VLAN entry.
Priority	This field displays the priority level which is assigned to frames belonging to this vendor ID based VLAN.
Weight	This field displays the weight of the vendor ID based VLAN entry.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.
Delete	Click <b>Delete</b> to remove the selected entry.

Table 211	I SWITCHING > VLAN > Vendor ID Ba	sed VLAN Setup
-----------	-----------------------------------	----------------

#### 56.13.1 Add/Edita Vendor ID Based VIAN

Click Add/Edit, or select an entry and click Add/Edit in the SWIICHING > VIAN > Vendor ID Based VIAN Setup to see this screen.




Figure 286 SWITCHING > VLAN > Vendor ID Based VLAN Setup > Add/Edit

The following table describes the fields in the above screen.

Table 212	SWITCHING	> VLAN >	Vendor II	D Based '	VLAN Setup >	• Add/Edit	
							_

LABEL	DESC RIPTIO N
Name	Enter a name up to 32 alphanumeric characters except [?], [ ], ['], or ["] for the vendor ID based VLAN entry.
MAC Address	Enter a MAC address that is bind to the vendor ID-based VLAN entry. This is the source MAC address of the data packet that is looked up when untagged packets arrive at the Switch.
Mask	Enter the mask for the specified source MAC address to determine which bits a packet's MAC address should match.
	Enter "f" for each bit of the specified MAC address that the traffic's MAC address should match. Enter "0" for the bits of the matched traffic's MAC address, which can be of any hexadecimal characters. For example, if you set the MAC address to 00:13:49:00:00:00 and the mask to ff:ff:ff:00:00:00, a packet with a MAC address of 00:13:49:12:34:56 matches this criteria.
VID	Enter an ID (from 1 to 4094) for the VLAN that is associated with the vendor ID based VLAN entry.
Priority	Select the priority level that the Switch assigns to frames belonging to this VLAN. The higher the numeric value you assign, the higher the priority for this vendor ID based VLAN entry.
Weight	Enter a number between 0 and 255 to specify the rule's weight. This is to decide the priority in which the rule is applied. The higher the number, the higher the rule's priority.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click <b>Clear</b> to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

## 56.14 Port-Based VIAN Setup

Port-based VLANs are VLANs where the packet forwarding decision is based on the destination MAC address and its associated port.

Port-based VLANs require allowed outgoing ports to be defined for each port. Therefore, if you wish to allow two subscriber ports to talk to each other, for example, between conference rooms in a hotel, you must define the egress (an egress port is an outgoing port, that is, a port through which a data packet leaves) for both ports.

Port-based VLANs are specific only to the Switch on which they were created.

- Note: When you activate port-based VLAN, the Switch uses a default VLAN ID of 1. You cannot change it.
- Note: In screens (such as **SYSTEM** > **IP** Setup and **SWITCHING** > Static MAC Filtering) that require a VID, you must enter 1 as the VID.


The port-based VLAN setup screen is shown next. The **CPU** management port forms a VLAN with all Ethernet ports.

# 56.15 Configure a Port-Based VIAN

Select **Port Based** as the VLAN Type in the **SYSTEM** > **Switch Setup** screen and then click **SWITCHING** > **VLAN** from the navigation panel to display the next screen.

Select either All Connected or Port Isolated from the drop-down list depending on your VLAN and VLAN security requirements. If VLAN members need to communicate directly with each other, then select All Connected. Select Port Isolated if you want to restrict users from communicating directly. Click Apply to save your settings.

The following screen shows users on a port-based, all-connected VLAN configuration.



#### Figure 287 SWITCHING > VLAN > Port Based VLAN Setup (All Connected)

The following screen shows users on a port-based, port-isolated VLAN configuration.




Figure 288 SWITCHING > VLAN: Port Based VLAN Setup (Port Isolation)

Table 213 SWI	[CHING > VLAN > Port Based VLAN Setup
LABEL	DESC RIPTIO N
Setting Wizard	Choose <b>Cument configuration</b> to display the Switch's curren

LABEL	DESC RIPTIO N
Setting Wizard	Choose Cument configuration to display the Switch's current port-based VLAN configuration.
	Choose <b>All connected</b> or <b>Port isolation</b> wizard to quickly set up a port-based VLAN according to the below descriptions.
	All connected means all ports can communicate with each other, that is, there are no virtual LANs. All incoming and outgoing ports are selected. This option is the most flexible but also the least secure.
	<b>Port isolation</b> means that each port can only communicate with the CPU management port and cannot communicate with each other. All incoming ports are selected while only the CPU outgoing port is selected. This option is the most limiting but also the most secure.
	After selecting the setting wizard, you can customize the port settings. Click on the ports to add or delete incoming or outgoing ports. The configuration will be saved only after you click <b>Apply</b> at the bottom of the screen.
Incoming	These are the ingress ports; an ingress port is an incoming port, that is, a port through which a data packet enters. If you wish to allow two subscriber ports to talk to each other, you must define the ingress port for both ports. The numbers in the top row denote the incoming port for the corresponding port listed on the left (its outgoing port). <b>CPU</b> refers to the Switch management port. By default it forms a VLAN with all Ethernet ports. If it does not form a VLAN with a particular port then the Switch cannot be managed from that port.
Outgoing	These are the egress ports; an egress port is an outgoing port, that is, a port through which a data packet leaves. If you wish to allow two subscriber ports to talk to each other, you must define the egress port for both ports. <b>CPU</b> refers to the Switch management port. By default it forms a VLAN with all Ethernet ports. If it does not form a VLAN with a particular port then the Switch cannot be managed from that port.

LABEL	DESC RIPIIO N
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 213 SWITCHING > VLAN > Port Based VLAN Setup (continued)

# C HAPTER 57 VIAN Iso la tion

This chapter shows you how to configure the Switch to prevent communications between ports in a VLAN.

## 57.1 VIAN Isolation Overview

VLAN Isolation allows you to do port isolation within a VLAN in a simple way. You specify which ports in a VLAN is not isolated by adding it to the promiscuous port list. The Switch automatically adds other ports in this VLAN to the isolated port list and blocks traffic between the isolated ports. A promiscuous port can communicate with any port in the same VLAN. An isolated port can communicate with the promiscuous ports only.

Note: You can have up to one VLAN Isolation rule for each VLAN.




Figure 289 VLAN Isolation Example

Note: Make sure you keep at least one port in the promiscuous port list for a VLAN with VLAN Isolation enabled. Otherwise, this VLAN is blocked from the whole network.

# 57.2 Configuring VIAN Isolation

Click SWIIC HING > VIAN Iso la tion in the navigation panel to display the screen as shown.

Figure 290	SWITCHING > VLAN Isolation
------------	----------------------------

8							
VLAN Isol	ation						
				🗢 AA	alean.	📒 Delete	
	Index	Active	Name	VLAN ID	Promis	euous Ports	

The following table describes the labels in this screen.

#### Table 214 SWITCHING > VLAN Isolation

IABEL	DESC RIPTIO N	
Index	This is the index number of the rule.	
Active	his shows whether this rule is activated or not.	
Name	This is the descriptive name for this rule.	
VLAN ID	This is the VLAN to which this rule is applied.	
Promiscuous Ports	ts This shows the ports that can communicate with any ports in the same VLAN.	
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.	
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.	
Delete	Click <b>De le te</b> to remove the selected entries.	

#### 57.2.1 Add/Edit a VIAN Isolation Rule

Click Add/Edit, or select an entry and click Add/Edit in the SWIIC HING > VIAN Isolation screen to display this screen.

### Figure 291 SWITCHING > VLAN Isolation > Add/Edit

Assilve:	<b>()</b> (** )		
home			
VENIE			
Prendetucus Parts			
	Apply	Oleen	Cancel

Table 215	SWITCHING >	VLAN Isolation > Add/Edit	
-----------	-------------	---------------------------	--

LABEL	DESC RIPTIO N	
Active	Enable the switch button to enable VLAN Isolation in a VLAN.	
Name	Enter a descriptive name (up to 32 printable ASCII characters except [?], [   ], ['], ["] or [, ]) for identification purposes.	
VLAN ID	Enter a VLAN ID from 1 to 4094. This is the VLAN to which this rule applies.	
Promiscuous Ports	Enter the number of the ports that can communicate with any ports in the same VLAN. Other ports belonging to this VLAN will be added to the isolation list and can only send and receive traffic from the ports you specify here.	

IABEL	DESC RIPTIO N	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Clear	Click Clear to clear the fields to the factory defaults.	
Cancel	Click <b>Cancel</b> to not save the configuration you make and return to the last screen.	

Table 215 SWITCHING > VLAN Isolation > Add/Edit (continued)

# C HAPTER 58 VIAN Mapping

This chapter shows you how to configure VLAN mapping on the Switch.

# 58.1 VIAN Mapping Overview

With VLAN mapping enabled, the Switch can map the VLAN ID and priority level of packets received from a private network to those used in the service provider's network.

The Switch checks incoming traffic from the switch ports (non-management ports) against the VLAN mapping table first, the MAC learning table and then the VLAN table before forwarding them through the Gigabit uplink port. When VLAN mapping is enabled, the Switch discards the tagged packets that do not match an entry in the VLAN mapping table. If the incoming packets are untagged, the Switch adds a PVID based on the VLAN setting.

Note: You cannot enable VLAN mapping and VLAN stacking at the same time.

#### 58.1.1 VLAN Mapping Example

In the following example figure, packets that carry VLAN ID 12 and are received on port 3 match a preconfigured VLAN mapping rule. The Switch translates the VLAN ID from 12 into 123 before forwarding the packets. Any packets carrying a VLAN tag other than 12 (such as 10) and received on port 3 will be dropped.




Figure 292 VLAN Mapping Example

### 58.1.2 What You Can Do

• Use the VIAN Mapping screen (Section 58.2 on page 394) to enable VLAN mapping on the Switch and

ports.

• Use the **VIAN Mapping Setup** screen (Section 58.3 on page 395) to enable and edit the VLAN mapping rules.

# 58.2 Enable VIAN Mapping

Click SWIICHING > VIAN Mapping in the navigation panel to display the screen as shown.

VLAN Mopping VLAN Mopping Setup 1 1.150 7.2100 Peil Active ŀ, ł. н, 01  $\hat{\boldsymbol{\lambda}}$ ĕ,  $5\hat{z}$  $\hat{t}_{i}^{c}$  ${\mathcal D}_{i}$ Control -Paper

Figure 293 SWITCHING > VLAN Mapping > VLAN Mapping

Table 216 SWITCHING > VLAN Mapping > VLAN Ma	apping
--	--------

IABEL	DESC RIPTIO N
Active	Enable the switch button to enable VLAN mapping on the Switch.
Port	This field displays the port number.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
Active	Select this check box to enable the VLAN mapping feature on this port. Clear this check box to disable the VLAN mapping feature.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

# 58.3 VIAN Mapping Setup

Click the **SWITCHING** > **VIAN Mapping** > **VIAN Mapping Setup** to display the screen as shown. Use this screen to view and configure the VLAN mapping rules.

Figure 294 SWITCHING > VLAN Mapping > VLAN Mapping Setup

VIAN M	apping	VLAN Mop	ping Selup			
					O Ad	d/Edit 📲 Delete
	Index	Active	Name	Port	MD	Translated Priority VID Priority

The following table describes the labels in this screen.

	<u> </u>	· <i>·</i> · · · · · ·	
Table 217	SWITCHING >	VLAN Mapping >	VLAN Mapping Setup

IABEL	DESC RIPTIO N	
Index	This is the number of the VLAN mapping entry in the table.	
Active	This shows whether this entry is activated or not.	
Name	This is the descriptive name for this rule.	
Port	This is the port number to which this rule is applied.	
VID	This is the customer VLAN ID in the incoming packets.	
Translated VID	This is the VLAN ID that replaces the customer VLAN ID in the tagged packets.	
Priority	This is the priority level that replaces the customer priority level in the tagged packets.	
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.	
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.	
Delete	Click <b>De le te</b> to remove the selected entries.	

#### 58.3.1 Add/Edit VIAN Mapping

Click Add/Edit, or select an entry and click Add/Edit in the SWIICHING > VIAN Mapping > VIAN Mapping Setup to display this screen. Use this screen to enable and edit the VLAN mapping rules.

Activo	() on	•
Name		
Port		
MD		
Transferred VID		
Priority	$\circ \sim$	
Apply	Glean	Cancel

Figure 295 SWITCHING > VLAN Mapping > VLAN Mapping Setup > Add/Edit

Table 218	SWITCHING >	VLAN Mapping > VLAN Mapping Setup > Add/Edit
-----------	-------------	--

IABEL	DESC RIPTIO N	
Active	Enable the switch button to activate this rule.	
Name	Enter a descriptive name (up to 32 printable ASCII characters except [?], [ ], ['], ["] or [,]) for identification purposes.	
Port	Type a port to be included in this rule.	
VID	Enter a VLAN ID from 1 to 4094. This is the VLAN tag carried in the packets and will be translated into the VID you specified in the <b>Thanslated VID</b> field.	
Translated VID	Enter a VLAN ID (from 1 to 4094) into which the customer VID carried in the packets will be translated.	
Priority	Select a priority level (from 0 to 7). This is the priority level that replaces the customer priority level in the tagged packets or adds to the untagged packets.	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Clear	Click Clear to clear the fields to the factory defaults.	
Cancel	Click Cancel to not save the configuration you make and return to the last screen.	

# C HAPTER 59 VIAN Stacking

This chapter shows you how to configure VLAN stacking on your Switch. See the chapter on VLANs for more background information on Virtual LANs (VLANs).

# 59.1 VIAN Stacking Overview

A service provider can use VLAN stacking to allow it to distinguish multiple customers VLANs, even those with the same (customer-assigned) VLAN ID, within its network.

Use VLAN stacking to add an outer VLAN tag to the inner IEEE 802.1Q tagged frames that enter the network. By tagging the tagged frames ("double-tagged" frames), the service provider can manage up to 4094 VLAN groups with each group containing up to 4094 customer VLANs. This allows a service provider to provide different service, based on specific VLANs, for many different customers.

A service provider's customers may require a range of VLANs to handle multiple applications. A service provider's customers can assign their own inner VLAN tags on ports for these applications. The service provider can assign an outer VLAN tag for each customer. Therefore, there is no VLAN tag overlap among customers, so traffic from different customers is kept separate.

## 59.1.1 VIAN Stacking Example

In the following example figure, both **A** and **B** are Service Provider's Network (SPN) customers with VPN tunnels between their head offices and branch offices respectively. Both have an identical VLAN tag for their VLAN group. The service provider can separate these two VLANs within its network by adding tag 37 to distinguish customer **A** and tag 48 to distinguish customer **B** at edge device **1** and then stripping those tags at edge device **2** as the data frames leave the network.




Figure 296 VLAN Stacking Example

## 59.2 VIAN Stacking Port Roles

Each port can have three VLAN stacking "roles", **Nomal**, **Access**, and **Tunnel** (the latter is for Gigabit ports only).

- Select Nomal for "regular" (non-VLAN stacking) IEEE 802.1Q frame switching.
- Select Access for ingress ports on the service provider's edge devices (1 and 2 in the VLAN stacking example figure). The incoming frame is treated as "untagged", so a second VLAN tag (outer VLAN tag) can be added.

Note: Static VLAN Tx Tagging MUST be disabled on a port where you choose Normal or Access.

• Select **Tunne1** (available for Gigabit ports only) for egress ports at the edge of the service provider's network. All VLANs belonging to a customer can be aggregated into a single service provider's VLAN (using the outer VLAN tag defined by the Service Provider's (SP) VLAN ID (VID)).

Note: Static VLAN Tx Tagging MUST be enabled on a port where you choose Tunnel.

## 59.3 VIAN Tag Format

A VLAN tag (service provider VLAN stacking or customer IEEE 802.1Q) consists of the following three fields.

Table 219 VLAN Tag Format

Type Priority VID

**Type** is a standard Ethernet type code identifying the frame and indicates that whether the frame carries IEEE 802.1Q tag information. **SP TPID** (Service Provider Tag Protocol Identifier) is the service provider VLAN stacking tag type. Many vendors use 0x8100 or 0x9100.

**TPID** (Tag Protocol Identifier) is the customer IEEE 802.1Q tag.

- If the VLAN stacking port role is Access port, then the Switch adds the SP TPID tag to all incoming frames on the service provider's edge devices (1 and 2 in the VLAN stacking example figure).
- If the VLAN stacking port role is **Tunnel** port, then the Switch only adds the **SP TPID** tag to all incoming frames on the service provider's edge devices (1 and 2 in the VLAN stacking example figure) that have an **SP TPID** different to the one configured on the Switch. (If an incoming frame's **SP TPID** is the same as the one configured on the Switch, then the Switch will not add the tag.)

**Priority** refers to the IEEE 802.1p standard that allows the service provider to prioritize traffic based on the class of service (CoS) the customer has paid for.

- On the Switch, configure priority level of the inner IEEE 802.1Q tag in the **PORT** > **Port Setup** screen.
- "0" is the lowest priority level and "7" is the highest.

**VID** is the VLAN ID. **SPVID** is the VID for the second (service provider's) VLAN tag.

#### 59.3.1 Frame Format

The frame format for an untagged Ethernet frame, a single-tagged 802.1Q frame (customer) and a "double-tagged" 802.1Q frame (service provider) is shown next.

Configure the fields as highlighted in the Switch SWIICHING > VIAN Stacking screens.

Table 220 Single and Double Tagged 802.1Q Frame Format

						DA	SA	Len/Etype	Data	FCS	Untagged Ethernet frame
			DA	SA	TPID	Prio rity	VID	Len/Etype	Data	FCS	IEEE 802.1Q customer tagged frame
DA	SA	SPIPID	Prio rity	VID	TPID	Prio rity	VID	Len/Etype	Data	FCS	Double-tagged frame

#### Table 221 802.1Q Frame

10.010 221			
DA	Destination Address	Priority	802.1p Priority
SA	Source Address	Len/Etype	Length and type of Ethernet frame
(SP)TPID	(Service Provider) Tag Protocol IDentifier	Data	Frame data
VID	VLAN ID	FCS	Frame Check Sequence

# 59.4 Configuring VIAN Stacking

Click SWIICHING > VIAN Stacking to display the screen as shown.

lw 🗇		
Port	Aple	Twinel PPID (Nex
	Normal v	
)	[Named v]	8100
2	Normal -	[7136]
5	Nonici v	8100
a.	Hormol ~	3196
10 C	Normal 2	8700
2	Hormot 🗠	0.000
7	Normal y	8100

Figure 297 SWITCHING > VLAN Stacking > VLAN Stacking

Table 222	SWITCHING >	VLAN Stacking >	VLAN Stacking
-----------	-------------	-----------------	---------------

IABEL	DESC RIPIIO N				
Active	Enable the switch button to enable VLAN stacking on the Switch.				
Port	This field displays the port number.				
*	Settings in this row apply to all ports.				
Use this row only if you want to make some settings the same for all ports. Use this row common settings and then make adjustments on a port-by-port basis.					
	Note: Changes in this row are copied to all the ports as soon as you make them.				
Role	Select <b>Nomal</b> to have the Switch ignore frames received (or transmitted) on this port with VLAN stacking tags. Anything you configure in <b>SPVID</b> and <b>Priority</b> of the <b>Port-based QinQ</b> or the <b>Selective QinQ</b> screen are ignored.				
	Select Access to have the Switch add the SP TPID tag to all incoming frames received on this port Select Access for ingress ports at the edge of the service provider's network.				
	Select <b>Tunnel</b> (available for Gigabit ports only) for egress ports at the edge of the service provider's network. Select <b>Tunnel</b> to have the Switch add the <b>Tunnel TPID</b> ( <b>HEX</b> ) tag to all outgoing frames sent on this port.				
	In order to support VLAN stacking on a port, the port must be able to allow frames of 1526 Bytes (1522 Bytes + 4 Bytes for the second tag) to pass through it.				

LABEL	DESC RIPTIO N
Tunnel TPID (HEX)	TPID is a standard Ethernet type code identifying the frame and indicates whether the frame carries IEEE 802.1Q tag information. Enter a four-digit hexadecimal number from 0000 to FFFF that the Switch adds in the outer VLAN tag of the frames sent on the tunnel ports. The Switch also uses this to check if the received frames are double-tagged.
	The value of this field is 0x8100 as defined in IEEE 802.1Q. It is used to identify the customer tag of an incoming frame. If the Switch needs to communicate with other vendors' devices, they should use the same TPID.
	Note: You can define up to four different tunnel TPIDs (including <b>8100</b> ) in this screen at a time.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 222 SWITCHING > VLAN Stacking > VLAN Stacking (continued)

# 59.5 Port-Based Q-in-Q

Port-based Q-in-Q lets the Switch treat all frames received on the same port as the same VLAN flows and add the same outer VLAN tag to them, even if they have different customer VLAN IDs.

Click SWIICHING > VIAN Stacking > Port-Based QinQ to display the screen as shown.

VLAN Slocking	Forl-Based Ging	Selective GinQ
Fan	arvid	Pristity
10		- (Q-14-)
	100	<u> </u>
2	1	0~
30	E Constanting	<u></u>
2.49		0.
1953	line and	<u></u>
÷	1	0
1	Jeanstein	<u>nv</u>
$\sim$	$\leq$	
-		
	Apply Done	A

Figure 298 SWITCHING > VLAN Stacking > Port-Based QinQ

Table 223	SWITCHING >	VLAN Stacking > Port-Based QinQ
	2001011100-	VEAN SIDENING > 1 ON-DUSED QING

IABEL	DESC RIPTIO N				
Port	This field displays the port number.				
*	Settings in this row apply to all ports.				
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.				
	Note: Changes in this row are copied to all the ports as soon as you make them.				
SPVID	<b>SPVID</b> is the service provider's VLAN ID (the outer VLAN tag). Enter the service provider ID (from 1 to 4094) for frames received on this port.				
Priority	Select a priority level (from 0 to 7). This is the service provider's priority level that adds to the frames received on this port.				
	"0" is the lowest priority level and "7" is the highest.				
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.				
Cancel	Click Cancel to begin configuring this screen afresh.				

## 59.6 Selective Q-in-Q

Selective Q-in-Q is VLAN-based. It allows the Switch to add different outer VLAN tags to the incoming frames received on one port according to their inner VLAN tags.

Note: Selective Q-in-Q rules are only applied to single-tagged frames received on the access ports. If the incoming frames are untagged or single-tagged but received on a tunnel port or cannot match any selective Q-in-Q rules, the Switch applies the port-based Q-in-Q rules to them.

Click SWIIC HING > VIAN Stacking > Selective QinQ to display the screen as shown.

Figure 299 SWITCHING > VLAN Stacking > Selective QinQ

VIAN stocking		Port-Based QloQ		Selective GinG				
						O Ack	deux.	C poste
0	index.	Active	Neme	. 8	ford	CVID.	58910	Piconte

The following table describes the labels in this screen.

Table 224	SWITCHING >	VLAN Stacking > Selective QinQ
-----------	-------------	--------------------------------

LABEL	DESC RIPTIO N	
Index	This is the number of the selective VLAN stacking rule.	
Active	his shows whether this rule is activated or not.	
Name	This is the descriptive name for this rule.	
Port	This is the port number to which this rule is applied.	
CVID	This is the customer VLAN ID in the incoming packets.	

XGS2220 Series User's Guide

	8
IABEL	DESC RIPIIO N
SPVID	This is the service provider's VLAN ID that adds to the packets from the subscribers.
Priority	This is the service provider's priority level in the packets.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.
Delete	Click <b>Delete</b> to remove the selected entries.

Table 224 SWITCHING > VLAN Stacking > Selective QinQ (continued)

## 59.6.1 Add/Edit Selective Q-in-Q

Click Add/Edit, or select an entry and click Add/Edit in the SWIICHING > VIAN Stacking > Selective QinQ screen to display this screen.

Active	C CFF	
Name		
Port		
CVID		
SPAD		
Priority	0 v	
Apply	Clear	Cancel

Figure 300 SWITCHING > VLAN Stacking > Selective QinQ > Add/Edit

The following table describes the labels in this screen.

Table 225	SWITCHING >	VLAN Stacking >	Selective	QinQ > Add/Edit
-----------	-------------	-----------------	-----------	-----------------

IABEL	DESC RIPTIO N
Active	Enable the switch button to activate this rule.
Name	Enter a descriptive name (up to 32 printable ASCII characters except [ ? ], [   ], [ ' ], [ " ] or [ , ]) for identification purposes.
Port	The port number identifies the port you are configuring.
CVID	Enter a customer VLAN ID (the inner VLAN tag) from 1 to 4094. This is the VLAN tag carried in the packets from the subscribers.
SPVID	<b>SPVID</b> is the service provider's VLAN ID (the outer VLAN tag). Enter the service provider ID (from 1 to 4094) for frames received on this port.
Priority	Select a priority level (from 0 to 7). This is the service provider's priority level that adds to the frames received on this port. "0" is the lowest priority level and "7" is the highest.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click <b>Clear</b> to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

# C HAPTER 60 NEIWORKING

The following chapters introduces the configurations of the links under the **NEIWORKING** navigation panel.

Quick links to chapters:

- ARP Setup
- DHCP
- Static Route

# C HAPTER 61 ARP Se tup

# 61.1 ARP Overview

Address Resolution Protocol (ARP) is a protocol for mapping an Internet Protocol address (IP address) to a physical machine address, also known as a Media Access Control or MAC address, on the local area network.

An IP (version 4) address is 32 bits long. In an Ethernet LAN, MAC addresses are 48 bits long. The ARP table maintains an association between each MAC address and its corresponding IP address.

## 61.1.1 What You Can Do

- Use the **ARP Learning** screen (Section 61.2 on page 407) to configure ARP learning mode on a perport basis.
- Use the Static ARP screen (Section 61.3 on page 408) to create static ARP entries that will display in the MONITOR > ARP Table screen and will not age out.

## 61.1.2 What You Need to Know

Read on for concepts on ARP that can help you configure the screen in this chapter.

#### 61.1.2.1 How ARP Works

When an incoming packet destined for a host device on a local area network arrives at the Switch, the Switch looks in the ARP Table and if it finds the address, it sends it to the device.

#### 61.1.2.2 ARP Learning Mode

The Switch supports three ARP learning modes: ARP-Reply, Gratuitous-ARP, and ARP-Request.


#### ARP-Reply

The Switch in ARP-Reply learning mode updates the ARP table only with the ARP replies to the ARP

405

requests sent by the Switch. This can help prevent ARP spoofing.

In the following example, the Switch does not have IP address and MAC address mapping information for hosts **A** and **B** in its ARP table, and host **A** wants to ping host **B**. Host **A** sends an ARP request to the Switch and then sends an ICMP request after getting the ARP reply from the Switch. The Switch finds no matched entry for host **B** in the ARP table and broadcasts the ARP request to all the devices on the LAN. When the Switch receives the ARP reply from host **B**, it updates its ARP table and also forwards host **A**'s ICMP request to host **B**. After the Switch gets the ICMP reply from host **B**, it sends out an ARP request to get host **A**'s MAC address and updates the ARP table with host **A**'s ARP reply. The Switch then can forward host **B**'s ICMP reply to host **A**.



#### G ra tuito us-ARP

A gratuitous ARP is an ARP request in which both the source and destination IP address fields are set to the IP address of the device that sends this request and the destination MAC address field is set to the broadcast address. There will be no reply to a gratuitous ARP request.

A device may send a gratuitous ARP packet to detect IP collisions. If a device restarts or its MAC address is changed, it can also use gratuitous ARP to inform other devices in the same network to update their ARP table with the new mapping information.

In Gratuitous-ARP learning mode, the Switch updates its ARP table with either an ARP reply or a gratuitous ARP request.

#### ARP-Request

When the Switch is in ARP-Request learning mode, it updates the ARP table with both ARP replies, gratuitous ARP requests and ARP requests.

Therefore in the following example, the Switch can learn host **A**'s MAC address from the ARP request sent by host **A**. The Switch then forwards host **B**'s ICMP reply to host **A** right after getting host **B**'s MAC address and ICMP reply.

	ARP Request	
2	ARF Reply	
3	CMP Request	
	12	AR <sup>2</sup> Request
		ARP Reply
		ICM <sup>e</sup> Request
		CMP Reply
	HOMP Reply	

# 61.2 ARP Learning

Use this screen to configure each port's ARP learning mode. Click **NETWORKING** > **ARP** Setup > **ARP Learning** in the navigation panel to display the screen as shown next.

Port .	ARP Learning Mode
9	ARP BCOV
34	ARP Rep y
2	ARP Rup v v
5	AtP-heply 🐱
24) 1	Ant-heply 🐱
5	AttAcept
6	Attivited k 🔗
1	

LABEL	DESC RIPTIO N
Port	This field displays the port number.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Changes in this row are copied to all the ports as soon as you make them.
ARP Learning	Select the ARP learning mode the Switch uses on the port.
Mode	Select $ARP \cdot Re p \cdot ly$ to have the Switch update the ARP table only with the ARP replies to the ARP requests sent by the Switch.
	Select <b>G tuito us-ARP</b> to have the Switch update its ARP table with either an ARP reply or a gratuitous ARP request.
	Select <b>ARP-Request</b> to have the Switch update the ARP table with both ARP replies, gratuitous ARP requests and ARP requests.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 226 NETWORKING > ARP Setup > ARP Learning

# 61.3 Static ARP

Use this screen to view and configure static ARP entries that will display in the **MONITOR** > **ARP Table** screen and will not age out. Click **NETWORKING** > **ARP Se tup** > **Static ARP** to display the screen as shown.

Figure 302	NETWORKING > ARP Setup > Static ARP	
ing and our		

Stolic A)	er 👘						
					😄 Addiðerið		a data -
	incles	Active	Nome	IP Address	MAC Acidness	VID	Port

IABEL	DESC RIPTIO N	
Index	This field displays the index number of an entry.	
Active	This field displays whether the entry is activated.	
Name	This field displays the descriptive name for this entry. This is for identification purposes only.	
IP Address	This is the IP address of a device connected to a Switch port with the corresponding MAC address below.	
MAC Address	This is the MAC address of the device with the corresponding IP address above.	
VID	This field displays the VLAN to which the device belongs.	
Port	This field displays the port to which the device connects.	
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.	
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.	
Delete	Click <b>Delete</b> to remove the selected entries.	

#### Table 227 NETWORKING > ARP Setup > Static ARP

### 61.3.1 Add/Edit Static ARP

Use this screen to add/edit static ARP entries. Click Add/Edit, or select an entry and click Add/Edit in the NEIWO RKING > ARP Setup > Static ARP to display this screen.

sette	🔵 on 🕽	
bierno		
P Actes		
NAC Address		
2D		
Port		
and the second sec	- Charles - Charles	- ha

Figure 303 NETWORKING > ARP Setup > Static ARP > Add/Edit

IABEL	DESC RIPTIO N
Active	Enable the switch button to activate your rule. You may temporarily deactivate a rule without deleting it by clearing this check box.
Name	Enter a descriptive name (up to 32 printable ASCII characters except [?], [ ], ['], ["] or [,]) for identification purposes.
IP Address	Enter the IP address of a device connected to a Switch port with the corresponding MAC address below.
MAC Address	Enter the MAC address of the device with the corresponding IP address above.
VID	Enter the ID number of VLAN to which the device belongs.
Port	Enter the number of port to which the device connects.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click <b>Clear</b> to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

 Table 228
 NETWORKING > ARP Setup > Static ARP > Add/Edit

# C HAPTER 62 DHCP

## 62.1 DHCPOverview

This chapter shows you how to configure the DHCP feature.

DHCP (Dynamic Host Configuration Protocol RFC 2131 and RFC 2132) allows individual computers to obtain TCP/IP configuration at start-up from a server. You can configure the Switch as a DHCP server or a DHCP relay agent. When configured as a server, the Switch provides the TCP/IP configuration for the clients. If you configure the Switch as a relay agent, then the Switch forwards DHCP requests to DHCP server on your network. If you do not configure the Switch as a DHCP server or relay agent then you must have a DHCP server in the broadcast domain of the client computers or else the client computers must be configured manually.

## 62.1.1 What You Can Do

- Use the DHC Pv4 Relay Status screen (Section 62.2 on page 412) to display the relay mode and status.
- Use the **DHCPv4 Option 82 Profile** screen (Section 62.3 on page 412) to create DHCPv4 option 82 profiles.
- Use the **DHCPv4** Smart Relay screen (Section 62.4 on page 414) to configure global DHCPv4 relay. You can also use this screen to apply different DHCP option 82 profile to certain ports on the Switch.
- Use the **DHCPv4 Relay VIAN Setting** screen (Section 62.5 on page 418) to configure your DHCPv4 settings based on the VLAN domain of the DHCPv4 clients. You can also use this screen to apply a different DHCP option 82 profile to certain ports in a VLAN.
- Use the DHC Pv6 Relay screen (Section 62.6 on page 420) to enable and configure DHCPv6 relay.
- Use the **DHCP Server Guard** screen (Section 62.7 on page 422) to specify whether ports are trusted or untrusted ports for DHCP packets.

## 62.1.2 What You Need to Know

Read on for concepts on DHCP that can help you configure the screens in this chapter.

#### DHC P Modes

If there is already a DHCP server on your network, then you can configure the Switch as a DHCP relay agent. When the Switch receives a request from a computer on your network, it contacts the DHCP server for the necessary IP information, and then relays the assigned information back to the computer.

#### DHC Pv4 Configuration Options

The DHCPv4 configuration on the Switch is divided into Smart Relay and VIAN screens. The screen you should use for configuration depends on the DHCP services you want to offer the DHCP clients on your network. Choose the configuration screen based on the following criteria:

- Smart Relay The Switch forwards all DHCP requests to the same DHCP server.
- **VIAN** The Switch is configured on a VLAN by VLAN basis. The Switch can be configured to relay DHCP requests to different DHCP servers for clients in different VLAN.

## 62.2 DHC Pv4 Re la y Sta tus

Click NETWORKING > DHCP > DHCPv4 Relay in the navigation panel. The DHCP Relay Status screen displays.

ing une off the the the		olay - Brier Rolay ore	2105
DHCP Relay Status	DHCP Option 82 Profile	DHCP Smart Relay	DHCP Relay VLAN Setting
Koley Mede	VEAN.1		
VID		Content Source Add	nu r
1		1/2/21/0/212	

Figure 304 NETWORKING > DHCP > DHCPv4 Relay > DHCP Relay Status

The following table describes the labels in this screen.

Table 229	NETWORKING > DHCP	> DHCPv4 Relav >	DHCP Relay Status

IABEL	DESC RIPTIO N
Relay Mode	This field displays:
MODE	<b>None</b> – if the Switch is not configured as a DHCP relay agent.
	$\mathbf{Smart}$ - if the Switch is configured as a DHCP relay agent only.
	<b>VIAN</b> – followed by a VLAN ID or multiple VLAN IDs if it is configured as a relay agent for specific VLANs.
VID	This field displays the ID number of the VLAN for which the Switch acts as a DHCP relay agent.
Current Source Address	This field displays the source IP address of the DHCP requests that the Switch forwards to a DHCP server.

# 62.3 DHC Pv4 Option 82 Profile

Use this screen to view and configure DHCPv4 option 82 profiles. Click **NETWORKING** > **DHCP** > **DHCPv4 Re lay** > **DHCP Option 82 Profile** link to display the screen as shown.

DHCP Status	DHCP Option 82	Profile DHCP Sm	nart Relay DHCP Re	elay VLAN Setting	
				O Add/Ed	R 📋 Deloto
	Profile Name	Circ	di-five	Remot	le-ID
FIDER	FISHING PRODUCT	Enable	Field	Enoble	Field
	default1	ON	slot-port, vian	061	
	default2		siot-port, vian, hostname	064	

Figure 305 NETWORKING > DHCP > DHCPv4 Relay > DHCP Option 82 Profile

Table 230 NETWORKING > DHCP > DHCPv4 Relay > DHCP Option 82 Profile

IABEL	DESC RIPTIO N
Profile Name	This field displays the descriptive name of the profile.
Circuit-ID	This section displays the Circuit ID sub-option including information that is specific to the relay agent (the Switch).
Enable	This field displays whether the Circuit ID sub-option is added to client DHCP requests.
Field	This field displays the information that is included in the Circuit ID sub-option.
Remote-ID	This section displays the Remote ID sub-option including information that identifies the relay agent (the Switch).
Enable	This field displays whether the Remote ID sub-option is added to client DHCP requests.
Field	This field displays the information that is included in the Remote ID sub-option.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.
Delete	Click <b>De le te</b> to remove the selected entries.

## 62.3.1 Add/Edit a DHC Pv4 Option 82 Profile

Use this screen to create DHCPv4 option 82 profiles. Click Add/Edit, or select an entry and click Add/Edit in the NEIWORKING > DHCP > DHCPv4 Re lay > DHCP Option 82 Profile link to display this screen.

Figure 306	NETWORKING >	DHCP > DHCPv4	Relay > DHCP	Option 82 Profile >	Add/Edit
------------	--------------	---------------	--------------	---------------------	----------

Name	
Ciscul-ID	sot port vian hostnamo string
Pernote-D	Cooble     max     max     sting

Note: The string of any field in this screen should not contain [?], [|], ['], ["] or [,].

IABEL	DESC RIPIIO N
Name	Enter a descriptive name for the profile for identification purposes. You can use up to 32 printable ASCII characters.
Circuit-ID	Use this section to configure the Circuit ID sub-option to include information that is specific to the relay agent (the Switch).
Enable	Select this option to have the Switch add the Circuit ID sub-option to client DHCP requests that it relays to a DHCP server.
slot-port	Select this option to have the Switch add the number of port that the DHCP client is connected to.
vlan	Select this option to have the Switch add the ID of VLAN which the port belongs to.
hostname	This is the system name you configure in the <b>SYSTEM</b> > <b>General Setup</b> screen.
	Select this option for the Switch to add the system name to the client DHCP requests that it relays to a DHCP server.
string	Enter a string of up to 64 printable ASCII characters that the Switch adds into the client DHCP requests.
Remote-ID	Use this section to configure the Remote ID sub-option to include information that identifies the relay agent (the Switch).
Enable	Select this option to have the Switch append the Remote ID sub-option to the option 82 field of DHCP requests.
mac	Select this option to have the Switch add its MAC address to the client DHCP requests that it relays to a DHCP server.
string	Enter a string of up to 64 printable ASCII characters for the remote ID information in this field.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.

# 62.4 Configuring DHCPv4 Smart Relay

Clear

Cancel

Use this screen to configure global DHCPv4 relay. Click NEIWORKING > DHCP > DHCPv4 Relay > DHCP Smart Relay to display the screen as shown.

Click Cancel to not save the configuration you make and return to the last screen.

Click Clear to clear the fields to the factory defaults.

DHCP Status DHCP	Option 82 Profile	DHCP Smart Keloy	DHCP Relay VLAN Setting
DHCP Smart Relay			
Adlve	() 0Ŧ)		
Remote DHOP Server 1	0.0.0.0		
Remote DICP Server 2	0.0.0.0		
Remote DHCP Server S	00000		
Collor 82 Polle		~	
	App	dy Cancel	
Port			
			🕒 AdduEdit 📋 Delete
index	Port		Arofile Nome

Figure 307 NETWORKING > DHCP > DHCPv4 Relay > DHCP Smart Relay

The following table describes the labels in this screen.

Table 232	NETWORKING > DHCP :	> DHCPv/ Palav >	S DHCP Smart Palay
	NELWORKING / DICL /		P DITCE SHIULI KEIUY

IABEL	DESC RIPIIO N
DHCP Smart Relay	/
Active	Select this check box to enable DHCPv4 relay.
Remote DHCP Server 1 3	Enter the IP address of a DHCPv4 server in dotted decimal notation.
Option 82 Profile	Select a pre-defined DHCPv4 option 82 profile that the Switch applies to all ports. The Switch adds the Circuit ID sub-option and/or Remote ID sub-option specified in the profile to DHCP requests that it relays to a DHCP server.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.
Port	
Use this section	to apply a different DHCP option 82 profile to certain ports on the Switch.
Index	This field displays a sequential number for each entry.
Port	This field displays the ports to which the Switch applies the settings.
Profile Name	This field displays the DHCP option 82 profile that the Switch applies to the ports.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.
Delete	Click <b>Delete</b> to remove the selected entries.

## 62.4.1 Add/Edit DHC Pv4 Global Relay Port

Use this screen to apply a different DHCP option 82 profile to certain ports on the Switch. To open this screen, Click Add/Edit, or select an entry and click Add/Edit in the Port section of the NEIWORKING > DHCP > DHCPv4 Re lay > DHCP Smart Re lay screen.

Figure 308 NETWORKING > DHCP > DHCPv4 Relay > DHCP Smart Relay > Add/Edit

Peif			
Color 2 code		<u>.</u>	
	Apply	Okur	Connect

The following table describes the labels in this screen.

Table 233		PVI Polav >	DHCP Smart Relay	> Add/Edit
TUDIE 200	INCLUMORKING /	CI V4 KEIUY /	DICE SHOLKEDY	Zuu/Luii

IABEL	DESC RIPTIO N
Port	Enter the number of ports to which you want to apply the specified DHCP option 82 profile.
	You can enter multiple ports separated by (no space) comma (,) or hyphen (-). For example, enter "3-5" for ports 3, 4, and 5. Enter "3,5,7" for ports 3, 5, and 7.
Option 82 Profile	Select a pre-defined DHCP option 82 profile that the Switch applies to the specified ports. The Switch adds the Circuit ID sub-option and/or Remote ID sub-option specified in the profile to DHCP requests that it relays to a DHCP server.
	The profile you select here has priority over the one you select in the <b>NETWORKING</b> $>$ <b>DHCP</b> $>$ <b>DHCPv4 Re lay</b> $>$ <b>DHCPv4 Sm art Re lay</b> screen.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click <b>Clear</b> to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

## 62.4.2 DHCP Smart Relay Configuration Example

The follow figure shows a network example where the Switch is used to relay DHCP requests for the **VIAN1** and **VIAN2** domains. There is only one DHCP server that services the DHCP clients in both domains.





Figure 309 DHCP Smart Relay Network Example

Configure the **NETWO RKING** > **DHC P** > **DHC Pv4 Re lay** > **DHC P Sm art Re lay** screen as shown. Make sure you select a DHCP option 82 profile (**de fa ult1** in this example) to set the Switch to send additional information (such as the VLAN ID) together with the DHCP requests to the DHCP server. This allows the DHCP server to assign the appropriate IP address according to the VLAN ID. Click **Apply** after you finish the configuration.

DHCP Status DHCP	Option 82 Profile	DHCP Smart Relay		
DHCP Smart Relay				
Active	CON 🔘			
Remote DHCP Server 1	192.168.1.100			
Remote DHCP Server 2	0.0.0.0	0.0.0.0		
Remote DHCP Server 3	0.0.0.0	0.0.0.0		
Option 82 Profile	default1	~		
Port	Apply Concer	AddyEdit 📋 Delete		
index.	Part	Profile Name		



# 62.5 DHC Pv4 VLAN Setting

Use this screen to configure your DHCP settings based on the VLAN domain of the DHCP clients. Click **NEIWO RKING > DHC P > DHC Pv4 Re lay > DHC P Re lay VLAN Setting** to display the screen as shown.

Figure 311 NETWORKING > DHCP > DHCPv4 Relay > DHCP Relay VLAN Setting

DHCF Status	DHC	P Option 82 Profile	DRCP Smart Relay	DHCP Keloy VLAN Selfing
DHCP Relay	VLAN Se	atting		
				🕒 Add/Edit 🔋 Delete
				Constraint E Decene
	VID	Remote DHCP Server	Source Address	
	1	172.21.40.3	0.0.0.0	
Port				
				😋 Ade/Edit 🛛 🦉 Delete
	Index	VID	Port	Profile Name

The following table describes the labels in this screen.

LABEL	DESC RIPTIO N		
DHCP Relay VLAN	l Setting		
VID	VID This field displays the ID number of the VLAN group to which this DHCP settings apply.		
Remote DHCP Server	This displays the IP address of a DHCP server in dotted decimal notation.		
Source Address	This field displays the source IP address you configured for DHCP requests from clients on this VLAN.		
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.		
Add/Edit Click Add/Edit to add a new entry or edit a selected one.			
Delete	Click <b>De le te</b> to remove the selected entries.		
Port			
Use this section to	apply a different DHCP option 82 profile to certain ports in a VLAN.		
Index	This field displays a sequential number for each entry. Click an index number to change the settings.		
VID This field displays the VLAN to which the ports belongs.			
Port This field displays the ports to which the Switch applies the settings.			
Profile Name	This field displays the DHCP option 82 profile that the Switch applies to the ports in this VLAN.		
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.		
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.		
Delete	Click <b>Delete</b> to remove the selected entries.		

Table 234 NETWORKING > DHCP > DHCPv4 Relay > DHCP Relay VLAN Setting

## 62.5.1 Add/Edit DHC Pv4 VIAN Setting

Use this screen to add/edit your DHCP settings based on the VLAN domain of the DHCP clients. Click the Add/Edit button in the DHCP Relay VLAN Setting section of the NEIWORKING > DHCP > DHCPv4 Relay > DHCP Relay VLAN Setting screen to access this screen.

Note: You must set up a management IP address for each VLAN that you want to configure DHCP settings for on the Switch.

Figure 312 NETWORKING > DHCP > DHCPv4 Relay > DHCP Relay VLAN Setting > Add/Edit (DHCP Relay VLAN Setting)

VD.		
Remote DHCP Server 1	0.000	
Kensole DHCPServer 2	0.0.0.0	
Remote DHOP Server 3	anna	
Source Address	0.0.0.0	
Option 82 Profile		
Арріу	Clear Cancel	

The following table describes the labels in this screen.

Table 235 NETWORKING > DHCP > DHCPv4 Relay > DHCP Relay VLAN Setting > Add/Edit (DHCP Relay VLAN Setting)

IABEL	DESC RIPIIO N
VID	Enter the ID number of the VLAN to which these DHCP settings apply.
Remote DHCP Server 1 3	Enter the IP address of a DHCP server in dotted decimal notation.
Source Address	Enter the source IP address that the Switch adds to DHCP requests from clients on this VLAN before forwarding them. If you leave this field set to <b>0.0.0</b> , the Switch automatically sets the source IP address of the DHCP requests to the IP address of the interface on which the packet is received.
	The source IP address helps DHCP clients obtain an appropriate IP address when you configure multiple routing domains on a VLAN.
Option 82 Profile	Select a pre-defined DHCP option 82 profile that the Switch applies to all ports in this VLAN. The Switch adds the Circuit ID sub-option and/or Remote ID sub-option specified in the profile to DHCP requests that it relays to a DHCP server.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click <b>Clear</b> to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

## 62.5.2 Add/Edit DHC Pv4 VIAN Port

Use this screen to apply a different DHCP option 82 profile to certain ports in a VLAN. Click the Add/Edit button in the Port section of the NEIWORKING > DHCP > DHCPv4 Re lay > DHCP Re lay VIAN Setting screen to access this screen.

#### Figure 313 NETWORKING > DHCP > DHCPv4 Relay > DHCP Relay VLAN Setting > Add/Edit (Port)

ort i	1
Salar da Hasile	· · · · · · · · · · · · · · · · · · ·
201223399999779	the second s

The following table describes the labels in this screen.

IABEL	DESC RIPTIO N
VID	Enter the ID number of the VLAN you want to configure here.
Port	Enter the number of ports to which you want to apply the specified DHCP option 82 profile.
	You can enter multiple ports separated by (no space) comma (,) or hyphen (-). For example, enter "3-5" for ports 3, 4, and 5. Enter "3,5,7" for ports 3, 5, and 7.
Option 82 Profile	Select a pre-defined DHCP option 82 profile that the Switch applies to the specified ports in this VLAN. The Switch adds the Circuit ID sub-option and/or Remote ID sub-option specified in the profile to DHCP requests that it relays to a DHCP server.
	The profile you select here has priority over the one you select in the <b>NEIWORKING</b> > <b>DHCP</b> > <b>DHCPv4 Relay</b> > <b>DHCP Relay VIAN Setting</b> (the <b>DHCP Relay VIAN Setting</b> section) > <b>Add/Edit</b> screen.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

# 62.6 DHC Pv6 Re la y

A DHCPv6 relay agent is on the same network as the DHCPv6 clients and helps forward messages between the DHCPv6 server (that is in another network) and the DHCPv6 clients.

The DHCPv6 relay agent can add the remote identification (remote-ID) option and the interface-ID option to the Relay-Forward DHCPv6 messages. The remote-ID option carries a user-defined string, such as the system name. The interface-ID option provides slot number, port information and the VLAN ID to the DHCPv6 server. The remote-ID option (if any) is stripped from the Relay-Reply messages before the relay agent sends the packets to the clients. The DHCPv6 server copies the interface-ID option from the Relay-Forward message into the Relay-Reply message and sends it to the relay agent. The interface-ID should not change even after the relay agent restarts.

Use this screen to view and configure DHCPv6 relay settings for a specific VLAN on the Switch. Click **NEIWO RKING** > **DHCP** > **DHCPv6 Re** la y in the navigation panel to display the screen as shown.

rigure 314		NG > DHCF > DHCF V	s keiuy	
DHCPv& Ro	əlay			
				😂 Add/Edit 🍵 Delete
	VID	Helper Address	Interface ID	Remote ID

Figure 314 NETWORKING > DHCP > DHCPv6 Relay

XGS2220 Series User's Guide

Table 237	NETWORKING > DHCP > DHCPv6 Relay
10010 20/	

IABEL	DESC RIPIIO N			
VID	This field displays the VLAN ID number.			
Helper Address	This field displays the IPv6 address of the remote DHCPv6 server for this VLAN.			
Interface ID	This field displays whether the interface-ID option is added to DHCPv6 requests from clients in this VLAN.			
Remote ID	This field displays whether the remote-ID option is added to DHCPv6 requests from clients in this VLAN.			
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.			
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.			
Delete	Click <b>De le te</b> to remove the selected entries.			

## 62.6.1 Add/Edit DHC Pv6 Re la y

Use this screen to add/edit DHCPv6 relay settings for a specific VLAN on the Switch. Click Add/Edit, or select an entry and click Add/Edit in the NEIWORKING > DHCP > DHCPv6 Relay screen to display this screen.




Figure 315 NETWORKING > DHCP > DHCPv6 Relay > Add/Edit

The following table describes the labels in this screen.

Table 238	NETWORKING > DHCP > DHCPv6 Relay > Add/Edit
10010 200	Herrier Brief Brief verkelag vidagean

LABEL	DESC RIPTIO N
VID	Enter the ID number of the VLAN to which the DHCPv6 server that will assign IP information belongs here.
Helper Address	<ul> <li>Enter the IPv6 address of the DHCPv6 server that will assign IP information here.</li> <li>An 128-bit IPv6 address is written as eight 16-bit hexadecimal blocks separated by colons (:). This is an example IPv6 address '2001:0db8:1a2b:0015:0000:0000:1a2f:0000'.</li> <li>IPv6 addresses can be abbreviated in two ways:</li> <li>Leading zeros in a block can be omitted. So '2001:0db8:1a2b:0015:0000:0000:1a2f:0000' can be written as '2001:db8:1a2b:15:00:1a2f:0'.</li> <li>Any number of consecutive blocks of zeros can be replaced by a double colon. A double colon can only appear once in an IPv6 address. So '2001:0db8:1a2f:0000:0000:1a2f:0000:0000:1a2f:0000:0000:1a2f:0000:0000:0015' can be written as '2001:0db8::0000:0000:015', '2001:0db8::0000:0000:1a2f::0015', '2001:db8::1a2f:0:0:15' or '2001:db8::012f::15'.</li> </ul>
Interface ID	Enable the switch button to have the Switch add the interface-ID option in the DHCPv6 requests from the clients in the specified VLAN before the Switch forwards them to a DHCPv6 server.

IABEL	DESC RIPTIO N
Remote ID	Enter a string of up to 64 printable ASCII characters (except [?], [ ], ['], ["] or [,]) to be carried in the remote-ID option. The Switch adds the remote-ID option in the DHCPv6 requests from the clients in the specified VLAN before the Switch forwards them to a DHCPv6 server.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click <b>Clear</b> to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

Table 238 NETWORKING > DHCP > DHCPv6 Relay > Add/Edit (continued)

# 62.7 DHCP Server Guard

Use this screen to specify whether ports are trusted or untrusted ports for DHCP packets. Click **NEIWORKING > DHCP > DHCP Server Guard** in the navigation panel to display the screen as shown.

Figure 316 NETWORKING > DHCP > DHCP Server Guard

DHCP Server Guar	4
DHCP Server Guo	d
Adive 🕄	AFT.
Port Setting	
Peri	Trusted Stone
	(Unincident ex-
1	Universities (
8.	0.hmusted w/
<b>1</b>	(Venuted v)
E.	Unneted w
5	(Umuted v)
£	(umuted x)
2	Analy Barray

The following table describes the labels in this screen.

Table 239 NETWORKING > DHCP > DHCP Server Guard

IABEL	DESC RIPIIO N		
DHCP Server Gua	DHCP Server Guard		
Active	Active Enable the switch button to enable DHCP Server Guard.		
Port Setting			

Table 239 NETWORKING > DHCP > DHCP Server Guard (continued)
---

IABEL	DESC RIPIIO N	
Port	The port number identifies the port you are configuring.	
*	Settings in this row apply to all ports. Use this row only if you want to make some settings the same for all ports. Use this row first to set	
	the common settings and then make adjustments on a port-by-port basis. Note: Changes in this row are copied to all the ports as soon as you make them.	
Trusted State	Select whether this port is a trusted port ( <b>Trusted</b> ) or an untrusted port ( <b>Untrusted</b> ). The Switch does not discard DHCP packets on trusted ports for any reason.	
	The Switch discards DHCP packets from untrusted ports when the packet is a DHCP server packet (for example, OFFER, ACK, or NACK).	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Cancel	Click Cancel to reset the fields to their last saved values.	

# C HAPTER 63 Static Route

# 63.1 Static Routing Overview

This chapter shows you how to configure static routes.

The Switch uses IP for communication with management computers, for example using HTTP, Telnet, SSH, or SNMP. Use IP static routes to have the Switch respond to remote management stations that are not reachable through the default gateway. The Switch can also use static routes to send data to a server or device that is not reachable through the default gateway, for example when sending SNMP traps or using ping to test IP connectivity.

The Switch usually uses the default gateway to route outbound traffic from computers on the LAN to the Internet. To have the Switch send data to devices not reachable through the default gateway, use static routes.

For example, the next figure shows a computer (A) connected to the Switch. The Switch routes most traffic from A to the Internet through the Switch's default gateway (RL). You create one static route to connect to services offered by your ISP behind router R2. You create another static route to communicate with a separate network behind a router R3 connected to the Switch.




Figure 317 Example of Static Routing Topology

## 63.1.1 What You Can Do

- Use the IPv4 Static Route screen (Section 63.2 on page 425) to configure and enable an IPv4 static route.
- Use the IPv6 Static Route screen (Section 63.3 on page 426) to configure and enable an IPv6 static route.

## 63.2 IPv4 Static Route

Click NEIWORKING > Static Routing > IPv4 Static Route to display the screen as shown.

Figure 318 NETWORKING > Static Routing > IPv4 Static Route

IPv4 Sk	atic Route						
					<b>O</b> <i>h</i>	id/Edit 📋	Delete
	index.	Active	Nome	Destination Address	Submet Wesk	Gateway Address	Matric

The following table describes the related labels you use to create a static route.

LABEL	DESC RIPIIO N			
Index	This field displays the index number of the route.			
Active	This field displays whether the static route is activated or not.			
Name	This field displays the descriptive name for this route. This is for identification purposes only.			
Destination Address	This field displays the IP network address of the final destination.			
Subnet Mask	This field displays the subnet mask for this destination.			
Gateway Address	This field displays the IP address of the gateway. The gateway is an immediate neighbor of your Switch that will forward the packet to the destination.			
Metric	This field displays the cost of transmission for routing purposes.			
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.			
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.			
Delete	Click <b>Delete</b> to remove the selected entries.			

#### 63.2.1 Add/Edit IPv4 Static Route

Click Add/Edit, or select an entry and click Add/Edit in the NEIWORKING > Static Routing > IPv4 Static Route screen to display this screen.

Active	(hor)	
None		1
Destination IP Address		
IP Subnot Mark		1
Colewoy IF Address		
Methic		
Apply	Clear	Cencel

Figure 319 NETWORKING > Static Routing > IPv4 Static Route > Add/Edit

The following table describes the related labels you use to create a static route.

LABEL	DESC RIPTIO N			
Active	This field allows you to activate or deactivate this static route.			
Name	Enter a descriptive name (up to 10 printable ASCII characters except [?], [ ], ['], ["] or [,]) for identification purposes.			
Destination IP Address	This parameter specifies the IP network address of the final destination.			
IP Subnet Mask	Enter the subnet mask for this destination. Routing is always based on network number. If you need to specify a route to a single host, use a subnet mask of 255.255.255.255 in the subnet mask field to force the network number to be identical to the host ID.			
Gateway IP Address	Enter the IP address of the gateway. The gateway is an immediate neighbor of your Switch that will forward the packet to the destination. The gateway must be a router on the same segment as your Switch.			
Metric	The metric represents the "cost" of transmission for routing purposes. IP routing uses hop count as the measurement of cost, with a minimum of 1 for directly connected networks. Enter a number that approximates the cost for this link. The number need not be precise, but it must be between 1 and 15. In practice, 2 or 3 is usually a good number.			
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.			
Clear	Click Clear to clear the fields to the factory defaults.			
Cancel	Click Cancel to not save the configuration you make and return to the last screen.			

Table 241	NFTWORKING > St	atic Routina > IPv4	<pre>Static Route &gt; Add/Edit</pre>
	INELWORKING > 31	alic Rouling $> 1974$	FSIGIIC ROULE > AGG/I

## 63.3 IPv6 Static Route

Click NETWORKING > Static Routing > IPv6 Static Route to display the screen as shown.

Figure 320 NETWORKING > Static Routing > IPv6 Static Route

IPv6 Static Route			
		<b>O</b> <i>M</i>	at/Echt 📋 Delete
Index	interface	Route Decthorion / Freits Length	Next Hop

The following table describes the related labels you use to create a static route.

IABEL	DESC RIPTIO N		
Index	This field displays the index number of the route.		
Interface	This field displays the descriptive name of the interface that is used to forward the packets to the destination.		
Route Destination / Prefix Length	This field displays the IPv6 subnet prefix and prefix length of the final destination.		
Next Hop	This field displays the IPv6 address of the gateway that helps forward the packet to the destination.		

IABEL	DESC RIPTIO N
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.
Delete	Click <b>Delete</b> to remove the selected entries.

Table 242 NETWORKING > Static Routing > IPv6 Static Route (continued)

## 63.3.1 Add/Edit IPv6 Static Route

Click Add/Edit, or select an entry and click Add/Edit in the NETWORKING > Static Routing > IPv6 Static Route to display this screen.

Interfacie Lype	VLAN •	
Interfacio ID		
Southe Deviltabilitier		
meta tengil		
Next Hop		ļ
	Appely Channel Channel	

The following table describes the related labels you use to create a static route.

IABEL	DESC RIPTIO N
Interface Type	Select the type of the IPv6 interface through which the IPv6 packets are forwarded.
	The Switch supports only the VLAN interface type at the time of writing.
Interface ID	Enter the ID number of the IPv6 interface through which the IPv6 packets are forwarded.
Route Destination	Enter the IPv6 address of the final destination.
Prefix Length	Enter the prefix length number of up to 64 for this destination.
Next Hop	Enter the IPv6 address of the next-hop router.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

Table 243 NETWORKING > Static Routing > IPv6 Static Route > Add/Edit

# C HAPTER 64 SEC URITY

The following chapters introduces the configurations of the links under the SEC URITY navigation panel.

Quick links to chapters:

- AAA
- Access Control
- Classifier
- Policy Rule
- Anti-Arpscan
- BPDU Guard
- Storm Control
- Error-Disable
- IP Source Guard
- DHCP Snooping
- ARP Inspection
- IPv6 Source Guard
- Port Authentication
- Port Security

# C HAPTER 65 AAA

# 65.1 Authentication, Authorization and Accounting (AAA)

This chapter describes how to configure authentication, authorization and accounting settings on the Switch.

The external servers that perform authentication, authorization and accounting functions are known as AAA servers. The Switch supports RADIUS (Remote Authentication Dial-In User Service) and TACACS+ (Terminal Access Controller Access-Control System Plus) as the external authentication, authorization, and accounting server.





#### 65.1.1 What You Can Do

- use the **RADIUS Server Setup** screen (Section 65.2 on page 430) to configure your RADIUS server settings.
- Use the TACACS+ Server Setup screen (Section 65.3 on page 432) to configure your TACACS+ authentication settings.
- Use the AAA Setup screen (Section 65.4 on page 434) to configure authentication, authorization and accounting settings, such as the methods used to authenticate users accessing the Switch and which database the Switch should use first.

## 65.1.2 What You Need to Know

Authentication is the process of determining who a user is and validating access to the Switch. The Switch can authenticate users who try to log in based on user accounts configured on the Switch itself. The Switch can also use an external authentication server to authenticate a large number of users.

Authorization is the process of determining what a user is allowed to do. Different user accounts may have higher or lower privilege levels associated with them. For example, user A may have the right to create new login accounts on the Switch but user B cannot. The Switch can authorize users based on user accounts configured on the Switch itself or it can use an external server to authorize a large number of users.

Accounting is the process of recording what a user is doing. The Switch can use an external server to

track when users log in, log out, execute commands and so on. Accounting can also record system related actions such as boot up and shut down times of the Switch.

#### Local User Accounts

By storing user profiles locally on the Switch, your Switch is able to authenticate and authorize users without interacting with a network AAA server. However, there is a limit on the number of users you may authenticate in this way.

#### RADIUS

RADIUS is a security protocol used to authenticate users by means of an external server instead of (or in addition to) an internal device user database that is limited to the memory capacity of the device. In essence, RADIUS authentication allows you to validate an unlimited number of users from a central location.

#### RADIUS and TACACS+

RADIUS and TACACS+ are security protocols used to authenticate users by means of an external server instead of (or in addition to) an internal device user database that is limited to the memory capacity of the device. In essence, RADIUS and TACACS+ authentication both allow you to validate an unlimited number of users from a central location.

The following table describes some key differences between RADIUS and TACACS+.

	RADIUS	TACACS+	
Transport Protocol	UDP (User Datagram Protocol)	TCP (Transmission Control Protocol)	
Encryption	Encrypts the password sent for authentication.	All communication between the client (the Switch) and the TACACS server is encrypted.	

Table 244 RADIUS vs. TACACS+

# 65.2 RADIUS Server Setup

Use this screen to configure your RADIUS server settings. Click SEC URITY > AAA > RADIUS Server Setup to view the screen as shown.

Figure	323	SECURITY >	AAA >	RADIUS Server Setup
rig uic	040		~~~~	

KADIUS Server S	elup				
Authenticolion	Server				
$\Delta h \approx h^{-1}$	na hara tanàn				
Terena I	25	1. 9 9. A. FI			
Dele's	Indec	IF ACIENCE	UDV Poř	shared secret	uncrypted shored secret
=	1	0.000	22.2		
	5	(4)(2)(	112		
le e a s. l		and the			
Delete	Louie e	P Asiatra	LIDE Bark	United General	Para galeri Darari Leverd
_	1	(d)(2))	1.18		
	2	00.20			
Afribute Marinacomp	1.000		Acaty (	-0 1% H	

Table 245	SECURITY > AAA > RADIUS Server Setup
-----------	--------------------------------------

LABEL	DESC RIPTIO N	
Authentication Server		
Use this section to configure your RADIUS authentication settings.		
Mode	This field is only valid if you configure multiple RADIUS servers.	
	Select <b>index-priority</b> and the Switch tries to authenticate with the first configured RADIUS server, if the RADIUS server does not respond then the Switch tries to authenticate with the second RADIUS server.	
	Select $\mathbf{w}$ und- $\mathbf{w}$ bin to alternate between the RADIUS servers that it sends authentication requests to.	
Timeout	Specify the amount of time in seconds that the Switch waits for an authentication request response from the RADIUS server.	
	If you are using two RADIUS servers then the timeout value is divided between the two RADIUS servers. For example, if you set the timeout value to 30 seconds, then the Switch waits for a response from the first RADIUS server for 15 seconds and then tries the second RADIUS server.	
Delete	Check this box if you want to remove an existing RADIUS server entry from the Switch. This entry is deleted when you click <b>Apply</b> .	
Index	This is a read-only number representing a RADIUS server entry.	
IP Address	Enter the IP address of an external RADIUS server in dotted decimal notation.	
UDP Port	The default port of a RADIUS server for authentication is <b>1812</b> . You need not change this value unless your network administrator instructs you to do so.	
Shared Secret	Specify a password (up to 32 alphanumeric characters except [?], [ ], ['], ["] or [,]) as the key to be shared between the external RADIUS server and the Switch. This key is not sent over the network. This key must be the same on the external RADIUS server and the Switch.	

LABEL	DESC RIPTIO N
Encrypted Shared Secret	This displays the encrypted shared secret in '*' format if yo∪ enabled Server Key Encryption in SEC URTY > AAA > AAA Setup.
	Note: If you forget the key you set, simply reset the key in the <b>Shared Secret</b> field. If a key is encrypted, it will remain in the encrypted format even if you later disable <b>Server Key Encryption</b> in <b>SEC URITY</b> > <b>AAA</b> > <b>AAA Se tup</b> .
	Note: The shared secret displayed in this field does not present the actual length of the shared secret.
Accounting Server	
Use this section to configure your RADIUS accounting server settings.	
Timeout	Specify the amount of time in seconds that the Switch waits for an accounting request response from the RADIUS accounting server.
Delete	Check this box if you want to remove an existing RADIUS accounting server entry from the Switch. This entry is deleted when you click <b>Apply</b> .
Index	This is a read-only number representing a RADIUS accounting server entry.
IP Address	Enter the IP address of an external RADIUS accounting server in dotted decimal notation.
UDP Port	The default port of a RADIUS accounting server for accounting is <b>1813</b> . You need not change this value unless your network administrator instructs you to do so.
Shared Secret	Specify a password (up to 32 alphanumeric characters except [?], [ ], ['], ["] or [,]) as the key to be shared between the external RADIUS accounting server and the Switch. This key is not sent over the network. This key must be the same on the external RADIUS accounting server and the Switch.
Encrypted Shared Secret	This displays the encrypted shared secret in '*' format if you enabled Server Key Encryption in SEC URITY > AAA > AAA Setup.
	Note: If you forget the key you set, simply reset the key in the <b>Shared Secret</b> field. If a key is encrypted, it will remain in the encrypted format even if you later disable <b>Server Key Encryption</b> in <b>SEC URTY</b> > <b>AAA</b> > <b>AAA Setup</b> .
	Note: The shared secret displayed in this field does not present the actual length of the shared secret.
Attribute	
Use this section to define the RADIUS server attribute for its account.	
NAS-IP-Address	Enter the IP address of the NAS (Network Access Server).
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.
,	

# 65.3 TACACS+ Server Setup

Use this screen to configure your TACACS+ server settings. Click SEC URTIY > AAA > TACACS+ Server Setup to view the screen as shown.

Figure 324	SECURITY > AAA > TACACS+ Server Setup
rig ule 044	

TACACS+ S	erver Seb	up.			
Authentica	fion Serv	er			
Mode Timeout	3	ndex-priofity 🕶 D seconds			
Delete	Index	IP Address	TCP Fort	Shored Secret	Encrypted Shared Secret
	I.	0.0.0	49		
	2	0.0.0	49		
Accounting	g Server				
Timeout	3	0 seconds			
Delete	Index	IP Address	TCP Port	Shared Secret	Encrypted Shared Secret
	I.	0.0.00	49		
	2	0.0.0.0	47		
			Apply	Cancel	

The following table describes the labels in this screen.

#### Table 246 SECURITY > AAA > TACACS+ Server Setup

LABEL	DESC RIPTIO N
Authentication Se	rver
Use this section to	configure your TACACS+ authentication settings.
Mode	This field is only valid if you configure multiple TACACS+ servers.
	Select <b>index-priority</b> and the Switch tries to authenticate with the first configured TACACS+ server, if the TACACS+ server does not respond then the Switch tries to authenticate with the second TACACS+ server.
	Select $\mathbf{wund}$ - $\mathbf{wbin}$ to alternate between the TACACS+ servers that it sends authentication requests to.
Timeout	Specify the amount of time in seconds that the Switch waits for an authentication request response from the TACACS+ server.
	If you are using <b>index-priority</b> for your authentication and you are using two TACACS+ servers then the timeout value is divided between the two TACACS+ servers. For example, if you set the timeout value to 30 seconds, then the Switch waits for a response from the first TACACS+ server for 15 seconds and then tries the second TACACS+ server.
Delete	Check this box if you want to remove an existing TACACS+ server entry from the Switch. This entry is deleted when you click <b>Apply</b> .
Index	This is a read-only number representing a TACACS+ server entry.
IP Address	Enter the IP address of an external TACACS+ server in dotted decimal notation.
TCP Port	The default port of a TACACS+ server for authentication is 49. You need not change this value unless your network administrator instructs you to do so.

XGS2220 Series User's Guide

	DECOMPTON N
IABEL	DESC RIPTIO N
Shared Secret	Specify a password (up to 32 alphanumeric characters except [?], [ ], ['], ['] or [,]) as the key to be shared between the external TACACS+ server and the Switch. This key is not sent over the network. This key must be the same on the external TACACS+ server and the Switch.
Encrypted Shared Secret	This displays the encrypted shared secret in '*' format if you enabled Server Key Encryption in SEC URITY > AAA > AAA Setup.
	Note: If you forget the key you set, simply reset the key in the <b>Shared Secret</b> field. If a key is encrypted, it will remain in the encrypted format even if you later disable <b>Server Key Encryption</b> in <b>SEC URITY</b> > <b>AAA</b> > <b>AAA Setup</b> .
	Note: The shared secret displayed in this field does not present the actual length of the shared secret.
Accounting Serve	r
Use this section to	configure your TACACS+ accounting settings.
Timeout	Specify the amount of time in seconds that the Switch waits for an accounting request response from the TACACS+ server.
Delete	Check this box if you want to remove an existing TACACS+ accounting server entry from the Switch. This entry is deleted when you click <b>Apply</b> .
Index	This is a read-only number representing a TACACS+ accounting server entry.
IP Address	Enter the IP address of an external TACACS+ accounting server in dotted decimal notation.
TCP Port	The default port of a TACACS+ accounting server is 49. You need not change this value unless your network administrator instructs you to do so.
Shared Secret	Specify a password (up to 32 alphanumeric characters except [?], [ ], ['], ["] or [,]) as the key to be shared between the external TACACS+ accounting server and the Switch. This key is not sent over the network. This key must be the same on the external TACACS+ accounting server and the Switch.
Encrypted Shared Secret	This displays the encrypted shared secret in '*' format if you enabled Server Key Encryption in SEC URITY > AAA > AAA Setup.
	Note: If you forget the key you set, simply reset the key in the <b>Shared Secret</b> field. If a key is encrypted, it will remain in the encrypted format even if you later disable <b>Server Key Encryption</b> in <b>SEC URITY</b> > <b>AAA</b> > <b>AAA Setup</b> .
	Note: The shared secret displayed in this field does not present the actual length of the shared secret.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 246	SECURITY >	AAA > TACACS+ Server Setu	o (continued)
-----------	------------	---------------------------	---------------

# 65.4 AAA Setup

Use this screen to configure authentication, authorization and accounting settings on the Switch. Click SEC URTIY > AAA > AAA Se tup to view the screen as shown.

AAA Setup					
Server Key Encr	ryption				
Active	() on				
Authentication					
Тура		Welhod 1	Mathod 2		Method 3
Publicate Intob	in	lacal v		l	. v
Legin		lacal v	• •	j	• •
athorization					
lype		Active	Console		Method
Lixed		07			radius – v
Della		07	•		inclus
Accounting					
Ipplote Period	0	minutes			
Тура	Active	Broodcost	Mode	Wathod	Privilege
System	() arr			radius - M	
Exerc.	() an		stort stop M	radiis i M	
Doffs	() ctt		start stop 🛩	<u>ເວດໃນ</u> ~	-
Commenced	O CH		alop-only	harcea+	0 👻
		والربية	Cancel		

Figure 325 SECURITY > AAA > AAA Setup

The following table describes the labels in this screen.

#### Table 247 SECURITY > AAA > AAA Setup

IABEL	DESC RIPIIO N		
Server Key Encrypti	Server Key Encryption		
Use this section to a	configure server key encryption settings.		
Active	Enable the switch button to enable server key (shared secret) encryption for RADIUS server and TACACS+ server for security enhancement.		
	The shared secret will be stored on the Switch in an encrypted format and displayed as '*' in the SEC URITY > AAA > RADIUS Server Setup and SEC URITY > AAA > TACACS+ Server Setup screens.		

LABEL	DESC RIPTIO N
Authentication	
Use this section to	o specify the methods used to authenticate users accessing the Switch.
Privilege Enable	These fields specify which database the Switch should use (first, second and third) to authenticate access privilege level for administrator accounts (users for Switch management
	Configure the access privilege of accounts through commands (see the Ethernet Switch CLI Reference Guide) for <b>local</b> authentication. The <b>TACACS</b> + and <b>RADIUS</b> are external servers. Before you specify the priority, make sure you have set up the corresponding database correctly first.
	You can specify up to three methods for the Switch to authenticate the access privilege level of administrators. The Switch checks the methods in the order you configure them (first <b>Method</b> <b>1</b> , then <b>Method 2</b> and finally <b>Method 3</b> ). You must configure the settings in the <b>Method 1</b> field. you want the Switch to check other sources for access privilege level specify them in <b>Method</b> and <b>Method 3</b> fields.
	Select $\log c  a  l$ to have the Switch check the access privilege configured for local authentication
	Select <b>radius</b> or <b>tacacs</b> + to have the Switch check the access privilege through the external servers.
Login	These fields specify which database the Switch should use (first, second and third) to authenticate administrator accounts (users for Switch management).
	Configure the local user accounts in the <b>SYSTEM</b> > <b>Logins</b> screen. The TACACS+ and RADIUS are external servers. Before you specify the priority, make sure you have set up the corresponding database correctly first.
	You can specify up to three methods for the Switch to authenticate administrator accounts. The Switch checks the methods in the order you configure them (first <b>Method 1</b> , then <b>Method 3</b> and finally <b>Method 3</b> ). You must configure the settings in the <b>Method 1</b> field. If you want the Switch to check other sources for administrator accounts, specify them in <b>Method 2</b> and <b>Method 3</b> fields.
	Select $local$ to have the Switch check the administrator accounts configured in the SYSTEM > $logins$ screen.
	Select $\mathbf{mdius}$ to have the Switch check the administrator accounts configured through the RADIUS Server.
	Select $tacacs+$ to have the Switch check the administrator accounts configured through the TACACS+ Server.
Authorization	
Use this section to	o configure authorization settings on the Switch.
Туре	Set whether the Switch provides the following services to a user.
	<ul> <li>Exec: Allow an administrator which logs into the Switch through Telnet or SSH to have a different access privilege level assigned through the external server.</li> <li>Dot1x: Allow an IEEE 802.1x client to have different bandwidth limit or VLAN ID assigned through the external server.</li> </ul>
Active	Enable the switch button to activate authorization for a specified event type.
Console	Select this to allow an administrator which logs in the Switch through the console port to have different access privilege level assigned through the external server.
Method	Select whether you want to use radius or tacacs+ for authorization of specific types of events
	RADIUS is the only method for IEEE 802.1x authorization.

IABEL	DESC RIPIIO N
Update Period	This is the amount of time in minutes before the Switch sends an update to the accounting server. This is only valid if you select the <b>start-stop</b> option for the <b>Exec</b> or <b>Dot1x</b> entries.
Туре	The Switch supports the following types of events to be sent to the accounting servers:
	• <b>System</b> – Configure the Switch to send information when the following system events occur: system boots up, system shuts down, system accounting is enabled, system accounting is disabled.
	• Exec – Configure the Switch to send information when an administrator logs in and logs out through the console port, telnet or SSH.
	<ul> <li>Dot1x – Configure the Switch to send information when an IEEE 802.1x client begins a session (authenticates through the Switch), ends a session as well as interim updates of a session.</li> </ul>
	<ul> <li>Commands – Configure the Switch to send information when commands of specified privilege level and higher are executed on the Switch.</li> </ul>
Active	Enable the switch button to activate accounting for a specified event type.
Broadcast	Select this to have the Switch send accounting information to all configured accounting servers at the same time.
	If you do not select this and you have two accounting servers set up, then the Switch sends information to the first accounting server and if it does not get a response from the accounting server then it tries the second accounting server.
Mode	The Switch supports two modes of recording login events. Select:
	• <b>start-stop</b> – to have the Switch send information to the accounting server when a user begins a session, during a user's session (if it lasts past the <b>Update Period</b> ), and when a user ends a session.
	• <b>stop-only</b> – to have the Switch send information to the accounting server only when a user ends a session.
Method	Select whether you want to use radius or tacacs+ for accounting of specific types of events.
	tacacs+ is the only method for recording Commands type of event.
Privilege	This field is only configurable for <b>Commands</b> type of event. Select the threshold command privilege level for which the Switch should send accounting information. The Switch will send accounting information when commands at the level you specify and higher are executed on the Switch.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click <b>Cancel</b> to begin configuring this screen afresh.

# 65.5 Technical Reference

This section provides technical background information on the topics discussed in this chapter.

## 65.5.1 Vendor Specific Attribute

RFC 2865 standard specifies a method for sending vendor-specific information between a RADIUS server and a network access device (for example, the Switch). A company can create Vendor Specific Attributes (VSAs) to expand the functionality of a RADIUS server.

The Switch supports VSAs that allow you to perform the following actions based on user authentication:

- Limit bandwidth on incoming or outgoing traffic for the port the user connects to.
- Assign account privilege levels (See the CLI Reference Guide for more information on account privilege levels) for the authenticated user.

The VSAs are composed of the following:

- Vendor ID: An identification number assigned to the company by the IANA (Internet Assigned Numbers Authority). Zyxel's vendor ID is 890.
- Vendor-Type: A vendor specified attribute, identifying the setting you want to modify.
- Vendor data: A value you want to assign to the setting.
- Note: Refer to the documentation that comes with your RADIUS server on how to configure VSAs for users authenticating through the RADIUS server.

The following table describes the VSAs supported on the Switch.

The following table describes the VSAs supported on the Switch. Note that these attributes only work when you enable authorization (see Section 65.4 on page 434).

FUNC TIO N	ATIRIBUIE
Ingress Bandwidth Assignment	Vendor-Id = <b>890</b> Vendor-Type = <b>1</b> Vendor-data = ingress rate (Kbps in decimal format)
Egress Bandwidth Assignment	Vendor-Id = <b>890</b> Vendor-Type = <b>2</b> Vendor-data = egress rate (Kbps in decimal format)
Privilege Assignment	<pre>Vendor-ID = 890 Vendor-Type = 3 Vendor-Data = "shell:priv-lvl=N" or Vendor-ID = 9 (CISCO) Vendor-Type = 1 (CISCO-AVPAIR) Vendor-Data = "shell:priv-lvl=N" where N is a privilege level (from 0 to 14). Note: If you set the privilege level of a login account differently on the RADIUS servers and the Switch, the user is assigned a privilege level from the database (RADIUS or local) the Switch uses first for user authentication.</pre>

Table 248 Supported VSAs

#### 65.5.1.1 Tunnel Protocol Attribute

You can configure tunnel protocol attributes on the RADIUS server (refer to your RADIUS server documentation) to assign a port on the Switch to a VLAN based on IEEE 802.1x authentication. The port VLAN settings are fixed and untagged. This will also set the port's VID. The following table describes the values you need to configure. Note that these attributes only work when you enable authorization (see Section 65.4 on page 434).

FUNC TIO N	ATIRIBUIE
VLAN Assignment	Tunnel-Type = <b>VLAN(13)</b> Tunnel-Medium-Type = <b>802(6)</b> Tunnel-Private-Group-ID = <b>VLAN ID</b>
	Note: You must also create a VLAN with the specified VID on the Switch.
	Note: The bolded values in this table are fixed values as defined in RFC 3580.

Table $2/9$	Supported Tunnel Protocol Attribute
10016 249	supponed tunnel Protocol Attribute

## 65.5.2 Supported RADIUS Attributes

Remote Authentication Dial-In User Service (RADIUS) attributes are data used to define specific authentication elements in a user profile, which is stored on the RADIUS server. This section lists the RADIUS attributes supported by the Switch.

Refer to RFC 2865 for more information about RADIUS attributes used for authentication.

Refer to RFC 2866 and RFC 2869 for RADIUS attributes used for accounting.

This section lists the attributes used by authentication functions on the Switch. In cases where the attribute has a specific format associated with it, the format is specified.

## 65.5.3 Attributes Used for Authentication

The following sections list the attributes sent from the Switch to the RADIUS server when performing authentication.

#### 65.5.3.1 Attributes Used for Authenticating Privilege Access

User-Name

- The format of the User-Name attribute is e nab #, where # is the privilege level (1 - 14).

User-Password

NAS-Identifier

NAS-IP-Address

#### 65.5.3.2 Attributes Used to Login Users

User-Name User-Password NAS-Identifier NAS-IP-Address

#### 65.5.3.3 Attributes Used by the IEEE 802.1x Authentication

User-Name NAS-Identifier NAS-IP-Address NAS-Port NAS-Port-Type - This value is set to **Ethe met(15)** on the Switch. Calling-Station-Id Frame-MTU EAP-Message State Message-Authenticator

## 65.5.4 Attributes Used for Accounting

The following sections list the attributes sent from the Switch to the RADIUS server when performing authentication.

#### 65.5.4.1 Attributes Used for Accounting System Events

NAS-IP-Address

NAS-Identifier

Acct-Status-Type

Acct-Session-ID

- The format of Acct-Session-Id is **date+time+8-digit sequential number**, for example, 2007041917210300000001. (date: 2007/04/19, time: 17:21:03, serial number: 00000001)

Acct-Delay-Time

#### 65.5.4.2 Attributes Used for Accounting Exec Events

The attributes are listed in the following table along with the time that they are sent (the difference between Console and Telnet/SSH Exec events is that the Telnet/SSH events utilize the Calling-Station-Id attribute):

ATIRIBUIE	START	INTERIM-UPDATE	STOP
User-Name	~	~	<b>&gt;</b>
NAS-Identifier	~	~	<b>~</b>
NAS-IP-Address	~	<b>~</b>	~
Service-Type	~	✓	<b>~</b>
Acct-Status-Type	~	<b>~</b>	<b>~</b>
Acct-Delay-Time	~	~	<b>~</b>
Acct-Session-Id	~	~	<b>~</b>
Acct-Authentic	<b>v</b>	~	>

Table 250 RADIUS Attributes – Exec Events through Console

Table 250	RADIUS Attributes – Ex	ec Events through	Console (continued)

ATIRIBUIE	START	INTERIM-UPDATE	STOP
Acct-Session-Time		~	~
Acct-Terminate-Cause			<

Table 251 RADIUS Attributes – Exec Events through Telnet/SSH

ATIRIBUIE	START	INTERIM-UPDATE	STOP
User-Name	~	✓	~
NAS-Identifier	~	¥	~
NAS-IP-Address	~	~	~
Service-Type	~	✓	~
Calling-Station-Id	~	✓	~
Acct-Status-Type	~	~	~
Acct-Delay-Time	~	~	~
Acct-Session-Id	~	✓	~
Acct-Authentic	~	~	~
Acct-Session-Time		✓	~
Acct-Terminate-Cause			~

#### 65.5.4.3 Attributes Used for Accounting IEEE 802.1x Events

The attributes are listed in the following table along with the time of the session they are sent:

ATIRIBUIE	START	INTERIM-UPDATE	STO P
User-Name	~	~	~
NAS-IP-Address	~	~	~
NAS-Port	~	~	~
Class	~	~	~
Called-Station-Id	~	~	~
Calling-Station-Id	~	~	¥
NAS-Identifier	~	~	~
NAS-Port-Type	~	✓	~
Acct-Status-Type	~	~	¥
Acct-Delay-Time	~	~	~
Acct-Session-Id	~	✓	~
Acct-Authentic	~	~	¥
Acct-Input-Octets		~	~
Acct-Output-Octets		~	~
Acct-Session-Time		~	~
Acct-Input-Packets		✓	<b>~</b>

Table 252 RADIUS Attributes – Exec Events through Console

Table 252 RADIUS Attributes - Exec Events through Console (continued)

ATIRIBUIE	START	INTERIM - UPDATE	STO P
Acct-Output-Packets		•	~
Acct-Terminate-Cause			<b>v</b>
Acct-Input-Gigawords		~	<b>~</b>
Acct-Output-Gigawords		<b>~</b>	<b>~</b>

# C HAPTER 66 Access Control

# 66.1 Access Control Overview

This chapter describes how to control access to the Switch.

A console port and FTP are allowed one session each, Telnet and SSH share nine sessions, up to five web sessions (five different user names and passwords) and/or limitless SNMP access control sessions are allowed.

Table 253 Access Control Overview

Console Port	SSH	Telnet	FTP	Web	SNMP
One session	Share up to 9 s	sessions	One session	Up to 5 accounts	No limit

A console port access control session and Telnet access control session cannot coexist when multi-login is disabled. See the CLI Reference Guide for more information on disabling multi-login.

## 66.1.1 What You Can Do

- Use the Service Access Control screen (Section 66.2 on page 443) to decide what services you may use to access the Switch.
- Use the **Remote Management** screen (Section 66.3 on page 444) to specify a group of one or more "trusted computers" from which an administrator may use a service to manage the Switch.
- Use the Account Security screen (Section 66.4 on page 445) to encrypt all passwords configured in the Switch. You can also display the authentication, authorization, external authentication server information (RADIUS or TACACS+), system and SNMP user account information in the configuration file saved.

# 66.2 Service Access Control

Service Access Control allows you to decide what services you may use to access the Switch. You may also change the default service port and configure "trusted computers" for each service in the SEC URITY > Access Control > Remote Management screen (discussed later). Click SEC URITY > Access Control > Control > Service Access Control to display the following screen.

Tervices	Active	Service Port	1	Imeout	Logi	(Triesul)
Centrole			4	Ninoles		
Tubrat	01	225	3	Minutes	150	Second
100	Con Co	22				
117	010	21	1	[Gestaid		
SUL	CONT	10	3.	(virsuble)		
H1775	(Cal.)	442				
1C1//P	Case Co					
2002	CONT					

The following table describes the fields in this screen.

LABEL	DESC RIPTIO N
Services	Services you may use to access the Switch are listed here.
Active	Enable the switch button for the corresponding services that you want to allow to access the Switch.
Service Port	For Telnet, SSH, FTP, HTTP or HTTPS services, you may change the default service port by typing the new port number in the <b>Service Port</b> field. If you change the default port number then you will have to let people (who wish to use the service) know the new port number for that service.
Timeout	Enter how many minutes (from 1 to 255) a management session can be left idle before the session times out. After it times out you have to log in with your password again. Very long idle timeouts may have security risks.
Login Timeout	The Telnet or SSH server do not allow multiple user logins at the same time. Enter how many seconds (from 30 to 300 seconds) a login session times out. After it times out you have to start the login session again. Very long login session timeouts may have security risks.
	For example, if User A attempts to connect to the Switch (through SSH), but during the login stage, do not enter the user name and/or password, User B cannot connect to the Switch (through SSH) before the <b>Login Timeout</b> for User A expires (default 150 seconds).
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 254 SECURITY > Access Control > Service Access Control

# 66.3 Remote Management

Use this screen to specify a group of one or more "trusted computers" from which an administrator may use a service to manage the Switch.

Click SEC URITY > Access Control > Remote Management to view the screen as shown next.

ecured C	llent Setup	0								
Linity	Active	Storf Address	End Address	Teinet	rn•	HIIP	ICMP	SNWP	35H	HTTPS
1	( ON ()	0.0.00	0.0.0.0		1	$[\mathcal{A}]$	$\sim$	$\mathbb{Z}$	$\sim$	1
2	0.07	0000	80.00							
3	🔵 o#)	) onnii	0.0.00							
4	0.07	onun	0.0.00							
5	) OF	)  onnu	0.0.00							
6	) ar	0000	0.0.00							
7	🔵 an j	0.0.00	0.0.00							
					$\sim$		$\sim$			

Figure 327 SECURITY > Access Control > Remote Management

The following table describes the labels in this screen.

Table 255 SECURITY > Access Control > Remote Management

IABEL	DESC RIPIIO N			
Entry	This is the client set index number. A "client set" is a group of one or more "trusted computers" from which an administrator may use a service to manage the Switch.			
Active	Enable the switch button to activate this secured client set. Clear the check box if you wish to temporarily disable the set without deleting it.			
Start Address	Configure the IP address range of trusted computers from which you can manage this Switch.			
End Address	The Switch checks if the client IP address of a computer requesting a service or protocol matches the range set here. The Switch immediately disconnects the session if it does not match.			
Telnet / FTP / HTTP / ICMP / SNMP / SSH / HTTPS	Select services that may be used for managing the Switch from the specified trusted computers.			
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.			
Cancel	Click Cancel to begin configuring this screen afresh.			

# 66.4 Account Security

Use this screen to encrypt all passwords configured in the Switch. This setting will affect how the password is shown (as plain text or encrypted text) in the configuration file saved in **MAINTENANCE** > **Configuration** > **Save Configuration**.

Note: Make sure to enable **Password Encryption** to avoid displaying passwords as plain text in the configuration file.

Note: Be careful who can access configuration files with plain text passwords!

**Password Encryption** encrypts all passwords in the configuration file. However, if you want to show some passwords as plain text in the configuration file, select them as below:

- Authentication information configured for Authentication in the SEC URITY > AAA > AAA Setup screen (Method 1/2/3 setting in the Privilege Enable and Login fields).
- Authorization information configured for Authorization in the SEC URITY > AAA > AAA Setup screen (Active/Console/Method setting in the Exec and Dot1x fields).
- Server information configured for Authentic ation Server in the SEC URTIY > AAA > RADIUS Server Setup screen, and for Authentic ation Server in the SEC URTIY > AAA > TACACS+ Server Setup screen (Mode / Time out fields).
- System account information configured in the Switch (admin, user login name, and password).
- **SNMP** user account information configured in the **SYSTEM** > **SNMP** > **SNMP** User screen (password for SNMP user authentication in the **Authentication** field, and the password for the encryption method for SNMP communication in the **Privacy** field).

Note: The passwords will appear as encrypted text when Password Encryption is Active.

Click SEC URITY > Access Control > Account Security to view the screen as shown next.

Account Security
Account Security
Password Energy I on 🗍 💷
Apply Concel
Display
□ AAA
Av her fication 🔄 Av horizotion 🔄 Server
User
□ System □ SNMP
Acety Concel

Figure 328 SECURITY > Access Control > Account Security

The following table describes the labels in this screen.

LABEL	DESC RIPIIO N			
Account Secu	rity			
Password Encryption	Select this check box to encrypt all passwords configured on the Switch. This displays the password as encrypted text, in a saved configuration file.			
	Otherwise, the passwords configured on the Switch are displayed in plain text.			
Apply	Click <b>Apply</b> to save your changes for <b>Account Security</b> to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.			
Cancel	Click Cancel to begin configuring Account Security afresh.			
Display				
Display	<ul> <li>Select which specific information to display in plain text, in the saved configuration file.</li> <li>Authentic a tion</li> <li>Authorization</li> <li>Server</li> </ul>			
User	<ul> <li>Select which user account information to display in plain text, in the saved configuration file.</li> <li>System</li> <li>SNMP</li> </ul>			
Apply	Click <b>Apply</b> to save your changes for <b>Display</b> to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.			
Cancel	Click Cancel to begin configuring Display afresh.			

Table 256 SECURITY > Access Control > Account Security

# 66.5 Technical Reference

This section provides technical background information on the topics discussed in this chapter.

### 66.5.1 SSH Overview


Unlike Telnet or FTP, which transmit data in clear text, SSH (Secure Shell) is a secure communication protocol that combines authentication and data encryption to provide secure encrypted communication between two hosts over an unsecured network.





#### 66.5.1.1 How SSH Works

The following table summarizes how a secure connection is established between two remote hosts.



**1** Host Identification

The SSH client sends a connection request to the SSH server. The server identifies itself with a host key. The client encrypts a randomly generated session key with the host key and server key and sends the result back to the server.

The client automatically saves any new server public keys. In subsequent connections, the server public key is checked against the saved version on the client computer.

2 Encryption Method

Once the identification is verified, both the client and server must agree on the type of encryption method to use.

3 Authentication and Data Transmission

After the identification is verified and data encryption activated, a secure tunnel is established between the client and the server. The client then sends its authentication information (user name and password) to the server to log in to the server.

#### 66.5.1.2 SSH Implementation on the Switch

Your Switch supports SSH version 2 using RSA authentication and three encryption methods (DES, 3DES and Blowfish). The SSH server is implemented on the Switch for remote management and file transfer on port 22. Only one SSH connection is allowed at a time.

#### 66.5.1.3 Requirements for Using SSH

You must install an SSH client program on a client computer (Windows or Linux operating system) that is used to connect to the Switch over SSH.

## 66.5.2 Introduction to HTIPS

HTTPS (HyperText Transfer Protocol over Secure Socket Layer, or HTTP over SSL) is a web protocol that encrypts and decrypts web pages. Secure Socket Layer (SSL) is an application-level protocol that enables secure transactions of data by ensuring confidentiality (an unauthorized party cannot read the transferred data), authentication (one party can identify the other party) and data integrity (you know if data has been changed).

It relies upon certificates, public keys, and private keys.

HTTPS on the Switch is used so that you may securely access the Switch using the Web Configurator. The SSL protocol specifies that the SSL server (the Switch) must always authenticate itself to the SSL client (the computer which requests the HTTPS connection with the Switch), whereas the SSL client only should authenticate itself when the SSL server requires it to do so. Authenticating client certificates is optional and if selected means the SSL-client must send the Switch a certificate. You must apply for a certificate for the browser from a Certificate Authority (CA) that is a trusted CA on the Switch.

Please refer to the following figure.

- 1 HTTPS connection requests from an SSL-aware web browser go to port 443 (by default) on the Switch's WS (web server).
- 2 HTTP connection requests from a web browser go to port 80 (by default) on the Switch's WS (web server).




Figure 331 HTTPS Implementation

Note: If you disable HTTP in the Service Access Control screen, then the Switch blocks all HTTP connection attempts.


#### 66.5.2.1 HTIPS Example

If you have not changed the default HTTPS port on the Switch, then in your browser enter "https://Switch IP Address/" as the web site address where "Switch IP Address" is the IP address or domain name of the Switch you wish to access.

#### Mozilla Fire fox Warning Messages


When you attempt to access the Switch HTTPS server, a **Yourconnection is not secure** screen may display. If that is the case, click **I Understand the Risks** and then the **Add Exception...** button.

Figure 332 Security Alert (Mozilla Firefox)



Confirm the HTTPS server URL matches. Click **Confirm Security Exception** to proceed to the Web Configurator login screen.

Figure 333 Security Alert (Mozilla Firefox)



### 66.5.3 Google Chrome Warning Messages

When you attempt to access the Switch HTTPS server, a **Your connection is not private** screen may display. If that is the case, click **Advanced** and then **Proceed to x.x.x.x (unsafe)** to proceed to the Web Configurator login screen.


Figure 334 Security Alert (Google Chrome 99.0.4844.82)

<b>A</b>
Your connection is not private
Attackers might be trying to steat your information from 172.21.40.6 (for example, parawords, messages, or credit cards). Learn more
NOTION CONTINUES INVAUS
Q . To get Chrone's highest level of accurry, and on enhanced protection
Hibe advanced
This server pould not prove that it is 172.81.48 $\epsilon_{\rm c}$ its security certificate is not constraintly
your computer's operating system. The may be caused by a misconfiguration or an attacked intercepting your connection.
Proceed to 17221/200 united

#### 66.5.3.1 Main Settings

After you accept the certificate and enter the login user name and password, the Switch main screen appears. The lock displayed in the bottom right of the browser status bar or next to the website address denotes a secure connection.





# C HA PTER 67 C la ssifie r

# 67.1 Classifier Overview

This chapter introduces and shows you how to configure the packet classifier on the Switch. It also discusses Quality of Service (QoS) and classifier concepts as employed by the Switch.

## 67.1.1 What You Can Do

- Use the Classifier Status screen (Section 67.2 on page 454) to view the classifiers configured on the Switch and how many times the traffic matches the rules.
- Use the **Classifier Setup** screen (Section 67.3 on page 454) to define the classifiers and view a summary of the classifier configuration. After you define the classifier, you can specify actions (or policy) to act upon the traffic that matches the rules.
- Use the Classifier Global Setting screen (Section 67.4 on page 459) to configure the match order and enable logging on the Switch.

## 67.1.2 What You Need to Know

Quality of Service (QoS) refers to both a network's ability to deliver data with minimum delay, and the networking methods used to control the use of bandwidth. Without QoS, all traffic data is equally likely to be dropped when the network is congested. This can cause a reduction in network performance and make the network inadequate for time-critical application such as video-on-demand.

A classifier groups traffic into data flows according to specific criteria such as the source address, destination address, source port number, destination port number or incoming port number. For example, you can configure a classifier to select traffic from the same protocol port (such as Telnet) to form a flow.

Configure QoS on the Switch to group and prioritize application traffic and fine-tune network performance. Setting up QoS involves two separate steps:

- 1 Configure classifiers to sort traffic into different flows.
- 2 Configure policy rules to define actions to be performed on a classified traffic flow (refer to Chapter 68 on page 462 to configure policy rules).

You can also configure policy routing to forward a classified traffic flow to a different gateway for cost savings and load sharing.

## 67.2 Classifier Status

Use this screen to view the classifiers configured on the Switch and how many times the traffic matches the rules.

Click SEC URITY > ACL > Classifier > Classifier Status to display the configuration screen as shown.

Figure 336 SECURITY > ACL > Classifier > Classifier Status

Clossifier S	tatus	Classifier Se	tup Classifi	er Global Sei	fing
Index	Active	Weight	Name	Match Court	Rule
Clear the	Closifier	0.00	O Classifier	G	0.T

The following table describes the labels in this screen.

IABEL	DESC RIPIIO N		
Index	This field displays the index number of the rule.		
Active	This field displays whether the rule is activated or not.		
Weight	This field displays the rule's weight. This is to indicate a rule's priority when the match order is set to $manual$ in the SEC URITY > ACL > Classifier > Classifier Global Setting screen.		
	The higher the number, the higher the rule's priority.		
Name	This field displays the descriptive name for this rule. This is for identification purpose only.		
Match Count	This field displays the number of times a rule is applied. It displays '-' if the rule does not have count enabled.		
Rule	This field displays a summary of the classifier rule's settings.		
Clear the Classifie	er en		
Any	Select Any, then click Clear to clear the matched count for all classifiers.		
Classifier	Select <b>Classifier</b> , enter a classifier rule name and then click <b>Clear</b> to erase the recorded statistical information for that classifier, or select <b>Any</b> to clear statistics for all classifiers.		
Clear	Click <b>Clear</b> to erase the recorded statistical information for the classifier.		

Table 257 SECURITY > ACL > Classifier > Classifier Status

# 67.3 Classifier Setup

Use this screen to view and configure the classifiers. After you define the classifier, you can specify actions (or policy) to act upon the traffic that matches the rules.

Click SEC URITY > ACL > Classifier Setup to display the configuration screen as shown.

Figure 337 SECURITY > ACL > Classifier > Classifier Setup

Classifier Status		Clossifier Setup		Classifier Global Setting		
					O Adoptite	I Towner
1	Index	Active	Weight	Nome		Fulle.

The following table describes the labels in this screen.

Table 258 SECURITY > ACL > Classifier > Classifier Setup

LABEL	DESC RIPTIO N			
Index	This field displays the index number of the rule.			
Active	This field displays $Yes$ when the rule is activated and $No$ when it is deactivated.			
Weight	The field displays the priority of the rule when the match order is in $manual$ mode. A higher weight means a higher priority.			
Name	This field displays the descriptive name for this rule. This is for identification purpose only.			
Rule	This field displays a summary of the classifier rule's settings.			
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.			
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.			
Delete	Click <b>Delete</b> to remove the selected entries.			

The following table shows some other common Ethernet types and the corresponding protocol number.

EIHERNETTYPE	PROTOCOLNUMBER
IP ETHII	0800
X.75 Internet	0801
NBS Internet	0802
ECMA Internet	0803
Chaosnet	0804
X.25 Level 3	0805
XNS Compat	0807
Banyan Systems	OBAD
BBN Simnet	5208
IBM SNA	80D5
AppleTalk AARP	80F3

 Table 259
 Common Ethernet Types and Protocol Numbers

In the Internet Protocol there is a field, called "Protocol", to identify the next level protocol. The following table shows some common protocol types and the corresponding protocol number. Refer to http://www.iana.org/assignments/protocol-numbers for a complete list.

Table 260	Common IP	Protocol	Types and	Protocol Numbers
-----------	-----------	----------	-----------	------------------

PRO TO C O L'TYPE	PRO TO C O L NUMBER	
ICMP	1	
TCP	6	
UDP	17	

Table 260 Common IP Protocol Types and Protocol Numbers

PRO TO C O L TYPE	PRO TO C O L NUMBER	
EGP	8	
L2TP	115	

## 67.3.1 Add/Edit a Classifier

Use this screen to define the classifiers. After you define the classifier, you can specify actions (or policy) to act upon the traffic that matches the rules.

Click Add/Edit, or select an entry and click Add/Edit in the SEC URITY > ACL > Classifier Setup screen to display this screen.

Figure 338 SECURITY > ACL > Classifier > Classifier Setup > Add/Edit

A25-44	1000 E			
0.078		1		
(Despt)	100 - 20 322 747	i		
190	2			
Court	8			
Conseque	NODe Y			
ingreas Rolf				
Part	O Art	0		
Per .	Q.ere	61		
toyec2				
-LAM	0.447	0		
Burg	O.Are	Oles		
$\{a_1^{i_1},\ldots,a_{i_m}^{i_m}\}_{i_m}^{i_m} \cdots$	0	(17922 ]-969		
increase succession and const	Q day	() we premer		
Deat halton // 40 Adams	0.47	(WAD-Was)		
10797.0		a second second second		
-94 (1942)	Q Sec	0		
na been	0.45	-01		
A content of	Q Are	0		
10.	0 4.9			
n march	O St State			
i eta Mitti eta dirik	0	survey ordered bud		
Jource 1 4 optics Thefs		4		
October 17 GARGETERS		81 a.		
toyet4	See.			
Cource Social Number	0.44			
October the territory	Gare	٥ <u>نــــــــــــــــــــــــــــــــــــ</u>		
			ALCONOMIC TO A	
			Acces Chris	Cthod

The following table describes the labels in this screen.

Table 261 SECURITY > ACL > Classifier > Classifier Setup > Add/Edit

IABEL	DESC RIPTIO N				
Active	Enable the switch button to enable this rule.				
Name	Enter a descriptive name for this rule for identifying purposes. You can enter up to 32 printable ASCII characters except [?], [ ], ['], ["] or [,].				
Weight	Enter a number between 0 and 65535 to specify the rule's weight. When the match order is in manual mode in the <b>Classifier Global Setting</b> screen, a higher weight means a higher priority.				
Log	Select this option to have the Switch create a log message when the rule is applied and record the number of matched packets in a particular time interval.				
	Note: Make sure you also enable logging in the Classifier Global Setting screen.				
Count	Select this option to have the Switch count how many times the rule is applied.				
Time Range	Select the name of the pre-configured schedule that you want to apply to the rule. The rule will be active only at the scheduled date and/or time.				
	If you select <b>None</b> , the rule will be active all the time.				
Ingress Por	t				
Port	Select Any to apply the rule to all ports.				
	Alternatively, to specify the ports enter the port numbers to which the rule should be applied. You can enter multiple ports separated by (no space) comma (,) or hyphen (-). For example, enter "3-5" for ports 3, 4, and 5. Enter "3,5,7" for ports 3, 5, and 7.				
Trunk	Select <b>Any</b> to apply the rule to all trunk groups.				
	Alternatively, to specify multiple trunks, enter the trunk group ID to apply the rule to multiple trunks. You can enter multiple trunks with (t) or (T) then the trunk group ID separated by (no space) comma (,) or hyphen (-). For example, enter "t3-t5" for trunks 3, 4, and 5. Enter "T3,T5,T7" for trunks 3, 5, and 7.				
Layer 2					
Specify the	e fields below to configure a layer 2 classifier.				
VLAN	Select <b>Any</b> to classify traffic from any VLAN or select the second option and specify the source VLAN ID in the field provided.				
Priority	Select <b>Any</b> to classify traffic from any priority level or select the second option and specify a priority level in the field provided.				
Ethernet Type	Select an Ethernet type or select <b>Other</b> and enter the Ethernet type number in hexadecimal value.				
Source	Select Any to apply the rule to all MAC addresses.				
MAC Address	To specify a source, select <b>MAC</b> / <b>Mask</b> to enter the source MAC address of the packet in valid MAC address format (six hexadecimal character pairs) and type the mask for the specified MAC address to determine which bits a packet's MAC address should match.				
	Enter "f" for each bit of the specified MAC address that the traffic's MAC address should match. Enter "0" for the bits of the matched traffic's MAC address, which can be of any hexadecimal characters. For example, if you set the MAC address to 00:13:49:00:00:00 and the mask to ff:ff:ff:00:00:00, a packet with a MAC address of 00:13:49:12:34:56 matches this criteria. If you leave the <b>Mask</b> field blank, the Switch automatically sets the mask to ff:ff:ff:ff:ff.				

IABEL	DESC RIPTIO N		
Destinatio	Select <b>Any</b> to apply the rule to all MAC addresses.		
n MAC Address	To specify a destination, select <b>MAC</b> / <b>Mask</b> to enter the destination MAC address of the packet in valid MAC address format (six hexadecimal character pairs) and type the mask for the specified MAC address to determine which bits a packet's MAC address should match.		
	Enter "f" for each bit of the specified MAC address that the traffic's MAC address should match. Enter "0" for the bits of the matched traffic's MAC address, which can be of any hexadecimal characters. For example, if you set the MAC address to 00:13:49:00:00:00 and the mask to ff:ff:ff:00:00:00, a packet with a MAC address of 00:13:49:12:34:56 matches this criteria. If you leave the <b>Mask</b> field blank, the Switch automatically sets the mask to ff:ff:ff:ff:ff:ff:ff:ff:ff:ff:ff:ff:ff:		
Layer 3			
Specify the	fields below to configure a layer 3 classifier.		
IPv4/IPv6 DSCP	Select <b>Any</b> to classify traffic from any DSCP or select the second option and specify a DSCP (DiffServ Code Point) number between 0 and 63 in the field provided.		
Preceden ce	Select <b>Any</b> to classify traffic from any precedence or select the second option and specify an IP Precedence (the first 3 bits of the 8-bit ToS field) value between 0 and 7 in the field provided.		
ToS	Select <b>Any</b> to classify traffic from any ToS or select the second option and specify Type of Service (the last 5 bits of the 8-bit ToS field) value between 0 and 255 in the field provided.		
IP Protocol	Select an IPv4 protocol type or select $0$ the r and enter the protocol number in decimal value.		
	You may select <b>Establish Only</b> for <b>TCP</b> protocol type. This means that the Switch will pick out the packets that are sent to establish TCP connections.		
IPv6 Next Header	Select an IPv6 protocol type or select <b>Other</b> and enter an 8-bit next header in the IPv6 packet. The Next Header field is similar to the IPv4 Protocol field. The IPv6 protocol number ranges from 1 to 255.		
	You may select <b>Establish Only</b> for <b>TCP</b> protocol type. This means that the Switch will identify packets that initiate or acknowledge (establish) TCP connections.		
Source IP	Enter a source IP address in dotted decimal notation.		
Address/ Address Prefix	Specify the address prefix by entering the number of ones in the subnet mask.		
	A subnet mask can be represented in a 32-bit notation. For example, the subnet mask "255.255.255.0" can be represented as "11111111111111111111000000000", and counting up the number of ones in this case results in 24.		
Destinatio	Enter a destination IP address in dotted decimal notation.		
n IP Address/ Address Prefix	Specify the address prefix by entering the number of ones in the subnet mask.		
Layer 4			
Specify the	fields below to configure a layer 4 classifier.		
Source Socket Number	Select <b>Any</b> to apply the rule to all TCP/UDP protocol port numbers or select the second option and enter a TCP/UDP protocol port number.		
NUTIDEI	Note: You must select either <b>UDP</b> or <b>TCP</b> in the <b>IP Protocol</b> field before you configure the socket numbers.		
Destinatio n Socket Number	Select <b>Any</b> to apply the rule to all TCP/UDP protocol port numbers or select the second option and enter a TCP/UDP protocol port number.		
	Note: You must select either <b>UDP</b> or <b>TCP</b> in the <b>IP Protocol</b> field before you configure the socket numbers.		
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.		

Table 261 SECURITY > ACL > Classifier > Classifier Setup > Add/Edit (continued)

XGS2220 Series User's Guide

Table 261 SECURITY > ACL > Classifier > Classifier Setup > Add/Edit (continued)

LABEL	DESC RIPTIO N
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

# 67.4 Classifier Global Setting

Use this screen to configure the match order and enable logging on the Switch. Click SEC URTY > ACL >  $C \ln ssifier > C \ln ssifier G \log b a l Setting$  to display the configuration screen as shown.

Classifier Statu	s Classifier Selup	Classifier Global Selling
Moleh Order Looging	auto v Active 3800 Interval 3800	
	Apply Con	vel

The following table describes the labels in this screen.

IABEL	DESC RIPTIO N
Match	Use this field to set the match order for the classifier rules.
Order	A traffic flow can only be classified to one classifier. When a traffic flow matches more than one classifier rule, the Switch classifies the traffic based on the <b>Match Order</b> .
	Select <b>manual</b> to have classifier rules applied according to the weight of each rule you configured in <b>SEC URITY</b> > <b>ACL</b> > <b>Classifier</b> > <b>Classifier</b> Setup. If they have the same weight, the Switch will classify the traffic to the classifier with a higher name priority (see <b>ClassifierName Priority</b> ).
	Alternatively, select <b>auto</b> to have classifier rules applied according to the layer of the item configured in the rule. Layer-4 items have the highest priority, and layer-2 items has the lowest priority. For example, you configure a layer-2 item (VLAN ID) in classifier A and configure a layer-3 item (source IP address) in classifier B. When an incoming packet matches both classifier rules, classifier B has priority over classifier A. If both classifiers have the same priority, the Switch will apply the classifier with a higher name priority.
	C la ssifie r Na m e Priority
	The longer the classifier name, the higher the classifier priority. If two classifier names are the same length, the bigger the character, the higher the classifier priority. The lowercase letters (such as a and b) have higher priority than the capitals (such as A and B) in the classifier name. For example, the classifier with the name of class 2, class a or class B takes priority over the classifier with the name of class 1 or class A.
Logging	
Active	Enable the switch button to allow the Switch to create a log when packets match a classifier rule during a defined time interval.

IABEL	DESC RIPTIO N
Interval	Set the length of the time period (in seconds) to count matched packets for a classifier rule. Enter an integer from 0 – 65535. 0 means that no logging is done.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

 Table 262
 SECURITY > ACL > Classifier > Classifier Global Setting (continued)

# 67.5 Classifier Example

The following screen shows an example where you configure a classifier that identifies all traffic from MAC address 00:50:ba:ad:4f:81 on port 2.

Adhie	C144 (C)	
tianie	esonole	
Weight	32767	
ing	0	
Count	D.	
The Ronge	tione w	
Pocket Formol	AB	- W
Ingress Part		
Port	C) Any	0 :
25.07M	O Any	0
Liryer 2		
VLAN	O Acr	0
Innae V1494	O Any	0
Pricety	O Ani	0 (0.)
ing our Price by	O Any	0 0.0
Sherlype	O A V	() Offices (Hint)
Selace NAC Address	C Any	OALAC/Mosk 00:500cmoct4191 )/
Oastinction NWC Address	O Any	CARCARE /
taryer 3		
IP Poolet Length	O Arry	D 10 Ustes
Inv4 DSCP	O Aria	0
IPv6 DSCP	O Arry	0
Precedence	O Acce	0
1:0	O Any	0
IP Protocol		Rh Ohk () Otten [Dec]
IPv6 Next Heid det		ablen Only Cottees [] [Dec]
Source P Address/Prefs		VIII
Destruction IP Address Prefix		
Construction and the second second	-	
Layer 4	121	0 10
Source Socker Number	O Arre	Ci (10)

Figure 340 Classifier: Example

After you have configured a classifier, you can configure a policy (in the SEC URITY > ACL > Policy Rule screen) to define actions on the classified traffic flow.

# C HAPTER 68 Policy Rule

## 68.1 Policy Rules Overview

This chapter shows you how to configure policy rules.

A classifier distinguishes traffic into flows based on the configured criteria (refer to Chapter 67 on page 453 for more information). A policy rule ensures that a traffic flow gets the requested treatment in the network.

## 68.1.1 What You Can Do

Use the **Policy Rule** screen (Section 68.2 on page 463) to enable the policy and display the active classifiers you configure in the **Classifier** screen.

### 68.1.2 DiffServ

DiffServ (Differentiated Services) is a class of service (CoS) model that marks packets so that they receive specific per-hop treatment at DiffServ-compliant network devices along the route based on the application types and traffic flow. Packets are marked with DiffServ Code Points (DSCPs) indicating the level of service desired. This allows the intermediary DiffServ-compliant network devices to handle the packets differently depending on the code points without the need to negotiate paths or remember state information for every flow. In addition, applications do not have to request a particular service or give advanced notice of where the traffic is going.

### 68.1.3 DSCP and Per Hop Behavior

DiffServ defines a new DS (Differentiated Services) field to replace the Type of Service (TOS) field in the IP header. The DS field contains a 2-bit unused field and a 6-bit DSCP field which can define up to 64 service levels. The following figure illustrates the DS field.

DSCP is backward compatible with the three precedence bits in the ToS octet so that non-DiffServ compliant, ToS-enabled network device will not conflict with the DSCP mapping.

DSCP (6 bits)	Unused (2 bits)
---------------	-----------------

The DSCP value determines the forwarding behavior, the PHB (Per-Hop Behavior), that each packet gets across the DiffServ network. Based on the marking rule, different kinds of traffic can be marked for different kinds of forwarding. Resources can then be allocated according to the DSCP values and the configured policies.

# 68.2 Polic y Rules

Click SEC URITY > ACL > Policy Rule in the navigation panel to display the screen as shown.

#### Figure 341 SECURITY > ACL > Policy Rule

ley Ru	la				
				O Actibal	· nitw
13	index	Active	Nume	Clossi	fice(s)

The following table describes the labels in this screen.

IABEL	DESC RIPTIO N
Index	This field displays the policy index number.
Active	This field displays whether policy is activated or not.
Name	This field displays the name you have assigned to this policy.
Classifier(s)	This field displays the names of the classifier to which this policy applies.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.
Delete	Click <b>Delete</b> to remove the selected entries.

Table 263 SECURITY > ACL > Policy Rule

## 68.2.1 Add/Edit a Policy Rule

You must first configure a classifier in the SEC URTIY > ACL > Classifier > Classifier Setup screen.

Click Add/Edit, or select an entry and click Add/Edit in the SEC URITY > ACL > Policy Rule screen to display this screen.

Source & Dectinotion Acros	(CT)
NATIO	
Croutery	
General Pasamelete	
You D	
Egnes Fort	
Priority	18-2
taan	
tes.	da →
Relating Forometers	
burdwidth .	0 ISAN
stat of worth name	
Action	
Forwarding	O se thorae O second the provid
niaiy	<ul> <li>It is shonge</li> <li>Set the products 300 interactly</li> <li>Set products statistic priority for with the interactivity to adaptly value.</li> </ul>
Débery	© No Shengri ⊜ Johthe puckerS KOS Red ⊜ Set the Otherry Codepoint field in the Ironse
Culdeing	Lend the pooset to the minor both social the pooset in the algens bath Ref. the poosets Monta
Revenue	(CTT)
	Out of profile action
	Change the protect Change the CCCP volue
	, Acuty Cher Control

Figure 342	SECURITY > ACL > Policy	v Rule > Add/Edit

The following table describes the labels in this screen.

IABEL	DESC RIPTIO N	
Source & Destinat	Source & Destination	
Active	Enable the switch button to enable the policy.	
Name	Enter a descriptive name for identification purposes. You can enter up to 32 printable ASCII characters except [?], [   ], ['], ["] or [,].	
Classifier(s)	This field displays the active classifiers you configure in the SEC URITY $>$ ACL $>$ Classifier $>$ Classifier Setup screen.	
	Select the classifiers to which this policy rule applies. To select more than one classifier, press [SHIFT] and select the choices at the same time.	

Table 264 SECURITY > ACL > Policy Rule > Add/Edit

LABEL	DESC RIPIIO N
General Paramet	ers
Set the fields belo Action field.	w for this policy. You only have to set the fields that is related to the actions you configure in the
Vlan ID	Specify a VLAN ID.
Egress Port	Enter the number of an outgoing port.
Priority	Specify a priority level.
DSCP	Specify a DSCP (DiffServ Code Point) number between 0 and 63.
TOS	Specify the Type Of Service (TOS) priority level.
	ters e the desired bandwidth available to a traffic flow. Traffic that exceeds the maximum bandwidth es where the network is congested) is called out-of-profile traffic.
Bandwidth	Specify the bandwidth in kilobit per second (Kbps). Enter a number between 1 and 1000000.
Out of Profile DSCP	Specify a new DSCP number (between 0 and 63) if you want to replace or remark the DSCP number for out-of-profile traffic.
Action	ns the Switch takes on the associated classified traffic flow.
Outgoing	specify only one action (option) for each category ( <b>Forwarding</b> , <b>Priority</b> , <b>Diffserv</b> , , <b>Metering</b> ) in a policy rule. h only applies one policy rule for each traffic flow.
Outgoing Note: The Switc Say you have a tr Switch only classif rule with which th	, <b>Metering</b> ) in a policy rule. In only applies one policy rule for each traffic flow. affic flow that matches several classifiers, and you specify a different policy rule for each. The ies the traffic flow to the classifier with the highest <b>Match Order</b> . The Switch then applies the policy e classifier is associated. You can set the classifier <b>Match Order</b> rule ( <b>manual</b> or <b>auto</b> ) in the <b>ACL</b> >
Outgoing Note: The Switch Say you have a tr Switch only classif rule with which th Classifier > Classifi	, <b>Metering</b> ) in a policy rule. In only applies one policy rule for each traffic flow. affic flow that matches several classifiers, and you specify a different policy rule for each. The ies the traffic flow to the classifier with the highest <b>Match Order</b> . The Switch then applies the policy
Outgoing Note: The Switc Say you have a tr Switch only classif rule with which th Classfier > Classif Let's say you set t on port 3.	, <b>Metering</b> ) in a policy rule. In only applies one policy rule for each traffic flow. affic flow that matches several classifiers, and you specify a different policy rule for each. The ies the traffic flow to the classifier with the highest <b>Match Order</b> . The Switch then applies the policy e classifier is associated. You can set the classifier <b>Match Order</b> rule ( <b>manual</b> or <b>auto</b> ) in the <b>ACL</b> > <b>ier Global settings</b> screen (see Section 67.4 on page 459 for more information).
Outgoing Note: The Switch Say you have a tr Switch only classif rule with which th Classfier > Classif Let's say you set t on port 3. If Policy 1 applies forward the pack	<b>Metering</b> ) in a policy rule. In only applies one policy rule for each traffic flow. affic flow that matches several classifiers, and you specify a different policy rule for each. The ies the traffic flow to the classifier with the highest Match Order. The Switch then applies the policy e classifier is associated. You can set the classifier Match Orderrule (manual or auto) in the ACL> ier Global settings screen (see Section 67.4 on page 459 for more information). wo classifiers (Class 1 and Class 2) and both identify all traffic from MAC address 11:22:33:44:55:66 to Class 1 and the action is to drop the packets, Policy 2 applies to Class 2 and the action is to
Outgoing Note: The Switch Say you have a tr Switch only classif rule with which th Classfier > Classifi Let's say you set t on port 3. If Policy 1 applies forward the pack If Policy 1 applies enable bandwidt	<b>Metering</b> ) in a policy rule. h only applies one policy rule for each traffic flow. affic flow that matches several classifiers, and you specify a different policy rule for each. The ies the traffic flow to the classifier with the highest Match Order. The Switch then applies the policy e classifier is associated. You can set the classifier Match Order rule (manual or auto) in the ACL> ier Global settings screen (see Section 67.4 on page 459 for more information). wo classifiers (Class 1 and Class 2) and both identify all traffic from MAC address 11:22:33:44:55:66 to Class 1 and the action is to drop the packets, Policy 2 applies to Class 2 and the action is to ets to the egress port, the Switch will forward the packets. to Class 1 and the action is to drop the packets, Policy 2 applies to Class 2 and the action is to
Outgoing Note: The Switc Say you have a tr Switch only classif rule with which th Classfier > Classifi Let's say you set t on port 3. If Policy 1 applies forward the pack If Policy 1 applies enable bandwidt	<b>Metering</b> ) in a policy rule. In a policy rule for each traffic flow. affic flow that matches several classifiers, and you specify a different policy rule for each. The ies the traffic flow to the classifier with the highest Match Order. The Switch then applies the policy e classifier is associated. You can set the classifier Match Order rule (manual or auto) in the ACL> ier Global settings screen (see Section 67.4 on page 459 for more information). wo classifiers (Class 1 and Class 2) and both identify all traffic from MAC address 11:22:33:44:55:66 to Class 1 and the action is to drop the packets, Policy 2 applies to Class 2 and the action is to ets to the egress port, the Switch will forward the packets. to Class 1 and the action is to drop the packets immediately. to Class 1 and the action is to forward the packets to the egress port, Policy 2 applies to Class 2 and the action is to forward the packets immediately.
Outgoing Note: The Switch Say you have a tr Switch only classif rule with which th Classfier > Classif Let's say you set to on port 3. If Policy 1 applies forward the pack If Policy 1 applies enable bandwidt If Policy 1 applies and the action is	<b>Metering</b> ) in a policy rule. h only applies one policy rule for each traffic flow. affic flow that matches several classifiers, and you specify a different policy rule for each. The ies the traffic flow to the classifier with the highest Match Order. The Switch then applies the policy e classifier is associated. You can set the classifier Match Order rule (manual or auto) in the ACL> ier Global settings screen (see Section 67.4 on page 459 for more information). wo classifiers (Class 1 and Class 2) and both identify all traffic from MAC address 11:22:33:44:55:66 to Class 1 and the action is to drop the packets, Policy 2 applies to Class 2 and the action is to ets to the egress port, the Switch will forward the packets. to Class 1 and the action is to drop the packets, Policy 2 applies to Class 2 and the action is to h limitation, the Switch will discard the packets immediately. to Class 1 and the action is to forward the packets to the egress port, Policy 2 applies to Class 2 and the action is to a negative packets immediately.
Outgoing Note: The Switch Say you have a tr Switch only classif rule with which th Classfier > Classif Let's say you set to on port 3. If Policy 1 applies forward the pack If Policy 1 applies enable bandwidt If Policy 1 applies and the action is	<ul> <li>Metering) in a policy rule.</li> <li>h only applies one policy rule for each traffic flow.</li> <li>affic flow that matches several classifiers, and you specify a different policy rule for each. The ies the traffic flow to the classifier with the highest Match Order. The Switch then applies the policy e classifier is associated. You can set the classifier Match Order. The Switch then applies the policy e classifiers is associated. You can set the classifier Match Order. The Switch then applies the policy e classifiers is associated. You can set the classifier Match Order. The Switch then applies the policy e classifiers is associated. You can set the classifier Match Order. The Switch then applies the policy e classifiers (Class 1 cand Class 2) and both identify all traffic from MAC address 11:22:33:44:55:66</li> <li>to Class 1 and the action is to drop the packets, Policy 2 applies to Class 2 and the action is to ets to the egress port, the Switch will forward the packets.</li> <li>to Class 1 and the action is to drop the packets, Policy 2 applies to Class 2 and the action is to h limitation, the Switch will discard the packets immediately.</li> <li>to Class 1 and the action is to forward the packets to the egress port, Policy 2 applies to Class 2 and the action is to enable bandwidth limitation, the Switch will forward the packets.</li> </ul>
Outgoing Note: The Switch Say you have a tr Switch only classif rule with which th Classfier > Classif Let's say you set t on port 3. If Policy 1 applies forward the pack If Policy 1 applies enable bandwidt If Policy 1 applies and the action is Forwarding	<ul> <li>Metering) in a policy rule.</li> <li>h only applies one policy rule for each traffic flow.</li> <li>affic flow that matches several classifiers, and you specify a different policy rule for each. The ies the traffic flow to the classifier with the highest Match Order. The Switch then applies the policy e classifier is associated. You can set the classifier Match Order rule (manual or auto) in the ACL&gt; ierGlobal settings screen (see Section 67.4 on page 459 for more information).</li> <li>wo classifiers (Class 1 and Class 2) and both identify all traffic from MAC address 11:22:33:44:55:66 to Class 1 and the action is to drop the packets, Policy 2 applies to Class 2 and the action is to ets to the egress port, the Switch will forward the packets.</li> <li>to Class 1 and the action is to drop the packets, Policy 2 applies to Class 2 and the action is to himitation, the Switch will discard the packets immediately.</li> <li>to Class 1 and the action is to forward the packets to the egress port, Policy 2 applies to Class 2 and the action is to enable bandwidth limitation, the Switch will forward the packets.</li> <li>Select No change to forward the packets.</li> <li>Select Discard the packet to drop the packets.</li> </ul>

LABEL	DESC RIPTIO N
Diffserv	Select <b>No change</b> to keep the TOS and/or DSCP fields in the packets.
	Select <b>Set the packet's TOS field</b> to set the TOS field with the value you configure in the <b>TOS</b> field.
	Select <b>Set the Diffserv Codepoint field in the frame</b> to set the DSCP field with the value you configure in the <b>DSCP</b> field.
Outgoing	Select Send the packet to the minorport to send the packet to the mirror port.
	Select Send the packet to the egress port to send the packet to the egress port.
	Select Set the packet's VIAN ID to set the packet's VLAN ID.
Metering	Enable the switch button to activate bandwidth limitation on the traffic flows then set the actions to be taken on out-of-profile packets.
Out of profile	Select the actions to be performed for out-of-profile traffic.
denon	Select <b>Drop the packet</b> to discard the out-of-profile traffic.
	Select <b>Change the DSCP value</b> to replace the DSCP field with the value specified in the <b>Out of profile DSCP</b> field.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click <b>Clear</b> to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

Table 264 SECURITY > ACL > Policy Rule > Add/Edit (continued)

# 68.3 Policy Example

The figure below shows an example SEC URTIY > ACL > Policy Rule screen where you configure a policy to limit bandwidth and discard out-of-profile traffic on a traffic flow classified using the Example classifier (refer to Section 67.5 on page 460).

Figure 343	Policy Example
------------	----------------

Astro-	
Name	[Test
Cicalians)	Factoria.
General Tarameters	
SANG FUIL	[T]
7.4 betay	10×
0.0CP	le l
123	1 13
Wetering Parameters	(JNC)
9and- 915	10000; K.000
out di Profile (2007	[c]
Action	
excended	<ul> <li>No change</li> <li>Depend the pocket</li> <li>Encoding the monoing frame an slout is maked for drapping.</li> </ul>
Filany	<ul> <li>No strange</li> <li>Set the posterior SO2 to polorie</li> <li>Replace the SO2 to polorie wild with the PTO2 value</li> <li>Replace the SO2 to priority wild with the interval22, platetly value</li> </ul>
Officery	<ul> <li>Ne change</li> <li>Sin the product RC2 field</li> <li>Replace the PTOS Field with the S02 lip alority value</li> <li>So the DTOS Field with the S02 lip alority value</li> </ul>
Ord (joint)	<ul> <li>Cend the product of the or mole-of-</li> <li>Cond the product for the ogress part</li> </ul>
Mentour.	(DHC)
	Out of profile action
	<ul> <li>Deep the poolse</li> <li>Change the DSCF value</li> <li>Set Coll (rep Processer)</li> <li>De not deep the rectating terms provided/ marks the conjugate</li> </ul>

# C HAPTER 69 Anti-Arpscan

# 69.1 Anti-Arpscan Overview

Address Resolution Protocol (ARP), RFC 826, is a protocol used to convert a network-layer IP address to a link-layer MAC address. ARP scan is used to scan the network of a certain interface for alive hosts. It shows the IP address and MAC addresses of all hosts found. Hackers could use ARP scan to find targets in your network. **Anti-apscan** is used to detect unusual ARP scan activity and block suspicious hosts or ports.

Unusual ARP scan activity is determined by port and host thresholds that you set. A port threshold is determined by the number of packets received per second on the port. If the received packet rate is over the threshold, then the port is put into an **En-Disable** state. You can recover the normal state of the port manually if this happens and after you identify the cause of the problem.

A host threshold is determined by the number of ARP-request packets received per second. There is a global threshold rate for all hosts. If the rate of a host is over the threshold, then that host is blocked by using a MAC address filter. A blocked host is released automatically after the MAC aging time expires.

Note: A port-based threshold must be larger than the host-based threshold or the host-based threshold will not work.

## 69.1.1 What You Can Do

- Use the Anti-Arpscan Status screen (Section 69.2 on page 469) to see what ports are trusted and are forwarding traffic or are disabled.
- Use the Anti-Arpscan Host Status screen (Section 69.3 on page 469) to view blocked hosts and clear selected ones.
- Use this Anti-Arpscan Setup screen (Section 69.4 on page 470) to enable anti-arpscan, set port and host thresholds as well as configure ports to be trusted or untrusted.
- Use the Anti-Anpscan Tiust Host screen (Section 69.5 on page 472) to create or remove trusted hosts identified by IP address and subnet mask. Anti-anpscan is not performed on trusted hosts.

## 69.1.2 What You Need to Know

- You should set an uplink port as a trusted port before enabling **Anti-arpscan** so as to prevent the port from being shutdown due to receiving too many ARP messages.
- When a port is configured as a trusted port, **Anti-arpscan** is not performed on the port. Both host and port thresholds are ignored for trusted ports. If the received ARP packet rate on a port or the received ARP-requests from a host exceed the thresholds, the trusted port will not be closed.
- If a port on the Switch is closed by **Anti-arpscan**, and you want to recover it, then do one of the following:

- Go to PORT > Port Setup. Clear Active and click Apply. Then select Active and click Apply again.
- Go to SEC URITY > Errdisable > Errdisable Recovery and set the interval for anti-arpscan. After the interval expires, the closed ports will become active and start receiving packets again.
- Use the command port no inactive.
- Refer to the port logs to see when a port was closed.

#### 69.2 Anti-Arpscan Status

Use this screen to see what ports are trusted and are forwarding traffic or are disabled. To open this screen, click **SEC URITY** > **Anti-Arpsc an** > **Anti-Arpsc an Status**.

Figure 344 SECURITY > Anti-Arpscan > Anti-Arpscan Status

Auli-Arpsonn Slolus	Ardi-Aqueron Host Status	Anli-Arpuran Selup				
Anti-Arpsoon is Disobled						
t wit	husted	Shrie				
I.	011	l konversión op				
2	OT D	licewooding.				
a -	( 10+ )	Terrarading				
А.	194	Terrarading				
2	( NI	harver sing				
*	( NI	Personal and				
×	OT C	l orwieding				

The following table describes the fields in this screen.

LABEL	DESC RIPIIO N	
Anti-Arpscan is	This shows whether $Anti-apscan$ is enabled or disabled on the Switch.	
Port	This field displays the port number of the Switch.	
Trusted	This field displays whether the port is trusted or untrusted. <b>Anti-apscan</b> is not performed on a trusted port.	
State	This field displays whether the port can forward traffic normally (Forwarding) or is disabled (En Disable).	

Table 265 SECURITY > Anti-Arpscan > Anti-Arpscan Status

## 69.3 Anti-Arpscan Host Status

Use this screen to view blocked hosts and unblock ones connected to certain ports. To open this screen, click SEC URITY > Anti-Arpscan > Anti-Arpscan Host Status.

Figure 345	SECURITY >	Anti-Arpscan >	Anti-Arpsca	n Host Status
rigure 545	JLCUNIT /	Ann-Aipscun /	Anii-Aipscu	11103131010

Anli-Arpscon Sl	alvs Anli-A	rpscon Host Status	Anli-Arpscon Se	lop Anli-/	Apseon Trush Host
Clear Filtered H	fost				
Port Ust		Clocr			
Fillered Hosl					
La state	Have 10	at a 2 state		Read.	21-11-
Index	Host P	MAC Addre	SS VLAN	Fort	State

The following table describes the fields in the above screen.

Table 266 SECURITY > Anti-Arpscan > Anti-Arpscan Host Status

LABEL	DESC RIPTIO N	
Clear Filtered host	·	
A filtered host is a bloc	ked IP address.	
Port List	Enter a port number or a series of port numbers separated by commas and spaces, and then click <b>Clear</b> to unblock all hosts connected to these ports.	
Filtered host	·	
This table lists information	on on blocked hosts.	
Index	This displays the index number of an IP address (a host) that has been blocked.	
Host IP	This displays the IP address of the blocked host.	
MAC Address	This displays the MAC address of the blocked host.	
VLAN	This displays the VLAN ID that shows which VLAN the blocked host is in.	
Port	This displays the port number to which the blocked host is connected.	
State	This shows <b>En-Disable</b> if the ARP-request rate from this host is over the threshold. Forwarding hosts are not displayed.	

# 69.4 Anti-Arpscan Setup

Use this screen to enable **Anti-Arpscan**, set port and host thresholds as well as configure ports to be trusted or untrusted. To open this screen, click **SEC URITY** > **Anti-Arpscan** > **Anti-Arpscan Setup**.

Anti Arpscan States	Anti-Amacon Host Status	Anti-Arpscon Selup
Active	() () ()	
Point Threadne ici	100 200	
thet have noted	10 98 <sup>5</sup>	
Port	Truste	o state
	and in	oled ~
*	July,	ole l v
1	the factor	oleit v
1	arth.	eled v
÷	Liste	ntact w [
<u>.</u>	Intr	elaci e
×	1977.	nisa vi
ł.		

Figure 346 SECURITY > Anti-Arpscan > Anti-Arpscan Setup

The following table describes the fields in the above screen.

IABEL	DESC RIPTIO N	
Active	Enable the switch button to enable <b>Anti-apscan</b> on the Switch.	
Port Threshold	A port threshold is determined by the number of packets received per second on the port if the received packet rate is over the threshold, then the port is put into an <b>Em Disable</b> state. Type the maximum number of packets per second allowed on the port before it is blocked.	
	Note: The allowed range is 2 to 255 packets received per second.	
Host Threshold	A host threshold is determined by the number of ARP-request packets received per second. This is the global threshold rate for all hosts. If the rate of a host is over the threshold, then that host is blocked by using a MAC address filter. A blocked host is released automatically after the MAC aging time expires.	
	Type the maximum number of ARP-request packets allowed by a host before it is blocked.	
	Note: The allowed range is 2 to 100 ARP-request packets per second.	
	Note: The port-based threshold must be larger than the host-based threshold or the host-based threshold will not be applied.	
Port	This field displays the port number.	
*	Settings in this row apply to all ports.	
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.	
	Note: Changes in this row are copied to all the ports as soon as you make them.	

Table 267 SECURITY > Anti-Arpscan > Anti-Arpscan Setup

IABEL	DESC RIPIIO N
Trusted State	Select <b>Untrusted</b> or <b>Thusted</b> for the associated port. <b>Anti-apscan</b> is not performed on trusted hosts.
Apply	Click $Apply$ to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click this to reset the values in this screen to their last-saved values.

Table 267 SECURITY > Anti-Arpscan > Anti-Arpscan Setup (continued)

## 69.5 Anti-Arpscan Trust Host

Use this screen to create or remove trusted hosts identified by IP address and subnet mask. Anti-apscan is not performed on trusted hosts. To open this screen, click SEC URITY > Anti-Apscan > Anti-Apscan Thust Host.

Figure 347 SECURITY > Anti-Arpscan > Anti-Arpscan Trust Host

Anfi-Anzycur	a Shalus	Anli-Arpscan Hast Status	Anti-Arpscon Selup	Anli-Arpse	an Irust Host
				O Atel/Celt	Delette
-01	Index	Nome	ileat if		Ricek

The following table describes the fields in the above screen.

LABEL	DESC RIPTIO N
Index	This field displays a sequential number for each trusted host.
Name	This field displays the name of the trusted host.
Host IP	This field displays the IP address of the trusted host.
Mask	This field displays the subnet mask of the trusted host.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.
Delete	Click <b>Delete</b> to remove the selected entries.

#### 69.5.1 Add/Edit Anti-Arpscan Trust Hosts

Use this screen to add/edit trusted hosts identified by IP address and subnet mask. Click Add/Edit, or select an entry and click Add/Edit in the SEC URITY > Anti-Appscan > Anti-Appscan Trust Host screen to view this screen.

#### Figure 348 SECURITY > Anti-Arpscan > Anti-Arpscan Trust Host > Add/Edit

Norte	5	
HOST IP		
3 <b>668</b> 33		
Apply	Clair	Crinoid

The following table describes the fields in the above screen.

LABEL	DESC RIPTIO N		
Name	Type a descriptive name of up to 32 printable ASCII (except [ ? ], [   ], [ ' ], [ " ] or [ , ]) characters to identify this host.		
Host IP	Type the IP address of the host.		
Mask	A trusted host may consist of a subnet of IP addresses. Type a subnet mask to create a single host or a subnet of hosts.		
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.		
Clear	Click <b>Clear</b> to clear the fields to the factory defaults.		
Cancel	Click Cancel to not save the configuration you make and return to the last screen.		

#### Table 269 SECURITY > Anti-Arpscan > Anti-Arpscan Trust Host > Add/Edit

# C HAPTER 70 BPDU Guard

### 70.1 BPDU Guard Overview

A BPDU (Bridge Protocol Data Units) is a data frame that contains information about STP. STP-aware switches exchange BPDUs periodically.

The BPDU guard feature allows you to prevent any new STP-aware switch from connecting to an existing network and causing STP topology changes in the network. If there is any BPDU detected on the ports on which BPDU guard is enabled, the Switch disables the ports automatically. You can then enable the ports manually in the **PORT** > **Port Setup** screen, or use the **SEC URITY** > **End isa ble** > **End isa ble Recovery** screen (see Section 72.5 on page 483) to have the ports become active after a certain time interval.

#### 70.2 BPDU Guard Status

Use this screen to view whether BPDU guard is enabled on the Switch and the port status. Click SEC URITY > BPDU Guard > BPDU Guard Status to view the following screen.

BPDV Guard Status	BPDU Guard Setup	
BFDU gvard global (	sehip: Diroble	
Port	A citive	Status
1	1.00	Forward bg
+	199	Forward bg
8	01	house and neg
<u>+</u>	- 10	horse and neg
5 B		Lorwouting;
6	- 20°	Lorwonding;
7		Forwarding

Figure 349 SECURITY > BPDU Guard > BPDU Guard Status

The following table describes the fields in the above screen.

LABEL	DESC RIPIIO N
BPDU guard global setup	This field displays whether BPDU guard is activated on the Switch.
Port	This field displays the port number.
Active	This shows whether BPDU guard is activated on the port.
Status	This shows whether the port is shut down ( <b>En disable</b> ) or able to transmit packets ( <b>Forwarding</b> ).

Table 270 SECURITY > BPDU Guard > BPDU Guard Status

## 70.3 BPDU Guard Setup

Use this screen to turn on the BPDU guard feature on the Switch and ports.

Click SEC URITY > BPDU Guard > BPDU Guard Setup to display the configuration screen as shown.

Poll Guard Status BPDU	Guard Setup
eto 🕕	
Port	Active
2.4	11
2	0
2	0
<u></u>	E1
22 - C	
1	
App	Garrise

Figure 350 SECURITY > BPDU Guard > BPDU Guard Setup

The following table describes the fields in the above screen.

 Table 271
 SECURITY > BPDU Guard > BPDU Guard Setup

LABEL	DESC RIPTIO N
Active	Enable the switch button to enable BPDU guard on the Switch.
Port	This field displays the port number.

IABEL	DESC RIPTIO N
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
Active	Select this check box to enable the BPDU guard feature on this port. The Switch shuts down this port if there is any BPDU received on the port.
	Clear this check box to disable the BPDU guard feature.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 271 SECURITY > BPDU Guard > BPDU Guard Setup (continued)

# C HAPTER 71 Storm Control

## 71.1 Storm Control Overview

This chapter introduces and shows you how to configure the storm control feature.

Storm control limits the number of broadcast, multicast and destination lookup failure (DLF) packets the Switch receives per second on the ports. When the maximum number of allowable broadcast, multicast and/or DLF packets is reached per second, the subsequent packets are discarded. Enable this feature to reduce broadcast, multicast and/or DLF packets in your network. You can specify limits for each packet type on each port.

#### 71.1.1 What You Can Do

Use the **Storm Control** screen (Section 71.2 on page 477) to limit the number of broadcast, multicast and destination lookup failure (DLF) packets the Switch receives per second on the ports.

## 71.2 Storm Control Setup

Click SEC URITY > Storm Control in the navigation panel to display the screen as shown next.

Figure 3	51	SECURITY	> Storm	Control
----------	----	----------	---------	---------

al de l		() (++)				
Port	Grou	ndoost (p81/x)-	36	uticant (pki//0		OLF (pkt/x)
3	,E3;		(12)		- 13L)	1
1		2	10 CE	<u>0</u> }	T	6
	Ū.	6	13	ý.	1	<u> </u> e
3		5	17	- <del>0</del> -	11	(C
34	101	5	10	<u>6</u> 2	0	(c
		9	1.35	0	(E)	6
a -	0	2	0	0	EI.	<u> </u> 0
ł		3		1. Sec. 1. Sec	$\sim$	上 へ
$\sim$		$\sim$		$\sim$	$\sim$	$\sim$

Table 272 SECURITY > Storm Control

LABEL	DESC RIPIIO N
Active	Enable the switch button to enable traffic storm control on the Switch. Disable the switch button to disable this feature.
Port	This field displays the port number.
*	Settings in this row apply to all ports. Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
Broadcast (pkt/s)	Select this option to enable and specify how many broadcast packets the Switch accepts per second on the port.
	The Switch will generate a trap and/or log when the actual rate is higher than the specified threshold.
Multicast (pkt/s)	Select this option to enable and specify how many multicast packets the Switch accepts per second on the port.
	The Switch will generate a trap and/or log when the actual rate is higher than the specified threshold.
DLF (pkt/s)	Select this option and specify how many destination lookup failure (DLF) packets the port receives per second.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to reset the fields.

# C HA PTER 72 Error-Disable

#### 72.1 Error-Disable Overview

This chapter shows you how to configure the rate limit for control packets on a port, and set the Switch to take an action (such as to shut down a port or stop sending packets) on a port when the Switch detects a pre-configured error. It also shows you how to configure the Switch to automatically undo the action after the error is gone.

#### 72.1.1 CPU Protection Overview

Switches exchange protocol control packets in a network to get the latest networking information. If a switch receives large numbers of control packets, such as ARP, BPDU or IGMP packets, which are to be processed by the CPU, the CPU may become overloaded and be unable to handle regular tasks properly.

The CPU protection feature allows you to limit the rate of ARP, BPDU and IGMP packets to be delivered to the CPU on a port. This enhances the CPU efficiency and protects against potential DoS attacks or errors from other networks. You then can choose to drop control packets that exceed the specified rate limit or disable a port on which the packets are received.

#### 72.1.2 Error-Disable Recovery Overview

Some features, such as loop guard or CPU protection, allow the Switch to shut down a port or discard specific packets on a port when an error is detected on the port. For example, if the Switch detects that packets sent out the ports loop back to the Switch, the Switch can shut down the ports automatically. After that, you need to enable the ports or allow the packets on a port manually through the Web Configurator or the commands. With error-disable recovery, you can set the disabled ports to become active or start receiving the packets again after the time interval you specify.

#### 72.1.3 What You Can Do

- Use the Endisable Status screen (Section 72.2 on page 480) to view whether the Switch detected that control packets exceeded the rate limit configured for a port or a port is disabled according to the feature requirements and what action you configure, and related information.
- Use the **CPU Protection** screen (Section 72.3 on page 481) to limit the maximum number of control packets (ARP, BPDU and/or IGMP) that the Switch can receive or transmit on a port.
- Use the Endisable Detect screen (Section 72.4 on page 482) to have the Switch detect whether the control packets exceed the rate limit configured for a port and configure the action to take once the limit is exceeded.
- Use the Endisable Recovery screen (Section 72.5 on page 483) to set the Switch to automatically undo an action after the error is gone.

#### 72.2 Error Disable Status

Use this screen to view whether the Switch detected that control packets exceeded the rate limit configured for a port or a port is disabled according to the feature requirements and what action you configure, and related information. Click **SEC URITY** > **End isa ble** > **End isa ble** Status to display the screen as shown.

ndisable Sh	atus CPU prol	ection I	Indisable De	bect -	Endisable Rec	overy	
nactive-rec	ison mode reset						
Port		_					
Cause	ART V		Heart				
Indisable SI	and to see						
protectore at	0108						
Port	Cause	Active	Mode	Role	Status	Recovery Time Leff (secs)	Total Dropped
	Loop Guard	Off	inactive-port	-	Forwarding	-	
	ARP	Off	inactive-port	0	Forwarding	-	
	8PD0	Off	inactive-port	0	Forwarding	-	-
1	IGMP.	( Off )	inactive-port	0	Forwarding	-	-
	Anfl-orpscon	OfF	Inactive-port	-	Forwarding	-	-
	SPDU Guard	Off	inactive-port	-	Forwarding	-	
	20.D	Off	inactive-port	-	Forwarding	-	-
	Loop Guard	Off	inactive-port	-	Forwarding	-	
	ARP	Off	inactive-port	0	Forwarding	-	
	8PDU	Off	inactive-port	0	Forwarding	-	-
2	IGMP	OfF	Inactive-port	0	Forwarding	-	-
	Anthorpicon	OFF	inactive-port	-	Forwarding	-	
	8PDU Guard	Off	inactive-port	-	Forwarding	-	-
	20LD	Off	inactive-port	-	Forwarding		
	Loop Guard	Off	inactive-port	-	Forwarding	-	-
	APP	( off )	inactive-port	0	Forwarding	-	
	8PD0	Off	inactive-port	0	Forwarding	-	
3	IG//P	Off	inactive-port	0	Forwarding	-	
	Anthorpsoon	Off	inactive-port	-	Forwarding	-	
	apply Gyard	Off			Form		~
	2000	utt	hactive-port		ronwording		

The following table describes the labels in this screen.

Table 273 SECURITY > Errdisable > Errdisable
--

LABEL	DESC RIPIIO N				
Inactive-reason mode reset					
Port Enter the number of the ports (separated by a comma) on which you want to reset inactive reason status.					

XGS2220 Series User's Guide

IABEL	DESC RIPTIO N					
Cause	Select the cause of inactive-reason mode you want to reset here.					
Reset	Click to reset the specified ports to handle ARP, BPDU or IGMP packets instead of ignoring them, if the ports is in inactive-reason mode.					
Errdisable Status						
Port	This is the number of the port on which you want to configure Errdisable Status.					
Cause	This displays the type of the control packet received on the port or the feature enabled on the port and causing the Switch to take the specified action.					
Active	This field displays whether the control packets (ARP, BPDU, and/or IGMP) on the port is being detected or not. It also shows whether loop guard, anti-arp scanning, BPDU guard or ZULD is enabled on the port.					
Mode	<ul> <li>This field shows the action that the Switch takes for the cause.</li> <li>inactive-port – The Switch disables the port.</li> <li>inactive-reason – The Switch drops all the specified control packets (such as BPDU) on the port.</li> <li>rate-limitation – The Switch drops the additional control packets the ports has to handle in every one second.</li> </ul>					
Rate	This field displays how many control packets this port can receive or transmit per second. It can be adjusted in <b>CPU Protection</b> . <b>0</b> means no rate limit.					
Status	<ul> <li>This field displays the errdisable status.</li> <li>Forwarding: The Switch is forwarding packets. Rate-limitation mode is always in Forwarding status.</li> <li>En-disable: The Switch disables the port on which the control packets are received (inactive-port) or drops specified control packets on the port (inactive-reason).</li> </ul>					
Recovery Time Left (secs)	This field displays the time (seconds) left before the ports becomes active of Errdisable Recovery.					
Total Dropped	This field displays the total packet number dropped by this port where the packet rate exceeds the rate of mode rate-limitation.					

Table 273	SECHRITY >	Frrdisable >	Errdisable Status	(continued)
	JLCORIT /			

### 72.3 CPU Protection Setup

Use this screen to limit the maximum number of control packets (ARP, BPDU and/or IGMP) that the Switch can receive or transmit on a port. Click SEC URTIY > Endisa ble > C PU Protection to display the screen as shown.

Note: After you configure this screen, make sure you also enable error detection for the specific control packets in the SEC URITY > End isa ble > End isa ble Detect screen.

Endisable Detect		
Umil (picys)		
1		
0		
Ĩ		

Figure 353 SECURITY > Errdisable > CPU Protection

Table 2/4 SECURITY > Enaisable > CPU Protection	Table 274	SECURITY > Errdisable > CPU Protection
---	-----------	--

IABEL	DESC RIPTIO N
Reason	Select the type of control packet you want to configure here.
Port	This field displays the port number.
*	Use this row to make the setting the same for all ports. Use this row first and then make adjustments to each port if necessary.
	Changes in this row are copied to all the ports as soon as you make them.
Rate Limit (pkt/s)	Enter a number from 0 to 256 to specify how many control packets this port can receive or transmit per second.
	<b>0</b> means no rate limit.
	You can configure the action that the Switch takes when the limit is exceeded.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

#### 72.4 Error-Disable Detect Setup

Use this screen to have the Switch detect whether the control packets exceed the rate limit configured for a port and configure the action to take once the limit is exceeded. Click SEC URTIY > End is a ble > End is a ble Detect to display the screen as shown.

Endisable Status	CPU protection	Errdisable Detect	Endisable Recov	ery
Cause		6ctter	Wode	
55		0	asstance v	
6 D.		D	ingot-pigot vi	
SPO (E		0	haot-bloot v	
GMF		0	naoti-e port w	

Figure 354 SECURITY > Errdisable > Errdisable Detect

Table 275	SECURITY >	Errdisable >	Errdisable Detect
-----------	------------	--------------	-------------------

IABEL	DESC RIPTIO N
Cause	This field displays the types of control packet that may cause CPU overload.
*	Use this row to make the setting the same for all entries. Use this row first and then make adjustments to each entry if necessary.
	Changes in this row are copied to all the entries as soon as you make them.
Active	Select this option to have the Switch detect if the configured rate limit for a specific control packet is exceeded and take the action selected below.
Mode	Select the action that the Switch takes when the number of control packets exceed the rate limit on a port, set in the SPC URTRY > Endisable > CPU Protection screen.
	<ul> <li>inactive-port – The Switch disables the port on which the control packets are received.</li> <li>inactive-reason – The Switch drops all the specified control packets (such as BPDU) on the port.</li> <li>mate-limitation – The Switch drops the additional control packets the ports has to handle in every one second.</li> </ul>
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

# 72.5 Error-Disable Recovery Setup

Use this screen to configure the Switch to automatically undo an action after the error is gone. Click SEC URITY > End is a ble > End is a ble Recovery to display the screen as shown.

Endisable Status	CPU protection	Endisable Detect	Endisable Recovery
Setse -	) an		
Reason	3	me Slohe	interval
		<b>C1</b>	
Joop givers		0	<u></u>
4 <b>9</b> *			300
trou.		. 🔾	202
(CDAP-		<b>Q</b>	300
anti erbitxa	é.	- Cl	300
bpopper.	i	6	300
2.4			300

Figure 355 SECURITY > Errdisable > Errdisable Recovery

LABEL	DESC RIPTIO N				
Active	Enable the switch button to turn on the error-disable recovery function on the Switch.				
Reason	This field displays the supported features that allow the Switch to shut down a port or discard packets on a port according to the feature requirements and what action you configure.				
*	Use this row to make the setting the same for all entries. Use this row first and then make adjustments to each entry if necessary.				
	Changes in this row are copied to all the entries as soon as you make them.				
Timer Status	Select this check box to allow the Switch to wait for the specified time interval to activate a port or allow specific packets on a port, after the error was gone. Clear the check box to turn off this rule.				
Interval	Enter the number of seconds (from 30 to 2592000) for the time interval.				
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.				
Cancel	Click Cancel to begin configuring this screen afresh.				

Table 276 SECURITY > Errdisable > Errdisable Recovery

# CHAPTER 73 IP Source Guard

## 73.1 IP Source Guard Overview

IP source guard uses a binding table to distinguish between authorized and unauthorized DHCP and ARP packets in your network. A binding contains these key attributes:

- MAC address
- VLAN ID
- IP address
- Port number

When the Switch receives a DHCP or ARP packet, it looks up the appropriate MAC address, VLAN ID, IP address, and port number in the binding table. If there is a binding, the Switch forwards the packet. If there is not a binding, the Switch discards the packet.

The Switch builds the binding table by snooping DHCP packets (dynamic bindings) and from information provided manually by administrators (static bindings).

IP source guard consists of the following features:

- Static bindings. Use this to create static bindings in the binding table.
- DHCP snooping. Use this to filter unauthorized DHCP packets on the network and to build the binding table dynamically.
- ARP inspection. Use this to filter unauthorized ARP packets on the network.

If you want to use dynamic bindings to filter unauthorized ARP packets (typical implementation), you have to enable DHCP snooping before you enable ARP inspection.

#### 73.1.1 What You Can Do

- Use the **IPv4 Source Guard** screen (Section 73.2 on page 486) to look at the current bindings for DHCP snooping and ARP inspection.
- Use the **IPv4 Source Guard Static Binding** screen (Section 73.3 on page 486) to manage static bindings for DHCP snooping and ARP inspection.

#### 73.1.2 What You Need to Know

The Switch builds the binding table by snooping DHCP packets (dynamic bindings) and from information provided manually by administrators (static bindings).

IP source guard consists of the following features:

- Static bindings. Use this to create static bindings in the binding table.
- DHCP snooping. Use this to filter unauthorized DHCP packets on the network and to build the binding table dynamically.
- ARP inspection. Use this to filter unauthorized ARP packets on the network.

If you want to use dynamic bindings to filter unauthorized ARP packets (typical implementation), you have to enable DHCP snooping before you enable ARP inspection.

#### 73.2 IPv4 Source Guard

Use this screen to look at the current bindings for DHCP snooping and ARP inspection. Bindings are used by DHCP snooping and ARP inspection to distinguish between authorized and unauthorized packets in the network. The Switch learns the bindings by snooping DHCP packets (dynamic bindings) and from information provided manually by administrators (static bindings). To open this screen, click **SEC URITY** > **IPv4 Source Guard** > **IP Source Guard**.

Figure 356 SECURITY > IPv4 Source Guard > IP Source Guard

If Source Guard Slat		Slolic (	Sinding				
Index	If Add	1050	VID	MAC Address	Pvrl	tease	lype:

The following table describes the labels in this screen.

LABEL	DESC RIPTIO N			
Index	This field displays a sequential number for each binding.			
IP Address	This field displays the IP address assigned to the MAC address in the binding.			
VID	This field displays the source VLAN ID in the binding.			
MAC Address	This field displays the source MAC address in the binding.			
Port	This field displays the port number in the binding. If this field is blank, the binding applies to all ports.			
Lease	This field displays how many days, hours, minutes, and seconds the binding is valid; for example, <b>2d3h4m5s</b> means the binding is still valid for 2 days, 3 hours, 4 minutes, and 5 seconds. This field displays <b>infinity</b> if the binding is always valid (for example, a static binding).			
Туре	This field displays how the Switch learned the binding.			
	$\mathbf{static}$ : This binding was learned from information provided manually by an administrator.			
	dhcp-snooping: This binding was learned by snooping DHCP packets.			

Table 277 SECURITY > IPv4 Source Guard > IP Source Guard

## 73.3 IPv4 Source Guard Static Binding

Use this screen to manage static bindings for DHCP snooping and ARP inspection. Static bindings are uniquely identified by the MAC address and VLAN ID. Each MAC address and VLAN ID can only be in one static binding. If you try to create a static binding with the same MAC address and VLAN ID as an existing static binding, the new static binding replaces the original one. To open this screen, click **SEC URITY > IPv4 Source Guard > IP Source Guard > Static Binding**.

Miscolice Gain	and Stone Rendering						
292781 292781	бня UPacho Qrashur		(Witham	2100			
Volic Riveling							
						O ALCOM	R 1000
	1 10 20	WARRA.	46	AAS As leads	iki	Le a e	20.00

Figure 357 SECURITY > IPv4 Source Guard > IP Source Guard > Static Binding


Table 278 SECURITY > IPv4 Source Guard > IP Source Guard > Static Binding
---

LABEL	DESC RIPTIO N		
ARP Freeze			
	s you to automatically create static bindings from the current ARP entries (either dynamically ARP entries) until the Switch's binding table is full.		
	earning mode should be set to <b>ARP-Request</b> in the <b>NEIWORKING &gt; ARP Setup &gt; ARP</b> screen before you use the ARP Freeze feature.		
Condition	All – Select this and click ARP Freeze to have the Switch automatically add all the current ARP entries to the static bindings table.		
	Port List – Select this and enter the number of the ports (separated by a comma).		
	You can enter multiple ports separated by (no space) comma (,) or hyphen (-) for a range. For example, enter "3-5" for ports 3, 4, and 5. Enter "3,5,7" for ports 3, 5, and 7.		
	ARP entries learned on the specified ports are added to the static bindings table after you click $\mathbf{ARP}$ Freeze.		
	VIAN List – Select this and enter the ID number of the VLANs (separated by a comma). ARP entries for the specified VLANs are added to the static bindings table after you click <b>ARP</b> Freeze.		
Static Binding			
Index	This field displays a sequential number for each binding.		
IP Address	This field displays the IP address assigned to the MAC address in the binding.		
VID	This field displays the source VLAN ID in the binding.		
MAC Address	This field displays the source MAC address in the binding.		
Port	This field displays the port number.		
Lease	This field displays how long the binding is valid.		
Туре	This field displays how the Switch learned the binding.		
	Static: This binding was learned from information provided manually by an administrator.		
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.		
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.		
Delete	Click <b>De le te</b> to remove the selected entries.		

#### 73.3.1 Add/Edit IPv4 Source Guard Static Binding

Use this screen to manage static bindings for DHCP snooping and ARP inspection. Static bindings are uniquely identified by the MAC address and VLAN ID. Each MAC address and VLAN ID can only be in one static binding. If you try to create a static binding with the same MAC address and VLAN ID as an existing static binding, the new static binding replaces the original one. Click Add/Edit, or select an entry and click Add/Edit in the SEC URTIY > IPv4 Source Guard > IP Source Guard > Static Binding screen to display this screen.

Figure 358 SECURITY > IPv4 Source Guard > IP Source Guard > Static Binding > Add/Edit



The following table describes the labels in this screen.

IABEL	DESC RIPIIO N			
IP Address	Enter the IP address assigned to the MAC address in the binding.			
VLAN	Enter the source VLAN ID in the binding.			
MAC Address	Enter the source MAC address in the binding. If this binding applies to all MAC addresses, select <b>Any</b> .			
Port	Specify the ports in the binding. If this binding has one port, select the first radio button and enter the port number in the field to the right. If this binding applies to all ports, select <b>Any</b> .			
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.			
Clear	Click Clear to clear the fields to the factory defaults.			
Cancel	Click Cancel to not save the configuration you make and return to the last screen.			

#### Table 279 SECURITY > IPv4 Source Guard > IP Source Guard > Static Binding > Add/Edit

# C HAPTER 74 DHCP Snooping

## 74.1 DHCP Snooping Overview

With DHCP snooping, the Switch can build the binding table dynamically by snooping DHCP packets (dynamic bindings) and filter unauthorized DHCP packets in your network.

The Switch uses a binding table to distinguish between authorized and unauthorized DHCP packets in your network. A binding contains these key attributes:

- MAC address
- VLAN ID
- IP address
- Port number

When the Switch receives a DHCP packet, it looks up the appropriate MAC address, VLAN ID, IP address, and port number in the binding table. If there is a binding, the Switch forwards the packet. If there is not a binding, the Switch discards the packet.

With DHCP snooping, the Switch can block a DHCP server on a snooped VLAN that comes from an untrusted port in your network.

#### 74.1.1 What You Can Do

- Use the **DHCP Snooping Status** screen (Section 74.2 on page 489) to look at various statistics about the DHCP snooping database.
- Use this **DHCP Snooping Setup** screen (Section 74.3 on page 492) to enable DHCP snooping on the Switch (not on specific VLAN), specify the VLAN where the default DHCP server is located, and configure the DHCP snooping database.
- Use the **DHCP Snooping Port Setup** screen (Section 74.4 on page 493) to specify whether ports are trusted or untrusted ports for DHCP snooping.
- Use the **DHCP Snooping VIAN Setup** screen (Section 74.5 on page 495) to enable DHCP snooping on each VLAN and to specify whether or not the Switch adds DHCP relay agent option 82 information to DHCP requests that the Switch relays to a DHCP server for each VLAN.
- Use the **DHCP Snooping VIAN Port Setup** screen (Section 74.6 on page 496) to apply a different DHCP option 82 profile to certain ports in a VLAN.

#### 74.2 DHCP Snooping Status

Use this screen to look at various statistics about the DHCP snooping database.

To open this screen, click SEC URITY > IPv4 Source Guard > DHCP Snooping > DHCP Snp. Status.

SHOP Sup. Skilles	DHCF Sop. Sclup	BHCP Snp. Port Sciup	DHCP Stip: VEAN Selop	DHCP Sup, VIAN Peri Selop
DHCP Snooping				
Deleterations.			Defeteres Defet	
Arg = 1.5			First Access middle many	n Harr
where exchange	500		in the second second second	p Can ker
And Inc.	2 C		Produce Address.	1
Arpha Sinang Deby Inertschy	Hane Distance	nina.	in-all dim terfa are	5 C
And Inc. Spay	No. 1 a	-	Forest extension Extension community	
Let ${\mathbb Z}$ be the scalar of the ${\mathbb Z}$	Hand		Unsupported ALANS	
us mi alle di lime	19976		healty are all the	New
ter Baka Kawa	No. 4 1	na seminal	La selly estated Service	gelden het
Casada -			Finite - Colline	
La solation gela			Internal distance we	1
Markey Folia Supper ful increters			LODE D'VEC	N
Augusta Indrees			Example in a second	
Anno an al Annel			Demographics (March	r
railed seads				
Group of Vickey				
Dens Valen	r			

Figure 359 SECURITY > IPv4 Source Guard > DHCP Snooping > DHCP Snp. Status

The following table describes the labels in this screen.

Table 280 SECURITY > IPv4 Source Guard > DHCP Snooping > DHCP Snp. Status

IABEL	DESC RIPTIO N	
Database Status		
	ne current settings for the DHCP snooping database. You can configure them in the <b>SEC URTIX</b> > <b>DHCP Snooping</b> > <b>DHCP Snp. Se tup</b> screen.	
Agent URL	This field displays the location of the DHCP snooping database.	
Write Delay TimerThis field displays how long (in seconds) the Switch tries to complete a specific update DHCP snooping database before it gives up.		
Abort Timer	This field displays how long (in seconds) the Switch waits to update the DHCP snooping database after the current bindings change.	
Agent Running	This field displays the status of the current update or access of the DHCP snooping database.	
	None: The Switch is not accessing the DHCP snooping database.	
	$\operatorname{\mathbf{Re}}\operatorname{\mathbf{ad}}$ : The Switch is loading dynamic bindings from the DHCP snooping database.	
	Write: The Switch is updating the DHCP snooping database.	
Delay Timer Expiry	This field displays how much longer (in seconds) the Switch tries to complete the current update before it gives up. It displays <b>Not Running</b> if the Switch is not updating the DHCP snooping database right now.	
Abort Timer Expiry	This field displays when (in seconds) the Switch is going to update the DHCP snooping database again. It displays <b>Not Running</b> if the current bindings have not changed since the last update.	
Last Succeeded Time	This field displays the last time the Switch updated the DHCP snooping database successfully.	

Table 280	SECURITY > IPv4 Source Guard > DHCP Snooping > DHCP Snp. Status (conti	nued)

IABEL	DESC RIPTIO N
Last Failed Time	This field displays the last time the Switch updated the DHCP snooping database unsuccessfully.
Last Failed Reason	This field displays the reason the Switch updated the DHCP snooping database unsuccessfully.
Counters	
This section displays hi or updated the DHCP	istorical information about the number of times the Switch successfully or unsuccessfully read ? snooping database.
Total Attempts	This field displays the number of times the Switch has tried to access the DHCP snooping database for any reason.
Startup Failures	This field displays the number of times the Switch could not create or read the DHCP snooping database when the Switch started up or a new URL is configured for the DHCP snooping database.
Successful Transfers	This field displays the number of times the Switch read bindings from or updated the bindings in the DHCP snooping database successfully.
Failed Transfers	This field displays the number of times the Switch was unable to read bindings from or update the bindings in the DHCP snooping database.
Successful Reads	This field displays the number of times the Switch read bindings from the DHCP snooping database successfully.
Failed Reads	This field displays the number of times the Switch was unable to read bindings from the DHCP snooping database.
Successful Writes	This field displays the number of times the Switch updated the bindings in the DHCP snooping database successfully.
Failed Writes	This field displays the number of times the Switch was unable to update the bindings in the DHCP snooping database.
Database Detail	
First Successful Access	This field displays the first time the Switch accessed the DHCP snooping database for any reason.
Last Ignored Bindings	Counters
from the DHCP bindin	ne number of times and the reasons the Switch ignored bindings the last time it read bindings g database. You can clear these counters by restarting the Switch or using CLI commands. ch CLI Reference Guide.
Binding Collisions	This field displays the number of bindings the Switch ignored because the Switch already had a binding with the same MAC address and VLAN ID.
Invalid Interfaces	This field displays the number of bindings the Switch ignored because the port number was a trusted interface or does not exist anymore.
Parse Failures	This field displays the number of bindings the Switch ignored because the Switch was unable to understand the binding in the DHCP binding database.
Expired Leases	This field displays the number of bindings the Switch ignored because the lease time had already expired.
Unsupported VLANs	This field displays the number of bindings the Switch ignored because the VLAN ID does not exist anymore.
Last Ignored Time	This field displays the last time the Switch ignored any bindings for any reason from the DHCP binding database.
Total Ignored Bindings	s Counters
	ne reasons the Switch has ignored bindings any time it read bindings from the DHCP binding lear these counters by restarting the Switch or using CLI commands. See the Ethernet Switch
Binding Collisions	This field displays the number of bindings the Switch has ignored because the Switch already had a binding with the same MAC address and VLAN ID.

XGS2220 Series User's Guide

LABEL	DESC RIPIIO N		
Invalid Interfaces This field displays the number of bindings the Switch has ignored because the port n was a trusted interface or does not exist anymore.			
Parse Failures This field displays the number of bindings the Switch has ignored because the S unable to understand the binding in the DHCP binding database.			
Expired Leases	This field displays the number of bindings the Switch has ignored because the lease time had already expired.		
Unsupported VLANs	This field displays the number of bindings the Switch has ignored because the VLAN ID does not exist anymore.		

Table 280 SECURITY > IPv4 Source Guard > DHCP Snooping > DHCP Snp. Status (continued)

## 74.3 DHCP Snooping Setup

Use this screen to enable DHCP snooping on the Switch (not on specific VLAN), specify the VLAN where the default DHCP server is located, and configure the DHCP snooping database. The DHCP snooping database stores the current bindings on a secure, external TFTP server so that they are still available after a restart.

To open this screen, click SEC URITY > IPv4 Source Guard > DHCP Snooping > DHCP Snp. Setup.

Note: The input string of any field in this screen should not contain [?], [|], ['], or [,].

HCP Snp. Stotus	DHCP Snp. Selup	DHCP Snp. Part Setup	DHCP Snp. VLAN Setup
DHCP Snooping Setu	p		
Active	ON C		
DI IOP VLAN	O nicoble O	I	
Database			
Agent URL			
linew of interval	300	second.	
orito solay interval	20.01	And and a	
Renew DH CP Shooping U	R	Her	a.me

Figure 360 SECURITY > IPv4 Source Guard > DHCP Snooping > DHCP Snp. Setup

Table 281	SECURITY >	> IPv4 Source Guard	> DHCP Snooping	> DHCP Snp. Setup
-----------	------------	---------------------	-----------------	-------------------

	DESC RIPTIO N
DHCP Snooping Setup	
Active	Enable the switch button to enable DHCP snooping on the Switch. You still have to enable DHCP snooping on specific VLAN and specify trusted ports.
	Note: If DHCP is enabled and there are no trusted ports, DHCP requests will not succeed.
DHCP VLAN	Select a VLAN ID if you want the Switch to forward DHCP packets to DHCP servers on a specific VLAN.
	Note: You have to enable DHCP snooping on the DHCP VLAN too.
	You can enable <b>Option 82 Profile</b> in the <b>SECURITY</b> > <b>IPv4 Source Guard</b> > <b>DHCP</b> <b>Snooping</b> > <b>DHCP Snp. VIAN Setup</b> screen to help the DHCP servers distinguish between DHCP requests from different VLAN.
	Select <b>Disa ble</b> if you do not want the Switch to forward DHCP packets to a specific VLAN.
Database	
	er than <b>Write Delay Interval</b> , it is possible that the next update is scheduled to occur e has finished successfully or timed out. In this case, the Switch waits to start the next the current one.
Agent URL	Enter the location of the DHCP snooping database. The location should be expressed like this: tttp:// {domain name or IP address}/directory, if applicable/file name; for example, tttp:// 192.168.10.1/database.txt. You can enter up to 256 printable ASCII
	characters except [ ? ], [   ], [ ' ], [ " ] or [ , ].
Timeout Interval	characters except [?], [], [], [], [] or [, ].         Enter how long (10 – 65535 seconds) the Switch tries to complete a specific update in the DHCP snooping database before it gives up.
Timeout Interval Write Delay Interval	Enter how long (10 – 65535 seconds) the Switch tries to complete a specific update in
	<ul> <li>Enter how long (10 – 65535 seconds) the Switch tries to complete a specific update in the DHCP snooping database before it gives up.</li> <li>Enter how long (10 – 65535 seconds) the Switch waits to update the DHCP snooping database the first time the current bindings change after an update. Once the next update is scheduled, additional changes in current bindings are automatically</li> </ul>
Write Delay Interval Renew DHCP	<ul> <li>Enter how long (10 - 65535 seconds) the Switch tries to complete a specific update in the DHCP snooping database before it gives up.</li> <li>Enter how long (10 - 65535 seconds) the Switch waits to update the DHCP snooping database the first time the current bindings change after an update. Once the next update is scheduled, additional changes in current bindings are automatically included in the next update.</li> <li>Enter the location of a DHCP snooping database, and click Renew if you want the Switch to load it. You can use this to load dynamic bindings from a different DHCP</li> </ul>
Write Delay Interval Renew DHCP	<ul> <li>Enter how long (10 - 65535 seconds) the Switch tries to complete a specific update in the DHCP snooping database before it gives up.</li> <li>Enter how long (10 - 65535 seconds) the Switch waits to update the DHCP snooping database the first time the current bindings change after an update. Once the next update is scheduled, additional changes in current bindings are automatically included in the next update.</li> <li>Enter the location of a DHCP snooping database, and click <b>Renew</b> if you want the Switch to load it. You can use this to load dynamic bindings from a different DHCP snooping database than the one specified in <b>Agent URL</b>.</li> <li>When the Switch loads dynamic bindings first. If there is a conflict, the Switch keeps the dynamic binding in volatile memory and updates the <b>Binding Collisions</b> counter in the</li> </ul>

# 74.4 DHCP Snooping Port Setup

Use this screen to specify whether ports are trusted or untrusted ports for DHCP snooping.

- Note: If DHCP snooping is enabled but there are no trusted ports, DHCP requests cannot reach the DHCP server.
- Note: The Switch will drop all DHCP requests if you enable DHCP snooping and there are no trusted ports.

You can also specify the maximum number for DHCP packets that each port (trusted or untrusted) can receive each second.

To open this screen, click SEC URITY > IPv4 Source Guard > DHCP Snooping > DHCP Snp. Port Setup.

OHCF Snp. Slobus	DHCP Snp. Selup	DHCF Snp. Porl selup
Tar	Server Nosted State	liale (pps)
225	Unbested v	
it.	Links sector	6
4	unicated	[¢
(c)	Lich start v	6
39	Unitsted	0
	<u>University</u>	0
6	Unifused w	0
	Little ad v	
		$\sim$
	Apply Enne	at

Figure 361 SECURITY > IPv4 Source Guard > DHCP Snooping > DHCP Snp. Port Setup

The following table describes the labels in this screen.

#### Table 282 SECURITY > IPv4 Source Guard > DHCP Snooping > DHCP Snp. Port Setup

LABEL	DESC RIPTIO N		
Port	This field displays the port number.		
*	Settings in this row apply to all ports.		
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.		
	Note: Changes in this row are copied to all the ports as soon as you make them.		
Server Trusted state	Select whether this port is a trusted port ( <b>Trusted</b> ) or an untrusted port ( <b>Untrusted</b> ).		
	Trusted ports are connected to DHCP servers or other switches, and the Switch discards DHCP packets from trusted ports only if the rate at which DHCP packets arrive is too high.		
	Untrusted ports are connected to subscribers, and the Switch discards DHCP packets from untrusted ports in the following situations:		
	• The packet is a DHCP server packet (for example, OFFER, ACK, or NACK).		
	<ul> <li>The source MAC address and source IP address in the packet do not match any of the current bindings.</li> </ul>		
	<ul> <li>The packet is a RELEASE or DECLINE packet, and the source MAC address and source port do not match any of the current bindings.</li> </ul>		
	The rate at which DHCP packets arrive is too high.		

LABEL	DESC RIPTIO N
Rate (pps)	Specify the maximum number for DHCP packets (1 – 2048) that the Switch receives from each port each second. The Switch discards any additional DHCP packets. Enter 0 to disable this limit, which is recommended for trusted ports.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click this to reset the values in this screen to their last-saved values.

 Table 282
 SECURITY > IPv4 Source Guard > DHCP Snooping > DHCP Snp. Port Setup (continued)

## 74.5 DHCP Snooping VIAN Setup

Use this screen to enable DHCP snooping on each VLAN and to specify whether or not the Switch adds DHCP relay agent option 82 information to DHCP requests that the Switch relays to a DHCP server for each VLAN.

To open this screen, click SEC URITY > IPv4 Source Guard > DHCP Snooping > DHCP Snp. VIAN Setup.

Figure 362 SECURITY > IPv4 Source Guard > DHCP Snooping > DHCP Snp. VLAN Setup

DHCP Snp. Status	DHCP Snp. Setup	DHCP Snp. Port Setup	DHCP Snp. VLA	N Setup
Solution VLAN by $\nabla D$		South		
The Number of VD	ANS: 1			
			$= - E \alpha_{0} (\mu   1)$	sen en
VIU	i	Inclaied	Option 82 Profile	6
		No w		<u>8</u>
- E		NO M		w.
			$= + 8 \alpha_{\rm H} \omega \Big]  .$	(gallere)
	Ap	Div Cancel		

The following table describes the labels in this screen.

IABEL	DESC RIPIIO N
Search VLAN by VID	Enter the VLAN ID you want to manage. Use a comma (,) to separate individual VLANs or a hyphen (-) to indicates a range of VLANs. For example, "3,4" or "3-9".
Search	Click this to display the specified range of VLANs in the section below.
The Number of VLANs	This displays the number of VLAN search results.
VID	This field displays the VLAN ID of each VLAN in the range specified above. If you configure the * VLAN, the settings are applied to all VLANs.

Table 283 SECURITY > IPv4 Source Guard > DHCP Snooping > DHCP Snp. VLAN Setup

IABEL	DESC RIPTIO N
Enabled	Select <b>Yes</b> to enable DHCP snooping on the VLAN. You still have to enable DHCP snooping on the Switch and specify trusted ports.
	Note: The Switch will drop all DHCP requests if you enable DHCP snooping and there are no trusted ports.
Option 82 Profile	Select a pre-defined DHCP option 82 profile that the Switch applies to all ports in the specified VLANs. The Switch adds the information (such as slot number, port number, VLAN ID and/or system name) specified in the profile to DHCP requests that it broadcasts to the DHCP VLAN, if specified, or VLAN. You can specify the DHCP VLAN in the <b>SEC URITY</b> > <b>IPv4 Sourc e Guard</b> > <b>DHCP Snooping</b> > <b>DHCP Snp. Setup</b> screen.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click this to reset the values in this screen to their last-saved values.

Table 283 SECURITY > IPv4 Source Guard > DHCP Snooping > DHCP Snp. VLAN Setup (continued)

## 74.6 DHCP Snooping VIAN Port Setup

Use this screen to apply a different DHCP option 82 profile to certain ports in a VLAN.

To open this screen, click SEC URITY > IPv4 Source Guard > DHCP Snooping > DHCP Snp. VIAN Port Setup.

Figure 363 SECURITY > IPv4 Source Guard > DHCP Snooping > DHCP Snp. VLAN Port Setup

DHCT Snp. Selup	DHCF Snp. Porl Selup	DHCF Snp. VLAN Selup	DHCP Snp. VLAN Port selop	
			O Assi at 🔒 Dente	
inche Inche	vic	Port	ProfileName	

The following table describes the labels in this screen.

Table 284	SECURITY >	> IPv4 Source Guard >	> DHCP Snooping >	> DHCP Snp.	VLAN Port Setup
-----------	------------	-----------------------	-------------------	-------------	-----------------

LABEL	DESC RIPTIO N	
Index	This field displays a sequential number for each entry.	
VID	This field displays the VLAN to which the ports belongs.	
Port	This field displays the ports to which the Switch applies the settings.	
Profile Name	This field displays the DHCP option 82 profile that the Switch applies to the ports.	
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.	
Delete	Click <b>De le te</b> to remove the selected entries.	

#### 74.6.1 Add/EDITDHCP Snooping VIAN Ports

Use this screen to apply a different DHCP option 82 profile to certain ports in a VLAN.

Click Add/Edit, or select an entry and click Add/Edit in the SEC URTIY > IPv4 Source Guard > DHCP Snooping > DHCP Snp. VIAN Port Setup screen to display this screen. Figure 364 SECURITY > IPv4 Source Guard > DHCP Snooping > DHCP Snp. VLAN Port Setup > Add/Edit

MD			
Port			
Option 52 Moffle	ciona di t	¥	
	Apply	Clean	General

The following table describes the labels in this screen.

Table 285	SECURITY > IPv4 Source	e Guard > DHCP Snoopina >	DHCP Snn	. VLAN Port Setup > Add/Edit
10010 200		Could' Brief cheeping -		

IABEL	DESC RIPTIO N
VID	Enter the ID number of the VLAN you want to configure here.
Port	Enter the number of ports to which you want to apply the specified DHCP option 82 profile.
	You can enter multiple ports separated by (no space) comma (,) or hyphen (-) for a range. For example, enter "3-5" for ports 3, 4, and 5. Enter "3,5,7" for ports 3, 5, and 7.
Option 82 Profile	<ul> <li>Select a pre-defined DHCP option 82 profile that the Switch applies to the specified ports in this VLAN. The Switch adds the information (such as slot number, port number, VLAN ID and/or system name) specified in the profile to DHCP requests that it broadcasts to the DHCP VLAN, if specified, or VLAN. You can specify the DHCP VLAN in the SEC URITY &gt; IPv4 Source Guard &gt; DHCP Snooping &gt; DHCP Snp. Setup screen.</li> <li>Note: The profile you select here has priority over the one you select in the SEC URITY &gt; IPv4 Source Guard &gt; DHCP Snooping &gt; DHCP Snoping &gt; DHCP Snoping &gt; DHCP Snooping</li></ul>
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

#### 74.7 Technical Reference

This section provides technical background information on the topics discussed in this chapter.

#### 74.7.1 DHCP Snooping Overview

Use DHCP snooping to filter unauthorized DHCP packets on the network and to build the binding table dynamically. This can prevent clients from getting IP addresses from unauthorized DHCP servers.

#### 74.7.1.1 Trusted vs. Untrusted Ports

Every port is either a trusted port or an untrusted port for DHCP snooping. This setting is independent of the trusted or untrusted setting for ARP inspection. You can also specify the maximum number for DHCP packets that each port (trusted or untrusted) can receive each second.

Trusted ports are connected to DHCP servers or other switches. The Switch discards DHCP packets from trusted ports only if the rate at which DHCP packets arrive is too high. The Switch learns dynamic bindings from trusted ports.

Note: If DHCP is enabled and there are no trusted ports, DHCP requests will not succeed.

Untrusted ports are connected to subscribers. The Switch discards DHCP packets from untrusted ports in the following situations:

- The packet is a DHCP server packet (for example, OFFER, ACK, or NACK).
- The source MAC address and source IP address in the packet do not match any of the current bindings.
- The packet is a RELEASE or DECLINE packet, and the source MAC address and source port do not match any of the current bindings.
- The rate at which DHCP packets arrive is too high.

#### 74.7.1.2 DHCP Snooping Database

The Switch stores the binding table in volatile memory. If the Switch restarts, it loads static bindings from permanent memory but loses the dynamic bindings, in which case the devices in the network have to send DHCP requests again. As a result, it is recommended you configure the DHCP snooping database.

The DHCP snooping database maintains the dynamic bindings for DHCP snooping and ARP inspection in a file on an external TFTP server. If you set up the DHCP snooping database, the Switch can reload the dynamic bindings from the DHCP snooping database after the Switch restarts.

You can configure the name and location of the file on the external TFTP server. The file has the following format:

Figure 365 DHCP Snooping Database File Format

```
<initial-checksum>
TYPE DHCP-SNOOPING
VERSION 1
BEGIN
<binding-1> <checksum-1>
<binding-2> <checksum-1-2>
...
<binding-n> <checksum-1-2-..-n>
END
```

The <initial-checksum> helps distinguish between the bindings in the latest update and the bindings from previous updates. Each binding consists of 72 bytes, a space, and another checksum that is used to validate the binding when it is read. If the calculated checksum is not equal to the checksum in the file, that binding and all others after it are ignored.

#### 74.7.1.3 DHCP Re lay Option 82 Information

The Switch can add information to DHCP requests that it does not discard. This provides the DHCP server more information about the source of the requests. The Switch can add the following information:

- Slot ID (1 byte), port ID (1 byte), and source VLAN ID (2 bytes)
- System name (up to 32 bytes)

This information is stored in an Agent Information field in the option 82 field of the DHCP headers of client DHCP request frames.

When the DHCP server responds, the Switch removes the information in the Agent Information field before forwarding the response to the original source.

You can configure this setting for each source VLAN. This setting is independent of the DHCP relay settings.

#### 74.7.1.4 Configuring DHCP Snooping

Follow these steps to configure DHCP snooping on the Switch.

- 1 Enable DHCP snooping on the Switch.
- 2 Enable DHCP snooping on each VLAN, and configure DHCP relay option 82.
- 3 Configure trusted and untrusted ports, and specify the maximum number of DHCP packets that each port can receive per second.
- 4 Configure static bindings.

# C HAPTER 75 ARP Inspection

## 75.1 ARP Inspection Status

Use this screen to look at the current list of MAC address filters that were created because the Switch identified an unauthorized ARP packet. When the Switch identifies an unauthorized ARP packet, it automatically creates a MAC address filter to block traffic from the source MAC address and source VLAN ID of the unauthorized ARP packet. To open this screen, click SEC URITY > IPv4 Source Guard > ARP Inspection > ARP Insp. Status.

Figure 366	SECURITY > IPv4 Source Guard > ARP Inspection > ARP Insp. Status
------------	--

Intel Namber of	Bår e linke et s				
					C/Papel C
	le des	WAS Address	300	5.4	Repty (Less)
					111 SON ( 01)

The following table describes the labels in this screen.

IABEL	DESC RIPTIO N
Total Number of Bindings	This field displays the current number of MAC address filters that were created because the Switch identified unauthorized ARP packets.
Index	This field displays a sequential number for each MAC address filter.
MAC Address	This field displays the source MAC address in the MAC address filter.
VID	This field displays the source VLAN ID in the MAC address filter.
Port	This field displays the source port of the discarded ARP packet.
Expiry (sec)	This field displays how long (in seconds) the MAC address filter remains in the Switch. You can also delete the record manually ( $De le te$ ).
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Delete	Click this to remove the selected entries.
Cancel	Click this to clear the <b>Delete</b> check boxes above.

Table 286 SECURITY > IPv4 Source Guard > ARP Inspection > ARP Insp. Status

500

### 75.2 ARP Inspection VIAN Status

Use this screen to look at various statistics about ARP packets in each VLAN. To open this screen, click SEC URITY > IPv4 Source Guard > ARP Inspection > ARP Insp. VIAN Status.

Figure 367 SEC	URITY > IPv4 Source Gu	ard > ARP Inspection >	> ARP Insp. VLAN Status
----------------	------------------------	------------------------	-------------------------

et subset of	10	- Contra			
nt frankar at V	acaa <sup>00</sup>				
net forerelation of V	VENE O				
					$1 = 2206 (\underline{\mu}_{1,1})^2 + 210$
30	sec-alcost	ercart .	- HOW	( devoced	UNIXEd
					CONTRACTOR OF

The following table describes the labels in this screen.

IABEL	DESC RIPTIO N
Search VLAN by VID	Specify the VLANs you want to view in the section below. Use a comma (,) to separate individual VLANs or a hyphen (-) to indicates a range of VLANs. For example, "3,4" or "3-9".
Search	Click this to display the specified range of VLANs in the section below.
The Number of	This is the number of VLANs that match the searching criteria and display in the list below.
VLANs	The number displays when you use the $\mathbf{Search}$ button to look for certain VLANs. The default value is 0.
VID	This field displays the VLAN ID of each VLAN in the range specified above.
Received	This field displays the total number of ARP packets received from the VLAN since the Switch last restarted.
Request	This field displays the total number of ARP Request packets received from the VLAN since the Switch last restarted.
Reply	This field displays the total number of ARP Reply packets received from the VLAN since the Switch last restarted.
Forwarded	This field displays the total number of ARP packets the Switch forwarded for the VLAN since the Switch last restarted.
Dropped	This field displays the total number of ARP packets the Switch discarded for the VLAN since the Switch last restarted.

Table 287 SECURITY > IPv4 Source Guard > ARP Inspection > ARP Insp. VLAN Status

# 75.3 ARP Inspection Log Status

Use this screen to look at log messages that were generated by ARP packets and that have not been sent to the syslog server yet. To open this screen, click SEC URITY > IPv4 Source Guard > ARP Inspection > ARP Insp. Log Status.

Figure 368	SECURITY > IPv4 Source Gud	ard $>$ ARP Inspection $>$	ARP Insp. Log Status
ing and 0000			7 (K) 11301 E0g 010100

ARP Insp. Status	ARP Insp. VLA	N Status ARP I	nsp. Log Status	ARP Insp. Schut	p ARP Insp.	Port Schup
Creating Togettation Tailal Number of B						
Index Po	at VID	Sender MAC	Aender IP	Pocket Number	Recision	Ime

IABEL	DESC RIPTIO N
Clearing Log Status Table	Click <b>Clear</b> to remove all the log messages that were generated by ARP packets and that have not been sent to the syslog server yet.
Total number of Bindings	This field displays the number of log messages that were generated by ARP packets and that have not been sent to the syslog server yet. If one or more log messages are dropped due to unavailable buffer, there is an entry called <b>overflow</b> with the current number of dropped log messages.
Index	This field displays a sequential number for each log message.
Port	This field displays the source port of the ARP packet.
VID	This field displays the source VLAN ID of the ARP packet.
Sender MAC	This field displays the source MAC address of the ARP packet.
Sender IP	This field displays the source IP address of the ARP packet.
Packet Number	This field displays the number of ARP packets that were consolidated into this log message. The Switch consolidates identical log messages generated by ARP packets in the log consolidation interval into one log message. You can configure this interval in the SEC URITY > IPv4 Sourc e Guard > ARP Inspection > ARP Insp. Setup screen.
Reason	This field displays the reason the log message was generated.
	<b>dhcp deny</b> : An ARP packet was discarded because it violated a dynamic binding with the same MAC address and VLAN ID.
	static deny: An ARP packet was discarded because it violated a static binding with the same MAC address and VLAN ID.
	deny: An ARP packet was discarded because there were no bindings with the same MAC address and VLAN ID.
	dhcp pemit: An ARP packet was forwarded because it matched a dynamic binding.
	static pemit: An ARP packet was forwarded because it matched a static binding.
	In the SEC URITY > IPv4 Source Guard > ARP Inspection > ARP Insp. VIAN Setup screen, you can configure the Switch to generate log messages when ARP packets are discarded or forwarded based on the VLAN ID of the ARP packet.
Time	This field displays when the log message was generated.

Table 288 SECURITY > IPv4 Source Guard > ARP Inspection > ARP Insp. Log Status

# 75.4 ARP Inspection Setup

Use this screen to enable ARP inspection on the Switch. You can also configure the length of time the Switch stores records of discarded ARP packets and global settings for the ARP inspection log. To open this screen, click SEC URITY > IPv4 Source Guard > ARP Inspection > ARP Insp. Setup.

ARP insp. Status	ARP Insp. VL	AN Status	ARP Insp. Log Status	ARP insp. Setup
ARP Inspection Sc	tup			
Ave not	🕒 ort j	•		
Tiller Aging time				
Elfer aging Time	200	she ands		
Log Profile				
Log Euffor Sten	32	ostrios.		
Sydng Rans	5	over the		
Log interval	1	end an ris		
		/oply	Consel	

Figure 369 SECURITY > IPv4 Source Guard > ARP Inspection > ARP Insp. Setup

The following table describes the labels in this screen.

LABEL	DESC RIPTIO N	
ARP Inspection Setup		
Active	Enable the switch button to enable ARP inspection on the Switch. You still have to enable ARP inspection on specific VLAN and specify trusted ports.	
Filter Aging Time		
Filter Aging Time	This setting has no effect on existing MAC address filters.	
	Enter how long (1 – 2147483647 seconds) the MAC address filter remains in the Switch after the Switch identifies an unauthorized ARP packet. The Switch automatically deletes the MAC address filter afterwards. Type 0 if you want the MAC address filter to be permanent.	
Log Profile		
Log Buffer Size	Enter the maximum number $(1 - 1024)$ of log messages that were generated by ARP packets and have not been sent to the syslog server yet. Make sure this number is appropriate for the specified <b>Syslog Rate</b> and <b>Log Interval</b> .	
	If the number of log messages in the Switch exceeds this number, the Switch stops recording log messages and simply starts counting the number of entries that were dropped due to unavailable buffer. Click <b>Clearing Log Status Table</b> in the <b>SEC URITY</b> > <b>IPv4 Source Guard</b> > <b>ARP Inspection</b> > <b>ARP Insp. Log Status</b> screen to clear the log and reset this counter.	
Syslog Rate	Type the maximum number of syslog messages the Switch can send to the syslog server in one batch. This number is expressed as a rate because the batch frequency is determined by the <b>Log Interval</b> . You must configure the syslog server to use this. Enter 0 if you do not want the Switch to send log messages generated by ARP packets to the syslog server.	
	The relationship between <b>Syslog Rate</b> and <b>Log Interval</b> is illustrated in the following examples:	
	• Four invalid ARP packets per second, <b>Syslog Rate</b> is 5, <b>Log Interval</b> is 1: the Switch sends 4 syslog messages every second.	
	• Six invalid ARP packets per second, <b>Syslog Rate</b> is 5, <b>Log Interval</b> is 2: the Switch sends 5 syslog messages every 2 seconds.	

Table 289 SECURITY > IPv4 Source Guard > ARP Inspection > ARP Insp. Setup

IABEL	DESC RIPIIO N
Log interval	Type how often (1 – 86400 seconds) the Switch sends a batch of syslog messages to the syslog server. Enter 0 if you want the Switch to send syslog messages immediately. See <b>Syslog Rate</b> for an example of the relationship between <b>Syslog Rate</b> and <b>Log Interval</b> .
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click this to reset the values in this screen to their last-saved values.

Table 289 SECURITY > IPv4 Source Guard > ARP Inspection > ARP Insp. Setup (continued)

## 75.5 ARP Inspection Port Setup

Use this screen to specify whether ports are trusted or untrusted ports for ARP inspection. You can also specify the maximum rate at which the Switch receives ARP packets on each untrusted port. To open this screen, click **SEC URITY > IPv4 Source Guard > ARP Inspection > ARP Insp. Port Setup**.

o. VLAN Stotus ARP Insp. Log Status ARP Insp. Selup. ARP insp. Port Setup lind Port **Initiated Strine** Rate(pps) fund interval (seconds).  $\tilde{\mathbf{x}}$ Untrustero 🥺 £. tohulied w 1.1 Untrusted 92 15 1 202 thing at w 15  $\overline{\mathbf{S}}$ £. Untrustero se 15. ġ. Uniu/les 🖬 15  $1\Lambda_{\rm c}$ 6. Unitideo M Brituate e w  $15^{\circ}$ 25  $\overline{13}$ Apply General.

Figure 370 SECURITY > IPv4 Source Guard > ARP Inspection > ARP Insp. Port Setup

The following table describes the labels in this screen.

Table 290 SECURITY > IPv4 Source Guard > ARP Inspection > ARP Insp. Port Setup

IABEL	DESC RIPTIO N
Port	This field displays the port number.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.

LABEL	DESC RIPTIO N
Trusted State	Select whether this port is a trusted port (Trusted) or an untrusted port (Untrusted).
	The Switch does not discard ARP packets on trusted ports for any reason.
	The Switch discards ARP packets on untrusted ports in the following situations:
	<ul> <li>The sender's information in the ARP packet does not match any of the current bindings.</li> </ul>
	<ul> <li>The rate at which ARP packets arrive is too high. You can specify the maximum rate at which ARP packets can arrive on untrusted ports.</li> </ul>
Limit	Rate and Burst Interval settings have no effect on trusted ports.
Rate (pps)	Specify the maximum rate (1 – 2048 packets per second) at which the Switch receives ARP packets from each port. The Switch discards any additional ARP packets. Enter 0 to disable this limit.
Burst Interval (seconds)	The burst interval is the length of time over which the rate of ARP packets is monitored for each port. For example, if the Rate is 15 pps and the burst interval is 1 second, then the Switch accepts a maximum of 15 ARP packets in every one-second interval. If the burst interval is 5 seconds, then the Switch accepts a maximum of 75 ARP packets in every five-second interval.
	Enter the length (1 – 15 seconds) of the burst interval.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click this to reset the values in this screen to their last-saved values.

#### Table 290 SECURITY > IPv4 Source Guard > ARP Inspection > ARP Insp. Port Setup (continued)

# 75.6 ARP Inspection VLAN Setup

Use this screen to enable ARP inspection on each VLAN and to specify when the Switch generates log messages for receiving ARP packets from each VLAN. To open this screen, click SEC URTIX > IPv4 Source Guard > ARP Inspection > ARP Insp. VIAN Setup.

Figure 371 SECURITY > IPv4 Source Guard > ARP Inspection > ARP Insp. VLAN Setup

	CHARLEN CONTRACTOR	ARP Insp. Porf Selup		our coul
en-in (A Alting (d))		Security		
he Number of VLANs:	t.			
			Page	]et i =
VID	Enge	ico:	Lo g	
	No.5	4	Nore w	
÷.).	1945	~]	Serve w	
			P 3 20	_]ct i
2				

Table 201	SECUDITY > IDv/ Source Cuard	ADD Inconcion	ADD Inco VI ANI Sotup
	SECURITY > IPv4 Source Guard		ARE INSP. VLAIN SEIUP

IABEL	DESC RIPIIO N
Search VLAN by VID	Specify the VLANs you want to manage in the section below. Use a comma (,) to separate individual VLANs or a hyphen (-) to indicates a range of VLANs. For example, "3,4" or "3-9".
Search	Click this to display the specified range of VLANs in the section below.
The Number of VLANs	This display the number of ARP inspection VLAN search results.
VID	This field displays the VLAN ID of each VLAN in the range specified above. If you configure the * VLAN, the settings are applied to all VLANs.
Enabled	Select $\mathbf{Yes}$ to enable ARP inspection on the VLAN. Select $\mathbf{No}$ to disable ARP inspection on the VLAN.
Log	Specify when the Switch generates log messages for receiving ARP packets from the VLAN.
	$\mathbf{None}$ : The Switch does not generate any log messages when it receives an ARP packet from the VLAN.
	$\mathbf{Deny}$ : The Switch generates log messages when it discards an ARP packet from the VLAN.
	$\mathbf{Pe}  \mathbf{m}  \mathbf{it}$ : The Switch generates log messages when it forwards an ARP packet from the VLAN.
	All: The Switch generates log messages every time it receives an ARP packet from the VLAN.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click this to reset the values in this screen to their last-saved values.

## 75.7 IPv6 Source Guard

The purpose of IPv6 source guard is to distinguish between authorized and unauthorized users by using a binding table that validates the source of IPv6 traffic. The binding table can be manually created or be learned through Dynamic Host Configuration Protocol version 6 snooping (DHCPv6 snooping). IPv6 source guard can deny IPv6 traffic from an unknown source. The IPv6 source guard binding table includes:

- IPv6 address
- IPv6 prefix
- VLAN ID
- Port number
- MAC address

Enable IPv6 source guard on a port for the Switch to check incoming IPv6 packets on that port. A packet is allowed when it matches any entry in the IPSG binding table. If a user tries to send IPv6 packets to the Switch that do not match an entry in the IPSG binding table, the Switch will drop these packets. The Switch forwards matching traffic normally. The IPv6 source guard related screens are available in standalone mode.

# 75.8 IPv6 Source Binding Status

Use this screen to look at the current IPv6 dynamic and static bindings and to remove dynamic bindings based on IPv6 address and/or IPv6 prefix. Bindings are used to distinguish between authorized and unauthorized packets in the network. The Switch learns the bindings by snooping DHCP packets (dynamic bindings) and from information provided manually by administrators (static bindings). To open this screen, click **SEC URITY > IPv6 Source Guard > IP Static Binding > IP Source Binding Status**.

Figure 372 SECURITY > IPv6 Source Guard > IP Static Binding > IP Source Binding Status

IPv8 Source	Binding Status	IPv6 Static Binding					
Clear Dynami	ie Source Binding	O Al O IP+6 Acotres O IP+6 Profix				) V(	
		— Hush —	Cancel				
Index	Source Address	MAC Address	VLAN	Port	Leone		Гуре

Table 292	SECURITY >	> IPv6 Source Guard >	IP Static Binding >	· IP Source Binding Status
-----------	------------	-----------------------	---------------------	----------------------------

LABEL	DESC RIPIIO N
Clear Dynamic Source Binding	Specify how you want the Switch to remove dynamic IPv6 source binding entries when you click <b>Flush</b> .
	<ul> <li>Select All to remove all of the dynamic entries from the IPv6 source binding table.</li> <li>Select IPv6 Address and enter an IPv6 address to remove the dynamic entries snooped with the specified IPv6 address.</li> <li>Select IPv6 Prefix and enter a Prefix address to remove the dynamic entries snooped with the specified Prefix address.</li> </ul>
Flush	Click this to remove dynamic IPv6 source binding entries according to your selections.
Cancel	Click this to reset the values above based or if not applicable, to clear the fields above.
Index	This field displays a sequential number for each binding.
Source Address	This field displays the source IP address in the binding. If the entry is blank, this field will not be checked in the binding.
MAC Address	This field displays the source MAC address in the binding. If the entry is blank, this field will not be checked in the binding.
VLAN	This field displays the source VLAN ID in the binding. If the entry is blank, this field will not be checked in the binding.
Port	This field displays the port number in the binding. If this field is blank, the binding applies to all ports.
Lease	This field displays how many days, hours, minutes, and seconds the binding is valid; for example, <b>2d3h4m5s</b> means the binding is still valid for 2 days, 3 hours, 4 minutes, and 5 seconds. This field displays <b>infinity</b> if the binding is always valid (for example, a static binding).
Туре	This field displays how the Switch learned the binding.
	${f s}$ : This static binding was learned from information provided manually by an administrator.
	<b>DH</b> : This dhcp-snooping binding was learned by snooping DHCP packets.

## 75.9 IPv6 Static Binding

Use this screen to view or configure an IPv6 source guard binding table entry and manage IPv6 static bindings. Static bindings are uniquely identified by the source IPv6 address / prefix. Each source IPv6 address / prefix can only be in one static binding. If you try to create a static binding with the same source IPv6 address / prefix as an existing static binding, the new static binding replaces the original one. To open this screen, click **SECURITY > IPv6 Source Guard > IPv6 Static Binding > IPv6 Static Binding**.

Figure 373 SECURITY > IPv6 Source Guard > IPv6 Static Binding > IPv6 Static Binding

			C Addition	Etabeter
Inde	a Adoteta	MAC Address	VLAN	Ped

The following table describes the labels in this screen.

LABEL	DESC RIPTIO N
Index	This field displays a sequential number for each binding.
Source Address	This field displays the IPv6 address or IPv6 prefix and prefix length in the binding.
MAC Address	This field displays the source MAC address in the binding. If the entry is blank, this field will not be checked in the binding.
VLAN	This field displays the source VLAN ID in the binding. If the entry is blank, this field will not be checked in the binding.
Port	This field displays the port number in the binding. If this field is blank, the binding applies to all ports.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.
Delete	Click <b>De le te</b> to remove the selected entries.

Table 293 SECURITY > IPv6 Source Guard > IPv6 Static Binding > IPv6 Static Binding

## 75.9.1 Add/Edit IPv6 Static Binding

Use this screen to manually create an IPv6 source guard binding table entry and manage IPv6 static bindings. Click Add/Edit, or select an entry and click Add/Edit in the SEC URITY > IPv6 Source Guard > IPv6 Static Binding > IPv6 Static Binding screen to display this screen.

508

Source Address	O P vi Arotes
	O IP vš Profix
MAC Address	⊖ Any
	o
VEAN	⊖ Ary
	0
Port	0.409
	0
	Apply Clear Concel

Figure 374 SECURITY > IPv6 Source Guard > IPv6 Static Binding > IPv6 Static Binding > Add/Edit

The following table describes the labels in this screen.

Table 294 SECURITY > IPv6 Source Guard > IPv6 Static Binding > IPv6 Static Binding > Ad
---

IABEL	DESC RIPTIO N
Source Address	Enter the <b>IPv6 Address</b> or <b>IPv6 Prefix</b> and prefix length in the binding.
MAC Address	Enter the source MAC address in the binding. If this binding does not check this field, select $\mathbf{Any}$ .
	Note: You cannot choose <b>Any</b> for all three of <b>MAC Address</b> , <b>VIAN</b> and <b>Port</b> . You must fill in at least one.
VLAN	Enter the source VLAN ID in the binding. If this binding does not check this field, select Any.
Port	Specify the ports in the binding. If this binding has one port, select the first radio button and enter the port number in the field to the right.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click <b>Clear</b> to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

## 75.10 IPv6 Source Guard Policy

Use this screen to have IPv6 source guard forward valid IPv6 addresses and/or IPv6 prefixes that are stored in the binding table and allow or block data traffic from all link-local addresses. To open this screen, click SEC URTIY > IPv6 Source Guard > IPv6 Source Guard > IPv6 Source Guard Policy.

- If you select Validate Address and not Validate Prefix, traffic for a binding entry that matches a IPv6 address and VLAN ID, port number, and MAC address will be forwarded. If this binding entry is a IPv6 prefix, the traffic will be denied.
- If you select **Validate Prefix** and not **Validate Address**, traffic for a binding entry that matches a IPv6 prefix and VLAN ID, port number, and MAC address will be forwarded. If this binding entry is a IPv6 address, the traffic will be denied.
- If you select both Validate Prefix and Validate Address then traffic matching either IPv6 address or prefix will be forwarded.

Figure 375	SECURITY > IPv6 Source Guard > IPv6 Source Guard > IPv6 Source Guard Policy
ing and one	

	ce Goord Policy	IPv6 301	arce Goard Porl Seloy	u .	
				📮 Acc-Latt	E Gente
10	index	Nome	Volidole Address	Volidore Prets	Link Local

Table 295	SECURITY > IPv6 Source Guard > IPv6 Source Guard > IPv6 Source	e Guard Policy

IABEL	DESC RIPTIO N
Index	This field displays a sequential number for each policy.
Name	This field displays the descriptive name for identification purposes for this IPv6 source guard policy.
Validate Address	This field displays the Validate Address status for this IPv6 source guard policy.
Validate Prefix	This field displays the <b>Validate Prefix</b> status for this IPv6 source guard policy.
Link Local	This field displays the <b>Link Local</b> traffic status for this IPv6 source guard policy.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.
Delete	Click <b>De le te</b> to remove the selected entries.

## 75.10.1 Add/Edit an IPv6 Source Guard Policy

Click Add/Edit, or select an entry and click Add/Edit in the SEC URITY > IPv6 Source Guard > IPv6 Source Guard > IPv6 Source Guard > IPv6 Source Guard Policy screen to display this screen.

Figure 376 SECURITY > IPv6 Source Guard > IPv6 Source Guard > IPv6 Source Guard Policy > Add/Edit

Name			
Validiate Address	() DIT		
Validate Prets	() or		
Link Local	Deny in		
	Apply	Clear	Ganeel

The following table describes the labels in this screen.

Table 296 SECURITY > IPv6 Source Guard > IPv6 Source Guard > IPv6 Source Guard Policy > Add/Edit

LABEL	DESC RIPIIO N
Name	Enter a descriptive name for identification purposes for this IPv6 source guard policy. You can enter up to 32 printable ASCII characters except [ $?$ ], [ $ $ ], [ $'$ ], [ $"$ ] or [,].
Validate Address	Select <b>Validate Address</b> to have IPv6 source guard forward valid addresses that are stored in the binding table.
Validate Prefix	Select <b>Validate Prefix</b> to have IPv6 source guard forward valid prefixes that are stored in the binding table.

IABEL	DESC RIPIIO N
Link Local	Select <b>Pemit</b> to allow data traffic from all link-local addresses; otherwise leave the setting at <b>Deny</b> . A link-local address is an IPv6 unicast address that can be automatically configured on any interface using the link-local prefix FE80::/10 and the interface identifier in the modified EUI-64 format.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

Table 296 SECURITY > IPv6 Source Guard > IPv6 Source Guard > IPv6 Source Guard Policy > Add/Edit

# 75.11 IPv6 Source Guard Port Setup

Use this screen to apply configured IPv6 source guard policies to ports you specify. Use port \* to apply a policy to all ports. To open this screen, click SEC URITY > IPv6 Source Guard >

Figure 377	SECURITY > IPv6	Source Guard > IPv6 Source Gu	Jard > IPv6 Source Gua	rd Port Setup
Sec. Sec.		the second s		

Port	Folloy Kome
-423	w.
-1	
.2.	
	~
4	<u></u>
5	
14 C	(U)
. E	$\sim$ $\stackrel{\circ}{=}$ $\sim$ $\sim$ $\sim$

Table 297	SECURITY > IPv6 Source	Guard > IPv6 Source	Guard > IPv6 Source (	Guard Port Setup
-----------	------------------------	---------------------	-----------------------	------------------

IABEL	DESC RIPTIO N
Port	This field displays the port number.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
Policy Name	Select an IPv6 source guard policy that the Switch will apply to this port.

LABEL	DESC RIPTIO N
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click this to reset the values in this screen to their last-saved values.

Table 297 SECURITY > IPv6 Source Guard > IPv6 Source Guard > IPv6 Source Guard Port Setup

# 75.12 IPv6 Snooping Policy Setup

Use this screen to view and dynamically create an IPv6 source guard binding table using a DHCPv6 snooping policy. A DHCPv6 snooping policy lets the Switch sniff DHCPv6 packets sent from a DHCPv6 server to a DHCPv6 client when it is assigning an IPv6 address. When a DHCPv6 client successfully gets a valid IPv6 address, DHCPv6 snooping builds the binding table dynamically. To open this screen, click **SEC URITY > IPv6 Source Guard > IPv6 Snooping > IPv6 Snooping Policy Setup**.

Note: If you do not select **Protocol** and **Prefix Glean**, then the Switch cannot perform DHCPv6 snooping.

Figure 378 SECURITY > IPv6 Source Guard > IPv6 Snooping > IPv6 Snooping Policy Setup

Add/Edit     Endex     Nome     Protocol     Prefs Gloon     Ecurit	IPv& Snoopi	ing Policy S	elup IPv6 Snooj	ping VLAN Selop		
Index Norse Protocol Prefs Gleon Umit Address					÷	
Index Naroe Protocol Pretty Glean					G Add/Edit	🛑 Deslerte
		Index	Nome	Protocol	Prefs Glean	

The following table describes the labels in this screen.

Table 298 SECURITY > IPv6 Source Guard > IPv6 Snooping > IPv6 Snooping Policy Setup
---

IABEL	DESC RIPTIO N
Index	This field displays a sequential number for each IPv6 snooping policy.
Name	This field displays the descriptive name for identification purposes for this IPv6 source guard policy.
Protocol	This field displays the protocols learned from DHCPv6 sniffed packets.
Prefix Glean	This field displays the IPv6 prefixes learned from DHCPv6 sniffed packets.
Limit Address Count	This field displays the number of IPv6 addresses and prefixes learned using the IPv6 snooping policy.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.
Delete	Click <b>Delete</b> to remove the selected entries.

## 75.12.1 Add/Edit a IPv6 Snooping Policy

Use this screen to dynamically create an IPv6 source guard binding table using a DHCPv6 snooping policy. Click Add/Edit, or select an entry and click Add/Edit in the SEC URITY > IPv6 Source Guard > IPv6 Snooping > IPv6 Snooping Policy Setup screen to display this screen.

Figure 379 SECURITY > IPv6 Source Guard > IPv6 Snooping > IPv6 Snooping Policy Setup > Add/Edit

Neme	
Protocol	
Prefix Gleon	OFF
Timil Address Count	
Apply	Clear Cancel

The following table describes the labels in this screen.

LABEL	DESC RIPIIO N
Name	Enter a descriptive name for identification purposes for this IPv6 snooping policy. You can enter up to 32 printable ASCII characters except [?], [   ], [ ' ], [ ' ] or [, ].
Protocol	Select <b>DHCP</b> to let the Switch sniff DHCPv6 packets sent from a DHCPv6 server to a DHCPv6 client.
Prefix Glean	Enable the switch button to learn the IPv6 prefix and length from DHCPv6 sniffed packets.
Limit Address Count	This is the number of IPv6 addresses and prefixes learned using the IPv6 snooping policy.
	Note: The maximum limit address count is the maximum size of the IPv6 source guard binding table. See the product data sheet for the latest specifications.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

## 75.13 IPv6 Snooping VIAN Setup

Use this screen to enable a DHCPv6 snooping policy on a specific VLAN interface. To open this screen, click SEC URITY > IPv6 Source Guard > IPv6 Snooping > IPv6 Snp. VLAN Setup.

Figure 380 SECURITY > IPv6 Source Guard > IPv6 Snooping > IPv6 Snp. VLAN Setup

IPv6 Scooping Policy Setup		IPvé Snooping VLAN Set	1p
			O Andrisat 📲 status
1	Index	histoce	Folicy

The following table describes the labels in this screen.

Table 300 SECURITY > IPv6 Source Guard > IPv6 Snooping > IPv6 Snp. VLAN Setup

LABEL	DESC RIPTIO N
Index	This field displays a sequential number for each binding.
Interface	This field displays the VLAN interface.

IABEL	DESC RIPTIO N
Policy	This field displays the DHCPv6 snooping policy.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.
Delete	Click <b>Delete</b> to remove the selected entries.

Table 300 SECURITY > IPv6 Source Guard > IPv6 Snooping > IPv6 Snp. VLAN Setup (continued)

## 75.13.1 Add/Edit an IPv6 Snooping VIAN

Use this screen to add/edit a DHCPv6 snooping policy on a specific VLAN interface. Click Add/Edit, or select an entry and click Add/Edit in the SEC URTIY > IPv6 Source Guard > IPv6 Snooping > IPv6 Snp. VIAN Setup screen to display this screen.

Figure 381 SECURITY > IPv6 Source Guard > IPv6 Snooping > IPv6 Snp. VLAN Setup > Add/Edit

Interface Policy	<u>\</u>	<u>191 v</u>
Apply	Clear	Doncel

The following table describes the labels in this screen.

LABEL	DESC RIPIIO N	
Interface	Select the VLAN interface to apply the selected DHCPv6 snooping policy.	
Policy	Select the IPv6 snooping policy to apply to this VLAN interface.	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Clear	Click <b>Clear</b> to clear the fields to the factory defaults.	
Cancel	Click <b>Cancel</b> to not save the configuration you make and return to the last screen.	

Table 301 SECURITY > IPv6 Source Guard > IPv6 Snooping > IPv6 Snp. VLAN Setup > Add/Edit

# 75.14 IPv6 DHCP Trust Se tup

Use this screen to specify which ports are trusted for DHCPv6 snooping. To open this screen, click SEC URITY > IPv6 Source Guard > DHCPv6 Trust Setup.

Note: DHCPv6 solicit packets are sent from a DHCPv6 client to a DHCPv6 server. Reply packets from a DHCPv6 server connected to an untrusted port are discarded.

Use port \* to have all ports be Untrusted or Trusted.

BHCrys trust Selup	
Trust Setting	
альна Ста	2
Port Setting	
Part	Trusted Store
	Urmetos 🛩
172	Umrusto f 🛩
( ) ( ) ( ) ( ) ( ) ( ) ( ) ( ) ( ) ( )	Unructo di 🛩
(A)	0 musted 💌
÷	Umeted v
- A	Umeted v
1.0.0	l u muste d 🛩
	Apply Daniel

Figure 382	SECURITY > IPv6 Source Guard > DHCPv6 Trust Setup
the second se	

Table 302	SECURITY >	IPv6 Source Guard	> DHCPv6 Trust Setup

LABEL	DESC RIPTIO N
Trust Setting	
Active	Enable the switch button to specify whether ports are trusted or untrusted ports for DHCP snooping. If you do not select this then <b>IPv6 DHCP Trust</b> is not used and all ports are automatically trusted.
Port Setting	
Port	This field displays the port number.
*	Settings in this row apply to all ports. Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis. Note: Changes in this row are copied to all the ports as soon as you make them.
Trusted State	<ul> <li>Select whether this port is a trusted port (Thusted) or an untrusted port (Untrusted).</li> <li>Trusted ports are connected to DHCPv6 servers or other switches.</li> <li>Untrusted ports are connected to subscribers, and the Switch discards DHCPv6 packets from untrusted ports in the following situations:</li> <li>The packet is a DHCPv6 server packet (for example, ADVERTISE, REPLY, or RELAY-REPLY).</li> <li>The source MAC address and source IP address in the packet do not match any of the current bindings.</li> </ul>

LABEL	DESC RIPTIO N
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click this to reset the values in this screen to their last-saved values.

Table 302 SECURITY > IPv6 Source Guard > DHCPv6 Trust Setup (continued)

# 75.15 Technical Reference

This section provides technical background information on the topics discussed in this chapter.

## 75.15.1 ARP Inspection Overview

Use ARP inspection to filter unauthorized ARP packets on the network. This can prevent many kinds of man-in-the-middle attacks, such as the one in the following example.




Figure 383 Example: Man-in-the-middle Attack

In this example, computer **B** tries to establish a connection with computer **A**. Computer **X** is in the same broadcast domain as computer **A** and intercepts the ARP request for computer **A**. Then, computer **X** does the following things:

- It pretends to be computer A and responds to computer B.
- It pretends to be computer **B** and sends a message to computer **A**.

As a result, all the communication between computer  $\mathbf{A}$  and computer  $\mathbf{B}$  passes through computer  $\mathbf{X}$ . Computer  $\mathbf{X}$  can read and alter the information passed between them.

#### 75.15.1.1 ARP Inspection and MAC Address Filters

When the Switch identifies an unauthorized ARP packet, it automatically creates a MAC address filter to block traffic from the source MAC address and source VLAN ID of the unauthorized ARP packet. You can configure how long the MAC address filter remains in the Switch.

These MAC address filters are different than regular MAC address filters.

- They are stored only in volatile memory.
- They do not use the same space in memory that regular MAC address filters use.

• They appear only in the **ARP Inspection** screens and commands, not in the **MAC Address Filter** screens and commands.

#### 75.15.1.2 Trusted vs. Untrusted Ports

Every port is either a trusted port or an untrusted port for ARP inspection. This setting is independent of the trusted or untrusted setting for DHCP snooping. You can also specify the maximum rate at which the Switch receives ARP packets on untrusted ports.

The Switch does not discard ARP packets on trusted ports for any reason.

The Switch discards ARP packets on untrusted ports in the following situations:

- The sender's information in the ARP packet does not match any of the current bindings.
- The rate at which ARP packets arrive is too high.

#### 75.15.1.3 Syslog

The Switch can send syslog messages to the specified syslog server when it forwards or discards ARP packets. The Switch can consolidate log messages and send log messages in batches to make this mechanism more efficient.

#### 75.15.1.4 Configuring ARP Inspection

Follow these steps to configure ARP inspection on the Switch.

1 Configure DHCP snooping.

Note: It is recommended you enable DHCP snooping at least one day before you enable ARP inspection so that the Switch has enough time to build the binding table.

- 2 Enable ARP inspection on each VLAN.
- 3 Configure trusted and untrusted ports, and specify the maximum number of ARP packets that each port can receive per second.

# C HAPTER 76 Port Authentic ation

# 76.1 Port Authentic ation Overview

This chapter describes the IEEE 802.1x, MAC, Guest VLAN, and Compound authentication methods.

- IEEE 802.1  $x^2$  An authentication server validates access to a port based on a user name and password provided by the user. A user that fails an authentication server can still access the port, but traffic from the user is forwarded to the guest VLAN port.
- MAC Authentic a tion An authentication server validates access to a port based on the MAC address and password of the client.
- Guest VIAN In either mode, if authentication fails the Switch can still allow the client to access the network on a Guest VIAN.
- **Compound Authentication** An authentication server validates access to a port based on combination of IEEE 802.1x and MAC Authentication. There are two modes:
  - Loose: The client authenticates using either IEEE 802.1x authentication or MAC Authentication.
  - Strict: The client authenticates using both IEEE 802.1x authentication and MAC Authentication.
- Note: All types of authentication use the RADIUS (Remote Authentication Dial In User Service, RFC 2138, 2139) protocol to validate users. You must configure a RADIUS server before enabling port authentication.
- Note: If you enable IEEE 802.1x authentication and MAC authentication on the same port, the Switch performs IEEE 802.1x authentication and MAC authentication. If a user fails to authenticate either through the IEEE 802.1x or MAC authentication method, then access to the port is denied.
- Note: IEEE 802.1x is not supported by all user operating systems. For details on compatibility, see your operating system documentation. If your operating system does not support 802.1x, you must install 802.1x client software.

## 76.1.1 What You Can Do

- Use the 802.1x screen (Section 76.2 on page 520) to activate IEEE 802.1x security.
- Use the MAC Authentication screen (Section 76.3 on page 521) to activate MAC authentication.
- Use the Guest VIAN screen (Section 76.4 on page 523) to enable and assign a guest VLAN to a port.


<sup>2.</sup> At the time of writing, IEEE 802.1x is not supported by all operating systems. See your operating system documentation. If your operating system does not support 802.1x, then you may need to install 802.1x client software.


• Use the **Compound Authentication** screen (Section 76.5 on page 525) to allow network access for clients that pass either IEEE 802.1x authentication OR MAC authentication, or pass both IEEE 802.1x authentication.

## 76.1.2 What You Need to Know

#### IEEE 802.1x Authentication

The following figure illustrates how a client connecting to a IEEE 802.1x authentication enabled port goes through a validation process. The Switch prompts the client for login information in the form of a user name and password after the client responds to its identity request. When the client provides the login credentials, the Switch sends an authentication request to a RADIUS server. The RADIUS server validates whether this client is allowed access to the port.






Nession Granzed/Renied

## 76.1.3 MAC Authentication

MAC authentication works in a very similar way to IEEE 802.1x authentication. The main difference is that the Switch does not prompt the client for login credentials. The login credentials are based on the source MAC address of the client connecting to a port on the Switch along with a password configured specifically for MAC authentication on the Switch.





Note: To enable port authentication, first activate the port authentication methods (both on the Switch and the ports), then configure the RADIUS server settings in the SEC URITY> AAA > RADIUS Server Setup screen.

## 76.2 Activate IEEE 802.1x Security

Use this screen to activate IEEE 802.1x security. Click SEC URITY > Port Authentic ation > 802.1x to display the configuration screen as shown.

o Ive A colu		() at () at					
fut	Active	Mex-key	Reputs	Repurts period secs	Quiet-period secs	To pedad sets	Supp-Timeour serts
40		1	lon~l			1	1
$\widetilde{W}_{i}$	0	2	On <b>v</b>	S 3603	0	(3)	35
25		Þ	Cer.~	3800	150	80	[30, 11]
3	0	2	Qn V	3600	0	[23	[3]
$\Phi_{i}^{i}$	13	12	Or w.	5862	100	1.52	1.82
5	0	7	$[\mathbf{C}_{\mathbf{D}},\mathbf{v}]$	300	0	[50	<u></u>
8		12	(area)	3800	[au	30	30
${\mathfrak X}_{{\mathbb Z}}^{n}$		2	<u>onv</u>	5022	0		101
10.00					$\sim$	$\sim$	

Figure 386 SECURITY > Port Authentication > 802.1x

Table 303	SECURITY > Port Authentication > $802.1x$

LABEL	DESC RIPTIO N	
Active	Enable the switch button to permit 802.1x authentication on the Switch.	
	Note: You must first enable 802.1x authentication on the Switch before configuring it on each port.	
EAPOL flood	Enable the switch button to flood EAPOL packets to all ports in the same VLAN.	
	EAP over LAN (EAPOL) is a port authentication protocol used in IEEE 802.1x. It is used to encapsulate and transmit EAP packets between the supplicant (a client device that requests access to the network resources or services) and authenticator (the Switch) directly over the LAN.	
	Note: <b>EAPOLflood</b> will not take effect when 802.1x authentication is enabled.	
Port	This field displays the port number. * means all ports.	
*	Settings in this row apply to all ports.	
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.	
	Note: Changes in this row are copied to all the ports as soon as you make them.	
Active	Select this to permit 802.1x authentication on this port. You must first allow 802.1x authentication on the Switch before configuring it on each port.	
Max-Req	Specify the number of times the Switch tries to authenticate clients before sending unresponsive ports to the Guest VLAN.	
	This is set to 2 by default. That is, the Switch attempts to authenticate a client twice. If the client does not respond to the first authentication request, the Switch tries again. If the client still does not respond to the second request, the Switch sends the client to the Guest VLAN. The client needs to send a new request to be authenticated by the Switch again.	
Reauth	Specify if a subscriber has to periodically re-enter his or her user name and password to stay connected to the port.	
Reauth-period secs	Specify the length of time required to pass before a client has to re-enter his or her user name and password to stay connected to the port.	
Quiet-period secs	Specify the number of seconds the port remains in the HELD state and rejects further authentication requests from the connected client after a failed authentication exchange	
Tx-period secs	Specify the number of seconds the Switch waits for client's response before re-sending an identity request to the client.	
Supp-Timeout secs	Specify the number of seconds the Switch waits for client's response to a challenge request before sending another request.	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Cancel	Click Cancel to begin configuring this screen afresh.	

# 76.3 Activate MAC Authentication

Use this screen to activate MAC authentication. Click **SEC URITY** > **Port Authentication** > **MAC Authentication** to display the configuration screen as shown.

	RITY > Port Authentication	> MAC Authentication
MAC Authenticoff	on	
Active	🕒 0#	
None Pelk		
Definitien	Dosh M	
Cose	Olppor Olower	
Password Type	O diallo O MAC-Addre	0
Password	rysel	
limeted	0	
Port	Active	Trusted-VLAN Dist
1		
2		
3		
4		
5		
6		
7		
_		
	Apply	Cencel

Table 304 SECURITY > Port Authentication > MAC Authentication


LABEL	DESC RIPTIO N
Active	Enable the switch button to permit MAC authentication on the Switch.
	Note: You must first enable MAC authentication on the Switch before configuring it on each port.
Name Prefix	Type the prefix that is appended to all MAC addresses sent to the RADIUS server for authentication. You can enter up to 32 printable ASCII characters except [?], [ ], ['], ["] or [,].
	If you leave this field blank, then only the MAC address of the client is forwarded to the RADIUS server.
Delimiter	Select the delimiter the RADIUS server uses to separate the pairs in MAC addresses used as the account user name (and password). You can select <b>Dash</b> (-), <b>Colon</b> (:), or <b>None</b> to use no delimiters at all in the MAC address.
Case	Select the case ( <b>Upper</b> or <b>Lower</b> ) the RADIUS server requires for letters in MAC addresses used as the account user name (and password).
Password Type	Select Static to have the Switch send the password you specify below or MAC-Address to use the client MAC address as the password.

IABEL	DESC RIPIIO N
Password	Type the password the Switch sends along with the MAC address of a client for authentication with the RADIUS server. You can enter up to 32 printable ASCII characters except [ $?$ ], [ $ $ ], [ $'$ ], ["] or [,].
Timeout	Specify the amount of time before the Switch allows a client MAC address that fails authentication to try and authenticate again. Maximum time is 3000 seconds.
	When a client fails MAC authentication, its MAC address is learned by the MAC address table with a status of denied. The timeout period you specify here is the time the MAC address entry stays in the MAC address table until it is cleared. If you specify 0 for the timeout value, the Switch uses the $Aging Time$ configured in the $SYSTEM > Switch Setup$ screen.
	Note: If the <b>Aging Time</b> in the <b>SYSTEM</b> > <b>Switc h Setup</b> screen is set to a lower value, then it supersedes this setting.
Port	This field displays a port number. * means all ports.
*	Use this row to make the setting the same for all ports. Use this row first and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
Active	Select this check box to permit MAC authentication on this port. You must first allow MAC authentication on the Switch before configuring it on each port.
Trusted-VLAN List	Enter the ID numbers of the trusted VLANs (separated by a comma). If a client's VLAN ID is specified here, the client can access the port and the connected networks without MAC authentication.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

 Table 304
 SECURITY > Port Authentication > MAC Authentication (continued)

# 76.4 Guest VIAN

When 802.1x or MAC Authentication is enabled on the Switch and its ports, clients that do not have the correct credentials are blocked from using the ports. You can configure your Switch to have one VLAN that acts as a guest VLAN. If you enable the guest VLAN (**102** in the example) on a port (**2** in the example), the user (**A** in the example) that is not IEEE 802.1x capable or fails to enter the correct user name and password can still access the port, but traffic from the user is forwarded to the guest VLAN. That is, unauthenticated users can have access to limited network resources in the same guest VLAN, such as the Internet. The access granted to the Guest VLAN depends on how the network administrator configures switches or routers with the guest network feature.



Use this screen to enable and assign a guest VLAN to a port. Click SEC URITY > Port Authentic ation > Guest VIAN to display the configuration screen as shown.

ta-	áctive.	GUND VIAN	Host-mode	Multi-see Num
17 <b>4</b> 1	C		Milti loci 🔍	
19	10	1 1	Mili-tal 👻	1
2	0		14.01 Ind. 14	1
12.1	0	1	M. Hotels	1
199			WHOM SV	1
5	C3	1 1	Jer Jat-ikM	1
·	C1	1	with the w	1
(a)	0		M.fi tal	10
		$\sim$	TE kol	$\sim$

Figure 389 SECURITY > Port Authentication > Guest VLAN

Table 305 SECURITY > Port Authentication > Guest VLA
--

IABEL	DESC RIPTIO N	
Port	This field displays a port number. * means all ports.	
*	Settings in this row apply to all ports.	
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.	
	Changes in this row are copied to all the ports as soon as you make them.	
Active	Select this check box to enable the guest VLAN feature on this port.	
	Clients that fail authentication are placed in the guest VLAN and can receive limited services.	

IABEL	DESC RIPIIO N
Guest VLAN	A guest VLAN is a pre-configured VLAN on the Switch that allows non-authenticated users to access limited network resources through the Switch. You must also enable IEEE 802.1x authentication on the Switch and the associated ports. Enter the number that identifies the guest VLAN.
	Make sure this is a VLAN recognized in your network.
Host-mode	Specify how the Switch authenticates users when more than one user connect to the port (using a hub).
	Select <b>Multi-Host</b> to authenticate only the first user that connects to this port. If the first user enters the correct credential, any other users are allowed to access the port without authentication. If the first user fails to enter the correct credential, they are all put in the guest VLAN. Once the first user who did authentication logs out or disconnects from the port, the rest of the users are blocked until a user does the authentication process again.
	Select Multi-Secure to authenticate each user that connects to this port.
Multi-secure Num	If you set <b>Host-mode</b> to <b>Multi-Secure</b> , specify the maximum number of users (between 1 and 24) that the Switch will authenticate on this port.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 305 SECURITY > Port Authentication > Guest VLAN (continued)

## 76.5 Compound Authentication

Use this screen to allow network access for clients that:

- pass either IEEE 802.1x authentication OR MAC authentication, or
- pass both IEEE 802.1x authentication AND MAC authentication.

The authentication modes are:

- In IEEE 802.1x authentication, the Switch prompts the client for login information in the form of a user name and password. When the client provides the login credentials, the Switch sends an authentication request to a RADIUS server. The RADIUS server validates whether this client is allowed access to the port. Use the SEC URITY > AAA > RADIUS Server Setup screen to configure the RADIUS server.
- In MAC authentication, the login credentials are based on the source MAC address of the client connecting to a port on the Switch along with a password configured specifically for MAC authentication on the Switch.

Click **SEC URITY** > **Port Authentic ation** > **Compound Authentic ation Mode** to display the configuration screen as shown.

Compound Authentication Mode		
Fort	Compound Authentication Mode	
•	Shiet ~	
1	Shiel ar	
2	Shiel	
з	Shiel w	
4	Shiel 👻	
ă	Shiel 💌	
Å.	Shiel w	
	Apply Concel	

Figure 390 SECURITY > Port Authentication > Compound Authentication Mode

Table 306	SECURITY >	Port Authentication >	Compound	Authentication Mode
-----------	------------	-----------------------	----------	---------------------

IABEL	DESC RIPIIO N
Port	This field displays a port number. * means all ports.
*	Settings in this row apply to all ports. Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis. Changes in this row are copied to all the ports as soon as you make them.
Compound Authentication Mode	Specify how the Switch authenticates clients for network access. Select <b>Strict</b> to allow network access to clients only when clients passes IEEE 802.1x authentication AND MAC authentication at the same time. Select <b>Loose</b> to allow network access to clients when clients passes IEEE 802.1x authentication OR MAC authentication.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

# 76.6 Technical Reference

This section provides technical background information on the topics discussed in this chapter.

## 76.6.1 IEEE 802.1x

The IEEE 802.1x is a standard for authentication as well as providing additional accounting and control features. It can be implemented both on wired and wireless networks. It is supported by Windows XP and a number of network devices. Some advantages of IEEE 802.1x are:

- User based identification
- Support for RADIUS (Remote Authentication Dial In User Service, RFC 2138, 2139) for centralized user profile and accounting management on a network RADIUS server.
- Support for EAP (Extensible Authentication Protocol, RFC 2486) that allows additional authentication methods to be deployed with no changes to the switch or the wired clients.

#### 76.6.2 RADIUS

RADIUS is based on a client-server model that supports authentication, authorization and accounting. The RADIUS server handles the following tasks:

• Authentication

Determines the identity of the users.

• Authorization

Determines the network services available to authenticated users once they are connected to the network.

• Accounting

Keeps track of the actions that are perform on the switch, such as login events.

RADIUS is a simple package exchange in which your switch acts as a message relay between the wired client and the network RADIUS server.

#### 76.6.2.1 Types of RADIUS Messages

The following types of RADIUS messages are exchanged between the switch and the RADIUS server for user authentication:

• Access-Request

Sent by a switch requesting authentication.

• Access-Reject

Sent by a RADIUS server rejecting access.

• Access-Accept

Sent by a RADIUS server allowing access.

• Access-Challenge

Sent by a RADIUS server requesting more information in order to allow access. The switch sends a proper response from the user and then sends another Access-Request message.

The following types of RADIUS messages are exchanged between the switch and the RADIUS server for user accounting:

• Accounting-Request

Sent by the switch requesting accounting.

Accounting-Response

Sent by the RADIUS server to indicate that it has started or stopped accounting.

The switch and the RADIUS server use a shared secret key, which is a password, they both know to authenticate the communications between them, and ensure network security. A shared key is not sent over the network.

The switch forwards the RADIUS requests of a client to the RADIUS server. The login password information exchanged is sent over the network and encrypted to protect the network from unauthorized access.

#### 76.6.3 EAP (Extensible Authentication Protocol) Authentication

This section discusses some popular authentication types: EAP-MD5, EAP-TLS, EAP-TTLS, PEAP and LEAP. Your wired LAN device may not support all authentication types.

EAP (Extensible Authentication Protocol) is an authentication protocol that runs on top of the IEEE 802.1x transport mechanism in order to support multiple types of user authentication. By using EAP to interact with an EAP-compatible RADIUS server, a switch helps a wired station and a RADIUS server perform authentication.

The type of authentication you use depends on the RADIUS server and an intermediary switch that supports IEEE 802.1x.

For EAP-TLS authentication type, you must first have a wired connection to the network and obtain the certificates from a certificate authority (CA). A certificate (also called digital IDs) can be used to authenticate users and a CA issues certificates and guarantees the identity of each certificate owner.

• EAP-MD5 (Message-Digest Algorithm 5)

MD5 authentication is the simplest one-way authentication method. The authentication server sends a challenge to the wired client. The wired client 'proves' that it knows the password by encrypting the password with the challenge and sends back the information. Password is not sent in plain text.

However, MD5 authentication has some weaknesses. Since the authentication server needs to get the plain text passwords, the passwords must be stored. Thus someone other than the authentication server may access the password file. In addition, it is possible to impersonate an authentication server as MD5 authentication method does not perform mutual authentication. Finally, MD5 authentication method does not support data encryption with dynamic session key. You must configure WEP encryption keys for data encryption.

• EAP-TLS (Transport Layer Security)

With EAP-TLS, digital certifications are needed by both the server and the wired clients for mutual authentication. The server presents a certificate to the client. After validating the identity of the server, the client sends a different certificate to the server. The exchange of certificates is done in the open before a secured tunnel is created. This makes user identity vulnerable to passive attacks. A digital certificate is an electronic ID card that authenticates the sender's identity. However, to implement EAPTLS, you need a Certificate Authority (CA) to handle certificates, which imposes a management overhead.

• EAP-TTLS (Tunneled Transport Layer Service)

EAP-TTLS is an extension of the EAP-TLS authentication that uses certificates for only the server-side authentications to establish a secure connection. Client authentication is then done by sending user name and password through the secure connection, thus client identity is protected. For client authentication, EAP-TTLS supports EAP methods and legacy authentication methods such as PAP, CHAP, MS-CHAP and MS-CHAP v2.

• PEAP (Protected EAP)

Like EAP-TTLS, server-side certificate authentication is used to establish a secure connection, then use simple user name and password methods through the secured connection to authenticate the clients, thus hiding client identity. However, PEAP only supports EAP methods, such as EAP-MD5, EAP-MSCHAPv2 and EAP-GTC (EAP-Generic Token Card), for client authentication. EAP-GTC is implemented only by Cisco.

• LEAP

LEAP (Lightweight Extensible Authentication Protocol) is a Cisco implementation of IEEE 802.1x.

## 76.6.4 EAPOL(EAPoverLAN)

EAPOL is a port authentication protocol used in IEEE 802.1x. It encapsulates and sends EAP packets from the LAN. EAPOL exchanges the following messages between a wired client and switch.

• EAPOL-Start

A wired client will send this message to a switch to let it know the wired client is ready.

• EAPOL-Key

The switch will send an encryption key to the wired client. It will be allowed access to the network when both of the switch and wired client have the correct encryption keys.

• EAP-Packet

Both of the wired client and the switch will send this message to complete the authentication process.

• EAPOL-Logoff

This message will be sent when the wired client wants to be disconnected from the network.

• EAPOL-Encapsulated-ASF-Alert

This message is sent If the authentication process is not completed yet, and alerts needs to be forwarded.

529

# C HAPTER 77 Port Security

# 77.1 Port Security Overview

This chapter shows you how to set up port security.

# 77.2 About Port Security

Port security allows only packets with dynamically learned MAC addresses and/or configured static MAC addresses to pass through a port on the Switch. The Switch can learn up to 8k MAC addresses in total with no limit on individual ports other than the sum cannot exceed.

For maximum port security, enable this feature, disable MAC address learning and configure static MAC addresses for a port. It is not recommended you disable port security together with MAC address learning as this will result in many broadcasts. By default, MAC address learning is still enabled even though the port security is not activated.

# 77.3 Port Security Setup

Click SEC URITY > Port Security in the navigation panel to display the screen as shown.

Port Security			
MAC Preeze			
Port Lat	La ca	:	
Port Security			
Active 🧧	14 💭		
Port	Active	Address Learning	timited Number of Learned MAC Address
1			٥
2			a
8		2	U
4			11
0		2	0
۵			a
7		8	a
5			U III
		Apply	intel

Figure 391 SECURITY > Port Security

Table 307	SECURITY > Port Security
10010 007	

IABEL	DESC RIPTIO N
MAC Freeze	
Port List	Enter the number of the ports (separated by a comma) on which you want to enable port security and disable MAC address learning. After you click <b>MAC</b> Freeze, all previously learned MAC addresses on the specified ports will become static MAC addresses and display in the <b>SWIICHING &gt; Static MAC</b> Forwarding screen.
MAC freeze	Click <b>MAC</b> Freeze to have the Switch automatically select the <b>Active</b> check boxes and clear the <b>Address Learning</b> check boxes only for the ports specified in the <b>Port List</b> .
Port Security	
Active	Enable the switch button to enable port security on the Switch.
Port	This field displays the port number.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some of the settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.

LABEL	DESC RIPTIO N
Active	Select this check box to enable the port security feature on this port. The Switch forwards packets whose MAC addresses is in the MAC address table on this port. Packets with no matching MAC addresses are dropped.
	Clear this check box to disable the port security feature. The Switch forwards all packets on this port.
Address Learning	MAC address learning reduces outgoing broadcast traffic. For MAC address learning to occur on a port, the port itself must be active with address learning enabled.
Limited Number of Learned MAC Address	Use this field to limit the number of (dynamic) MAC addresses that may be learned on a port. For example, if you set this field to "5" on port 2, then only the devices with these five learned MAC addresses may access port 2 at any one time. A sixth device must wait until one of the five learned MAC addresses ages out. MAC address aging out time can be set in the <b>SYSTEM</b> > <b>Switc h Se tup</b> screen. The valid range is from "0" to "32K". "0" means this feature is disabled.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click <b>Cancel</b> to begin configuring this screen afresh.

 Table 307
 SECURITY > Port Security (continued)

# C HAPTER 78 MAINTENANCE

## 78.1 Overview

This chapter explains how to configure the screens that let you maintain the firmware and configuration files.

## 78.1.1 What You Can Do

- Use the Certificates screen (Section 78.2 on page 533) to see the Certificate screen and import the Switch's CA-signed certificates.
- Use the **ClusterManagement** screens (Section 78.5 on page 538) to manage the switches within a cluster and view cluster status.
- Use the **Restore Configuration** screen (Section 78.8 on page 543) to upload a stored device configuration file.
- Use the **Backup Configuration** screen (Section 78.9 on page 543) to save your configurations for later use.
- Use the Auto Configuration screen (Section 78.10 on page 544) to overwrite the running configuration stored in the Switch's RAM.
- Use the **Erase Running-Configuration** screen (Section 78.11 on page 545) to reset the configuration to the Zyxel default configuration settings.
- Use the **Save Configuration** screen (Section 78.12 on page 546) to save the current configuration settings to a specific configuration file on the Switch.
- Use the **Configure Clone** screen (Section 78.13 on page 547) to copy the basic and advanced settings from a source port to a destination port or ports.
- Use the **Diagnostic** screen (Section 78.14 on page 548) to ping IP addresses, run a traceroute, perform port tests or show the Switch's location between devices.
- Use the Firm ware Upgrade screen (Section 78.15 on page 550) to upload the latest firmware.
- Use the **Reboot System** screen (Section 78.16 on page 552) to restart the Switch without physically turning the power off and load a specific configuration file.
- Use the Tech-Support screen (Section 78.17 on page 553) to create reports for customer support if there are problems with the Switch.

## 78.2 Certificates

The Switch can use HTTPS certificates that are verified by a third party to create secure HTTPS connections between your computer and the Switch. This way, you may securely access the Switch using the Web Configurator. See Section 66.5.2 on page 449 for more information about HTTPS.

Certificates are based on public-private key pairs. A certificate contains the certificate owner's identity and public key. Certificates provide a way to exchange public keys for use in authentication.

Click **MAINTENANCE** > Certificates to open the following screen. Use this screen to import the Switch's CA-signed certificates.



Certificates					
Certificate	8				
Please speci File Path Password	-	the HTTPS certificate H No file chosen	le to be imported. The certific	ate lile must be the Binary	PRCS#12 format.
					🛢 Dalata
	Service	Subject	Issuer	Volid From	Valid To
	HTTPS	/CN=X3800 bc99119bb8c3	Mar 27 00:00:43 2081 GMT		

The following table describes the labels in this screen.


IABEL	DESC RIPTIO N
File Path	Click Choose File or Browse to find the certificate file you want to upload.
Password	Enter the certificate file's password that was created when the PKCS #12 file was exported. The password consists of up to 32 printable ASCII characters except [?], [   ], ['], ["] or [, ].
Import	Click this button to save the certificate that you have enrolled from a certification authority from your computer to the Switch.
Service	This field displays the service type that this certificate is for.
Subject	This field displays identifying information about the certificate's owner, such as CN (Common Name), OU (Organizational Unit or department), O (Organization or company) and C (Country). It is recommended that each certificate have unique subject information.
Issuer	This field displays identifying information about the certificate's issuing certification authority, such as a common name, organizational unit or department, organization or company and country.
Valid From	This field displays the date that the certificate becomes applicable.
Valid To	This field displays the date that the certificate expires.
	Select an entry's check box to select a specific entry.
Delete	Click this button to delete the certificate (or certification request). You cannot delete a certificate that one or more features is configured to use.

#### Table 308 MAINTENANCE > Certificates

#### 78.2.1 HTIPS Certificates

Use this screen to view the HTTPS certificate details. Click a hyperlink in the Service column in the MAINTENANCE > Certificates screen to open the following screen.

Figure 393 MAINTENANCE > Certificates > HTTPS



## 78.3 Technical Reference

This section provides technical background information on the topics discussed in this chapter.

## 78.3.1 FIP Command Line

This section shows some examples of uploading to or downloading files from the Switch using FTP commands. First, understand the filename conventions.

#### 78.3.2 Filename Conventions

The configuration file (also known as the romfile or ROM) contains the Zyxel factory default configuration settings in the screens such as password, Switch setup, IP Setup, and so on. Once you have customized the Switch's settings, they can be saved back to your computer under a filename of your choosing.

ZyNOS (Zyxel Network Operating System sometimes referred to as the "ras" file) is the system firmware

and has a "bin" filename extension.

Table 309	Filename Conventions

FILE TYPE	INTERNALNAME	EXTERNALNAME	DESC RIPIIO N
Configuration File	config1 config2	*.cfg	This is the configuration filename on the Switch. Uploading the config file replaces the specified configuration file system, including your Switch configurations, system-related data (including the default password), the error log and the trace log.

You can store up to two images, or firmware files of the same device model, on the Switch. Only one image is used at a time.

- Run the boot image <1 | 2> command to specify which image is updated when firmware is loaded using the Web Configurator and to specify which image is loaded when the Switch starts up.
- You can also use FTP commands to upload firmware to any image.

The Switch supports dual firmware images, ras-0 and ras-1. You can switch from one to the other by using the boot image <index> command, where <index> is 1 (ras-0) or 2 (ras-1). See the CLI Reference Guide for more information about using commands. The system does not reboot after it switches from one image to the other.

#### 78.3.2.1 Example FIP Commands

ftp> put firmware.bin ras-0

This is a sample FTP session showing the transfer of the computer file "firmware.bin" to the Switch's **Firm ware 1**.

ftp> get config1 config1.cfg

This is a sample FTP session saving the Switch's configuration file 1 (Config1) to a file called "config1.cfg" on your computer.

If your (T)FTP client does not allow you to have a destination filename different than the source, you will need to rename them as the Switch only recognizes "config" and "ras". Be sure you keep unaltered copies of both files for later use.

# Be sure to upload the correct model firm ware as uploading the wrong model firm ware may damage your device.

#### 78.3.3 FIP Command Line Procedure

- **1** Launch the FTP client on your computer.
- 2 Enter open, followed by a space and the IP address of your Switch.
- **3** Press [ENTER] when prompted for a user name.
- 4 Enter your password as requested (the default is "1234").
- 5 Enter bin to set transfer mode to binary.

- 6 Use put to transfer files from the computer to the Switch, for example, put firmware.bin ras transfers the firmware on your computer (firmware.bin) to the Switch and renames it to "ras". Similarly, put config.cfg config1 transfers the configuration file on your computer (config.cfg) to the Switch and renames it to "config1". Likewise get config1 config.cfg transfers the configuration file on the Switch to your computer and renames it to "config.cfg". See Table 309 on page 536 for more information on filename conventions.
- 7 Enter quit to exit the ftp prompt.

### 78.3.4 GUI-based FIP Clients

The following table describes some of the commands that you may see in GUI-based FTP clients.

COMMAND	DESC RIPTIO N
Host Address	Enter the address of the host server.
Login Type	Anonymous. This is when a user I.D. and password is automatically supplied to the server for anonymous access. Anonymous logins will work only if your ISP or service administrator has enabled this option. Normal.
	The server requires a unique User ID and Password to login.
Transfer Type	Transfer files in either single-byte printable characters (plain text format) or in binary mode. Configuration and firmware files should be transferred in binary mode.
Initial Remote Directory	Specify the default remote directory (path).
Initial Local Directory	Specify the default local directory (path).

Table 310 General Commands for GUI-based FTP Clients

#### 78.3.5 FIP Restrictions

FTP will not work when:

- FTP service is disabled in the SEC URITY > Access Control > Service Access Control screen.
- The IP addresses in the SEC URITY > Access Control > Remote Management screen does not match the client IP address. If it does not match, the Switch will disconnect the FTP session immediately.

## 78.4 Cluster Management Overview

Cluster Management allows you to manage switches through one Switch, called the cluster manager. The switches must be directly connected and be in the same VLAN group so as to be able to communicate with one another.

Table 311 Zyxel Clustering Management Specifications


Maximum number of cluster members	24
Cluster Member Models	Must be compatible with Zyxel cluster management implementation.

Table 311	Type Clustering Management Specifications
	Zyxel Clustering Management Specifications

Cluster Manager	The Switch through which you manage the cluster member switches.
Cluster Members	The switches being managed by the cluster manager Switch.

In the following example, switch **A** in the basement is the cluster manager and the other switches on the upper floors of the building are cluster members.

Figure 394 Clustering Application Example



## 78.4.1 What You Can Do

- Use the Cluster Management Status screen (Section 78.5 on page 538) to view the role of the Switch within the cluster and to access a cluster member Switch's Web Configurator.
- Use the Cluster Management Setup screen (Section 78.6 on page 539) to configure clustering management.

## 78.5 Cluster Management Status

Use this screen to view the role of the Switch within the cluster and to access a cluster member Switch's Web Configurator.

Click **MAINTENANCE** > Cluster Management in the navigation panel to display the following screen.

Note: A cluster can only have one manager.

Figure 395	MAINTENANCE >	Cluster Management >	Cluster Management Status
Ing une 000		closici management -	closici management oraros

Cluster Wonogement Status Cluster Monogement Setup				
s - to Hear agen	ilia en e bebriterruterry			
The Number C	Wentber = 1			
Indec	www.wddmaa	0.0008	Asodal	status
1	ere et an det and	7000	A2024	Courses.

Table 312 MAINTENIANCES	Cluster Management >	> Cluster Management Status

IABEL	DESC RIPTIO N
Status	This field displays the role of this Switch within the cluster.
	Manager
	Member (you see this if you access this screen in the cluster member Switch directly and not through the cluster manager)
	None (neither a manager nor a member of a cluster)
Manager	This field displays the cluster manager Switch's hardware MAC address.
The Number Of Member	This field displays the number of switches that make up this cluster. The following fields describe the cluster member switches.
Index	You can manage cluster member switches through the cluster manager Switch. Each number in the <b>Index</b> column is a hyperlink leading to the cluster member Switch's Web Configurator.
MAC Address	This is the cluster member Switch's hardware MAC address.
Name	This is the cluster member Switch's <b>System Name</b> .
Model	This field displays the model name.
Status	This field displays:
	<b>Online</b> (the cluster member Switch is accessible)
	$\mathbf{Error}$ (for example the cluster member Switch password was changed or the Switch was set as the manager and so left the member list, and so on)
	<b>Offline</b> (the Switch is disconnected – <b>Offline</b> shows approximately 1.5 minutes after the link between cluster member and manager goes down)

## 78.6 Clustering Management Setup

Use this screen to configure clustering management. Click **MAINTENANCE** > Cluster Management > Cluster Management Setup to display the next screen.

Figure 396	MAINTENANCE >	Cluster Management >	> Cluster Management Setup

1999 - 1999 - 1999 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 - 1997 -	ement Status	Cluster Managemen	it Setup		
Sustering Ma	nager				
R <sub>1</sub> (2)(relation)	CINID				
Variw CD					
20 C					
2.5.4					
P.D.		Auxily	Concel		
	ndidate	the second se			
Clustering Ca	ndidate	the second se			
	ndidate	the second se		C ANDIGUT	E Culture
	ndidate	the second se			E Culture Andrei

IABEL	DESC RIPIIO N
Clustering Manager	The following fields relate to configuring the cluster manager.
Active	Enable the switch button to have this Switch become the cluster manager switch. A cluster can only have one manager. Other (directly connected) switches that are set to be cluster managers will not be visible in the <b>Clustering Candidates</b> list. If a Switch that was previously a cluster member is later set to become a cluster manager, then its <b>Status</b> is displayed as <b>Emor</b> in the <b>Cluster Management Status</b> screen and a warning icon (AL) appears in the member summary list below.
Name	Type a name to identify the <b>Clustering Manager</b> . You may use up to 32 printable ASCII characters except [?], [ ], ['], ["] or [,]. (spaces are allowed).
VID	This is the VLAN ID and is only applicable if the Switch is set to <b>802.1Q</b> VLAN. All switches must be directly connected and in the same VLAN group to belong to the same cluster. Switches that are not in the same VLAN group are not visible in the <b>Clustering Candidates</b> list. This field is ignored if the <b>Clustering Manager</b> is using <b>Port-based</b> VLAN.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.
Clustering Candidate	The next summary table shows the information for the clustering members configured.
Add	Click this button to create a new clustering candidate.
Edit	Click this button to configure the clustering candidate.
Delete	Click this button to remove the clustering candidate.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Index	This is the index number of a cluster member switch.
MAC Address	This is the cluster member switch's hardware MAC address.
Name	This is the cluster member switch's System Name.
Model	This is the cluster member switch's model name.

Table 313 MAINTENANCE > Cluster Management > Cluster Management Setup

Click the **Add**/**Edit** button to open the **Add**/**Edit** screen. Use this screen to configure a clustering candidate for the Switch.

Figure 397	MAINTENANCE >	Cluster Management >	Cluster Management Setup :	> Add/Edit
------------	---------------	----------------------	----------------------------	------------



The following table describes the labels in this screen.

LABEL	DESC RIPTIO N
List	A list of suitable candidates found by auto-discovery is shown here. The switches must be directly connected. Directly connected switches that are set to be cluster managers will not be visible in the <b>Clustering Candidate</b> list. Switches that are not in the same management VLAN group will not be visible in the <b>Clustering Candidate</b> list.
Password	Each cluster member's password is its Web Configurator password. Select a member in the <b>Clustering Candidate</b> list and then enter its Web Configurator password. If that switch administrator changes the Web Configurator password afterwards, then it cannot be managed from the <b>Cluster Manager</b> . Its <b>Status</b> is displayed as <b>Error</b> in the <b>Cluster Management Status</b> screen.
	If multiple devices have the same password then hold [SHIFT] and click those switches to select them. Then enter their common Web Configurator password.
	You can enter up to 32 printable ASCII characters except [?], [ ], ['], ["] or [,].
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to reset the fields to the factory defaults.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 314 MAINTENANCE > Cluster Management > Cluster Management Setup > Add/Edit

### 78.7 Technical Reference

This section provides technical background information on the topics discussed in this chapter.

### 78.7.1 Cluster Member Switch Management

Go to the **MAINTENANCE** > **Clustering Management** > **Clustering Management Status** screen of the cluster manager switch and then select an **Index** hyperlink from the list of members to go to that cluster member switch's Web Configurator home page. This cluster member Web Configurator home page and the home page that you would see if you accessed it directly are different.

			Alternitiers A
DALIHI CARD	MONIKOK	STATIN	P281
CAN INCRUID	ALC: Used	Close Versensen 1	Aster D. Ressoners
	IN A Marghdon of mole	Converse di Kartago	Conserved an end
	Loss to de	where the strategy of the stra	line appropriate
	Heral Los	L'Arriva.	100
	Extended Landon	~	- 1118-
	Ever Mathin	a Dul Make	<ul> <li>UNESITE</li> </ul>
	States also when	<ul> <li>1 We when only in our</li> </ul>	Pala an an
	Quint any	<ul> <li>PAST strategies 2 strategie</li> </ul>	Mark School
		<ul> <li>Dui relate sing</li> </ul>	
		<ul> <li>Two Need above Discovery</li> </ul>	
		<ul> <li>Model ang show data pri-</li> </ul>	
		<ul> <li>All CARL There Service</li> </ul>	
SWITCH NG	NETWO SIGN G	SOCURITY	WA NTENA NCC
Loss Crowl	ALC: NO SHOP	666 C	Magnatic
Alexans	N All Caroninia	<ul> <li>CADRUID enter tellop</li> </ul>	
<ul> <li>Menory</li> </ul>	LEC2	s AAAA ay go	(example)
de store	<ul> <li>DEPARTATION</li> </ul>	Anomy Constant	
<ul> <li>THERE</li> </ul>	N DIM STORES	A compare descend for that	
<ul> <li>2 singlet and because</li> </ul>	Chaire Streeting	<ul> <li>Are all deleting reach</li> </ul>	
Ny BARD	a Pro Maile Roser	<ul> <li>Area and area are</li> </ul>	
2018/1			

Figure 398 Cluster Management: Cluster Member Web Configurator Screen

#### 78.7.1.1 Uploading Firmware to a Cluster Member Switch

You can use FTP to upload firmware to a cluster member switch through the cluster manager switch as shown in the following example.

Figure 399 Example: Uploading Firmware to a Cluster Member Switch

```
C:\>ftp 192.168.1.1
Connected to 192.168.1.1.
220 Switch FTP version 1.0 ready at Thu Jan 1 00:58:46 1970
User (192.168.0.1:(none)): admin
331 Enter PASS command
Password:
230 Logged in
ftp> ls
200 Port command okay
150 Opening data connection for LIST
--w--w- 1 owner group 3042210 Jul 01 12:00 ras
                                    393216 Jul 01 12:00 config
-rw-rw-rw- 1 owner group
--w--w--w- 1 owner group
                                          0 Jul 01 12:00 fw-00-a0-c5-01-23-46
-rw-rw-rw- 1 owner group
                                          0 Jul 01 12:00 config-00-a0-c5-01-23-46
226 File sent OK
ftp: 297 bytes received in 0.00Seconds 297000.00Kbytes/sec.
ftp> bin
200 Type I OK
ftp> put 470ACAQ0.bin fw-00-a0-c5-01-23-46
200 Port command okay
150 Opening data connection for STOR fw-00-a0-c5-01-23-46
226 File received OK
ftp: 262144 bytes sent in 0.63Seconds 415.44Kbytes/sec.
ftp>
```

The following table explains some of the FTP parameters.

FIP PARAMEIER	DESC RIPTIO N
User	Enter "admin".
Password	The Web Configurator password default is 1234.
ls	Enter this command to list the name of cluster member switch's firmware and configuration file.
470ACAQ0.bin	This is the name of the firmware file you want to upload to the cluster member switch.
fw-00-a0-c5-01-23-46	This is the cluster member switch's firmware name as seen in the cluster manager switch.
config-00-a0-c5-01-23-46	This is the cluster member switch's configuration file name as seen in the cluster manager switch.

Table 315 FTP Upload to Cluster Member Example

### 78.8 Restore Configuration

Use this screen to restore a previously saved configuration file (See Section 78.9 on page 543 for more information on how to back up a configuration file) from your computer to the Switch.

Click MAINTENANCE > Configuration > Restore Configuration to access this screen.

Figure 400 MAINTENANCE > Configuration > Restore Configuration

Restore Configuration	
The section of the site in the second	
La lestace the closibe vental	guration formality, browserfter, practice of the postiguration file and siles Basiero Mittee.
le Portri Choose Hile	No île chosen
Handonsee	

- 1 Click Choose File or Browse to locate the configuration file you wish to restore.
- 2 After you have specified the file, click Restore.

The Switch will run on the restored configuration after the restore process.

Figure 401	Configure	tion Restoring		
Restore Contiguration				
		Configure	ation restoring	

### 78.9 Backup Configuration

Backing up your Switch configurations allows you to create various "snap shots" of your device from which you may restore at a later date. Use this screen to back up your current Switch configuration to a computer.

To access this screen, click **MAINTENANCE** > **Configuration** > **Backup Configuration** in the navigation panel.

Figure 402 MAINTENANCE > Configuration > Backup Configuration



Follow the steps below to back up the current Switch configuration to your computer in this screen.

- 1 Select which Switch configuration file you want to download to your computer.
- 2 Click Backup.
- 3 If the current configuration file is open and/or downloaded to your computer automatically, you can click **File** > **Save As** on your computer to save the file to a specific place.

If a dialog box pops up asking whether you want to open or save the file, click **Save** or **Save File** to download it to the default downloads folder on your computer. If a **Save As** screen displays after you click **Save** or **Save File**, choose a location to save the file on your computer from the **Save in** drop-down list box and type a descriptive name for it in the **File name** list box. Click **Save** to save the configuration file to your computer.

### 78.10 Auto Configuration

The Switch can download an pre-saved auto configuration file automatically when you reboot the Switch using the DHCP or HTTPS mode. This will overwrite the running configuration stored in the Switch's RAM instead of the startup configuration stored in the Switch's flash memory.

To access this screen, click MAINTENANCE > Configuration > Auto Configuration in the navigation panel.

Naco
NMLY
🕐 SFF 📜
DF 101 ×
1
Ze gala - Diamand

Figure 403 MAINTENANCE > Configuration > Auto Configuration

Table 314	MAINTENANCE > Configuration > Auto Configuration	
	MAINTENANCE > CONTIGUIQUION > AUTO CONTIGUIQUION	


IABEL	DESC RIPHO N	
Use this section to	view the auto configuration status after you restarted the Switch.	
Mode	This field shows the mode ( <b>DHCP</b> or <b>HTTPS</b> ) that is used for auto configuration after you enabled auto configuration and restarted the Switch.	
	It shows None if auto configuration was not enabled.	
State	This field shows whether auto configuration was executed successfully the last time the Switch rebooted.	
	None – Auto configuration was disabled and not executed.	
	$\mathbf{Success}$ – An auto configuration file was downloaded successfully to the Switch.	
	$\mathbf{Un-success}$ – An auto configuration file was not downloaded to the Switch.	
Filename	This field displays the name of the auto configuration file that was downloaded the last time the Switch rebooted.	
	It shows blank if auto configuration was not enabled or not executed successfully.	
Use this section to	enable auto configuration and select the mode that you want to use for auto configuration.	
Active	Enable the switch button to enable auto configuration.	
Mode	Select <b>DHCP</b> to have the Switch use the TFTP server IP address and auto configuration file name assigned by a DHCP server to download a pre-saved configuration file when the Switch reboots.	
	Note: The Switch should act as a DHCP client to send a DHCP request with DHCP option 60 so that it can get the TFTP server address and configuration file name from the DHCP server.	
	Select <b>HTTPS</b> to have the Switch use the URL you specified in the <b>HTTPS URL</b> field to access a web server and download the auto configuration file using HTTPS.	
DHCP VLAN ID	Enter the VLAN ID of the DHCP server that assigns the TFTP server IP address and auto configuration file name to the Switch.	
HTTPS URL	Type the URL that can be used to access and download the auto configuration file from a web server using HTTPS. For example, https://webserverlPaddress/configfilename.cfg.	
	Note: You must fill in this field if you select <b>HTIPS</b> in the <b>Mode</b> field. Otherwise, auto configuration will not work.	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Cancel	Click Cancel to begin configuring this screen afresh.	

### 78.11 Erase Running-Configuration

Follow the steps below to remove the running configuration on the Switch. Unlike when you reset the Switch to the factory defaults, the user name, password, system logs, memory logs, baud rate and SSH service are not removed.

To access this screen, click **MAINTENANCE** > **Configuration** > **Ease Running Configuration** in the navigation panel.

1 In the **Erase Running Configuration** screen, click the **Erase** button to clear all Switch configuration information you configured and return to the Zyxel default configuration settings.





2 Click **YES** to remove the running configuration on the Switch.

Figure 405 Erase Running Configuration: Confirmation



3 In the Web Configurator, click the Save button in the top of the screen to make the changes take effect. If you want to access the Switch Web Configurator again, you may need to change the IP address of your computer to be in the same subnet as that of the default Switch IP address (192.168.1.1 or DHCP-assigned IP).

### 78.12 Save Configuration

To access this screen, click **MAINTENANCE** > **Configuration** > **Save Configuration** in the navigation panel.

Click **Config 1** to save the current configuration settings permanently to **Configuration 1** on the Switch. These configurations are set up according to your network environment.

Click **Config 2** to save the current configuration settings permanently to **Configuration 2** on the Switch. These configurations are set up according to your network environment.

Click **Custom Default** to save the current configuration settings permanently to a customized default file on the Switch. If configuration changes cause the Switch to behave abnormally, click **Custom Default** (in the **MAINTENANCE** > **Reboot System** screen) to have the Switch automatically reboot and restore the saved **Custom Default** configuration file.

Figure 406 MAINTENANCE > Configuration > Save Configuration



Note: If a customized default file was not saved, clicking **Custom Default** in the **MAINTENANCE** > **Reboot System** screen loads the factory default configuration on the Switch.

Alternatively, click  $S_{ave}$  on the top right in any screen to save the configuration changes to the current configuration.

Note: Clicking the **Apply** button after making configuration does NOT save the changes permanently. All unsaved changes are erased after you reboot the Switch.

# 78.13 Configure Clone

Cloning allows you to copy the basic and advanced settings from a source port to a destination port or ports. Click **MAINTENANCE** > **Configuration** > **Configure Clone** to open the following screen.

Figure 407 MAINTENANCE > Configuration > Configure Clone

Configure Clone		
Configure Clone		
Search	Herst interdient	
Pred 1	Ŷ	
1		
Port Features		
Control Control of		
STAILA		
🖸 2004 "Thoja		
□ PORT		
Distre	Auto 10 Recovery	DB10V Central
Dramet CAM	<ul> <li>Over L Antonio Re-</li></ul>	Green Othernet
		Example a second sec
Symmetry Dag to a	<b>2000</b>	
SWIR HINE		
Bandwidth Conitol	Diftery	IGMP Cliering
Large et 21 Per des and to a setting p	Descar Channel	District Press of
Marriel	MID Scoregory Press Micropy	Iskal pde Kopat Space agginese Protocol.
Machphrist providing base. Problem d.	Produktion and Michael All	Pringe (A.     P
	Consequitive ( WANG)	ULAN Mapping
VLANIC Member	VLAN Stacking	
NETWORKING		
Att Learning		
SK 160 Y		
🗌 Ash Agunas	Aiel happendares	🗆 CAS Antonios
1000 20 Second and 1	DHI 2565 Inval Series	IFAA Second Council
MAC AuthenFootion	Port Access Authenflootor	For Security
Control Control		
	Apply Connel	
	with the second se	

Table 317 MAINTENANCE > Configuration > Configure Clone

IABEL	DESC RIPTIO N	
Configure Clon	e	
Source/ Destination	Enter the source port under the $\mathbf{Sourc} \mathbf{e}$ label. This port's attributes are copied.	
Port	Enter the destination port or ports under the <b>De stina tion</b> label. These are the ports which are going to have the same attributes as the source port. You can enter individual ports separated by a comma or a range of ports by using a dash.	
	Example:	
	2, 4, 6 indicates that ports 2, 4 and 6 are the destination ports.	
	2-6 indicates that ports 2 through 6 are the destination ports.	
Port Features		
Port	Select * to apply all settings to the port. Use this first to select the common settings and then remove the settings you do not want copied.	
	Select a feature's check box to select a specific feature. Otherwise, select the check box in the table heading row to select all features for a category.	
SYSTEM	Select the system feature (you configured in the <b>SYSTEM</b> menus) to be copied to the destination ports. Otherwise, select the <b>SYSTEM</b> check box in the table heading row to select all features for a category.	
PORT	Select which port features (you configured in the <b>PORT</b> menus) should be copied to the destination ports. Otherwise, select the <b>PORT</b> check box in the table heading row to select all features for a category.	
SWITCHING	Select which switching features (you configured in the <b>SWIICHING</b> menus) should be copied to the destination ports. Otherwise, select the <b>SWIICHING</b> check box in the table heading row to select all features for a category.	
NETWORKING	Select the networking feature (you configured in the <b>NEIWO RKING</b> menus) to be copied to the destination ports. Otherwise, select the <b>NEIWO RKING</b> check box in the table heading row to select all features for a category.	
SECURITY	Select which security features (you configured in the <b>SEC URITY</b> menus) should be copied to the destination ports. Otherwise, select the <b>SEC URITY</b> check box in the table heading row to select all features for a category.	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Cancel	Click Cancel to begin configuring this screen afresh.	

### 78.14 Diagnostic

Click **MAINTENANCE** > **Diagnostic** in the navigation panel to open this screen. Use this screen to ping IP addresses, run a traceroute, perform port tests or show the Switch's location between devices.

lagnostic			
<b>1</b> (-11)			
The first		Fraqe Soule Fedt	4 
Olex.	* 9 * *	0.**	E2
<ul> <li>Authorization Notice</li> </ul>		f Addew/Ikai vone ID	
Conta PAdorea Stati Tran	78 - Îl		===  2}  2
Harmet Forcest		manananan	
Not Park Task			
Cable Disgrantes O			
No.4			
the oler 185			
Carl Carl			

Figure	408	MAINTENANCE > Diagnos	tic
rig uic	100		111

Table 318 N	MAINTENANCE >	Diagnostic
-------------	---------------	------------

LABEL	DESC RIPTIO N
Ping Test	
IPv4	Select this option if you want to ping an IPv4 address. Otherwise, select – to send ping requests to all VLANs on the Switch.
IPv6	Select this option if you want to ping an IPv6 address. You can also select $vlan$ and specify the ID number of the VLAN to which the Switch is to send ping requests. Otherwise, select – to send ping requests to all VLANs on the Switch.
IP Address/Host Name	Type the IP address or host name of a device that you want to ping in order to test a connection.
	Click <b>Ping</b> to have the Switch ping the IP address.
Source IP Address	Type the source IP address that you want to ping in order to test a connection.
Address	Click <b>Ping</b> to have the Switch ping the IP address.
Count	Enter the number of ICMP Echo Request (ping) messages the Switch continuously sends.
Trace Route Test	

LABEL	DESC RIPIIO N
IPv4	Select this option if you want to trace the route packets taken to a device with an IPv4 address. Otherwise, select - to trace the path on any VLAN.
	Note: The device to which you want to run a traceroute must belong to the VLAN you specify here.
IPv6	Select this option if you want to trace the route packets taken to a device with an IPv6 address.
IP Address/Host Name	Enter the IP address or host name of a device to which you want to perform a traceroute.
Nume	Click <b>Thace Route</b> to have the Switch perform the traceroute function. This determines the path a packet takes to the specified device.
TTL	Enter the Time To Live (TTL) value for the ICMP Echo Request packets. This is to set the maximum number of the hops (routers) a packet can travel through. Each router along the path will decrement the TTL value by one and forward the packets. When the TTL value becomes zero and the destination is not found, the router drops the packets and informs the sender.
Wait Time	Specify how many seconds the Switch waits for a response to a probe before running another traceroute.
Queries	Specify how many times the Switch performs the traceroute function.
Ethernet Port Test	
Port	Enter a port number and click <b>Port Test</b> to perform an internal loopback test.
Cable Diagnostic	
Port	Enter an Ethernet port number and click <b>Diagnose</b> to perform a physical wire-pair test of the Ethernet connections on the specified ports. The following fields display when you diagnose a port.
Locator LED	Enter a time interval (in minutes) and click <b>Blink</b> to show the actual location of the Switch between several devices in a rack.
	The default time interval is 30 minutes.
	Click $\operatorname{Stop}$ to have the Switch terminate the blinking locater LED.

 Table 318
 MAINTENANCE > Diagnostic (continued)

# 78.15 Firmware Upgrade

You can upgrade the Switch's firmware through Web Configurator or NCC.

### Firmware Upgrade Through NCC

In cloud management mode, NCC will first check if the firmware on the Switch needs to be upgraded. If it does, the Switch will upgrade the firmware immediately. If the firmware does not need to be upgraded, but there is newer firmware available for the Switch, then it will be upgraded according to the firmware upgrade schedule for the Switch on the NCC.

On the NCC web portal, go to **Site-wide** > **Configure** > **Firmware management** to schedule the firmware upgrade time.

Note: While the Switch is rebooting, do NOT turn off the power.

#### Firm ware Upgrade Through the Web Configurator

Use the following screen to upgrade your Switch to the latest firmware. The Switch supports dual firmware images, **Firmware 1** and **Firmware 2**. Use this screen to specify which image is updated when firmware is uploaded using the Web Configurator and to specify which image is loaded when the Switch starts up.

Note: Make sure you have downloaded (and unzipped) the correct model firmware and version to your computer before uploading to the device.

Click MAINTENANCE > Firm ware Upgrade to view the screen as shown next.

immwore Upgrode		
Norte	vecit;1	
	area of a staticate production	
det det te transmissionen das en	Received A AN AN AN ANY TAXY TAXY TAXY	
	Rectard 1	
Boolimage		
Cohent Soch Image - Thirth she 1		
Consynamically investigation		
	opply ivites:	
to prove be write included brown be, cov	alon Alline of the Associate and ASA Constants	
Renveste 💷		

Figure 409 MAINTENANCE > Firmware Upgrade

The top of the screen shows which firmware version is currently **Running** on the Switch. Click **Choose File** or **Browse** to locate the firmware file you wish to upload to the Switch in the **File Path** field. Click **Upgrade** to load the new firmware. The Switch does not apply the uploaded firmware immediately. Firmware upgrades are only applied after you reboot the Switch using the uploaded firmware.

Click the **Config Boot Image** drop-down list box to select the boot image (**Fim ware 1** or **Fim ware 2**) you want the Switch to use when rebooting, click **Apply**. Restart the Switch (manually or using the **MAINTENANCE** > **Reboot System** screen) to apply the firmware image you selected.

After the process is complete, see the **DASHBOARD** screen to verify your current firmware version number.

Table 319 MAINTENANCE > Firmware Upgrade

LABEL	DESC RIPTIO N
Name	This is the name of the Switch that you are configuring.
Version	The Switch has 2 firmware sets, Firmware 1 and Firmware 2, residing in flash.
	• <b>Running</b> shows the version number (and model code) and MM/DD/YYYY creation date of the firmware currently in use on the Switch ( <b>Firmware 1</b> or <b>Firmware 2</b> ). The firmware information is also displayed at System Information in Basic Setting.
	• Firm ware 1 shows its version number (and model code) and MM/DD/YYYY creation date.
	• Firm ware 2 shows its version number (and model code) and MM/DD/YYYY creation date.
Boot Image	
Current Boot Image	This displays which firmware is currently in use on the Switch (Firmware 1 or Firmware 2).
Config Boot Image	Select which firmware (Firmware 1 or Firmware 2) should load, click Apply and reboot the Switch to see changes, you will also see changes in the Current Boot Image field above as well.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.
Firmware	Choose to upload the new firmware to (Firmware) 1 or (Firmware) 2.
File Path	Click Choose File or Browse to locate the firmware file you wish to upload to the Switch.
Upgrade	Click <b>Upgrade</b> to load the new firmware. Firmwares are only applied after a reboot. To reboot, go to <b>MAINTENANCE</b> > <b>Reboot System</b> and click <b>Config 1</b> , <b>Config 2</b> or <b>Factory</b> <b>Default (Config 1</b> , <b>Config 2</b> , <b>Factory Default</b> , and <b>Custom Default</b> are the configuration files you want the Switch to use when it restarts).

### 78.16 Reboot System

**Reboot System** allows you to restart the Switch without physically turning the power off. It also allows you to load configuration one (**Config 1**), configuration two (**Config 2**), a **Custom Default** or the **Factory Default** configuration when you reboot. Follow the steps below to reboot the Switch.


Click **MAINTENANCE > Reboot System** to view the screen as shown next.

Figure 410	MAINTENANCE > Reboot System
------------	-----------------------------

Rebord System	
An energial Case de presidente en	Contractor d
	Configh
	$(\lambda = \lambda_0 2)$
that and 2 years evaluated	Daskap Februit
	oustom verbuik

1 Click the **Config 1**, **Config 2**, **Factory Default**, or **Custom Default** button to reboot and load that configuration file. The confirmation screen displays.

Figure 411 Reboot Confirmation



2 Click YES and then wait for the Switch to restart. This takes up to 2 minutes.

Click Config 1 and follow steps 1 to 2 to reboot and load configuration one on the Switch.

Click Config 2 and follow steps 1 to 2 to reboot and load configuration two on the Switch.

Click Factory Default and follow steps 1 to 2 to reboot and load Zyxel factory default configuration settings on the Switch.

Click **Custom Default** and follow steps 1 to 2 to reboot and load a customized default file on the Switch. This will save the custom default configuration settings to both **Configuration 1** and **Configuration 2**.

Note: If a customized default file was not saved, clicking **Custom Default** loads the factory default configuration on the Switch.

### 78.17 Tech-Support

The Tech-Support feature is a log enhancement tool that logs useful information such as CPU utilization history, memory and Mbuf (Memory Buffer) log and crash reports for issue analysis by customer support should you have difficulty with your Switch. The Tech Support menu eases your effort in obtaining reports and it is also available in CLI command by typing "Show tech-support" command.

Click **MAINTENANCE** > Tech-Support to see the following screen.




Figure 412 MAINTENANCE > Tech-Support

You may need WordPad or similar software to see the log report correctly. The table below describes

the fields in the above screen.

Table 320	MAINTENANCE > Tech-Support
-----------	----------------------------

LABEL	DESC RIPIIO N
CPU	Type a number ranging from 50 to 100 in the CPU threshold box, and type another number ranging from 5 to 60 in the seconds box then click <b>Apply</b> .
	For example, 80 for CPU threshold and 5 for seconds means a log will be created when CPU utilization reaches over 80% and lasts for 5 seconds.
	The log report holds 7 days of CPU log data and is stored in volatile memory (RAM). The data is lost if the Switch is turned off or in event of power outage. After 7 days, the logs wrap around and new ones and replace the earliest ones.
	The higher the CPU threshold number, the fewer logs will be created, and the less data technical support will have to analyze and vice versa.
Mbuf	Type a number ranging from 50 to 100 in the Mbuf (Memory Buffer) threshold box. The Mbuf log report is stored in flash (permanent) memory.
	For example, Mbuf 50 means a log will be created when the Mbuf utilization is over 50%.
	The higher the Mbuf threshold number, the fewer logs will be created, and the less data technical support will have to analyze and vice versa.
All	Click <b>Download</b> to see all the log report and system status. This log report is stored in flash memory. If the <b>All</b> log report is too large, you can download the log reports separately below.
Crash	Click <b>Download</b> to see the crash log report. The log will include information of the last crash and is stored in flash memory.
CPU	Click <b>Download</b> to see the CPU history log report. The 7-days log is stored in RAM and you will need to save it, otherwise it will be lost when the Switch is shutdown or during power outage.
Memory	Click <b>Download</b> to see the memory section log report. This log report is stored in flash memory.
Mbuf	Click <b>Download</b> to see the Mbuf (Memory Buffer) log report. This log report is stored in flash memory.
ROM	Click <b>Download</b> to see the Read Only Memory (ROM) log report. This report is stored in flash memory.
L3	Click <b>Download</b> to see the layer-3 Switch log report. The log only applies to the layer-3 Switch models. This report is stored in flash memory.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

### 78.17.1 Tech-Support Download

When you click  $\mathbf{Download}$  to save your current Switch configuration to a computer, the following screen appears. When the log report has downloaded successfully, click  $\mathbf{Back}$  to return to the previous screen.

Figure 413	MAINTENANCE > Tech-Support: Download
rigule 410	

Tech-Support download
Downloading the tech-support file. Please well for a moment.
Back

# CHAPTER 79 Networked AV Mode

### 79.1 Overview

Aside from the Web Configurator in Standard mode that has a complete set of configuration for network installation, you can switch to Networked AV mode. Networked AV mode contains just the necessary configurations for setting up and managing audio-video traffic on your network.

AV over IP is the transmission of audio-video data over an IP network.

Use a browser that supports HTML5, such Microsoft Edge, Mozilla Firefox, or Google Chrome. The recommended minimum screen resolution is 1024 by 768 pixels.

The following sections introduces the configuration and functions of the Web Configurator In Networked AV mode.

Click **Networked AV** at the top left of the Web Configurator to switch between the Web Configurator's **Standard** or **Networked AV** mode.

Figure 414 Web Configurator - Networked AV Mode Switch

Abara keel a based on 172	$\left( \left[ H(t,t) \in C(t,s) \in C(t,t) = 0 \right] \right)$	С.	Ċ.	<u>m</u>	$\leq$	ĘΣ.	$\overline{\mathcal{A}}_{0}$	÷.
---------------------------	--	----	----	----------	--------	-----	------------------------------	----

### 79.2 Help

The Web Configurator's online help has descriptions of individual Networked AV mode screens and some supplementary information.

Click the Help link from a Web Configurator screen to scan the QR code or click the web link to display the online help.



### 79.3 Summary

Use the **SUMMARY** screen to see the Switch's front panel port status, connected ports information, networked AV information, Nebula Cloud Control status, and a link to go to the **IP Se tup** screen (Section 79.11 on page 565).

The SUMMARY screen displays when you log into the Switch in Networked AV mode.

556



Figure 416 Summary (example PoE model)

The following table describes the labels in this screen.

IABEL	DESC RIPTIO N
Auto Refresh	Click the Pause Auto Refresh or Resume Auto Refresh icon to stop or resume the screen update.
Port Status	This chart displays the status of the Switch's front panel ports with connection (IED and $Port$ ).
Networked AV Int	ormation
IP Setup	This link takes you to a screen where you can configure the IP address and subnet mask (necessary for Switch management) and set up to 128 IP routing domains.
IGMP-Snooping VLAN	This displays the ID number of the VLAN group upon which the Switch is to perform IGMP snooping.
IGMP-Snooping	This displays $\mathbf{Ac}$ tive when IGMP snooping is enabled to forward group multicast traffic only to ports that are members of that group.
	Otherwise, it is <b>Inactive</b> .
IGMP-Querier	This displays <b>Active</b> when the Switch is allowed to send IGMP General Query messages to the VLANs with the multicast hosts attached.
	Otherwise, it is <b>Inactive</b> .
IP Interface	This displays the IP address of the Switch for it to be managed over the network.
Unknown	This displays the action to perform when the Switch receives an unknown multicast frame.
Multicast	It displays $\mathbf{Drop}$ when the frames are discarded.
	It displays $\mathbf{Flooding}$ when the frames are sent to all ports.
	It displays <b>Drop on VIAN</b> when the frames are discarded on the specified VLANs.
Power Usage(W)	For PoE models.
	This chart displays the used PoE Watts over the total number of Watts provided on this Switch.

#### Table 321 SUMMARY

XGS2220 Series User's Guide

LABEL	DESC RIPTIO N
Cloud Control Status	This displays the registration and connection status between the Switch and the NCC (Nebula Control Center).
	Click NCC Discovery or the switch button to go to SYSTEM > Cloud Management screen.
Port	This displays the port of this Switch.
Port Name	This displays the port description of this Switch.
Link Speed	This displays the speed (either <b>100M</b> for 100 Mbps, <b>1G</b> for 1 Gbps, <b>2.5G</b> for 2.5 Gbps, <b>5G</b> for 5 Gbps, or <b>10G</b> for 10 Gbps) and the duplex ( <b>F</b> for full duplex or <b>H</b> for half). It also shows the cable type ( <b>Copper</b> or <b>Fiber</b> ) for the combo ports. This field displays <b>Down</b> if the port is not connected to any device.
Bandwidth Usage (Tx)	These display the percentage of bandwidth usage on this port as a percentage of the <b>Link Speed</b> .
Bandwidth Usage (Rx)	
IGMP Leave Mode	This displays $\mathbf{Immediate}$ when the Switch receives IGMP leave packets, the Switch will close the multicast stream immediately without any further action.
	This displays <b>Fast</b> when the Switch will further generate a group specific query packet to all the receivers. This could prevent the traffic being cut if some receivers still want to receive the multicast stream.
	This displays <b>Nomal</b> when the Switch receives an IGMP leave message from a host on a port, it forwards the message to the multicast router. The multicast router then sends out an IGMP Group-Specific Query (GSQ) message to determine whether other hosts connected to the port should remain in the specific multicast group. The Switch forwards the query message to all hosts connected to the port and waits for IGMP reports from hosts to update the forwarding table for this port.

Table 321 SUMMARY (continued)

# 79.4 MONITOR

The following sections introduce the **MONTIOR** screens.

# 79.5 What You Can Do

• Use the System Information screen (Section 79.6 on page 558) to check the firmware version number and monitor the Switch temperature.

# 79.6 System Information

In the navigation panel, click **MONTIOR** > **System Information** to display the screen as shown. Use this screen to view general system information. You can check the firmware version number and monitor the Switch temperature.

#### Figure 417 MONITOR > System Information

erikan lakarawaya					
STATISTICS STATES					
vatern information					
a dan ta kina ta	ALL VILLE				
and a spin day	ALL STREET, BILLS				
A SALAR TARGET	et as exclusion per enable				
New Warne	100 P (2010) 2				
A second constraints	24.0				
emory United too					
Dot as	tarat	5 C V	Cost (at lat		Killer M (Fig
194 B		(Lyny) Diffy	Conception (action)		3 (b) (C) (C) (C) (C) (C) (C) (C) (C) (C) (C
000000	2100	110.0	1. MAR 94 (1)		. 192.
andware leavilat					
$= \operatorname{Transmission} \{ (i) \}$	<ul> <li>Melt x<sup>+</sup></li> </ul>	(ave).	2445	1000	Jacob and
2.57	Airwid )	40.00	(1 <b>4</b> )	195	20.5
View.	-storned T	10 A	4.1	2.7	1.2
84.	Sector 1	60 N	10 N		W 5
UAD LOHD (MY)	statu	1.000.0	19.42	P.H.	Print to B
ast.	, increased .).	2585	25.94	286	64
98. J.	I band I	- 00	4.05	1991	(02)
2003	Conversi )	1707	-740		6.0
(Volage(A)	344	Zera d	e13	E MH	Tree will
4077	( Indiana)	16.7	20.2	24.43	1410-005
1.97	(ired)	1215	2.00	2.672	110.00
2.27	I housed 1	2.00	3,000	1,2,520	<b>V000</b>
1.22	Turned (	2/19	2/35	2,013	120
- Sec	(Interest)	0.06	0.025	17.26	11.434-445

The following table describes the labels in this screen.

#### Table 322 MONITOR > System Information

LABEL	DESC RIPIIO N	
System Information	on	
System Name	This field displays the descriptive name of the Switch for identification purposes.	
Product Model	This field displays the product model of the Switch. Use this information when searching for firmware upgrade or looking for other support information in the website.	
ZyNOS F/W Version	This field displays the version number of the Switch's current firmware including the creation date.	
Ethernet Address	This field refers to the Ethernet MAC (Media Access Control) address of the Switch.	
CPU Utilization Current (%)	CPU utilization quantifies how busy the system is. <b>Cument</b> (%) displays the current percentage of CPU utilization.	
Memory Utilization Memory utilization shows how much DRAM memory is available and in use. It also displays the current percentage of memory utilization.		
Name	This field displays the name of memory pool.	
Total (byte)	This field displays the total number of bytes in this memory pool.	
Used (byte)	This field displays the number of bytes being used in this memory pool.	
Utilization (%)	This field displays the percentage (%) of memory being used in this memory pool.	
Hardware Monitor		

XGS2220 Series User's Guide

IABEL	DESC RIPTIO N
Temperature (C/F)	<b>BOARD/MAC/PHY</b> refers to the location of the temperature sensor on the Switch printed circuit board.
Status	This field displays <b>Nomal</b> for temperatures below the threshold and <b>Enor</b> for those above.
Current	This shows the current temperature at this sensor.
MAX	This field displays the maximum temperature measured at this sensor.
MIN	This field displays the minimum temperature measured at this sensor.
Threshold	This field displays the upper temperature limit at this sensor.
Fan Speed (RPM)	A properly functioning fan is an essential component (along with a sufficiently ventilated, cool operating environment) in order for the device to stay within the temperature threshold. Each fan has a sensor that is capable of detecting and reporting if the fan speed falls below the threshold shown.
Status	<b>Nomal</b> indicates that this fan is functioning above the minimum speed. <b>Enor</b> indicates that this fan is functioning below the minimum speed.
Current	This field displays this fan's current speed in Revolutions Per Minute (RPM).
MAX	This field displays this fan's maximum speed measured in Revolutions Per Minute (RPM).
MIN	This field displays this fan's minimum speed measured in Revolutions Per Minute (RPM). "<41" is displayed for speeds too small to measure (under 2000 RPM).
Threshold	This field displays the minimum speed at which a normal fan should work.
Voltage(V)	The power supply for each voltage has a sensor that is capable of detecting and reporting if the voltage falls out of the tolerance range.
Status	<b>Nomal</b> indicates that the voltage is within an acceptable operating range at this point; otherwise <b>Error</b> is displayed.
Current	This is the current voltage reading.
MAX	This field displays the maximum voltage measured at this point.
MIN	This field displays the minimum voltage measured at this point.
Threshold	This field displays the percentage tolerance of the voltage with which the Switch still works.

Table 322	MONITOR > System Information	(continued)

### 79.7 SYSTEM

The following sections introduces the SYSTEM screens.

# 79.8 What You Can Do

- Use the Cloud Management screen (Section 79.9 on page 561) to view NCC Connection status and enable/disable NCC Discovery.
- Use the General Setup screen (Section 79.10 on page 563) to configure general settings such as the system name and time.
- Use the IP Setup screen (Section 79.11 on page 565) to configure the default gateway device, the default domain name server and add IP domains.
- Use the Logins screen (Section 79.12 on page 567) to change the system password, configure passwords for up to four users and set their privilege level.

- Use the **SNMP** screen (Section 79.13 on page 569) to configure your SNMP (Simple Network Management Protocol) settings.
- Use the **SNMP User** screen (Section 79.14 on page 571) to create SNMP users for authentication with managers using SNMP v3 and associate them to SNMP groups.
- Use the **SNMP Trap Group** screen (Section 79.15 on page 573) to specify the types of SNMP traps that should be sent to each SNMP manager.
- Use the **SNMP Trap Port** screen (Section 79.16 on page 574) to set whether a trap received on the ports would be sent to the SNMP manager.

### 79.9 Cloud Management


The Zyxel Nebula Control Center (NCC) is a cloud-based network management system that allows you to remotely manage and monitor Zyxel Nebula APs, Ethernet switches and security gateways.

The Switch is managed and provisioned automatically by the NCC (Nebula Control Center) when:

- It is connected to the Internet.
- The Nebula Control Center Discovery feature is enabled.
- It has been registered in the NCC.

Click **SYSTEM** > **Cloud Management** in the navigation panel to display this screen.





IABEL	DESC RIPHO N
Nebula Control	Enable the switch button to turn on Nebula Control Center (NCC) discovery on the Switch.
Center (NCC) Discovery	This field displays:
	<ul> <li>The Switch Internet connection status.</li> <li>The connection status between the Switch and NCC.</li> <li>The Switch registration status on NCC.</li> </ul>
	Mouse over the circles to display detailed information.
	To pass your Switch management to NCC, first make sure your Switch is connected to the Internet. Then go to NCC and register your Switch.
	]. Internet
	Green – The Switch is connected to the Internet.
	Orange – The Switch is not connected to the Internet.
	2. Ne bula
	Green – The Switch is connected to NCC.
	Orange – The Switch is not connected to NCC.
	3. Registration
	Green – The Switch is registered on NCC.
	Gray – The Switch is not registered on NCC.
	Note: All circles will gray out if you disable Nebula Discovery.
Connection Status	This table displays the NCC connection status information.
310105	Use the status logs in the <b>Internet</b> , <b>Nebula</b> , and <b>Registration</b> fields for connection troubleshooting.

Table 323 SYSTEM > Cloud Management

Enable **Nebula Control Center (NCC) Discovery** to turn on NCC discovery on the Switch. If the Switch has Internet access and has been registered in the NCC, it will go into cloud management mode.

Disable **Nebula Control Center (NCC) Discovery** to turn off NCC discovery on the Switch. The Switch will NOT discover the NCC and remain in standalone mode.

This screen has a QR code containing the Switch's serial number and Registration MAC address for handy NCC registration of the Switch using the Nebula Mobile app. First, download the app from the Google Play store for Android devices or the App Store for iOS devices and create an organization and site. Open the Nebula Mobile app and follow the wizard to scan the **Register Device** QR code to register the Switch on NCC.

### 79.10 General Setup

Use this screen to configure general settings such as the system name and time. Click SYSTEM > GeneralSetup in the navigation panel to display the screen as shown.

Figure 419	SYSTEM >	General Setup
rigure 419	SISIEIVI /	General serue

General Setup	
Aydıra Karası Lacafon Sarası Pas- A Nora	
Hambrid, Sirver when Kendey Inco Server IP Address Tarse Anter Alys statement Cover a filme Loss manufationes) Anter IP circ	L(x)=x(1)(x)     x)
n ever u one (yysymmetric) line - zona Proyton - Savara (Sava 2 har - Data Und - Data	staz     ×     tr       staz     ×       staz     ×
	Apple Conset

Note: The input string of any field in this screen should not contain [?], [|], ['], or [,].

The following table describes the labels in this screen.

IABEL	DESC RIPTIO N
System Name	Choose a descriptive name for identification purposes. This name consists of up to 64 printable ASCII characters; spaces are allowed.
Location	Enter the geographic location of your Switch. You can use up to 128 printable ASCII characters; spaces are allowed.
Contact Person's Name	Enter the name of the person in charge of this Switch. You can use up to 32 printable ASCII characters; spaces are allowed.
Use Time Server when Bootup	Enter the time service protocol that your time server uses. Not all time servers support all protocols, so you may have to use trial and error to find a protocol that works. The main differences between them are the time format.
	When you select the <b>Daytime</b> ( <b>RFC-867</b> ) format, the Switch displays the day, month, year and time with no time zone adjustment. When you use this format it is recommended that you use a Daytime timeserver within your geographical time zone.
	Time (RFC-868) format displays a 4-byte integer giving the total number of seconds since 1970/ 1/1 at 00:00:00.
	NTP (RFC-1305) is similar to Time (RFC-868).
	<b>None</b> is the default value. Enter the time manually. Each time you turn on the Switch, the time and date will be reset to 2020-01-01 00:00:00.
Time Server IP Address	Enter the IP address or domain name of your timeserver. The Switch searches for the timeserver for up to 60 seconds.
Time Server Sync Interval	Enter the period in minutes between each time server synchronization. The Switch checks the time server after every synchronization interval.
Current Time	This field displays the time you open this menu (or refresh the menu).

Table 324 SYSTEM > General Setup

IABEL	DESC RIPTIO N
New Time (hh:mm:ss)	Enter the new time in hour, minute and second format. The new time then appears in the <b>Current Time</b> field after you click <b>Apply</b> .
Current Date	This field displays the date you open this menu.
New Date (yyyy- mm-dd)	Enter the new date in year, month and day format. The new date then appears in the Cument Date field after you click Apply.
Time Zone	Select the time difference between UTC (Universal Time Coordinated, formerly known as GMT, Greenwich Mean Time) and your time zone from the drop-down list box.
Daylight Saving Time	Daylight saving is a period from late spring to early fall when many countries set their clocks ahead of normal local time by one hour to give more daytime light in the evening.
	Enable the switch button if you use Daylight Saving Time.
Start Date	Configure the day and time when Daylight Saving Time starts if you selected <b>Daylight Saving</b> <b>Time</b> . The time is displayed in the 24 hour format. Here are a couple of examples:
	Daylight Saving Time starts in most parts of the United States on the second Sunday of March. Each time zone in the United States starts using Daylight Saving Time at 2 A.M. local time. So in the United States you would select <b>Second</b> , <b>Sunday</b> , <b>March</b> and <b>2:00</b> .
	Daylight Saving Time starts in the European Union on the last Sunday of March. All of the time zones in the European Union start using Daylight Saving Time at the same moment (1 A.M. GMT or UTC). So in the European Union you would select <b>Last, Sunday, March</b> and the last field depends on your time zone. In Germany for instance, you would select <b>2:00</b> because Germany's time zone is one hour ahead of GMT or UTC (GMT+1).
End Date	Configure the day and time when Daylight Saving Time ends if you selected <b>Daylight Saving</b> <b>Time</b> . The time field uses the 24 hour format. Here are a couple of examples:
	Daylight Saving Time ends in the United States on the first Sunday of November. Each time zone in the United States stops using Daylight Saving Time at 2 A.M. local time. So in the United States you would select <b>First</b> , <b>Sunday</b> , <b>November</b> and <b>2:00</b> .
	Daylight Saving Time ends in the European Union on the last Sunday of October. All of the time zones in the European Union stop using Daylight Saving Time at the same moment (1 A.M. GMT or UTC). So in the European Union you would select <b>Iast, Sunday</b> , <b>October</b> and the last field depends on your time zone. In Germany for instance, you would select <b>2:00</b> because Germany's time zone is one hour ahead of GMT or UTC (GMT+1).
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 324	SYSTEM >	General Setup	(continued)
	OTOTENT	0011010100100	1001111100001

### 79.11 IP Setup

Use the IP Setup screen to configure the default gateway device, the default domain name server and add IP domains.

Note: The Switch allows you to set a static IP interface in the same subnet that already has a DHCP-assigned IP interface on the Switch. The Switch will use the static IP you set and the DHCP-assigned IP will be set to 0.0.0.

Figure 420 SYSTEM > IP Setup

IP Selvp					
In Setup					
	arce ay omo Sorver 1 ome Server 7		Apply Concel		
IP Interfo	ce				
				O Add/Edit	曽 Daleta
	Index	IP address	12 Subnet Mosk	VID	Туре
	1	10.214.35.43	256,256,266,0	I	DHCP

LABEL	DESC RIPIIO N	
IP Setup		
Default Gateway	Type the IP address of the default outgoing gateway in dotted decimal notation, for example 192.168.1.254.	
Domain Name Server 1/2	Enter a domain name server IPv4 address in order to be able to use a domain name instead of an IP address.	
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.	
Cancel	Click <b>Cancel</b> to reset the fields to your previous configuration.	
IP Interface		
Use this section to	o view and configure IP routing domains on the Switch.	
Index	This field displays the index number of an entry.	
IP Address	This field displays the IP address of the Switch in the IP domain.	
IP Subnet Mask	This field displays the subnet mask of the Switch in the IP domain.	
VID	This field displays the VLAN identification number of the IP domain on the Switch.	
Туре	This field displays the type of IP address status. Static or DHCP.	
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.	
Add/Edit	Click Add/Edit to add a new IP interface or edit a selected one.	
Delete	Click <b>Delete</b> to remove the selected IP interfaces.	

Table 225	SVSTENA > ID Sotup
10016 323	SYSTEM > IP Setup

### 79.11.1 Add/Edit IP Interfaces

Use this screen to add or edit IP interfaces. Click Add/Edit, or select an entry and click Add/Edit in the SYSTEM > IP Setup screen to display this screen.

Figure 421	SYSTEM > IP Setup > Add/Edi
Figure 421	SIZIEW > IN ZEIND > VOU/FO

Outproten		
$\bigcirc$ 0 rate . If its fille as		
<ul> <li>Apple by the</li> </ul>		
in Jubine Fredrik		
2 P		
Anythy .	C. e.e.	Const.

Table 326	SYSTEM > IP Setup > Add/Edit
	SISILM / IL SEIUP / AUU/LUI

IABEL	DESC RIPTIO N
DHCP Client	Select this option if you have a DHCP server that can assign the Switch an IP address, subnet mask, a default gateway IP address and a domain name server IP address automatically.
Static IP Address	Select this option if you do not have a DHCP server or if you wish to assign static IP address information to the Switch. You need to fill in the following fields when you select this option.
IP Address	Enter the IP address of your Switch in dotted decimal notation, for example, 192.168.1.1. This is the IP address of the Switch in an IP routing domain.
IP Subnet Mask	Enter the IP subnet mask of an IP routing domain in dotted decimal notation, for example, 255.255.255.0.
VID	Enter the VLAN identification number to which an IP routing domain belongs.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click <b>Clear</b> to clear the fields to the factory defaults.
Cancel	Click <b>Cancel</b> to not save the configuration you make and return to the last screen.

### 79.12 Logins

Up to five people (one administrator and four non-administrators) may access the Switch through Web Configurator at any one time.

• An administrator is someone who can both view and configure Switch changes. The user name for the Administrator is always **admin**. The default administrator password is **1234**.

Note: It is highly recommended that you change the default administrator password (1234).

• A non-administrator (user name is something other than **admin**) is someone who can view and/or configure Switch settings. The configuration right varies depending on the user's privilege level.

Click **SYSTEM**> Logins to view the screen as shown.

#### Figure 422 SYSTEM > Logins

gins				
dministration				
DREAS AND DREASE AND DR		0		
Iow Polowed II.				
totado lo contri	1	1		
			ar you drange II. Bre system with	NUM YOU OUT I
dił Logins	strantish john	Contractic Storwards		
login	, n	Pairword	Setype to confirm	Fittlege
			Retype to contino	Piktikge
login			Setype to confirm	Piklikge
logn , –			Setype to confirm	Piktløge
ř. –			Setype to confirm	Privile 

Note: The input string in any field of this screen should not contain [?], [|], ['], ["] or [,]. In the **Password** fields, [space] is also not allowed.

The following table describes the labels in this screen.

Table 327 STSTEM > Logins		
IABEL	DESC RIPTIO N	
Administrator		
This is the default administrator account with the "admin" user name. You cannot change the default administrator user name.		
Old Password	Enter the existing system password (1234 is the default password when shipped).	
New Password	Enter your new system password.	
Retype to confirm	Re-enter your new system password for confirmation.	
Edit Logins		
give users higher pri	passwords for up to four users. These users can have read-only or read/write access. You can vileges through the Web Configurator or the CLI. For more information on assigning privileges the Ethernet Switch CLI Reference Guide.	
Login	This is the index of an user account.	
User Name	Set a user name (up to 32 printable ASCII characters except [ ? ], [   ], [ ' ], [ " ], or [ , ]).	
Password	Enter your new system password.	
Retype to confirm	Retype your new system password for confirmation.	

LABEL	DESC RIPHO N
Privilege	Enter the privilege level for this user. At the time of writing, users may have a privilege level of 0, 3, 13, or 14 representing different configuration rights as shown below.
	<ul> <li>0 – Display basic system information.</li> <li>3 – Display configuration or status.</li> </ul>
	<ul> <li>13 – Configure features except for login accounts, SNMP user accounts, the authentication method sequence and authorization settings, multiple logins, administrator and enable passwords, and configuration information display.</li> </ul>
	<ul> <li>14 – Configure login accounts, SNMP user accounts, the authentication method sequence and authorization settings, multiple logins, and administrator and enable passwords, and display configuration information.</li> </ul>
	Users can run command lines if the session's privilege level is greater than or equal to the command's privilege level. The session privilege initially comes from the privilege of the login account. For example, if the user has a privilege of 5, he or she can run commands that requires privilege level of 5 or less but not more.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 327 SYSTEM > Logins (continued)

### 79.13 Configure SNMP

Use this screen to configure your SNMP settings. Simple Network Management Protocol (SNMP) is an application layer protocol used to manage and monitor TCP/IP-based devices. SNMP is used to exchange management information between the network management system (NMS) and a network element (NE). A manager station can manage and monitor the Switch through the network through SNMP version 1 (SNMPv1), SNMP version 2c or SNMP version 3. The next figure illustrates an SNMP management operation. SNMP is only available if TCP/IP is configured.




Figure 423 SNMP Management Model

An SNMP managed network consists of two main components: agents and a manager.

An agent is a management software module that resides in a managed Switch (the Switch). An agent translates the local management information from the managed Switch into a form compatible with SNMP. The manager is the console through which network administrators perform network management functions. It executes applications that control and monitor managed devices.

The managed devices contain object variables or managed objects that define each piece of information to be collected about a Switch. Examples of variables include number of packets received, node port status and so on. A Management Information Base (MIB) is a collection of managed objects. SNMP allows a manager and agents to communicate for the purpose of accessing these objects.

SNMP itself is a simple request or response protocol based on the manager or agent model. The manager issues a request and the agent returns responses using the following protocol operations:

	Communds
IABEL	DESC RIPIIO N
Get	Allows the manager to retrieve an object variable from the agent.
GetNext	Allows the manager to retrieve the next object variable from a table or list within an agent. In SNMPv1, when a manager wants to retrieve all elements of a table from an agent, it initiates a Get operation, followed by a series of GetNext operations.
Set	Allows the manager to set values for object variables within an agent.
Trap	Used by the agent to inform the manager of some events.

Table 328 SNMP Commands

#### SNMP v3 and Security

SNMP v3 enhances security for SNMP management. SNMP managers can be required to authenticate with agents before conducting SNMP management sessions.

Security can be further enhanced by encrypting the SNMP messages sent from the managers. Encryption protects the contents of the SNMP messages. When the contents of the SNMP messages are encrypted, only the intended recipients can read them.

#### Click **SYSTEM** > **SNMP** > **SNMP** to view the screen as shown.

MP S	NMP Usor	SNMP Trap Group	SNMP Trop Port	
eneral S	etting			
62107	9	20 V		
Sol Comm	nite 9	101:		
el Commu	4.7 0	4.600		
(de Comm	.els 2	Jbie	G	
rap <mark>Oesli</mark> r	nation			10-10-10-10
	tation Version	r	#out	Usumanne
rap Destin Index	nation		fad 182 165	Usumanie
rap Destli Index T	nation Version	# [0000	182	

Note: The string of any field in this screen should not contain [?], [], [], [], [] or [,].

LABEL	DESC RIPTIO N			
General Setting				
Use this section to s	pecify the SNMP version and community (password) values.			
Version	Select the SNMP version for the Switch. The SNMP version on the Switch must match the version on the SNMP manager. Choose SNMP version 2c (v2c), SNMP version 3 (v3) or both (v3v2c).			
	SNMP version 2c is backwards compatible with SNMP version 1.			
Get Community	Enter the <b>GetCommunity</b> string, which is the password for the incoming Get- and GetNext-requests from the management station.			
	The GetCommunity string is only used by SNMP managers using SNMP version 2c or lower.			
Set Community	Enter the <b>Set Community</b> string, which is the password for incoming Set- requests from the management station.			
	The Set Community string is only used by SNMP managers using SNMP version 2c or lower.			
Trap Community	Enter the <b>Tap Community</b> string, which is the password sent with each trap to the SNMP manager.			
	The Thap Community string is only used by SNMP managers using SNMP version 2c or lower.			
Trap Destination				
Use this section to c	configure where to send SNMP traps from the Switch.			
Index	This is the index of a trap destination.			
Version	Specify the version of the SNMP trap messages.			
IP	Enter the IP addresses of up to four managers to send your SNMP traps to.			
Port	Enter the port number upon which the manager listens for SNMP traps.			
Username	Enter the user name to be sent to the SNMP manager along with the SNMP v3 trap.			
	This user name must match an existing account on the Switch (configured in the <b>SYSTEM</b> > <b>SNMP</b> > <b>SNMP</b> Use <b>r</b> screen).			
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.			
Cancel	Click Cancel to begin configuring this screen afresh.			

Table 329 SYSTEM > SNMP

# 79.14 Configure SNMP User

Use this screen to create SNMP users for authentication with managers using SNMP v3 and associate them to SNMP groups. An SNMP user is an SNMP manager. Click **SYSTEM** > **SNMP** User to view the screen as shown.

Figure 425 SYSTEM > SNMP > SNMP User

SNMP	SNMP User	SNMP Trop	Group	SNMP Trap Fort		
					🗘 Acid-bant	S.L.W.
	Index	liventone	Security Level	Solitentication	Polysicy	Simp

LABEL	DESC RIPTIO N			
Index	This is a read-only number identifying a login account on the Switch.			
Username	is field displays the user name of a login account on the Switch.			
Security Level	This field displays whether you want to implement authentication and/or encryption for SNM communication with this user.			
Authentication	This field displays the authentication algorithm used for SNMP communication with this user.			
Privacy	This field displays the encryption method used for SNMP communication with this user.			
Group	This field displays the SNMP group to which this user belongs.			
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.			
Add/Edit	Click Add/Edit to add a new entry or edit a selected one.			
Delete	Click <b>De le te</b> to remove the selected entries.			

Table 330 SYSTEM > SNMP > SNMP User

### 79.14.1 Add/Edit SNMP User

Use this screen to create SNMP users for authentication with managers using SNMP v3 and associate them to SNMP groups. An SNMP user is an SNMP manager. Click **Add/Edit**, or select an entry and click **Add/Edit** in the **SYSTEM** > **SNMP** > **SNMP** User screen to view this screen.

Note: Use the user name and password of the login accounts you specify in this screen to create accounts on the SNMP v3 manager.

Figure 426 SYSTEM > SNMP > SNMP User > Add/Edit

Usemame				
Secondly Level	no cuth v			
Authentication	MDS ~	Prowned		
Privolog	DES M	Fassword		
Cavarga	odmin 💉			
		Apply	Clear	Concel

Note: The input string of any field in this screen should not contain [?], [|], ['], or [,].

Table 331	SYSTEM > SNMP > SNMP User > Add/Edit	

IABEL	DESC RIPTIO N				
Username	Specify the user name of a login account on the Switch. You can enter up to 32 printable ASCII characters.				
Security Level	Select whether you want to implement authentication and/or encryption for SNMP communication from this user. Choose:				
	<ul> <li>no auth – to use the user name as the password string to send to the SNMP manager. This is equivalent to the Get, Set and Trap Community in SNMP v2c. This is the lowest security level.</li> </ul>				
	<ul> <li>auth – to implement an authentication algorithm for SNMP messages sent by this user.</li> <li>priv – to implement authentication and encryption for SNMP messages sent by this user. This is the highest security level.</li> </ul>				
	Note: The settings on the SNMP manager must be set at the same security level or higher than the security level settings on the Switch.				
Authentication	Select an authentication algorithm. <b>MD5</b> (Message Digest 5) and <b>SHA</b> (Secure Hash Algorithm) are hash algorithms used to authenticate SNMP data. SHA authentication is generally considered stronger than MD5, but is slower.				
Password	Enter the password of up to 32 printable ASCII characters (except [?], [ ], ['], ["], [space], or [,]) for SNMP user authentication.				
Privacy	Specify the encryption method for SNMP communication from this user. You can choose one of the following:				
	<ul> <li>DES – Data Encryption Standard is a widely used (but breakable) method of data encryption. It applies a 56-bit key to each 64-bit block of data.</li> </ul>				
	<ul> <li>AES – Advanced Encryption Standard is another method for data encryption that also uses a secret key. AES applies a 128-bit key to 128-bit blocks of data.</li> </ul>				
Password	Enter the password of up to 32 printable ASCII characters (except [?], [ ], ['], ["], [space], or [,]) for encrypting SNMP packets.				
Group	SNMP v3 adopts the concept of View-based Access Control Model (VACM) group. SNMP managers in one group are assigned common access rights to MIBs. Specify in which SNMP group this user is.				
	admin – Members of this group can perform all types of system configuration, including the management of administrator accounts.				
	<b>re a d-write</b> – Members of this group have read and write rights, meaning that the user can create and edit the MIBs on the Switch, except the user account and AAA configuration.				
	$\mathbf{re}  \mathbf{a}  \mathbf{d} \cdot \mathbf{o}  \mathbf{nly}$ – Members of this group have read rights only, meaning the user can collect information from the Switch.				
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.				
Clear	Click <b>Clear</b> to clear the fields to the factory defaults.				
Cancel	Click Cancel to not save the configuration you make and return to the last screen.				

# 79.15 Configure SNMP Trap Group

Use this screen to specify the types of SNMP traps that should be sent to each SNMP manager. Click **SYSTEM** > **SNMP** > **SNMP** Thap Group to view the screen as shown.

Figure 427	SYSTENA >	SNIMP >	SVIVA	Tran	Group
rigure 427	3131E/V1 >	JINNE >	21V/VIL	nap	GIOUD

SNMP SNMP User	SNMP Trap Group	SNMP Trop Port			
Top Definition in	~				
_ bysien			Infedore		
colorian   temperature   transport   post	<ul> <li>⇒ varmant</li> <li>⇒ voltage</li> <li>⇒ konjegene k</li> <li>⇒ konjegene k</li> </ul>	<ul> <li>Investment for</li> </ul>	<ul> <li>Introp</li> <li>Interpretendents</li> <li>Interpretendents</li> </ul>	<ul> <li>☐ In adown</li> <li>☐ dorm-control</li> </ul>	⊖ Ma ⊡ suid
	- adjances.		D AMA		
			<ul> <li>Output emission</li> </ul>	cuthorization	<ul> <li>Cooperating</li> </ul>
			_]awitch		
∐iphg	Indeed the		_ sto ]] clossifier	📋 mocrable	
		Apply	Guidel		

LABEL	DESC RIPTIO N
Trap Destination IP	Select one of your configured trap destination IP addresses. These are the IP addresses of the SNMP managers. You must first configure a trap destination IP address in the <b>SYSTEM</b> > <b>SNMP</b> > <b>SNMP</b> screen.
	Use the rest of the screen to select which traps the Switch sends to that SNMP manager.
	Select the individual SNMP traps that the Switch is to send to the SNMP station. The traps are grouped by category. Selecting a category in the heading row automatically selects all of the SNMP traps under that category. Clear the check boxes for individual traps that you do not want the Switch to send to the SNMP station. Clearing a category's check box automatically clears all of the category's trap check boxes (the Switch only sends traps from selected categories).
ApplyClick Apply to save your changes to the Switch's run-time memory. The Switch loses to changes if it is turned off or loses power, so use the Save link on the top navigation point save your changes to the non-volatile memory when you are done configuring.	
Cancel	Click Cancel to begin configuring this screen afresh.

Table 332 SYSTEM > SNMP > SNMP Trap Group

# 79.16 Enable or Disable Sending of SNMP Traps on a Port

Click **SYSTEM** > **SNMP** > **SNMP** Thap Port to view the screen as shown. Use this screen to set whether a trap received on the ports would be sent to the SNMP manager.

SNMP	SNMP Usar	SNMP Trop Group	SNMP Trop Port
Colors	leoguae	×	
	Port	Activ	e
		D	
		12	
	52		
	14	5	
	- 24	8	
	34		
	3		
	14	~ •	$\sim \sim \sim$
			$\sim\sim\sim$
$\sim$		~ ~ ~-	
	1	Apply General	

Figure 428 SYSTEM > SNMP > SNMP Trap Port

IABEL	DESC RIPTIO N
Options	Select the trap type you want to configure here.
Port	This field displays a port number.
*	Settings in this row apply to all ports. Use this row only if you want to make some of the settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis. Changes in this row are copied to all the ports as soon as you make them.
Active	Select this check box to enable the trap type of SNMP traps on this port. The Switch sends the related traps received on this port to the SNMP manager. Clear this check box to disable the sending of SNMP traps on this port.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 333 SYSTEM > SNMP > SNMP Trap Port

### 79.17 PORT


The following sections introduce the **PORT** screens.

# 79.18 Link Aggregation

This section shows you how to logically aggregate physical links to form one logical, higher-bandwidth link.

Link aggregation (trunking) is the grouping of physical ports into one logical higher-capacity link. You may want to trunk ports if for example, it is cheaper to use multiple lower-speed links than to under-utilize a high-speed, but more costly, single-port link. However, the more ports you aggregate then the fewer available ports you have. A trunk group is one logical link containing multiple ports.

The beginning port of each trunk group must be physically connected to form a trunk group.



### 79.18.1 What You Can Do

- Use the **Link Aggregation Status** screen (Section 79.19 on page 576) to view ports you have configured to be in the trunk group, ports that are currently transmitting data as one logical link in the trunk group and so on.
- Use the **Link Aggregation Setting** screen (Section 79.20 on page 578) to configure to enable static link aggregation.
- Use the **Link Aggregation Control Protocol** screen (Section 79.21 on page 579) to enable Link Aggregation Control Protocol (LACP).

### 79.19 Link Aggregation Status

Use the **Link Aggregation Status** screen to view ports you have configured to be in the trunk group, ports that are currently transmitting data as one logical link in the trunk group and so on.

Click **PORT**> **Link Aggregation** > **Link Aggregation** Status in the navigation panel to display the screen as shown.

tink Aggreg	galian Shalus	Link Aggreg	alian Selling	Tink Aggregation Cr	entral Protoco
Group ID	Incided Ports	Synchronized Ports	Aggregator 10	Criterio	Stolur
	-	-		accedelence:	-
P?				sts det mind	
<b>T</b> .)				sts datimine	
14				are definited	
12				ar di muc	
16	-	-		aced lence:	
17	-	-		gent-huor	

Figure 430 PORT > Link Aggregation > Link Aggregation Status

IABEL	DESC RIPTIO N
Group ID	This field displays the group ID to identify a trunk group, that is, one logical link containing multiple ports.
Enabled Ports	These are the ports you have configured in the <b>Link Aggregation Setting</b> screen to be in the trunk group.
	The port numbers displays only when this trunk group is activated and there is a port belonging to this group.
Synchronized Ports	These are the ports that are currently transmitting data as one logical link in this trunk group.
Aggregator ID	Link Aggregator ID consists of the following: system priority, MAC address, key, port priority and port number.
	The ID displays only when there is a port belonging to this trunk group and LACP is also enabled for this group.
Criteria	This shows the outgoing traffic distribution algorithm used in this trunk group. Packets from the same source and/or to the same destination are sent over the same link within the trunk.
	$\operatorname{src}$ - $\operatorname{mac}$ means the Switch distributes traffic based on the packet's source MAC address.
	dst-mac means the Switch distributes traffic based on the packet's destination MAC address.
	src-dst-mac means the Switch distributes traffic based on a combination of the packet's source and destination MAC addresses.
	${f src}$ - ${f ip}$ means the Switch distributes traffic based on the packet's source IP address.
	dst-ip means the Switch distributes traffic based on the packet's destination IP address.
	src - dst-ip means the Switch distributes traffic based on a combination of the packet's source and destination IP addresses.
Status	This field displays how these ports were added to the trunk group. It displays:
	<ul> <li>Static - if the ports are configured as static members of a trunk group.</li> <li>IACP- if the ports are configured to join a trunk group through LACP.</li> </ul>

Table 334 PORT > Link Aggregation > Link Aggregation Status

# 79.20 Link Aggregation Setting

Use the **Link Aggregation Setting** screen to enable static link. Link aggregation (trunking) is the grouping of physical ports into one logical higher-capacity link. You may want to trunk ports if for example, it is cheaper to use multiple lower-speed links than to under-utilize a high-speed, but more costly, single-port link. However, the more ports you aggregate then the fewer available ports you have. A trunk group is one logical link containing multiple ports.

Click PORT> Link Aggregation > Link Aggregation Setting to display the screen shown next.

Link Aggregation Status	Unk Aggregation Setting Unk Aggregation		
Group ID	Active		Citterio
10	22	-312	s det mane w
- 12	Ū.	2	definice v
10	11		dst.max v
T4	D	10	det maa v
1978-	Ū	7	dstimud v
18	0	57	dstimed v
17	~ <b>D</b>	~ .	del mod y
1		Second Second	
For		Croop	
2		(Natarix)	
2		(Natery)	
		Neew	
(A)		Nores	
4		Notes:	
e 1		North Sel	~ ~ ~
	$\sim$		$\sim$
~ ~ ~		<u></u>	

Figure 431 PORT > Link Aggregation > Link Aggregation Setting

The following table describes the labels in this screen.

Table 335 PORT> Link Aggregation > Link Aggregation Setting

LABEL	DESC RIPTIO N		
This is the only so	This is the only screen you need to configure to enable static link aggregation.		
Group ID The field identifies the link aggregation group, that is, one logical link containing multiple ports.			
Active	Select this to activate a trunk group.		

IABEL	DESC RIPTIO N
Criteria	Select the outgoing traffic distribution type. Packets from the same source and/or to the same destination are sent over the same link within the trunk. By default, the Switch uses the smedst-mac distribution type. If the Switch is behind a router, the packet's destination or source MAC address will be changed. In this case, set the Switch to distribute traffic based on its IP address to make sure port trunking can work properly.
	Select $\mathbf{src} \cdot \mathbf{mac}$ to distribute traffic based on the packet's source MAC address.
	Select $dst-mac$ to distribute traffic based on the packet's destination MAC address.
	Select src-dst-mac to distribute traffic based on a combination of the packet's source and destination MAC addresses.
	Select $\mathbf{src}$ - $\mathbf{ip}$ to distribute traffic based on the packet's source IP address.
	Select $\mathbf{dst}$ - $\mathbf{ip}$ to distribute traffic based on the packet's destination IP address.
	Select <b>src</b> - <b>dst</b> - <b>ip</b> to distribute traffic based on a combination of the packet's source and destination IP addresses.
Port	This field displays the port number.
Group	Select the trunk group to which a port belongs.
	Note: When you enable the port security feature on the Switch and configure port security settings for a port, you cannot include the port in an active trunk group.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

 Table 335
 PORT> Link Aggregation > Link Aggregation Setting (continued)

# 79.21 Link Aggregation Control Protocol

When you enable LACP link aggregation on a port, the port can automatically negotiate with the ports at the remote end of a link to establish trunk groups. LACP also allows port redundancy, that is, if an operational port fails, then one of the "standby" ports become operational without user intervention.

Click PORT> Link Aggregation > Link Aggregation Control Protocol to display the screen shown next.

Note: Do NOT configure this screen unless you want to enable dynamic link aggregation.

status Unic	Aggregation Setting	Unk Aggregation Control Protocol	
202102	CII ()		
System Mooly	10510		
Gro	vp D	LAGE Active	
		<b>D</b>	
	4 3		
	3	-	
	4		
	5		
	5) (	<u></u>	
	28		
		LACE Timeout	
	₩0.000 ₩ 2	30 ve steriotech	
	•	<u>30 ve</u> ] secucivets   <u>30 ve</u> ] secucivets	
		30 v   seconds   30 v   seconds   30 v   seconds	
	- - - -	<u>30 v</u> ] securate   <u>30 v</u> ] securate   <u>30 v</u> ] securate   <u>30 v</u> ] securate   <u>30 v</u> ] securate	
	, , ,	30 w       30 w	
	- - - - - -	30 v         seconds	
	1 0 3 5 8	30 m       30 m	
	- - - - - -	30 v         seconds	

Figure 432 PORT > Link Aggregation > Link Aggregation Control Protocol

Table 336	PORT > Link Aggregation >	Link Aggregation Control Protocol
-----------	---------------------------	-----------------------------------

IABEL	DESC RIPTIO N	
Active	Enable the switch button to enable Link Aggregation Control Protocol (LACP).	
System Priority	LACP system priority is a number between 1 and 65535. The switch with the lowest system priority (and lowest port number if system priority is the same) becomes the LACP "server". The LACP "server" controls the operation of LACP setup. Enter a number to set the priority of an active port using Link Aggregation Control Protocol (LACP). The smaller the number, the higher the priority level.	
Use this section t	o enable LACP on trunks.	
Group ID	The field identifies the link aggregation group, that is, one logical link containing multiple ports.	
LACP Active	Select this option to enable LACP for a trunk.	
Use this section to configure LACP timeout on ports.		
Port	This field displays the port number.	

XGS2220 Series User's Guide

LABEL	DESC RIPTIO N
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
LACP Timeout	Timeout is the time interval between the individual port exchanges of LACP packets in order to check that the peer port in the trunk group is still up. If a port does not respond after three tries, then it is deemed to be "down" and is removed from the trunk. Set a short timeout (1 second) for busy trunked links to ensure that disabled ports are removed from the trunk group as soon as possible.
	Select either 1 second or 30 seconds.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

Table 336 PORT > Link Aggregation > Link Aggregation Control Protocol (continued)

### 79.22 PoEStatus

A powered device (PD) is a device such as an access point or a switch, that supports PoE (Power over Ethernet) so that it can receive power from another device through an Ethernet port.

You can also set priorities so that the Switch is able to reserve and allocate power to certain PDs.

Note: The PoE (Power over Ethernet) devices that supply or receive power and their connected Ethernet cables must all be completely indoors.




Figure 433 PoE Example Application

To view the current amount of power that PDs are receiving from the Switch, click **PORT** > **PoESe tup** > **PoESta tus**.

of Blacks	POSiSchup					
ere Viele og		Section + Barris				
and Parvis P	ά.	1122-00				
Constantin (M)		8.7				
an shi iyo ta		9. 9.2 7				
Recorded Fore	1000 00 00 00 00 00 00 00 00 00 00 00 00	in an				
anaging na	(1) (94) (	\$ <del>6</del> 30				
2.61	- Sicile	040	tricely.	Scene Cp	Carlowing Power (A)	Mar fune (#,
	USH	1065	10.0	20.01		
1.7	We what	r i	(i.e.)		65	
4	U7204		1.654	10.00	200 -	S.
- 4		1 - C	11.0	447.44	74	
		1.00	1.5.9	10.00	. 54	28
- X	B state.	5 (e)	(1. e	100 Mar.	P(2)	
- 33	and the second	161	17.0	1. Star Star	0.0	(#)
	8.2A		1. e.	21.44		
					$\sim$	
	Minutation of		her			$\sim$

Figure 434 PORT > PoE Setup > PoE Status

The following table describes the labels in this screen.

Table 337 PORT > PoE Setup > PoE Status

IABEL	DESC RIPTIO N		
PoE Mode	This field displays the power management mode used by the Switch, whether it is in <b>Classific a tion</b> or <b>Consumption</b> mode.		
Total Power (W)	This field displays the total power the Switch can provide to the connected PoE-enabled devices on the PoE ports.		
PoE Usage (%)	This field displays the amount of power currently being supplied to connected PoE devices (PDs) as a percentage of the total PoE power the Switch can supply.		
	When PoE usage reaches 100%, the Switch will shut down PDs one-by-one according to the PD priority which you configured in $PORT > PoESe tup > PoESe tup$ .		
Consuming Power (W)	This field displays the amount of power the Switch is currently supplying to the connected PoE- enabled devices.		
Allocated Power (W)	This field displays the total amount of power the Switch (in classification mode) has reserved for PoE after negotiating with the connected PoE devices. It shows <b>NA</b> when the Switch is in consumption mode.		
	Consuming Power(W) can be less than or equal but not more than the Allocated Power(W).		
Remaining Power (W)	This field displays the amount of power the Switch can still provide for PoE.		
	Note: The Switch must have at least 16 W of remaining power in order to supply power to a PoE device, even if the PoE device needs less than 16 W.		
Port	This is the port index number.		
State	This field shows which ports can receive power from the Switch. You can set this in Section 79.23 on page 583.		
	<ul> <li>Disable – The PD connected to this port cannot get power supply.</li> <li>Enable – The PD connected to this port can receive power.</li> </ul>		

IABEL	DESC RIPTIO N			
Class	This shows the power classification of the PD. Each PD has a specified maximum power that fall under one of the classes.			
	The Class is a number from 0 to 6, where each value represents the range of power that the Switch provides to the PD.			
	Each class corresponds to a default maximum power that can be extended in <b>Port</b> > <b>PoE Se tup</b> > <b>PoE Se tup</b> to the following values.			
	<ul> <li>Class 0 - default: 0.44 W to 15.4 W.</li> <li>Class 1 - default: 0.44 W to 4 W.</li> <li>Class 2 - default: 0.44 W to 7 W.</li> <li>Class 3 - default: 0.44 W to 15.4 W.</li> <li>Class 4 - default: 0.44 W to 30 W.</li> <li>Class 5 - default: 0.44 W to 45 W.</li> <li>Class 6 - default: 0.44 W to 60 W.</li> </ul>			
Priority	<ul> <li>When the total power requested by the PDs exceeds the total PoE power budget on the Switch, you can set the PD priority to allow the Switch to provide power to ports with higher priority first.</li> <li>Critic al has the highest priority.</li> <li>High has the Switch assign power to the port after all critical priority ports are served.</li> <li>Low has the Switch assign power to the port after all critical and high priority ports are served.</li> </ul>			
Power-Up	This field displays the PoE standard the Switch uses to provide power on this port.			
Consuming Power (W)	This field displays the current amount of power consumed by the PD from the Switch on this port.			
Max Power (W)	This field displays the maximum amount of power the PD could use from the Switch on this port.			

Table 337 PORT > PoE Setup > PoE Status (continued)

# 79.23 PoESetup

Use this screen to set the PoE power management mode, priority levels, power-up mode and the maximum amount of power for the connected PDs.

Click PORT > PoE Setup > PoE Setup, the following screen opens.

1000	C. Secondario	Q Constraints			
erenne fisk	<b>CE</b> )				
( NI	tatul.	men	11000	ANTIMATE	A MERCEN VIEW
	100	Long Pol	Maring Trans		
		the state	lines A		1.0
10	8	100.00	line and the		
- 20 C	1	Hen	1825		
	6	(14 T)	linger v		
10		101-	18154		1 1
- 22	8	10	1001001 22.22		<b>B</b> .
		10. 27	(1979)	1 1	
	6	De Al	15132		5
	1	100.00	(End)	1.1	
	-	Dell'A	Internal	1	
11		0.04-0.00	(Louis V		
100	19	1 m m	0803		
	10	110.00	Inclusion 1994		
100		lies el	licities in licitios in		
1.1	5	114 11			~~~~
					$\sim$ $\sim$
	6	the second se	Constant Constant	$\sim$	
	1.00				8 

Figure 435 PORT > PoE Setup > PoE Setup

#### Table 338 Port > PoE Setup > PoE Setup

IABEL	DESC RIPTIO N						
PoE Mode	Select the power management mode you want the Switch to use.						
	<ul> <li>Classification – Select this if you want the Switch to reserve the maximum power for each PD according to the PD's power class and priority level. If the total power supply runs out, PDs with lower priority do not get power to function. In this mode, the maximum power is reserved based on what you configure in Max Power or the standard power limit for each class.</li> <li>Communitient Select this if you want the Switch to supply the actual power that the PD</li> </ul>						
	<ul> <li>Consumption – Select this if you want the Switch to supply the actual power that the PD needs. The Switch also allocates power based on a port's Max Power and the PD's power class and priority level. The Switch puts a limit on the maximum amount of power the PD can request and use. In this mode, the default maximum power that can be delivered to the PD is 33 W (IEEE 802.3at Class 4) or 22 W (IEEE 802.3at Classes 0 to 3).</li> </ul>						
Continuous PoE	Select <b>ON</b> to guarantee continuous power supply to the connected PDs while the Switch is restarting after a warm reboot. The Switch will NOT perform a power cycle on the connected PDs.						
	If you do a cold reboot, the Switch also restarts the connected PDs.						
Port	This is the port index number.						
*	Settings in this row apply to all ports.						
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.						
	Changes in this row are copied to all the ports as soon as you make them.						
Active	Select this to provide power to a PD connected to the port.						
	If left unchecked, the PD connected to the port cannot receive power from the Switch.						

IABEL	DESC RIPTIO N
Priority	When the total power requested by the PDs exceeds the total PoE power budget on the Switch, you can set the PD priority to allow the Switch to provide power to ports with higher priority.
	Select <b>C ritic a I</b> to give the highest PD priority on the port.
	Select <b>High</b> to set the Switch to assign the remaining power to the port after all critical priority ports are served.
	Select $\mathbf{Low}$ to set the Switch to assign the remaining power to the port after all critical and high priority ports are served.
Power-Up	Set how the Switch provides power to a connected PD at power-up.
	802.3af – the Switch follows the IEEE 802.3af Power over Ethernet standard to supply power to the connected PDs during power-up.
	$\mathbf{Legacy}$ – the Switch can provide power to the connected PDs that require high inrush currents at power-up. Inrush current is the maximum, instantaneous input current drawn by the PD when first turned on.
	<b>Pre</b> - <b>802.3a</b> t – the Switch initially offers power on the port according to the IEEE 802.3af standard, and then switches to support the IEEE 802.3at standard within 75 milliseconds after a PD is connected to the port. Select this option if the Switch is performing 2-event Layer-1 classification (PoE+ hardware classification) or the connected PD is NOT performing Layer 2 power classification using Link Layer Discovery Protocol (LLDP).
	802.3at – the Switch supports the IEEE 802.3at High Power over Ethernet standard and can supply power of up to 30 W per Ethernet port. IEEE 802.3at is also known as PoE+ or PoE Plus. An IEEE 802.3at compatible device is referred to as Type 2. Power Class 4 (High Power) can only be used by Type 2 devices. If the connected PD requires a Class 4 current when it is turned on, it will be powered up in this mode.
	Force-802.3at – the Switch offers power of up to 33 W on the port without performing PoE hardware classification. Select this option if the connected PD does not comply with any PoE standard and requests power higher than a standard power limit.
	$\label{eq:Pre-802.3bt} \textbf{t} - the Switch offers power on the port according to the IEEE 802.3bt standard. Select this option if the connected PD was developed before the IEEE 802.3bt standard is implemented but requires power between 33 W and 60 W. IEEE 802.3bt is also known as PoE++ or PoE Plus Plus.$
	802.3bt – the Switch supports the IEEE 802.3bt standard and can supply power of up to 60 W per Ethernet port to the connected PDs at power-up.
Max Power (mW)	Specify the maximum amount of power the PD could use from the Switch on this port. If you leave this field blank, the Switch refers to the standard or default maximum power for each class.
LLDP Power Via MDI	Select this to have the Switch negotiate PoE power with the PD connected to the port by transmitting LLDP Power Via MDI TLV frames. This helps the Switch allocate less power to the PD on this port. The connected PD must be able to request PoE power through LLDP.
	The Power Via MDI TLV allows PoE devices to advertise and discover the MDI power support capabilities of the sending port on the remote device.
	<ul> <li>Port Class</li> <li>MDI Supported</li> <li>MDI Enabled</li> <li>Pair Controllable</li> <li>PSE Power Pairs</li> <li>Power Class</li> </ul>
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click <b>Cancel</b> to begin configuring this screen afresh.

 Table 338
 Port > PoE Setup > PoE Setup (continued)

# 79.24 Port Setup

Use this screen to configure Switch port settings. Click **PORT** > **Port Setup** in the navigation panel to display the configuration screen.

Figure 436 PORT > Port Setup

900 - E	Active	Nate	Special	apres.	Box Control	30.00 90.006	88.00	98 -	1012030	1000
35	a (		2.16	শ	E ancie M	<u>0 v</u>	Pear	19	Sec. 1	- 24
			- A. I.S	w	Exactle w	U.V.	Principal Street		8:11	2
			Aclo	<u></u>	Charle v	ψv	Pear	¥.	8.00	-3
£	8 (		2. lo	<u>~</u>	Couple v	.Q.v.	PV-1	•	8-12	- 2
<b>8</b> 5				<u>~</u>	Frank w	<u>. 10 ve</u>	PV-2	×.	811	2
¥ .	8		<u>A44</u>	<u> </u>	k  dd w  d v	<u> </u>	NV.	<u>×</u>	9-++	- 2
£1	<b>Ø</b>		0.05	(w)	<u>0.000</u> v	<u>0 v</u>	$ \mathbf{P}_{\mathbf{x}_{n}} $	×.	Serie .	- 3
4			1.1.	-	Problem!	M	M	×.	4	
				<u> </u>		0.4	1%41		1350	-

The following table describes the labels in this screen.

Table 339	PORT > Port Setup
10010 007	

IABEL	DESC RIPIIO N						
Port	This is the port index number.						
*	Settings in this row apply to all ports. Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis. Note: Changes in this row are copied to all the ports as soon as you make them.						
Active	Select this check box to enable a port. The factory default for all ports is enabled. A port must be enabled for data transmission to occur.						
Name	Type a descriptive name that identifies this port. You can enter up to 128 printable ASCII characters except [?], [   ], ['] or ["]. Note: Due to space limitations, the port name may be truncated in some Web Configurator screens.						

IABEL	DESC RIPHO N
Speed/Duplex	Select the speed and the duplex mode of the Ethernet connection on this port. The choices are <b>Auto</b> , <b>Auto</b> -1G, 10-an (10M/auto-negotiation), <b>10M</b> / <b>Full Duplex</b> , <b>100-an</b> (100M/auto-negotiation), <b>2.5G</b> / <b>Full Duplex</b> , <b>5G</b> / <b>Full Duplex</b> , and <b>100M</b> / <b>Full Duplex</b> for a 100Base-T connection. <b>1G</b> / <b>Full Duplex</b> is supported by both 1000Base-T and 1000Base-X connections. <b>10G</b> / <b>Full Duplex</b> is supported by the 10 Gigabit Ethernet connections on the Switch that has a 10 Gigabit interface.
	Selecting <b>Auto-1G</b> or <b>Auto</b> (auto-negotiation) allows one port to negotiate with a peer port automatically to obtain the connection speed and duplex mode that both ends support. When auto-negotiation is turned on, a port on the Switch negotiates with the peer automatically to determine the connection speed and duplex mode. If the peer port does not support auto- negotiation or turns off this feature, the Switch determines the connection speed by detecting the signal on the cable and using half duplex mode. When the Switch's auto-negotiation is turned off, a port uses the pre-configured speed and duplex mode when making a connection, thus requiring you to make sure that the settings of the peer port are the same in order to connect.
Flow Control	A concentration of traffic on a port decreases port bandwidth and overflows buffer memory causing packet discards and frame losses. <b>Flow Control</b> is used to regulate transmission of signals to match the bandwidth of the receiving port.
	The Switch uses IEEE 802.3x flow control in full duplex mode and backpressure flow control in half duplex mode.
	IEEE 802.3x flow control is used in full duplex mode to send a pause signal to the sending port, causing it to temporarily stop sending signals when the receiving port memory buffers fill.
	Back Pressure flow control is typically used in half duplex mode to send a "collision" signal to the sending port (mimicking a state of packet collision) causing the sending port to temporarily stop sending signals and resend later.
	Select <b>Tx Rx</b> to allow the Switch port to send pause signal to the connected device, and for the connected device to send a pause signal to the Switch. The Switch will temporarily stop sending signals after receiving pause signal.
	Select $\mathbf{T}_{\mathbf{k}}$ to allow the Switch port to send pause signal to the connected device.
	Select $\mathbf{R}_{\mathbf{x}}$ to allow the connected device to send a pause signal to the Switch. The Switch will temporarily stop sending signals.
	Otherwise, select <b>Disa ble</b> .
802.1p Priority	This priority value is added to incoming frames without a (802.1p) tag.
BPDU Ctrl	Configure the way to treat BPDUs received on this port. You must activate <b>Bridging Control</b> <b>Protocol Thansparency</b> in the <b>SYSTEM &gt; Switch Setup</b> screen first.
	Select $\mathbf{Peer}$ to process any BPDU (Bridge Protocol Data Units) received on this port.
	Select Tunnel to forward BPDUs received on this port.
	Select <b>Disc and</b> to drop any BPDU received on this port.
	Select <b>Network</b> to process a BPDU with no VLAN tag and forward a tagged BPDU.
Media Type	You can insert either an SFP+ transceiver or an SFP+ Direct Attach Copper (DAC) cable into the 10 Gigabit interface of the Switch.
	Select the media type (SFP+ or $DAC10G$ ) of the SFP+ module that is attached to the 10 Gigabit interface.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

 Table 339
 PORT > Port Setup (continued)

### 79.25 SWIICHING

The following sections introduce the SWITCHING screens.

### 79.26 Port Mirroring

Port mirroring allows you to copy a traffic flow to a monitor port (the port you copy the traffic to) in order that you can examine the traffic from the monitor port without interference.

Click SWITCHING > Mimoring in the navigation panel to display the Mimoring screen. Use this screen to select a monitor port and specify the traffic flow to be copied to the monitor port.

**Minoring** Addiete **Vioritor** Fort Forti. **Meriored** Developer ÷ E (246) V mpress st Ingeness M. ð. Û. Ingrass M. 4. Increases. ÷, Incide M 5 Ingroup M ÷. ing too M Acably Council

Figure 437 SWITCHING > Mirroring

The following table describes the labels in this screen.

Table 340 SWITCHING > Mirroring

IABEL	DESC RIPIIO N								
Active	Enable the switch button to activate port mirroring on the Switch. Disable the switch to disable the feature.								
Monitor Port	The monitor port is the port you copy the traffic to in order to examine it in more detail without interfering with the traffic flow on the original ports. Enter the port number of the monitor port.								
Port	This field displays the port number.								
*	Settings in this row apply to all ports. Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis. Note: Changes in this row are copied to all the ports as soon as you make them.								

XGS2220 Series User's Guide

IABEL	DESC RIPTIO N
Mirrored	Select this option to mirror the traffic on a port.
Direction	Specify the direction of the traffic to mirror by selecting from the drop-down list box. Choices are <b>Fgress</b> (outgoing), <b>Ingress</b> (incoming) and <b>Both</b> .
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to reset the fields.

Table 340 SWITCHING > Mirroring (continued)

### 79.27 Multicast

Traditionally, IP packets are transmitted in one of either two ways – Unicast (1 sender to 1 recipient) or Broadcast (1 sender to everybody on the network). Multicast delivers IP packets to just a group of hosts on the network.

IGMP (Internet Group Management Protocol) is a network-layer protocol used to establish membership in a multicast group – it is not used to carry user data. Refer to RFC 1112, RFC 2236 and RFC 3376 for information on IGMP versions 1, 2 and 3 respectively.

This section shows you how to configure various multicast features.

#### 79.27.1 What You Can Do

- Use the IPv4 Multic a st Status screen (Section 79.28 on page 589) to view multicast group information.
- Use the IGMP Snooping screen (Section 79.29 on page 590) to enable IGMP snooping to forward group multicast traffic only to ports that are members of that group.
- Use the IGMP Snooping VIAN screen (Section 79.30 on page 594) to perform IGMP snooping on up to 16 VLANs.
- Use the IGMP Filtering Profile screen (Section 79.31 on page 596) to specify a range of multicast groups that clients connected to the Switch are able to join.

### 79.28 IPv4 Multic a st Sta tus

Click SWIIC HING > Multic a st > IPv4 Multic a st Status to display the screen as shown. This screen shows the IPv4 multicast group information.

If v4 Multicost Stolu	IGMP Snooping	IGMP Snooping VLA	an l
Index	V10	Pat	Nutional Group
	I	18	224.000.291
2	I.	16	224100.252
1	I.	16	2322xx2552%)

Figure 438 SWITCHING > Multicast > IPv4 Multicast Status

IABEL	DESC RIPIIO N
Index	This is the index number of the entry.
VID	This field displays the multicast VLAN ID.
Port	This field displays the port number that belongs to the multicast group.
Multicast Group	This field displays IP multicast group addresses.

Table 341 SWITCHING > Multicast > IPv4 Multicast Status

## 79.29 IGMP Snooping

A Switch can passively snoop on IGMP packets transferred between IP multicast routers or switches and IP multicast hosts to learn the IP multicast group membership. It checks IGMP packets passing through it, picks out the group registration information, and configures multicasting accordingly. IGMP snooping allows the Switch to learn multicast groups without you having to manually configure them.

The Switch forwards multicast traffic destined for multicast groups (that it has learned from IGMP snooping or that you have manually configured) to ports that are members of that group. IGMP snooping generates no additional network traffic, allowing you to significantly reduce multicast traffic passing through your Switch.

Click SWIICHING > Multic ast > IGMP Snooping to display the screen as shown.

94 Wull	licast Status	1	CMP Shoo	ping	IGM7 S	nooping	VLAN 3	GWZ Filtering	Profile	
292				- 23	Isue					
00.00				1	1					
Stelen V	Hindows -			Ť	d 🔍					
(0,0,1)	197			E						
South trivial		- 6	80.	1015275	ь					
oz apieł	adq			-1	$k < m < p < \infty$					
ALK HE	n y Astron			1	FUE					
sur inc	a de la Constitu	National de la constante de la Constante de la constante de la Constante de la constante de la	CARRA .	1	04 0					
ek hour.	k. React have	2		1	Densery -	Elbers.	66	1.59 MU 7.201		
the star	Notices non	e Herev	51.65676970	- 22		Citered	ens de	awa di tu Grist	<i>16</i>	
	Nultical Stat	1.000	1020230054	1.1		0.0065	599864 - 1044666 -	0.00000000000000	eas:1	
		-		-9						
Port	Intrackte Legyw	Nort	vol Leone	ř	et la enva	Group United	Max Group Number	Theoffing	IGW/ Elliving Profile	IGNE Guerie Node
36	10	0	E 18	ő	1			Der: v	(Debp) s	Allow
11	0.1	0	40.5	10	200	0	1	Dervery	Derson y	d work
$\sim$	0	0	24.	10	201	tt		Der v	(Celouri	ALION
5	101	0	46.	10	-20	1.1	1	Den y	Louisen -	- Autoral
4	0	0	Acre 1	0	22		+ 1	Deter v	2 should be	Autors
12	a	0	100	18	200	Ö.	12	De - ×	iteran -	- Sige
16	-D.	0	3222.	0	2%	Ð	10 I.	Dec	(0.000)	- Salary
4		0	4532	10	77.	0	13 j	U. y	r.full	المراجع (-
						$\sim$		$\sim$		<u>A.12-</u>
					-			~	0.0	

Figure 439 SWITCHING > Multicast > IGMP Snooping

The following table describes the labels in this screen.

#### Table 342 SWITCHING > Multicast > IGMP Snooping

IABEL	DESC RIPTIO N
Active	Enable the switch button to enable IGMP Snooping to forward group multicast traffic only to ports that are members of that group.
Querier	Select this to allow the Switch to send IGMP General Query messages to the VLANs with the multicast hosts attached.
Querier Version	IGMP snooping query works only when both host and Switch support the same IGMP version.
	Select $\mathbf{v2}$ to allow the Switch to send IGMPv2 queries only.
	Select $\mathbf{v3}$ to allow the Switch to send IGMPv3 queries only.

IABEL	DESC RIPTIO N
Report Proxy	Select this to allow the Switch to act as the IGMP report proxy and leave proxy. It will report group changes to a connected multicast router.
	The Switch not only checks IGMP packets between multicast routers or switches and multicast hosts to learn the multicast group membership, but also replaces the source MAC address in an IGMP $v1/v2$ report with its own MAC address before forwarding to the multicast router or switch. When the Switch receives more than one IGMP $v1/v2$ join report that requests to join the same multicast group, it only sends a new join report with its MAC address. This helps reduce the number of multicast join reports passed to the multicast router or switch.
	The Switch sends a leave message with its MAC address to the multicast router or switch only when it receives the leave message from the last host in a multicast group.
Host Timeout	Specify the time (from 1 to 16711450) in seconds that elapses before the Switch removes an IGMP group membership entry if it does not receive report messages from the port.
802.1p Priority	Select a priority level (0 – 7) to which the Switch changes the priority in outgoing IGMP control packets. Otherwise, select <b>No-Change</b> to not replace the priority.
IGMP Filtering Active	Enable the switch button to enable IGMP filtering to control which IGMP groups a subscriber on a port can join.
	If you enable IGMP filtering, you must create and assign IGMP filtering profiles for the ports that you want to allow to join multicast groups.
IGMP Snooping Smart Forward Active	Enable the switch button to enable sending of multicast frame to querier port and IGMP subscriber groups. Otherwise, the querier port forwards the frames only when it receives a join report and it belongs to the IGMP group.
Unknown Multicast Frame	<ul> <li>Specify the action to perform when the Switch receives an unknown multicast frame.</li> <li>Select <b>Flooding</b> to send the frames to all ports.</li> <li>Select <b>Drop</b> to discard the frames.</li> <li>Select <b>Drop</b> on <b>VIAN</b> and enter the VLAN ID numbers to discard the frames on the specified VLANs. Use a dash to specify consecutive VLANs and a comma (no spaces) to specify non-consecutive VLANs. For example, 51–53 includes 51, 52 and 53, but 51,53 does not include 52.</li> </ul>
Unknown Multicast Frame to Querier Port	<ul> <li>Specify the action to perform when Unknown Multic ast Frame is set to Drop.</li> <li>Select Drop to discard the frames.</li> <li>Select Forwarding to send the frames to all querier ports.</li> <li>Select Forwarding on VIAN and enter the VLAN ID numbers to send the frames to the ports which are used as an IGMP query port on the specified VLANs. Use a dash to specify consecutive VLANs and a comma (no spaces) to specify non-consecutive VLANs. For example, 51–53 includes 51, 52 and 53, but 51,53 does not include 52.</li> </ul>
Reserved Multicast Group	The IP address range of 224.0.0.0 to 224.0.0.255 are reserved for multicasting on the local network only. For example, 224.0.0.1 is for all hosts on a local network segment and 224.0.0.9 is used to send RIP routing information to all RIP v2 routers on the same network segment. A multicast router will not forward a packet with the destination IP address within this range to other networks. See the IANA web site for more information.
	The layer-2 multicast MAC addresses used by Cisco layer-2 protocols, 01:00:0C:CC:CC:CC and 01:00:0C:CC:CC:CD, are also included in this group.
	Specify the action to perform when the Switch receives a frame with a reserved multicast address.
	<ul> <li>Select <b>Flooding</b> to send the frames to all ports.</li> <li>Select <b>Drop</b> to discard the frames.</li> </ul>
Use this section to c	onfigure IGMP Snooping on each port.
Port	This field displays the port number.

 Table 342
 SWITCHING > Multicast > IGMP Snooping (continued)

LABEL	DESC RIPTIO N
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Changes in this row are copied to all the ports as soon as you make them.
Immediate Leave	Select this option to set the Switch to remove this port from the multicast tree when an IGMP version 2 leave message is received on this port.
	Select this option if there is only one host connected to this port.
Normal Leave	Enter an IGMP normal leave timeout value (from 200 to 6348800) in miliseconds. Select this option to have the Switch use this timeout to update the forwarding table for the port.
	In normal leave mode, when the Switch receives an IGMP leave message from a host on a port, it forwards the message to the multicast router. The multicast router then sends out an IGMP Group-Specific Query (GSQ) message to determine whether other hosts connected to the port should remain in the specific multicast group. The Switch forwards the query message to all hosts connected to the port and waits for IGMP reports from hosts to update the forwarding table.
	This defines how many seconds the Switch waits for an IGMP report before removing an IGMP snooping membership entry when an IGMP leave message is received on this port from a host.
Fast Leave	Enter an IGMP fast leave timeout value (from 200 to 6348800) in miliseconds. Select this option to have the Switch use this timeout to update the forwarding table for the port.
	In fast leave mode, right after receiving an IGMP leave message from a host on a port, the Switch itself sends out an IGMP Group-Specific Query (GSQ) message to determine whether other hosts connected to the port should remain in the specific multicast group. This helps speed up the leave process.
	This defines how many seconds the Switch waits for an IGMP report before removing an IGMP snooping membership entry when an IGMP leave message is received on this port from a host.
Group Limited	Select this option to limit the number of multicast groups this port is allowed to join.
Max Group Number	Enter the number of multicast groups this port is allowed to join. Once a port is registered in the specified number of multicast groups, any new IGMP join report frames is dropped on this port.
Throttling	IGMP throttling controls how the Switch deals with the IGMP reports when the maximum number of the IGMP groups a port can join is reached.
	Select <b>Deny</b> to drop any new IGMP join report received on this port until an existing multicast forwarding table entry is aged out.
	Select $\operatorname{Replace}$ to replace an existing entry in the multicast forwarding table with the new IGMP reports received on this port.
IGMP Filtering Profile	Select the name of the IGMP filtering profile to use for this port. Otherwise, select <b>De fa ult</b> to prohibit the port from joining any multicast group.
	You can create IGMP filtering profiles in the <b>SWIICHING &gt; Multic a st &gt; IGMP Filtering Profile</b> screen.

#### Table 342 SWITCHING > Multicast > IGMP Snooping (continued)

IABEL	DESC RIPIIO N
IGMP Querier Mode	The Switch treats an IGMP query port as being connected to an IGMP multicast router (or server). The Switch forwards IGMP join or leave packets to an IGMP query port.
	Select $Auto$ to have the Switch use the port as an IGMP query port if the port receives IGMP query packets.
	Select <b>Fixed</b> to have the Switch always use the port as an IGMP query port. Select this when you connect an IGMP multicast server to the port.
	Select <b>Edge</b> to stop the Switch from using the port as an IGMP query port. The Switch will not keep any record of an IGMP router being connected to this port. The Switch does not forward IGMP join or leave packets to this port.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click <b>Cancel</b> to begin configuring this screen afresh.

Table 342 SWITCHING > Multicast > IGMP Snooping (continued)

# 79.30 IGMP Snooping VIAN

You can configure the Switch to automatically learn multicast group membership of any VLANs. The Switch then performs IGMP snooping on the first 16 VLANs that send IGMP packets. This is referred to as auto mode. Alternatively, you can specify the VLANs that IGMP snooping should be performed on. This is referred to as fixed mode. In fixed mode the Switch does not learn multicast group membership of any VLANs other than those explicitly added as an IGMP snooping VLAN.

Click SWIICHING > Multic a st > IG MP Snooping VIAN to display the screen as shown.

Note: You can perform IGMP snooping on up to 16 VLANs.

Pv4 Mollic	asl Status	IGMP Snooping	IGMP Snooping VLAN	IGMP Fillering In-	file
IGME Sno	oping VIAN				
Vade	<b>O a</b> to	() Anns	ank Council		
VLAN					
VLAN				Q Aquildi 👔	NHW:
VLAN	listes	Nette	VIU	Q Aculat 📳	nt w

Figure 440 SWITCHING > Multicast > IGMP Snooping VLAN

594

Table 343	SWITCHING >	Multicast >	IGMP Snoopin	
	30011C11110 /	Monicusi -		9

IABEL	DESC RIPTIO N			
IGMP Snooping	y VLAN			
Mode	Select <b>auto</b> to have the Switch learn multicast group membership information of any VLANs automatically.			
	Select $\mathbf{fixed}$ to have the Switch only learn multicast group membership information of the VLANs that you specify below.			
	In either <b>auto</b> or <b>fixed</b> mode, the Switch can learn up to 16 VLANs.			
	The Switch drops any IGMP control messages which do not belong to these 16 VLANs.			
	You must also enable IGMP snooping in the <b>SWIIC HING</b> > <b>Multic a st</b> > <b>IGMP Snooping</b> screen first.			
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.			
Cancel	Click Cancel to begin configuring this screen afresh.			
VLAN	·			
Use this section	of the screen to add VLANs on which the Switch is to perform IGMP snooping.			
Index	This is the index number of the IGMP snooping VLAN entry in the table.			
Name	This field displays the descriptive name for this VLAN group.			
VID	This field displays the ID number of the VLAN group.			
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.			
Add/Edit	Click Add/Edit to create a new entry or edit a selected one.			
Delete	Click <b>De le te</b> to remove the selected entries.			

### 79.30.1 Add/Edit IGMP Snooping VIANs

This screen allows you to add an IGMP snooping VLAN or edit an existing one.

To access this screen, click the Add/Edit button or select an entry from the list and click the Add/Edit button.

Namo		
VI.1		
Αφρίγ	Glear	Ganoel

Figure 441 SWITCHING > Multicast > IGMP Snooping VLAN > Add/Edit

IABEL	DESC RIPTIO N
Name	Enter the descriptive name (up to 32 printable ASCII characters except [ ? ], [   ], [ ' ], [ " ] or [ , ]) of the VLAN for identification purposes.
VID	Enter the ID of a static VLAN; the valid range is between 1 and 4094.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

Table 344 SWITCHING > Multicast > IGMP Snooping VLAN > Add/Edit

## 79.31 IG MP Filtering Profile

An IGMP filtering profile specifies a range of multicast groups that clients connected to the Switch are able to join. A profile contains a range of multicast IP addresses which you want clients to be able to join. Profiles are assigned to ports (in the SWITCHING > Multicast > IGMP Snooping screen). Clients connected to those ports are then able to join the multicast groups specified in the profile. Each port can be assigned a single profile. A profile can be assigned to multiple ports.

Click SWIIC HING > Multic a st > IG MP Filte ring Profile link to display the screen as shown.

Py4 Molfice	st Status	IGMP Snooping	IGMP Snooping VLAN	IGMP Filte	ring Profile
			O Ado Profila	0 Ark: 3.6	Collect-
	Froile (	lame	Stort address	End	Address
	i Defe	x-1			
			0,0,0		0.0 <mark>0</mark>
	000	<b>2</b>			(1999) 
17			222 200	21	1000
E1			525-0000	200	226.00

Figure 442 SWITCHING > Multicast > IGMP Filtering Profile

The following table describes the labels in this screen.

IABEL	DESC RIPIIO N	
Profile Name	This field displays the descriptive name of the profile.	
Start Address	This field displays the start of the multicast address range.	
End Address	This field displays the end of the multicast address range.	
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.	
Add Profile	Click this to add a new IGMP filtering profile.	

Table 345 SWITCHING > Multicast> IGMP Filtering Profile

IABEL	DESC RIPTIO N
Add Rule	Click Add Rule to add a new rule and specify the profile it belongs to in the Add Rule screen.
	You can also select a profile entry and click <b>Add Rule</b> to add an additional rule for the selected profile.
Delete	Select a profile and click $\mathbf{De}  \mathbf{le}  \mathbf{te}$ to remove the selected profile and the accompanying rules.
	Select a rule from a profile and click $\mathbf{De}  \mathbf{le}  \mathbf{te}$ to remove the selected rule.

Table 345 SWITCHING > Multicast> IGMP Filtering Profile (continued)

### 79.31.1 Add IGMP Filtering Profile

To access this screen, click the Add Profile button in the SWIICHING > Multic ast > IGMP Filtering Profile screen.

Figure 443 SWITCHING > Multicast > IGMP Filtering Profile > Add Profile

hori Address	924.000	0	
and Address	224.0.0	224.0.0.0	
Add/FdB	Clear	Concel	

The following table describes the labels in this screen.

Table 346	SWITCHING > Multicas	i > IGMP Filtering	Profile > Add Profile
-----------	----------------------	--------------------	-----------------------

LABEL	DESC RIPIIO N
Profile Name	Enter a descriptive name for the profile for identification purposes. You can enter up to 32 printable ASCII characters except [?], [   ], [ ' ], [ "] or [, ].
Start Address	Type the starting multicast IP address for a range of multicast IP addresses that you want to belong to the IGMP filter profile.
End Address	Type the ending multicast IP address for a range of IP addresses that you want to belong to the IGMP filter profile. If you want to add a single multicast IP address, enter it in both the <b>Start Address</b> and <b>End Address</b> fields.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

### 79.31.2 Add IGMP Filtering Rule

Click Add Rule in the SWIICHING > Multicast > IGMP Filtering Profile screen to access this screen.

Figure 444 SWITCHING > Multicast > IGMP Filtering Profile > Add Rule

Profile Nome	rollet	$\sim$
Shert Address	224.0.0.0	
Ind Address	924.0.0.0	
Add/Edit	Clear	Geneel

The following table describes the labels in this screen.

Table 347 SWITCHING > Multicast > IGMP Filtering Profile > Add Rule

LABEL	DESC RIPTIO N
Profile Name	Select a profile from the drop-down list to add a additional rule for the existing profile.
Start Address	Type the starting multicast IP address for a range of multicast IP addresses that you want to belong to the IGMP filter profile.
End Address	Type the ending multicast IP address for a range of IP addresses that you want to belong to the IGMP filter profile. If you want to add a single multicast IP address, enter it in both the <b>Start Address</b> and <b>End Address</b> fields.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click <b>Clear</b> to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

## 79.32 VIAN


This section shows you how to configure 802.1Q tagged and port-based VLANs.

### 79.32.1 What You Can Do

- Use the VIAN Status screen (Section 79.33 on page 601) to view and search all static VLAN groups.
- Use the VIAN Detail screen (Section 79.33.1 on page 602) to view detailed port settings and status of the static VLAN group.
- Use the Static VIAN screen (Section 79.34 on page 603) to configure a static VLAN for the Switch.
- Use the VIAN Port Setup screen (Section 79.35 on page 605) to configure the static VLAN (IEEE 802.1Q) settings on a port.

### 79.32.2 What You Need to Know

Read this section to know more about VLAN and how to configure the screens.



#### Figure 445 Shared Server Using VLAN Example

#### IEEE 802.1Q Tagged VIANs


A tagged VLAN uses an explicit tag (VLAN ID) in the MAC header to identify the VLAN membership of a frame across bridges – they are not confined to the switch on which they were created. The VLANs can be created statically by hand dynamically through GVRP. The VLAN ID associates a frame with a specific VLAN and provides the information that switches need to process the frame across the network. A tagged frame is 4 bytes longer than an untagged frame and contains 2 bytes of TPID (Tag Protocol Identifier, residing within the type or length field of the Ethernet frame) and 2 bytes of TCI (Tag Control Information, starts after the source address field of the Ethernet frame).

The CFI (Canonical Format Indicator) is a single-bit flag, always set to zero for Ethernet switches. If a frame received at an Ethernet port has a CFI set to 1, then that frame should not be forwarded as it is to an untagged port. The remaining twelve bits define the VLAN ID, giving a possible maximum number of 4,096 VLANs. Note that user priority and VLAN ID are independent of each other. A frame with VID (VLAN Identifier) of null (0) is called a priority frame, meaning that only the priority level is significant and the default VID of the ingress port is given as the VID of the frame. Of the 4,096 possible VIDs, a VID of 0 is used to identify priority frames and value 4095 (FFF) is reserved, so the maximum possible VLAN configurations are 4,094.

TPID	User Priority	CFI	VLAN ID
2 Bytes	3 Bits	1 Bit	12 bits

#### Forwarding Tagged and Untagged Frames

Each port on the Switch is capable of passing tagged or untagged frames. To forward a frame from an 802.1Q VLAN-aware switch to an 802.1Q VLAN-unaware switch, the Switch first decides where to forward the frame and then strips off the VLAN tag. To forward a frame from an 802.1Q VLAN-unaware switch to an 802.1Q VLAN-aware switch, the Switch first decides where to forward the frame, and then inserts a VLAN tag reflecting the ingress port's default VID. The default PVID is VLAN 1 for all ports, but this can be changed.



A broadcast frame (or a multicast frame for a multicast group that is known by the system) is duplicated only on ports that are members of the VID (except the ingress port itself), thus confining the broadcast to a specific domain.

#### 79.32.2.1 Automatic VIAN Registration

GARP and GVRP are the protocols used to automatically register VLAN membership across switches.

#### GARP

GARP (Generic Attribute Registration Protocol) allows network switches to register and de-register attribute values with other GARP participants within a bridged LAN. GARP is a protocol that provides a generic mechanism for protocols that serve a more specific application, for example, GVRP.

#### GARP Timers

Switches join VLANs by making a declaration. A declaration is made by issuing a Join message using GARP. Declarations are withdrawn by issuing a Leave message. A Leave All message terminates all registrations. GARP timers set declaration timeout values.

#### GVRP

GVRP (GARP VLAN Registration Protocol) is a registration protocol that defines a way for switches to register necessary VLAN members on ports across the network. Enable this function to permit VLAN groups beyond the local Switch.

Please refer to the following table for common IEEE 802.1Q VLAN terminology.

VIAN PARAMEIER	TERM	DESC RIPIIO N		
VLAN Type	Permanent VLAN	This is a static VLAN created manually.		
	Dynamic VLAN	This is a VLAN configured by a GVRP registration or de-registration process.		
VLAN Administrative	Registration Fixed	Fixed registration ports are permanent VLAN members.		
Control	Registration Forbidden	Ports with registration forbidden are forbidden to join the specified VLAN.		
	Normal Registration	Ports dynamically join a VLAN using GVRP.		

Table 348 IEEE 802.1Q VLAN Terminology


VIAN PARAMEIER	TERM	DESC RIPTIO N		
VLAN Tag Control	Tagged	Ports belonging to the specified VLAN tag all outgoing frames transmitted.		
	Untagged	Ports belonging to the specified VLAN do not tag all outgoing frames transmitted.		
VLAN Port	Port VID	This is the VLAN ID assigned to untagged frames that this port received.		
	Acceptable Frame Type	You may choose to accept both tagged and untagged incoming frames, just tagged incoming frames or just untagged incoming frames on a port.		
	Ingress filtering	If set, the Switch discards incoming frames for VLANs that do not have this port as a member.		

Table 348 IEEE 802.1Q VLAN Terminology (continued)

#### 79.32.2.2 Port VIAN Trunking

Enable **VIAN Thunking** on a port to allow frames belonging to unknown VLAN groups to pass through that port. This is useful if you want to set up VLAN groups on end devices without having to configure the same VLAN groups on intermediary devices.

Refer to the following figure. Suppose you want to create VLAN groups 1 and 2 (V1 and V2) on devices A and B. Without **VIAN Thunking**, you must configure VLAN groups 1 and 2 on all intermediary switches C, D and E; otherwise they will drop frames with unknown VLAN group tags. However, with **VIAN Thunking** enabled on ports in each intermediary switch you only need to create VLAN groups in the end devices (A and B). C, D and E automatically allow frames with VLAN group tags 1 and 2 (VLAN groups that are unknown to those switches) to pass through their VLAN trunking ports.



## 79.33 VIAN Status

Use this screen to view and search all static VLAN groups. Click **SWIICHING** > **VIAN** > **VIAN** Status from the navigation panel to display the screen as shown next.

Figure 448	SWITCHING >	VLAN >	<b>VLAN Status</b>
------------	-------------	--------	--------------------

Whi Slatve 2	RAIN SHE	VL/04 7 ort Setup				
4048 <mark>803</mark> 10.42	1	1000				
The Sheeber of a	ize il					
1.22	VID	Ter al	Fagger Roll	il segurited	Bigard's a	0.850 0.02 2060
a sec	ian I	ta a	Lapport In 1	8 agailed	Bigand'e a Ruide	11.855) <u>1</u>
****	708 1	tara ⊥ ∔	Lagger Fol			auto.
# 14 m	- 62	жена 1 1 1	toggen (s. ) 1		P., 50	3 4 4 5

Table 349 SWITCHING > VLAN > VLAN Status

IABEL	DESC RIPTIO N
VLAN Search by VID	Enter (an) existing VLAN ID numbers (use a comma (,) to separate individual VLANs or a hyphen (-) to indicate a range of VLANs. For example, " $3,4$ " or " $3-9$ ") and click <b>Search</b> to display only the specified VLANs in the list below.
	Leave this field blank and click $\operatorname{Searc} h$ to display all VLANs configured on the Switch.
The Number of VLAN	This is the number of VLANs configured on the Switch.
The Number of	This is the number of VLANs that match the searching criteria and display in the list below.
Search Results	This field displays only when you use the $\operatorname{Searc} h$ button to look for certain VLANs.
Index	This is the VLAN index number. Click an index number to view more VLAN details.
VID	This is the VLAN identification number that was configured in the corresponding VLAN configuration screen.
Name	This fields shows the descriptive name of the VLAN.
Tagged Port	This field shows the tagged ports that are participating in the VLAN.
Untagged Port	This field shows the untagged ports that are participating in the VLAN.
Elapsed Time	This field shows how long it has been since a normal VLAN was registered or a static VLAN was set up.
Status	This field shows how this VLAN was added to the Switch.
	• Dynamic – using GVRP
	• Static – added as a permanent VLAN

### 79.33.1 VLAN De tails

Use this screen to view detailed port settings and status of the static VLAN group. Click an index number in the **VLAN Status** screen to display VLAN details.

/LAN Ston	OR .		tan c	VLA.		VI.	1000	Port 2	10.000																
# ANSIN	aler,		61		est (H																				
MD.				13																					
Depart In	999			85	G = G	9																			
aulo:				- 22	$(d_{2})$																				
Fort Numi	itan er																				10.0	n vg	geo:	infe:	2.9
Port Numi	Coer e		<u>98</u>	12	14	16	16	20	**	24	24	20	30	22	34	26	35	42	42	44	-010 -44	n vy	940 50	1/v S2	
		1		15			10 12	20 17	92 71	24 13	24 24	20 27	30 29	22 81	34 33	15 38	35 37	41	45 43		00 44 58	16036	_		54
	10	1 2 1	10 	1	14	16	12		100	- E ) ;				22 41				38 C.	20 - E	44	- 010 - 44	40 40	50	52	54 40

Table 350 SWITCHING > VLAN > VLAN Status > VLAN Status Details

LABEL	DESC RIPTIO N
VID	This is the VLAN identification number that was configured in the corresponding VLAN configuration screen.
Elapsed Time	This field shows how long it has been since a normal VLAN was registered or a static VLAN was set up.
Status	This field shows how this VLAN was added to the Switch.
	<ul> <li>Dynamic: using GVRP</li> <li>Static: added as a permanent entry</li> </ul>
Port Number	This section displays the ports that are participating in a VLAN. A tagged port is marked as $\mathbf{T}$ an untagged port is marked as $\mathbf{U}$ and ports not participating in a VLAN are marked as "-".

# 79.34 Configure a Static VIAN

Use a static VLAN to decide whether an incoming frame on a port should be

- sent to a VLAN group as normal depending on its VLAN tag.
- sent to a group whether it has a VLAN tag or not.
- blocked from a VLAN group regardless of its VLAN tag.

You can also tag all outgoing frames (that were previously untagged) from a port with the specified VID.

Use this screen to view and configure a static VLAN for the Switch. Click **SWIICHING** > **VIAN** > **Static VIAN** to display the screen as shown next.

/LAN Status	Static VLAN	VLAN Port Setup			
				🗘 Acci/Coli	🔮 De ste
	¥10	Active	Norm		
D		6	1.)		
11	2.5	( 199 ) I	D.)		
8	A	(	2		
0	100	(	91409100		

Figure 450 SWITCHING > VLAN > Static VLAN

Table 351 SWITCHING > VLAN > Static VLAN

IABEL	DESC RIPTIO N
VID	This field displays the ID number of the VLAN group.
Active	This field indicates whether the VLAN settings are enabled or disabled.
Name	This field displays the descriptive name for this VLAN group.
	Select an entry's check box to select a specific entry. Otherwise, select the check box in the table heading row to select all entries.
Add/Edit	Click Add/Edit to add a new static VLAN or edit a selected one.
Delete	Click <b>Delete</b> to remove the selected static VLAN.

#### 79.34.1 Add/Edit a Static VIAN

Use this screen to configure a static VLAN for the Switch. Click Add/Edit, or select an entry and click Add/Edit in the SWITCHING > VLAN > Static VLAN screen to display this screen.

Figure 451 SWITHCING > VLAN > Static VLAN > Add/Edit

anto				
LAN CO	arp (C			
Fot -		Control		Toosing
(a)		[Korpol y]		📓 Iv Tona be
)	ONerricat	Citized	Chostdae	🛃 la loggi (a.
2	O Normal	Diteri	Of noticiden	📓 De Faca ha
3	O Hormal	Diffeod	C Fk (siddon	🖾 Tel Tel gla na
4	Obtance	Ottesi	Cheolad-e	🗱 ta baggine
5	ONerrick	Difeto	Offersididen	📓 în Tragano
ð.	Orioma	() Face:	Repidsen	🖾 DeTes o no
	Offerred	CLP SHIT	C tookiden	ta leggere
~	· · · · · · · · · · · · · · · · · · ·			

XGS2220 Series User's Guide

604

LABEL	DESC RIPTIO N
Active	Enable the switch button to activate the VLAN settings.
Name	Enter a descriptive name for the VLAN group for identification purposes. This name consists of up to 64 printable ASCII characters. The string should not contain [?], [ ], ['], ["] or [, ].
VLAN Group ID	Enter the VLAN ID for this static entry; the valid range is between 1 and 4094.
Port	The port number identifies the port you are configuring.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
Control	Select <b>Nomal</b> for the port to dynamically join this VLAN group using GVRP. This is the default selection.
	Select $\mathbf{Fixed}$ for the port to be a permanent member of this VLAN group.
	Select Forbidden if you want to prohibit the port from joining this VLAN group.
Tagging	Select <b>Tx Tagging</b> if you want the port to tag all outgoing frames transmitted with this VLAN Group ID.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Clear	Click Clear to clear the fields to the factory defaults.
Cancel	Click Cancel to not save the configuration you make and return to the last screen.

Table 352 SWITHCING > VLAN > Static VLAN > Add/Edit

# 79.35 VLAN Port Setup

Use this screen to configure the static VLAN (IEEE 802.1Q) settings on a port. Click **SWIICHING** > **VIAN** > **VIAN** Port Setup to display the screen as shown.

Figure 452 SWITCHING > VLAN > VLAN Port Setup

Set 1	Ingers Shows	P/10	Representative Protocol Types	Vie in the sking	Salaten (
+	- Q -	- 18 ki	(A) (A)	20	<b>A</b>
b.	( ( ) )	4	(A		1.1
÷	11		14 N		E.F.
ŝ.	0.00	<u>i                                     </u>	[4,		111
¥	- 11	<u> </u>	$ \mathbf{a}  =  \mathbf{v} $		ÉÉ
-	(1	<u>i                                     </u>	4		ET.
i i					0
1	0	- B		125	0
ý	ø	- 14 IV			0
ř.	G		<b>v</b>	100	0
* *	0	- 192 March 193		-	

Table 353	SWITCHING > VLAN > VLAN Port Setup
10010 000	

IABEL	DESC RIPIIO N
Port	This field displays the port number.
*	Settings in this row apply to all ports.
	Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis.
	Note: Changes in this row are copied to all the ports as soon as you make them.
Ingress Check	If this check box is selected, the Switch discards incoming frames on a port for VLANs that do not include this port in its member set.
	Clear this check box to disable ingress filtering.
PVID	A PVID (Port VLAN ID) is a tag that adds to incoming untagged frames received on a port so that the frames are forwarded to the VLAN group that the tag defines.
	Enter a number between 1 and 4094 as the port VLAN ID.
Acceptable	Specify the type of frames allowed on a port. Choices are All, Tag Only and Untag Only.
Frame Type	Select All from the drop-down list box to accept all untagged or tagged frames on this port. This is the default setting.
	Select $\operatorname{Tag} Only$ to accept only tagged frames on this port. All untagged frames will be dropped.
	Select <b>Untag Only</b> to accept only untagged frames on this port. All tagged frames will be dropped.
VLAN Trunking	Enable <b>VIAN Trunking</b> on ports connected to other switches or routers (but not ports directly connected to end users) to allow frames belonging to unknown VLAN groups to pass through the Switch.
Isolation	Select this to allows this port to communicate only with the CPU management port and the ports on which the isolation feature is NOT enabled.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

# 79.36 SEC URITY

The following sections introduce the SEC URITY screens.

## 79.37 Access Control

A console port and FTP are allowed one session each, Telnet and SSH share nine sessions, up to five Web sessions (five different user names and passwords) and/or limitless SNMP access control sessions are allowed.

Table 354 Access Control Overview

Console Port	SSH	Telnet	FTP	Web	SNMP
One session	Share up to 9 s	sessions	One session	Up to 5 accounts	No limit

XGS2220 Series User's Guide

A console port access control session and Telnet access control session cannot coexist when multi-login is disabled. See the CLI Reference Guide for more information on disabling multi-login.

This section describes how to control access to the Switch.

### 79.37.1 What You Can Do

- Use the Service Access Control screen (Section 79.38 on page 607) to decide what services you may use to access the Switch.
- Use the **Remote Management** screen (Section 79.39 on page 608) to specify a group of one or more "trusted computers" from which an administrator may use a service to manage the Switch.

### 79.38 Service Access Control

Service Access Control allows you to decide what services you may use to access the Switch. You may also change the default service port and configure "trusted computers" for each service in the **Remote Management** screen (discussed earlier). Click **SEC URITY** > **Access Control** > **Service Access Control** to view the screen as shown.

Services	Active	Service Fort	1	limeou)	tog	in Time out
Conside			5	of put to		
1and	CON CO	23	12	Moutes	18	locende
334	CON SO	2				
TTT:	00	21	(*	where a		
mn	(OH ())	114	1	- At-obs		
1 + 1/2	(99)	10 				
6.3/1*	COLO 1					
39038	(COHE)					

Figure 453 SECURITY > Access Control > Service Access Control

The following table describes the fields in this screen.

Table 355 SECURITY > Access Control > Service Access Control

LABEL	DESC RIPTIO N
Services	Services you may use to access the Switch are listed here.
Active	Enable the switch button for the corresponding services that you want to allow to access the Switch.

IABEL	DESC RIPTIO N
Service Port	For Telnet, SSH, FTP, HTTP or HTTPS services, you may change the default service port by typing the new port number in the <b>Service Port</b> field. If you change the default port number then you will have to let people (who wish to use the service) know the new port number for that service.
Timeout	Enter how many minutes (from 1 to 255) a management session can be left idle before the session times out. After it times out you have to log in with your password again. Very long idle timeouts may have security risks.
Login Timeout	The Telnet or SSH server do not allow multiple user logins at the same time. Enter how many seconds (from 30 to 300 seconds) a login session times out. After it times out you have to start the login session again. Very long login session timeouts may have security risks.
	For example, if User A attempts to connect to the Switch (through SSH), but during the login stage, do not enter the user name and/or password, User B cannot connect to the Switch (through SSH) before the <b>Login Timeout</b> for User A expires (default 150 seconds).
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

 Table 355
 SECURITY > Access Control > Service Access Control (continued)

# 79.39 Remote Management

Use this screen to specify a group of one or more "trusted computers" from which an administrator may use a service to manage the Switch.

Click SEC URITY > Access Control > Remote Management to view the screen as shown next.

Remote Management										
Secured C	lient Setup									
Entry	Active	Stort Address	End Address	Teinel	FTP	HTTP	ICMP	SNMP	55H	HTTPS
1	ON 🔘	0.0.00	0.0.0.0		15	w <sup>r</sup>	$\mathcal{A}^{\prime}$	d.	сř.	×
2	OOF	0.0.00	0.0.0.0							
э	Off )	0.0.00	0.0.0.0							
- 4	O OFF	0.0.00	0.0.0.0							
5	Off )	0.0.00	0.0.0.0							
6	O OFF	0.0.00	0.0.0.0							
7	Off )	0.0.00	0.0.0.0							
					$\sim$		$\sim$	0		
			A sector		-			-		
			Apply	Concel						

Table 356 SECURITY > Access Control > Remote Management

IABEL	DESC RIPTIO N
Entry	This is the client set index number. A "client set" is a group of one or more "trusted computers" from which an administrator may use a service to manage the Switch.
Active	Enable the switch button to activate this secured client set. Clear the check box if you wish to temporarily disable the set without deleting it.
Start Address	Configure the IP address range of trusted computers from which you can manage this Switch.
End Address	The Switch checks if the client IP address of a computer requesting a service or protocol matches the range set here. The Switch immediately disconnects the session if it does not match.
Telnet / FTP / HTTP / ICMP / SNMP / SSH / HTTPS	Select services that may be used for managing the Switch from the specified trusted computers.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to begin configuring this screen afresh.

## 79.40 Storm Control

Storm control limits the number of broadcast, multicast and destination lookup failure (DLF) packets the Switch receives per second on the ports. When the maximum number of allowable broadcast, multicast and/or DLF packets is reached per second, the subsequent packets are discarded. Enable this feature to reduce broadcast, multicast and/or DLF packets in your network. You can specify limits for each packet type on each port.

Click SEC URITY > Storm Control in the navigation panel to display the screen as shown next.

Figure 455	SECURITY > Storm Control
------------	--------------------------

al de la						
ort	- Erci	odcost (pši/z)	Mi	uticant (pkt/4)		OUT (pkt/x)
3	,E3;	1	(12)		- 11	1
1		<u>n</u>	DED:	0	Ē	C
÷	0	6	13	ġ.	11	<u> </u> 0
3	D	5	17	-0-		(C
ą.	0	<u>3</u> :	105	ð:	- 0	C
*		9	()(3))	0	(D)	6
ē.	0	4	0	0	E.	<u> </u> c
2	10	3	10	0.	1	6
_	_	$\sim$	$\frown$	$\sim$	$\sim$	

Table 357 SECURITY > Storm Control

LABEL	DESC RIPIIO N
Active	Enable the switch button to enable traffic storm control on the Switch. Disable the switch button to disable this feature.
Port	This field displays the port number.
*	Settings in this row apply to all ports. Use this row only if you want to make some settings the same for all ports. Use this row first to set the common settings and then make adjustments on a port-by-port basis. Note: Changes in this row are copied to all the ports as soon as you make them.
Broadcast (pkt/s)	Select this option and specify how many broadcast packets the port receives per second.
Multicast (pkt/s)	Select this option and specify how many multicast packets the port receives per second.
DLF (pkt/s)	Select this option and specify how many destination lookup failure (DLF) packets the port receives per second.
Apply	Click <b>Apply</b> to save your changes to the Switch's run-time memory. The Switch loses these changes if it is turned off or loses power, so use the <b>Save</b> link on the top navigation panel to save your changes to the non-volatile memory when you are done configuring.
Cancel	Click Cancel to reset the fields.

# 79.41 MAINTENANCE

This section explains how to configure the screens that let you maintain the firmware and configuration files.

## 79.42 What You Can Do


- Use the **Restore Configuration** screen (Section 79.43 on page 611) to upload a stored device configuration file.
- Use the **Backup Configuration** screen (Section 79.44 on page 611) to save your configuration for later use.
- Use the Save Configuration screen (Section 79.45 on page 612) to save the current configuration settings to a specific configuration file on the Switch.
- Use the Firm ware Upgrade screen (Section 79.46 on page 613) to upload the latest firmware.
- Use the **Reboot System** screen (Section 79.47 on page 613) to restart the Switch without physically turning the power off and load a specific configuration file.
- Use the Tech-Support screen (Section 79.48 on page 614) to create reports for customer support if there are problems with the Switch.

### 79.43 Restore Configuration

Use this screen to restore a previously saved configuration file from your computer to the Switch.

Click MAINTENANCE > Configuration > Restore Configuration to access this screen.

Figure 456 MAINTENANCE > Configuration > Restore Configuration



- 1 Click Choose File or Browse to locate the configuration file you wish to restore.
- 2 After you have specified the file, click Restore.

The Switch will run on the restored configuration after the restore process.

Figure 457 Configuration Restoring

Restore Cor	nligvration		
		Configuration restoring	

# 79.44 Backup Configuration

Backing up your Switch configurations allows you to create various "snap shots" of your device from which you may restore at a later date. Use this screen to back up your current Switch configuration to a computer.

To access this screen, click **MAINTENANCE** > **Configuration** > **Backup Configuration** in the navigation panel.

Figure 458 MAINTENANCE > Configuration > Backup Configuration

Backup Config	uration		
This page allows:	you to back up the dev	loek o	ment configuration to your wateriation. Now allok the Bookup button.
Configuration	Running Contig	v	
	Beickup		

Follow the steps below to back up the current Switch configuration to your computer in this screen.

- 1 Select which Switch configuration file you want to download to your computer.
- 2 Click Backup.
- 3 If the current configuration file is open and/or downloaded to your computer automatically, you can click **File** > **Save As** on your computer to save the file to a specific place.

If a dialog box pops up asking whether you want to open or save the file, click **Save** or **Save File** to download it to the default downloads folder on your computer. If a **Save As** screen displays after you click **Save** or **Save File**, choose a location to save the file on your computer from the **Save in** drop-down list box and type a descriptive name for it in the **File name** list box. Click **Save** to save the configuration file to your computer.

## 79.45 Save Configuration

To access this screen, click **MAINTENANCE** > **Configuration** > **Save Configuration** in the navigation panel.

Click **Current Configuration** to save the current configuration settings permanently to the Switch. This configuration is set up according to your network environment.

Click **Custom Default** to save the current configuration settings permanently to a customized default file on the Switch.

Figure 459 Maintenance > Configuration > Save Configuration

Sove Configuration		
Maria Dandaria dana a	Carrent Configuration	-
Seve Centigeration as	Contour Colord	

Note: If a customized default file was not saved, clicking **Custom Default** loads the factory default configuration on the Switch.

Alternatively, click  $\mathbf{Save}$  on the top right in any screen to save the configuration changes to the current configuration.

Note: Clicking the **Apply** button after making configuration does NOT save the changes permanently. All unsaved changes are erased after you reboot the Switch.

## 79.46 Firmware Upgrade

Use the following screen to upgrade your Switch to the latest firmware.

Note: Make sure you have downloaded (and unzipped) the correct model firmware and version to your computer before uploading to the device.

Click MAINTENANCE > Firm ware Upgrade to view the screen as shown next.

Figure 460 MAINTENANCE > Firmware Upgrade

himwary Opgrade				
firmwore Upgrade				
	NORM		vector	
	9.80220-0-111	our ning	$\operatorname{Veloc}(\operatorname{ec.vt.}(\operatorname{Se} \mid \operatorname{Vel}(\operatorname{H}/\operatorname{Se}))$	
keepsy media her waaraa	mustres be were the record accord the country (c	Site the and taken the	ande instantes	
No Polla - Cleve a	like (15. Mered a rate			
1 ipger a b				

Click **Choose File** or **Browse** to locate the firmware file you wish to upload to the Switch. Firmware upgrades are only applied after a reboot. Click **Upgrade** to load the new firmware.

After the firmware upgrade process is complete, see the **MONITOR** > **System Information** screen to verify your current firmware version number.

LABEL	DESC RIPIIO N	
Name	This is the name of the Switch that you are configuring.	
Version	This is the version number (and model code) and MM/DD/YYYY creation date of the firmware currently in use on the Switch. The firmware information is also displayed in <b>MONIIOR &gt; SYSTEM Information</b> .	
File Path	Click <b>Choose File</b> or <b>Browse</b> to locate the firmware file you wish to upload to the Switch.	
Upgrade	Click <b>Upgrade</b> to load the new firmware. Firmware upgrades are only applied after a reboot. To reboot, go to <b>MAINTENANCE &gt; Reboot System</b> and click <b>Current Configuration</b> , <b>Factory Default</b> , or <b>Custom Default</b> ( <b>Current Configuration</b> , <b>Factory Default</b> , and <b>Custom Default</b> are the configuration files you want the Switch to use when it restarts).	

Table 358 MAINTENANCE > Firmware Upgrade


## 79.47 Reboot System

**Reboot System** allows you to restart the Switch without physically turning the power off. It also allows you to load the **Current Configuration**, a **Custom Default** or the **Factory Default** configuration when you reboot. Follow the steps below to reboot the Switch.

Click MAINTENANCE > Reboot System to view the screen as shown next.



1 Click the Cument Configuration, Factory Default, or Custom Default button to reboot and load that configuration file. The confirmation screen displays.



2 Click YES and then wait for the Switch to restart. This takes up to 2 minutes.

Click Cument Configuration and follow steps 1 to 2 to reboot and load configuration one on the Switch.

Click Factory Default and follow steps 1 to 2 to reboot and load Zyxel factory default configuration settings on the Switch.

Click Custom Default and follow steps 1 to 2 to reboot and load a customized default file on the Switch.

## 79.48 Tech-Support

The Tech-Support feature is a log enhancement tool that logs useful information such as CPU utilization history, memory and Mbuf (Memory Buffer) log and crash reports for issue analysis by customer support should you have difficulty with your Switch. The Tech Support menu eases your effort in obtaining reports and it is also available in CLI command by typing "Show tech-support" command.

Click MAINTENANCE > Tech-Support to see the following screen.

Figure 463	MAINTENANCE > Tech-Support
------------	----------------------------

Tech-Support	
Town Support	Developed
ROM	Dawniege

You may need WordPad or similar software to see the log report correctly. The table below describes

LABEL	DESC RIPTIO N	
Tech-Support	Click <b>Download</b> to see all the log report and system status. This log report is stored in flash memory. If the All log report is too large, you can download the log reports separately below.	
ROM	Click $\mathbf{Download}$ to see the Read Only Memory (ROM) log report. This report is stored in flash memory.	

the fields in the above screen.

Table 359	MAINTENANCE >	Tech-Support
	MAINTENANCE /	16CII-30PPOI

### 79.48.1 Tech-Support Download

When you click Download to save your current Switch configuration to a computer, the following screen appears. When the log report has downloaded successfully, click Back to return to the previous screen.

Figure 464 MAINTENANCE > Tech-Support: Download

ech-Support download	
Downloading the tech-support file. Pieces well for a moment.	
Back.	

# PART III Throuble shooting and Appendices

## C HAPTER 80 Trouble shooting

This chapter offers some suggestions to solve problems you might encounter. The potential problems are divided into the following categories.

- Power, Hardware Connections, and LEDs
- Switch Access and Login
- Switch Configuration

## 80.1 Power, Hardware Connections, and LEDs

The Switch does not turn on. None of the LEDs turn on.

- 1 Make sure you are using the power adapter or cord included with the Switch.
- 2 Make sure the power adapter or cord is connected to the Switch and plugged in to an appropriate power source. Make sure the power source is turned on.
- 3 Disconnect and re-connect the power adapter or cord to the Switch.
- 4 If the problem continues, contact the vendor.

One of the LEDs does not behave as expected.

- 1 Make sure you understand the normal behavior of the LED. See Section 3.3 on page 53.
- 2 Check the hardware connections. See Section 3.1 on page 44.
- 3 Inspect your cables for damage. Contact the vendor to replace any damaged cables.
- 4 Disconnect and re-connect the power adapter or cord to the Switch.
- 5 If the problem continues, contact the vendor.

## 80.2 Switch Access and Login

I can see the  $\mathbf{Login}$  screen, but I cannot log in to the Switch. (I forgot the user name and/or password.)

- 1 Check the Switch's management mode by using the CLOUD LED. See Section 3.3 on page 53 for more information on the LED descriptions.
  - If you are in Cloud management mode, use the Local credentials Password to log in to the cloud mode local GUI. The Local credentials Password can be found in Site-wide > Configure > General settings > Device configuration: Local credentials: Password in the NCC portal.
  - If you are in standalone management mode, use the default user name **admin** and the default password **1234**.
- 2 Depending on your Switch's management mode, make sure you have entered the correct user name and password. These fields are case-sensitive, please make sure [Caps Lock] is not on.
- **3** You may have exceeded the maximum number of concurrent Telnet sessions. Close other Telnet sessions or try connecting again later.

Check that you have enabled logins for HTTP or Telnet. If you have configured a secured client IP address, your computer's IP address must match it. Refer to the chapter on access control for details.

- 4 If this does not work, or you are not sure what the Switch's management mode is, you have to reset the device to its factory defaults (standalone management mode) first. See Section 4.9 on page 97 for more information on resetting the Switch. (Temporarily disconnect the Internet connection to the Switch after the reset process, to prevent the Switch from being managed by NCC again.)
  - Note: After performing step 4 and you want to use the Cloud management mode, make sure the Switch is registered in your organization and site in the NCC portal. To register the Switch again, scan the QR code using the Zyxel Nebula Mobile app. See the Section on page 32 for more information on using the app to register the Switch.

#### I forgot the IP address for the Switch.

1 Use the domain name "setup.zyxel" to access the Switch whether the Switch is using a DHCP-assigned IP or static IP address. If you cannot use this method, please use the following method to find the IP address.

Note: This requires your computer to be directly connected to the Switch. Make sure your computer is able to connect to a DNS server through the Switch.

- 2 The default IP address is http://DHCP-assigned IP (when connecting to a DHCP server) or 192.168.1.1.
- 3 Use the NCC (Nebula Control Center) or the ZON utility to find the IP address. The Switch must be registered and added to a site in Nebula in order for it to be managed using Nebula.

- 4 If the Switch is removed from a site in Nebula, all the settings in the configuration file are reset to the Nebula factory defaults except for the IP address. If you changed the default dynamic IP address to a static IP address while the Switch was in a site in Nebula, the Switch will retain that static IP address after you remove it from the site in Nebula.
- 5 If this does not work, you have to reset the device to its factory defaults. See Section 4.9.2 on page 98.

#### I forgot the user name and/or password.

- 1 The default user name is **admin** and the default password is **1234**.
- 2 If this does not work, you have to reset the device to its factory defaults. See Section 4.9.2 on page 98.

I cannot see or access the Login screen in the Web Configurator.

- 1 Make sure you are using the correct IP address.
  - The default IP address is http://DHCP-assigned IP (when connecting to a DHCP server) or 192.168.1.1.
  - If you changed the IP address, use the new IP address.
  - If you changed the IP address and have forgotten it, see the troubleshooting suggestions for I forgot the IP address for the Switch.
- 2 Check the hardware connections, and make sure the LEDs are behaving as expected. See Section 3.3 on page 53.
- 3 Make sure your Internet browser does not block pop-up windows and has JavaScripts and Java enabled.
- 4 Make sure your computer is in the same subnet as the Switch. (If you know that there are routers between your computer and the Switch, skip this step.)
- 5 Reset the device to its factory defaults, and try to access the Switch with the default IP address. See Section 4.8 on page 97.
- 6 If the problem continues, contact the vendor, or try the advanced suggestion.

#### Advanced Suggestion

• Try to access the Switch using another service, such as Telnet. If you can access the Switch, check the remote management settings to find out why the Switch does not respond to HTTP.

#### Pop-up Windows, JavaScripts and Java Permissions

In order to use the Web Configurator you need to allow:

- Web browser pop-up windows from your device.
- JavaScripts (enabled by default).
- Java permissions (enabled by default).

There is unauthorized access to my Switch through telnet, HTTP and SSH.

Go to the **MONITOR** > **System Log** screen to check for logs of unauthorized access to your Switch. To avoid unauthorized access, configure the secured client setting in the **SEC URITY** > **Access Control** > **Remote Management** screen for telnet, HTTP and SSH (see Section 66.3 on page 444). Computers not belonging to the secured client set cannot get permission to access the Switch.

## 80.3 Switch Configuration

I lost my configuration settings after I restart the Switch.

Make sure you save your configuration into the Switch's non-volatile memory each time you make changes. Click **Save** at the top right of the Web Configurator to save the configuration permanently. See also Section 78.12 on page 546 for more information about how to save your configuration.



I accidentally unplugged the Switch. I am not sure which configuration file will be loaded.

If you plug the power cable back to the Switch, it will reboot and load the configuration file that was used the last time. For example, if **Config 1** was used on the Switch before you accidentally unplugged the Switch, **Config 1** will be loaded when rebooting.

620

## A PPENDIX A Customer Support

In the event of problems that cannot be solved by using this manual, you should contact your vendor. If you cannot contact your vendor, then contact a Zyxel office for the region in which you bought the device.

For Zyxel Communications offices, see *https://se nvice-pmvider.zyxel.com/global/en/contact-us* for the latest information.

For Zyxel Networks offices, see *https://www.zyxel.com/index.shtml* for the latest information.

Please have the following information ready when you contact an office.

#### Required Information

- Product model and serial number.
- Warranty Information.
- Date that you received your device.
- Brief description of the problem and the steps you took to solve it.

#### Corporate Headquarters (Worldwide)

#### Taiwan

- Zyxel Communications Corporation
- https://www.zyxelcom

#### Asia

#### China

- Zyxel Communications (Shanghai) Corp.
   Zyxel Communications (Beijing) Corp.
   Zyxel Communications (Tianjin) Corp.
- https://www.zyxelcom/cn/zh/

#### India

- Zyxel Technology India Pvt Ltd.
- https://www.zyxelcom/in/en/

#### Ka za khsta n

- Zyxel Kazakhstan
- https://www.zyxel.kz

#### Ko re a

- Zyxel Korea Corp.
- http://www.zyxel.kr

#### Ma la ysia

- Zyxel Malaysia Sdn Bhd.
- http://www.zyxelcom.my

#### Pa kista n

- Zyxel Pakistan (Pvt.) Ltd.
- http://www.zyxelcom.pk

#### **Philippines**

- Zyxel Philippines
- http://www.zyxelcom.ph

#### Singapore

- Zyxel Singapore Pte Ltd.
- http://www.zyxel.com.sg

#### Ta iwa n

- Zyxel Communications Corporation
- https://www.zyxelcom/tw/zh/

#### Tha ila nd

- Zyxel Thailand Co., Ltd.
- https://www.zyxel.com/th/th/

#### Vie tna m

- Zyxel Communications Corporation-Vietnam Office
- https://www.zyxelcom/vn/vi

#### Europe

#### Be la rus

- Zyxel BY
- https://www.zyxelby

#### Bulg a ria

- Zyxel България
- https://www.zyxelcom/bg/bg/

#### Czech Republic

- Zyxel Communications Czech s.r.o
- https://www.zyxel.com/cz/cs/

#### De nm a rk

- Zyxel Communications A/S
- https://www.zyxelcom/dk/da/

#### Finla nd

- Zyxel Communications
- https://www.zyxelcom/fi/fi/

#### Fra nc e

- Zyxel France
- https://www.zyxel.fr

#### Gemany

- Zyxel Deutschland GmbH
- https://www.zyxel.com/de/de/

#### Hung a ry

- Zyxel Hungary & SEE
- https://www.zyxel.com/hu/hu/

#### Ita ly

- Zyxel Communications Italy
- https://www.zyxelcom/it/it/

#### Ne the rlands

- Zyxel Benelux
- https://www.zyxel.com/nl/nl/

#### Norway

- Zyxel Communications
- https://www.zyxel.com/no/no/

#### Poland

- Zyxel Communications Poland
- https://www.zyxelcom/pl/pl/

#### Ro m a nia

• Zyxel Romania

• https://www.zyxelcom/ro/ro

#### Russia

- Zyxel Russia
- https://www.zyxel.com/nu/nu/

#### Slo va kia

- Zyxel Communications Czech s.r.o. organizacna zlozka
- https://www.zyxelcom/sk/sk/

#### Spain

- Zyxel Communications ES Ltd.
- https://www.zyxel.com/es/es/

#### Sweden

- Zyxel Communications
- https://www.zyxel.com/se/sv/

#### Switze rla nd

- Studerus AG
- https://www.zyxelch/de
- https://www.zyxelch/fr

#### Turke y

- Zyxel Turkey A.S.
- https://www.zyxelcom/tr/tr/

#### UK

- Zyxel Communications UK Ltd.
- https://www.zyxelcom/uk/en/

#### Ukra ine

- Zyxel Ukraine
- http://www.ua.zyxel.com

#### South America

#### Argentina

- Zyxel Communications Corporation
- https://www.zyxelcom/co/es/

#### Bra zil

- Zyxel Communications Brasil Ltda.
- https://www.zyxelcom/br/pt/

#### Colombia

- Zyxel Communications Corporation
- https://www.zyxelcom/co/es/

#### Ecuador

- Zyxel Communications Corporation
- https://www.zyxelcom/co/es/

#### South America

- Zyxel Communications Corporation
- https://www.zyxelcom/co/es/

#### Middle East

#### Isra e l

- Zyxel Communications Corporation
- http://il.zyxel.com/

#### North America

#### USA

- Zyxel Communications, Inc. North America Headquarters
- https://www.zyxelcom/us/en/

## **APPENDIX B** Common Services

The following table lists some commonly-used services and their associated protocols and port numbers. For a comprehensive list of port numbers, ICMP type or code numbers and services, visit the IANA (Internet Assigned Number Authority) web site.

- **Name**: This is a short, descriptive name for the service. You can use this one or create a different one, if you like.
- **Protocol:** This is the type of IP protocol used by the service. If this is **TCP**/**UDP**, then the service uses the same port number with TCP and UDP. If this is **Use r-Defined**, the **Port**(s) is the IP protocol number, not the port number.
- Port(s): This value depends on the Protocol. Please refer to RFC 1700 for further information about port numbers.
  - If the Protocol is TCP, UDP, or TCP/UDP, this is the IP port number.
  - If the Protocol is USER, this is the IP protocol number.
- Description: This is a brief explanation of the applications that use this service or the situations in which this service is used.

NAME	PROTOCOL	PO RI(S)	DESC RIPTIO N
AH (IPSEC_TUNNEL)	User-Defined	51	The IPSEC AH (Authentication Header) tunneling protocol uses this service.
AIM/New-ICQ	TCP	5190	AOL's Internet Messenger service. It is also used as a listening port by ICQ.
AUTH	TCP	113	Authentication protocol used by some servers.
BGP	TCP	179	Border Gateway Protocol.
BOOTP_CLIENT	UDP	68	DHCP Client.
BOOTP_SERVER	UDP	67	DHCP Server.
CU-SEEME	TCP	7648	A popular videoconferencing solution from
	UDP	24032	White Pines Software.
DNS	TCP/UDP	53	Domain Name Server, a service that matches web names (for example <i>www.zyxelcom</i> ) to IP numbers.
esp (ipsec_tunnel)	User-Defined	50	The IPSEC ESP (Encapsulation Security Protocol) tunneling protocol uses this service.
FINGER	ТСР	79	Finger is a UNIX or Internet related command that can be used to find out if a user is logged on.
FTP	TCP	20	File Transfer Program, a program to enable fast
	ТСР	21	transfer of files, including large files that may not be possible by email.
H.323	TCP	1720	NetMeeting uses this protocol.
HTTP	TCP	80	Hyper Text Transfer Protocol – a client or server protocol for the world wide web.

#### Table 360 Commonly Used Services



NAME	PROTOCOL	PO RI(S)	DESC RIPTIO N
HTTPS	TCP	443	HTTPS is a secured http session often used in e- commerce.
ICMP	User-Defined	1	Internet Control Message Protocol is often used for diagnostic or routing purposes.
ICQ	UDP	4000	This is a popular Internet chat program.
IGMP (MULTICAST)	User-Defined	2	Internet Group Multicast Protocol is used when sending packets to a specific group of hosts.
IKE	UDP	500	The Internet Key Exchange algorithm is used for key distribution and management.
IRC	TCP/UDP	6667	This is another popular Internet chat program.
MSN Messenger	TCP	1863	Microsoft Networks' messenger service uses this protocol.
NEW-ICQ	TCP	5190	An Internet chat program.
NEWS	TCP	144	A protocol for news groups.
NFS	UDP	2049	Network File System – NFS is a client or server distributed file service that provides transparent file sharing for network environments.
NNTP	TCP	119	Network News Transport Protocol is the delivery mechanism for the USENET newsgroup service.
PING	User-Defined	1	Packet INternet Groper is a protocol that sends out ICMP echo requests to test whether or not a remote host is reachable.
POP3	TCP	110	Post Office Protocol version 3 lets a client computer get e-mail from a POP3 server through a temporary connection (TCP/IP or other).
РРТР	TCP	1723	Point-to-Point Tunneling Protocol enables secure transfer of data over public networks. This is the control channel.
PPTP_TUNNEL (GRE)	User-Defined	47	PPTP (Point-to-Point Tunneling Protocol) enables secure transfer of data over public networks. This is the data channel.
RCMD	TCP	512	Remote Command Service.
REAL_AUDIO	TCP	7070	A streaming audio service that enables real time sound over the web.
REXEC	TCP	514	Remote Execution Daemon.
RLOGIN	TCP	513	Remote Login.
RTELNET	TCP	107	Remote Telnet.
RTSP	TCP/UDP	554	The Real Time Streaming (media control) Protocol (RTSP) is a remote control for multimedia on the Internet.
SFTP	TCP	115	Simple File Transfer Protocol.
SMTP	ТСР	25	Simple Mail Transfer Protocol is the message- exchange standard for the Internet. SMTP enables you to move messages from one email server to another.
SNMP	TCP/UDP	161	Simple Network Management Program.
SNMP-TRAPS	TCP/UDP	162	Traps for use with the SNMP (RFC:1215).

Table 360	Commonly Used Services	(continued)
-----------	------------------------	-------------

NAME	PROTOCOL	PO RI(S)	DESC RIPIIO N
SQL-NET	TCP	1521	Structured Query Language is an interface to access data on many different types of database systems, including mainframes, midrange systems, UNIX systems and network servers.
SSH	TCP/UDP	22	Secure Shell Remote Login Program.
STRM WORKS	UDP	1558	Stream Works Protocol.
SYSLOG	UDP	514	Syslog allows you to send system logs to a UNIX server.
TACACS	UDP	49	Login Host Protocol used for (Terminal Access Controller Access Control System).
TELNET	TCP	23	Telnet is the login and terminal emulation protocol common on the Internet and in UNIX environments. It operates over TCP/IP networks. Its primary function is to allow users to log into remote host systems.
TFTP	UDP	69	Trivial File Transfer Protocol is an Internet file transfer protocol similar to FTP, but uses the UDP (User Datagram Protocol) rather than TCP (Transmission Control Protocol).
VDOLIVE	TCP	7000	Another videoconferencing solution.

Table 360 Commonly Used Services (continued)

## A PPENDIX C IPv6

#### O ve rvie w

IPv6 (Internet Protocol version 6), is designed to enhance IP address size and features. The increase in IPv6 address size to 128 bits (from the 32-bit IPv4 address) allows up to  $3.4 \times 10^{38}$  IP addresses.

#### IPv6 Addressing

The 128-bit IPv6 address is written as eight 16-bit hexadecimal blocks separated by colons (:). This is an example IPv6 address 2001:0db8:1a2b:0015:0000:1a2f:0000.

IPv6 addresses can be abbreviated in two ways:

- Leading zeros in a block can be omitted. So 2001:0db8:1a2b:0015:0000:0000:1a2f:0000 can be written as 2001:db8:1a2b:15:0:0:1a2f:0.
- Any number of consecutive blocks of zeros can be replaced by a double colon. A double colon can only appear once in an IPv6 address. So 2001:0db8:0000:0000:1a2f:0000:0000:0015 can be written as 2001:0db8::1a2f:0000:0000:0015, 2001:0db8:0000:0000:1a2f::0015, 2001:db8::1a2f:0:0:15 or 2001:db8:0:0:1a2f::15.

#### Prefix and Prefix Length

Similar to an IPv4 subnet mask, IPv6 uses an address prefix to represent the network address. An IPv6 prefix length specifies how many most significant bits (start from the left) in the address compose the network address. The prefix length is written as "/x" where x is a number. For example,

2001:db8:1a2b:15::1a2f:0/32

means that the first 32 bits (2001:db8) is the subnet prefix.

#### Link-local Address

A link-local address uniquely identifies a device on the local network (the LAN). It is similar to a "private IP address" in IPv4. You can have the same link-local address on multiple interfaces on a device. A link-local unicast address has a predefined prefix of fe80::/10. The link-local unicast address format is as follows.

Table 361 Link-local Unicast Address Format

1111 1110 10	0	Interface ID
10 bits	54 bits	64 bits

#### GlobalAddress

A global address uniquely identifies a device on the Internet. It is similar to a "public IP address" in IPv4. A global unicast address starts with a 2 or 3.

629

#### Unspecified Address

An unspecified address (0:0:0:0:0:0:0:0:0 or ::) is used as the source address when a device does not have its own address. It is similar to "0.0.0.0" in IPv4.

#### Loopback Address

A loopback address (0:0:0:0:0:0:0:0:1 or ::1) allows a host to send packets to itself. It is similar to "127.0.0.1" in IPv4.

#### Multic a st Addre ss

In IPv6, multicast addresses provide the same functionality as IPv4 broadcast addresses. Broadcasting is not supported in IPv6. A multicast address allows a host to send packets to all hosts in a multicast group.

Multicast scope allows you to determine the size of the multicast group. A multicast address has a predefined prefix of ff00::/8. The following table describes some of the predefined multicast addresses.

Table 362 Predefined Multicast Address

MULTICASTADDRESS	DESC RIPHO N
FF01:0:0:0:0:0:0:1	All hosts on a local node.
FF01:0:0:0:0:0:0:2	All routers on a local node.
FF02:0:0:0:0:0:1	All hosts on a local connected link.
FF02:0:0:0:0:0:0:2	All routers on a local connected link.
FF05:0:0:0:0:0:0:2	All routers on a local site.
FF05:0:0:0:0:1:3	All DHCP severs on a local site.

The following table describes the multicast addresses which are reserved and cannot be assigned to a multicast group.

Table 363 Reserved Multicast Addres	Table 363	Reserved	<b>Multicast</b>	Address
-------------------------------------	-----------	----------	------------------	---------

	Keselveu Mullicusi Aut
MULIICAS	STADDRESS
FF00:0:0:	:0:0:0:0:0
FF01:0:0:	:0:0:0:0:0
FF02:0:0:	:0:0:0:0:0
FF03:0:0:	:0:0:0:0:0
FF04:0:0:	:0:0:0:0:0
FF05:0:0:	:0:0:0:0:0
FF06:0:0:	:0:0:0:0:0
FF07:0:0:	:0:0:0:0:0
FF08:0:0:	:0:0:0:0:0
FF09:0:0:	:0:0:0:0:0
FF0A:0:0:	:0:0:0:0:0
FF0B:0:0:	:0:0:0:0:0
FF0C:0:0:	:0:0:0:0:0
FF0D:0:0:	:0:0:0:0:0
FF0E:0:0:	:0:0:0:0:0
FFOF:0:0:	:0:0:0:0:0

#### Subnet Masking

#### Interface ID

In IPv6, an interface ID is a 64-bit identifier. It identifies a physical interface (for example, an Ethernet port) or a virtual interface (for example, the management IP address for a VLAN). One interface should have a unique interface ID.

#### **EUI-64**

The EUI-64 (Extended Unique Identifier) defined by the IEEE (Institute of Electrical and Electronics Engineers) is an interface ID format designed to adapt with IPv6. It is derived from the 48-bit (6-byte) Ethernet MAC address as shown next. EUI-64 inserts the hex digits fffe between the third and fourth bytes of the MAC address and complements the seventh bit of the first byte of the MAC address. See the following example.

#### Table 364

MAC		00	: 13	: 49	: 12	: 34	: 56	
Table 365								
EUI- 64	02 :	13	: 49	: FF	: FE	: 12	: 34	: 56


#### DHC Pv6

The Dynamic Host Configuration Protocol for IPv6 (DHCPv6, RFC 3315) is a server-client protocol that allows a DHCP server to assign and pass IPv6 network addresses, prefixes and other configuration information to DHCP clients. DHCPv6 servers and clients exchange DHCP messages using UDP.

Each DHCP client and server has a unique DHCP Unique IDentifier (DUID), which is used for identification when they are exchanging DHCPv6 messages. The DUID is generated from the MAC address, time, vendor assigned ID and/or the vendor's private enterprise number registered with the IANA. It should not change over time even after you reboot the device.

#### Identity Association

An Identity Association (IA) is a collection of addresses assigned to a DHCP client, through which the server and client can manage a set of related IP addresses. Each IA must be associated with exactly one interface. The DHCP client uses the IA assigned to an interface to obtain configuration from a DHCP server for that interface. Each IA consists of a unique IAID and associated IP information. The IA type is the type of address in the IA. Each IA holds one type of address. IA\_NA means an identity association for non-temporary addresses and IA\_TA is an identity association for temporary addresses. An IA\_NA option contains the T1 and T2 fields, but an IA\_TA option does not. The DHCPv6 server uses T1 and T2 to control the time at which the client contacts with the server to extend the lifetimes on any addresses in the IA\_NA before the lifetimes expire. After T1, the client sends the server (S1) (from which the addresses in the IA\_NA were obtained) a Renew message. If the time T2 is reached and the server does not respond, the client sends a Rebind message to any available server (S2). For an IA\_TA, the



client may send a Renew or Rebind message at the client's discretion.

#### DHCP Re la y Agent

A DHCP relay agent is on the same network as the DHCP clients and helps forward messages between the DHCP server and clients. When a client cannot use its link-local address and a well-known multicast address to locate a DHCP server on its network, it then needs a DHCP relay agent to send a message to a DHCP server that is not attached to the same network.

The DHCP relay agent can add the remote identification (remote-ID) option and the interface-ID option to the Relay-Forward DHCPv6 messages. The remote-ID option carries a user-defined string, such as the system name. The interface-ID option provides slot number, port information and the VLAN ID to the DHCPv6 server. The remote-ID option (if any) is stripped from the Relay-Reply messages before the relay agent sends the packets to the clients. The DHCP server copies the interface-ID option from the Relay-Forward message into the Relay-Reply message and sends it to the relay agent. The interface-ID should not change even after the relay agent restarts.

#### Pre fix De le g a tio n

Prefix delegation enables an IPv6 router to use the IPv6 prefix (network address) received from the ISP (or a connected uplink router) for its LAN. The Switch uses the received IPv6 prefix (for example, 2001:db2::/ 48) to generate its LAN IP address. Through sending Router Advertisements (RAs) regularly by multicast, the Switch passes the IPv6 prefix information to its LAN hosts. The hosts then can use the prefix to generate their IPv6 addresses.

#### IC MPv6

Internet Control Message Protocol for IPv6 (ICMPv6 or ICMP for IPv6) is defined in RFC 4443. ICMPv6 has a preceding Next Header value of 58, which is different from the value used to identify ICMP for IPv4. ICMPv6 is an integral part of IPv6. IPv6 nodes use ICMPv6 to report errors encountered in packet processing and perform other diagnostic functions, such as "ping".

#### Neighbor Discovery Protocol (NDP)

The Neighbor Discovery Protocol (NDP) is a protocol used to discover other IPv6 devices and track neighbor's reachability in a network. An IPv6 device uses the following ICMPv6 messages types:

- Neighbor solicitation: A request from a host to determine a neighbor's link-layer address (MAC address) and detect if the neighbor is still reachable. A neighbor being "reachable" means it responds to a neighbor solicitation message (from the host) with a neighbor advertisement message.
- Neighbor advertisement: A response from a node to announce its link-layer address.
- Router solicitation: A request from a host to locate a router that can act as the default router and

forward packets.

• Router advertisement: A response to a router solicitation or a periodical multicast advertisement from a router to advertise its presence and other parameters.

#### IPv6 Cache

An IPv6 host is required to have a neighbor cache, destination cache, prefix list and default router list. The Switch maintains and updates its IPv6 caches constantly using the information from response messages. In IPv6, the Switch configures a link-local address automatically, and then sends a neighbor solicitation message to check if the address is unique. If there is an address to be resolved or verified, the Switch also sends out a neighbor solicitation message. When the Switch receives a neighbor advertisement in response, it stores the neighbor's link-layer address in the neighbor cache. When the Switch uses a router solicitation message to query for a router and receives a router advertisement message, it adds the router's information to the neighbor cache, prefix list and destination cache. The Switch creates an entry in the default router list cache if the router can be used as a default router.

When the Switch needs to send a packet, it first consults the destination cache to determine the next hop. If there is no matching entry in the destination cache, the Switch uses the prefix list to determine whether the destination address is on-link and can be reached directly without passing through a router. If the address is onlink, the address is considered as the next hop. Otherwise, the Switch determines the next-hop from the default router list or routing table. Once the next hop IP address is known, the Switch looks into the neighbor cache to get the link-layer address and sends the packet when the neighbor is reachable. If the Switch cannot find an entry in the neighbor cache or the state for the neighbor is not reachable, it starts the address resolution process. This helps reduce the number of IPv6 solicitation and advertisement messages.

#### Multic a st Liste ner Disc overy

The Multicast Listener Discovery (MLD) protocol (defined in RFC 2710) is derived from IPv4's Internet Group Management Protocol version 2 (IGMPv2). MLD uses ICMPv6 message types, rather than IGMP message types. MLDv1 is equivalent to IGMPv2 and MLDv2 is equivalent to IGMPv3.

MLD allows an IPv6 switch or router to discover the presence of MLD listeners who wish to receive multicast packets and the IP addresses of multicast groups the hosts want to join on its network.

MLD snooping and MLD proxy are analogous to IGMP snooping and IGMP proxy in IPv4.

MLD filtering controls which multicast groups a port can join.

#### MID Messages

A multicast router or switch periodically sends general queries to MLD hosts to update the multicast forwarding table. When an MLD host wants to join a multicast group, it sends an MLD Report message for that address.

An MLD Done message is equivalent to an IGMP Leave message. When an MLD host wants to leave a multicast group, it can send a Done message to the router or switch. The router or switch then sends a group-specific query to the port on which the Done message is received to determine if other devices connected to this port should remain in the group.

#### Example - Enabling IPv6 on Windows XP/2003/Vista

By default, Windows XP and Windows 2003 support IPv6. This example shows you how to use the ipv6 install command on Windows XP or 2003 to enable IPv6. This also displays how to use the ipconfig command to see auto-generated IP addresses.

IPv6 is installed and enabled by default in Windows Vista. Use the *ipconfig* command to check your automatic configured IPv6 address as well. You should see at least one IPv6 address available for the interface on your computer.

#### Example – Enabling DHC Pv6 on Windows XP

Windows XP does not support DHCPv6. If your network uses DHCPv6 for IP address assignment, you have to additionally install a DHCPv6 client software on your Windows XP. (Note: If you use static IP addresses or Router Advertisement for IPv6 address assignment in your network, ignore this section.)

This example uses Dibbler as the DHCPv6 client. To enable DHCPv6 client on your computer:

- 1 Install Dibbler and select the DHCPv6 client option on your computer.
- 2 After the installation is complete, select Start > All Programs > Dib b ler DHC Pv6 > C lient Install as service.
- 3 Select Start > Control Panel > Administrative Tools > Services.
- 4 Double click Dibbler a DHC Pv6 client.

- E A	3 <b>8 2 a</b>						
E dei ritser (Lose )	Services (Local)	NE					
	Dibbler - a DHCPv6 client	10.5	Description	1004	tomat type	Logener	ġ,
	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	Statute care in conclusion we	Ann declar .		<ul> <li>A second second</li> </ul>	Local in Form	- 1
	Start the screeks	ADU.: Cirt	Managana	Control		In Dur	3
		Halbiden all-Style ent. Halbigen i Die Station Ziele	Choice et al.	100.00	Automode d'allans à	Loss States	
	and the second sec	Water and the sector Connector		2.00	Merry.	Helenik See	
	Descriptore	Busider:	recheck.	Starter -	· A Sector	Het. Auft	
	Dibble a pertable DHCING	Male war Reporting De Was	Alcohenia.	Serve :	Automotic .	Loss 2009	
	This is OHCIVE client, yonour	Hat one se	Distriction in	Stort rs	A distance de	Ison Svitch	
	07.2.	Aperestorate during a set			No.	trian Sector	
	10.5 Z.	Station for the second second second	the second second		Marine	(diversity)	
		Ref Contextual of the rest	The residence		20043	1965-01910	- 31

5 Click Start and then OK.

and Jugits	Encourse De mole sie
le die une	DI 3%X +#
ling age com	2 stick a DIICTNO class
Description	Calls applied 05 ave 01 - 2025 aver an inn 072
Peinio escual Lorno de Frica	ta 1919 M. Mark Linner of ables nation and contracts contracts of 1919 Mark
St. optiop i	3 è de 👘
ender och m	Sugar
india ad a Ist	Salant Di 25   Pizala   Decave
Your says 1,	
Contraction of the local data	Prain Decare first, gie, obestal gra, etcessischet er erzie


Now your computer can obtain an IPv6 address from a DHCPv6 server.

#### Example - Enabling IPv6 on Windows 7

Windows 7 supports IPv6 by default. DHCPv6 is also enabled when you enable IPv6 on a Windows 7 computer.

To enable IPv6 in Windows 7:

- 1 Select Control Panel > Network and Sharing Center > Local Area Connection.
- 2 Select the Internet Protocol Version 6 (TCP/IPv6) check box to enable it.
- 3 Click **OK** to save the change.



- 4 Click Close to exit the Local Area Connection Status screen.
- 5 Select Start > All Programs > Accessories > Command Prompt.
- 6 Use the *ipconfig* command to check your dynamic IPv6 address. This example shows a global address (2001:b021:2d::1000) obtained from a DHCP server.


#### Example - Enabling IPv6 on Windows 10

Windows 10 supports IPv6 by default. DHCPv6 is enabled when you enable IPv6 on a Windows 10 PC.

To enable IPv6 in Windows 10:

- 1 Select Control Panel > Network and Sharing Center.
- 2 On the left side of the Network and Sharing Center, select Change adapter settings.
- 3 Right-click your network connection and select Properties.

- 4 Select the Internet Protocol Version 6 (TCP/IPv6) check box to enable it.
- 5 Click **OK** to save the changes for the selected network adapter.



6 Click OK to exit the selected network adapter Properties screen.

#### Example - Enabling DHCPv6 on Windows 10

Windows 10 supports DHCPv6 by default. To enable DHCPv6 client on your computer:

- 1 Select Start > Setting s > Ne twork & Internet.
- 2 On the left side of the **Network & Internet**, select **Ethernet**. Then select the Ethernet network you are connected to.
- 3 Under IP assignment, select Edit.
- 4 Under Edit IP settings, select Automatic (DHCP) or Manual. Then click Save.

Jit IP settings	
Actonizaciónic N	
let a col	
37M	Cancel

- When you select Automatic (DHCP), the IP address settings and DNS server address setting are set automatically by your router.
- When you select Manual, you can manually set your IP address settings and DNS server address.

Now your computer can obtain an IPv6 address from a DHCPv6 server.

## A PPENDIX D Legal Information

#### Copyright

Copyright © 2022 by Zyxel and/or its affiliates.

The contents of this publication may not be reproduced in any part or as a whole, transcribed, stored in a retrieval system, translated into any language, or transmitted in any form or by any means, electronic, mechanical, magnetic, optical, chemical, photocopying, manual, or otherwise, without the prior written permission of Zyxel and/or its affiliates.

Published by Zyxel and/or its affiliates. All rights reserved.

#### Disc la im e r

Zyxel does not assume any liability arising out of the application or use of any products, or software described herein. Neither does it convey any license under its patent rights nor the patent rights of others. Zyxel further reserves the right to make changes in any products described herein without notice. This publication is subject to change without notice.

#### Regulatory Notice and Statement

#### **United States of America**



The following information applies if you use the product within USA area. US Importer: Zyxel Communications, Inc, 1130 North Miller Street Anaheim, CA92806-2001, https://www.zyxel.com/us/en/

#### Federal Communications Commission (FCC) EMC Statement

- This device complies with Part 15 of FCC rules. Operation is subject to the following two conditions:
  - (1) This device may not cause harmful interference.
  - (2) This device must accept any interference received, including interference that may cause undesired operations.
- Changes or modifications not expressly approved by the party responsible for compliance could void the user's authority to operate the equipment.
- This equipment has been tested and found to comply with the limits for a Class A digital device, pursuant to part 15 of the FCC Rules. These limits are designed to provide reasonable protection against harmful interference when the equipment is operated in a commercial environment. This equipment generates, uses, and can radiate radio frequency energy and, if not installed and used in accordance with the instruction manual, may cause harmful interference to correct the interference at his own expense.

#### Canada

The following information applies if you use the product within Canada area.

#### Innovation, Science and Economic Development Canada ICES statement CAN ICES-3 (A)/NMB-3(A)

#### **European Union and United Kingdom**



The following information applies if you use the product within the European Union and United Kingdom.

#### EMC statement

WARNING: This equipment is compliant with Class A of EN55032. In a residential environment this equipment may cause radio interference.

638

COUNTRY	ISO 3166 2 LETTER CODE	COUNTRY	ISO 3166 2 LETTER CODE
Austria	AT	Liechtenstein	LI
Belgium	BE	Lithuania	LT
Bulgaria	BG	Luxembourg	LU
Croatia	HR	Malta	MT
Cyprus	СҮ	Netherlands	NL
Czech Republic	CR	Norway	NO
Denmark	DK	Poland	PL
Estonia	EE	Portugal	PT
Finland	FI	Romania	RO
France	FR	Serbia	RS
Germany	DE	Slovakia	SK
Greece	GR	Slovenia	SI
Hungary	HU	Spain	ES
Iceland	IS	Sweden	SE
Ireland	IE	Switzerland	СН
Italy	IT	Turkey	TR
Latvia	LV	United Kingdom	GB

#### List of National Codes

#### Safety Warnings

- To avoid possible eye injury, do NOT look into an operating fiber-optic module's connector.
- Do NOT use this product near water, for example, in a wet basement or near a swimming pool.
- Do NOT expose your device to dampness, dust or corrosive liquids.
- Do NOT store things on the device.
- Do NOT obstruct the device ventilation slots as insufficient airflow may harm your device. For example, do not place the device in an enclosed space such as a box or on a very soft surface such as a bed or sofa.
- Do NOT install, use, or service this device during a thunderstorm. There is a remote risk of electric shock from lightning.
- Connect ONLY suitable accessories to the device.
- Do NOT open the device or unit. Opening or removing covers can expose you to dangerous high voltage points or other risks. Only qualified service personnel should service or disassemble this device. Please contact your vendor for further information.
- Make sure to connect the cables to the correct ports.
- Place connecting cables carefully so that no one will step on them or stumble over them.
- Always disconnect all cables from this device before servicing or disassembling.
  Do NOT remove the plug and connect it to a power outlet by itself; always attach the plug to the power adaptor first before connecting it to
- Do NOT remove the plug and connect in to a power outlet by itself; diways anach the plug to the power adaptor hist before connecting in to a power outlet.
   Do NOT allow anything to rest on the power adaptor or cord and do NOT place the product where anyone can walk on the power adaptor
- Do NOI allow anything to rest on the power adaptor or cord and do NOI place the product where anyone can walk on the power adaptor or cord.
- Please use the provided or designated connection cables/power cables/adaptors. Connect it to the right supply voltage (for example, 110V AC in North America or 230V AC in Europe). If the power adaptor or cord is damaged, it might cause electrocution. Remove it from the device and the power source, repairing the power adapter or cord is prohibited. Contact your local vendor to order a new one.
- Do NOT use the device outside, and make sure all the connections are indoors. There is a remote risk of electric shock from lightning.
   CAUTION: RISK OF EXPLOSION IF BATTERY IS REPLACED BY AN INCORRECT TYPE, DISPOSE OF USED BATTERIES ACCORDING TO THE INSTRUCTION. Dispose them at the applicable collection point for the recycling of electrical and electronic device. For detailed information about recycling of this product, please contact your local city office, your household waste disposal service or the store where you purchased the product.
- Use ONLY power wires of the appropriate wire gauge for your device. Connect it to a power supply of the correct voltage.
- Fuse Warning! Replace a fuse only with a fuse of the same type and rating.
- The POE (Power over Ethernet) devices that supply or receive power and their connected Ethernet cables must all be completely indoors.
- The following warning statements apply, where the disconnect device is not incorporated in the device or where the plug on the power supply cord is intended to serve as the disconnect device,

- For PERMANENTLY CONNECTED DEVICES, a readily accessible disconnect device shall be incorporated external to the device;

- For PLUGGABLE DEVICES, the socket-outlet shall be installed near the device and shall be easily accessible.
- This device must be grounded by qualified service personnel. Never defeat the ground conductor or operate the device in the absence of a suitably installed ground conductor. Contact the appropriate electrical inspection authority or an electrician if you are uncertain that suitable grounding is available.
- If your device has an earthing screw (frame ground), connect the screw to a ground terminal using an appropriate AWG ground wire. Do this before you make other connections.
- If your device has no earthing screw, but has a 3-prong power plug, make sure to connect the plug to a 3-hole earthed socket.
- When connecting or disconnecting power to hot-pluggable power supplies, if offered with your system, observe the following guidelines: – Install the power supply before connecting the power cable to the power supply.
- Unplug the power cable before removing the power supply.
- If the system has multiple sources of power, disconnect power from the system by unplugging all power cables from the power supply.
- CLASS 1 LASER PRODUCT
- APPAREIL À LASER DE CLASS 1

- PRODUCT COMPLIES WITH 21 CFR 1040.10 AND 1040.11.
- PRODUIT CONFORME SELON 21 CFR 1040.10 ET 1040.11.

#### Important Safe ty Instructions

- 1 Warning! Energy Hazard. Remove all metal jewelry, watches, and so on from your hands and wrists before serving the Switch.
- 2 Caution! The RJ-45 jacks are not used for telephone line connection.
- 3 Hazardous Moving Parts. Keep body parts away from fan blades.
- 4 Hot Surface. Do not touch.
- 1 Avertissement: Risque de choc électrique. Retirer tout bijoux en métal et votre montre de vos mains et poignets avant de manipuler cet appareil.
- 2 Attention: Les câbles RJ-45 ne doivent pas être utilisés pour les connections téléphoniques.
- 3 Mobilité des pièces détachées. S'assurer que les pièces détachées ne sont pas en contact avec les pales du ventilateur.
- 4 Surface brûlante. Ne pas toucher.

#### Environment Statement

#### Disposal and Recycling Information

The symbol below means that according to local regulations your product and/or its battery shall be disposed of separately from domestic waste. If this product is end of life, take it to a recycling station designated by local authorities. At the time of disposal, the separate collection of your product and/or its battery will help save natural resources and ensure that the environment is sustainable development.

Die folgende Symbol bedeutet, dass Ihr Produkt und/oder seine Batterie gemäß den örtlichen Bestimmungen getrennt vom Hausmüll entsorgt werden muss. Wenden Sie sich an eine Recyclingstation, wenn dieses Produkt das Ende seiner Lebensdauer erreicht hat. Zum Zeitpunkt der Entsorgung wird die getrennte Sammlung von Produkt und/oder seiner Batterie dazu beitragen, natürliche Ressourcen zu sparen und die Umwelt und die menschliche Gesundheit zu schützen.

El símbolo de abajo indica que según las regulaciones locales, su producto y/o su batería deberán depositarse como basura separada de la doméstica. Cuando este producto alcance el final de su vida útil, llévelo a un punto limpio. Cuando llegue el momento de desechar el producto, la recogida por separado éste y/o su batería ayudará a salvar los recursos naturales y a proteger la salud humana y medioambiental.

Le symbole ci-dessous signifie que selon les réglementations locales votre produit et/ou sa batterie doivent être éliminés séparément des ordures ménagères. Lorsque ce produit atteint sa fin de vie, amenez-le à un centre de recyclage. Au moment de la mise au rebut, la collecte séparée de votre produit et/ou de sa batterie aidera à économiser les ressources naturelles et protéger l'environnement et la santé humaine.

Il simbolo sotto significa che secondo i regolamenti locali il vostro prodotto e/o batteria deve essere smaltito separatamente dai rifiuti domestici. Quando questo prodotto raggiunge la fine della vita di servizio portarlo a una stazione di riciclaggio. Al momento dello smaltimento, la raccolta separata del vostro prodotto e/o della sua batteria aiuta a risparmiare risorse naturali e a proteggere l'ambiente e la salute umana.

Symbolen innebär att enligt lokal lagstiftning ska produkten och/eller dess batteri kastas separat från hushållsavfallet. När den här produkten når slutet av sin livslängd ska du ta den till en återvinningsstation. Vid tiden för kasseringen bidrar du till en bättre miljö och mänsklig hälsa genom att göra dig av med den på ett återvinningsställe.

640



#### 台灣

以下訊息僅適用於產品銷售至台灣地區

• 這是甲類的資訊產品,在居住的環境中使用時,可能會造成射頻干擾,在這種情況下,使用者會被要求採取某些適當的對策。」

安全警告 - 為了您的安全, 請先閱讀以下警告及指示:

- 請勿將此產品接近水、火焰或放置在高溫的環境。
- 避免設備接觸
   -任何液體 切勿讓設備接觸水、雨水、高濕度、污水腐蝕性的液體或其他水份。
   灰塵及污物 切勿接觸灰塵、污物、沙土、食物或其他不合適的材料。
- 一次產次方物。仍須接觸次產。方物。乃工。食物或其他不自過的作
   雷雨天氣時,不要安裝,使用或維修此設備。有遭受電擊的風險。
- 国际气氛时,不安安表,使用或症间此故痛。有道受电
   切勿重摔或撞擊設備,並勿使用不正確的電源變壓器。
- 防約里評或理事設備,並為使用不正確的電源委
   若接上不正確的電源變壓器會有爆炸的風險。
- 請勿隨意更換產品內的電池。
- 如果更換不正確之電池型式,會有爆炸的風險,請依製造商說明書處理使用過之電池。
- 請將廢電池丟棄在適當的電器或電子設備回收處。
- 請勿將設備解體。
- 請勿阻礙設備的散熱孔,空氣對流不足將會造成設備損害。
- 請插在正確的電壓供給插座 (如: 北美 / 台灣電壓 110V AC · 歐洲是 230V AC)。
- 假若電源變壓器或電源變壓器的纜線損壞,請從插座拔除,若您還繼續插電使用,會有觸電死亡的風險。
- 請勿試圖修理電源變壓器或電源變壓器的纜線,若有毀損,請直接聯絡您購買的店家,購買一個新的電源變壓器。
- 請勿將此設備安裝於室外,此設備僅適合放置於室內。
- 請勿隨一般垃圾丟棄。
- 請參閱產品背貼上的設備額定功率。
- 請參考產品型錄或是彩盒上的作業溫度。
- 設備必須接地,接地導線不允許被破壞或沒有適當安裝接地導線,如果不確定接地方式是否符合要求可聯繫相應的電氣檢驗機構檢驗。
- 如果您提供的系統中有提供熱插拔電源,連接或斷開電源請遵循以下指導原則:
  - 先連接電源線至設備連,再連接電源。
  - 先斷開電源再拔除連接至設備的電源線。
  - 如果系統有多個電源·需拔除所有連接至電源的電源線再關閉設備電源。
- 產品沒有斷電裝置或者採用電源線的插頭視為斷電裝置的一部分,以下警語將適用:
  - 對永久連接之設備,在設備外部須安裝可觸及之斷電裝置;
  - 對插接式之設備,插座必須接近安裝之地點而且是易於觸及的。

#### About the Symbols

Various symbols are used in this product to ensure correct usage, to prevent danger to the user and others, and to prevent property damage. The meaning of these symbols are described below. It is important that you read these descriptions thoroughly and fully understand the contents.

SYMBOL	EXPLANATION
	Alternating current (AC):
$\sim$	AC is an electric current in which the flow of electric charge periodically reverses direction.
	Direct current (DC):
	DC if the unidirectional flow or movement of electric charge carriers.
	Earth; ground:
	A wiring terminal intended for connection of a Protective Earthing Conductor.
	Class II equipment:
	The method of protection against electric shock in the case of class II equipment is either double insulation or reinforced insulation.

#### Explanation of the Symbols

#### Viewing Certifications

Go to *http://www.zyxe.lcom* to view this product's documentation and certifications.

#### Zyxel Limited Warranty

Zyxel warrants to the original end user (purchaser) that this product is free from any defects in material or workmanship for a specific period (the Warranty Period) from the date of purchase. The Warranty Period varies by region. Check with your vendor and/or the authorized Zyxel local distributor for details about the Warranty Period of this product. During the warranty period, and upon proof of purchase, should the product have indications of failure due to faulty workmanship and/or materials, Zyxel will, at its discretion, repair or replace the defective products or components without charge for either parts or labor, and to whatever extent it shall deem necessary to restore the product of equal or higher value, and will be solely at the discretion of Zyxel. This warranty shall not apply if the product has been modified, misused, tampered with, damaged by an act of God, or subjected to abnormal working conditions.

#### Note

Repair or replacement, as provided under this warranty, is the exclusive remedy of the purchaser. This warranty is in lieu of all other warranties, express or implied, including any implied warranty of merchantability or fitness for a particular use or purpose. Zyxel shall in no event be held liable for indirect or consequential damages of any kind to the purchaser.

To obtain the services of this warranty, contact your vendor. You may also refer to the warranty policy for the region in which you bought the device at http://www.zyxelcom/web/support\_warranty\_info.php.

#### Registration

Register your product online at www.zyxe.lcom to receive email notices of firmware upgrades and related information.

#### Trademarks

The trademarks mentioned in this publication are used for identification purposes only and may be properties of their respective owners.

## Index

## Numbers

10 Gigabit port
requirement for maximum performance 29
10G port 29
802.1P priority 265, 587

## Α

AAA 429 accounting 429 authentication 429 authorization 429 AAA (Authentication, Authorization and Accounting) 429 access control account security 445 limitations 443, 607 login account 187, 567 overview 443, 606 remote management 444, 608 service port 443, 607 SNMP 195 account security 445 Account Security screen 446 accounting setup 434 Address Resolution Protocol (ARP) 123, 405, 547, 548 admin 446 administrator password 61, 188, 568 age 356 aging time 199 air circulation for cooling 40 All connected Setting Wizard 388 anti-arpscan 468 blocked hosts 469 host threshold 470 status 469

trusted hosts 472 applications backbone 36 bridging 36 IEEE 802.1Q VLAN 37 PoE 35 switched workgroup 37 ARP how it works 405 learning mode 405 overview 405 ARP (Address Resolution Protocol) 123 ARP inspection 485, 516 and MAC filter 516 configuring 517 syslog messages 517 trusted ports 517 ARP Learning screen 407 ARP scan 468 ARP Setup screen 407 ARP Table screen 123 ARP-Reply 405 ARP-Request 406 authentication setup 434 authentication, authorization and accounting 429 authorization privilege levels 437 setup 434 authorized technician install the Switch 40 auto PD recovery 208 enable 208 restart 208 use LLDP or ping 208 auto-crossover port 46 automatic PD recovery create 210 automatic VLAN registration 367, 600 auto-MDIX port 46

#### В

back up configuration file 543, 611 bandwidth control 332, 333 egress rate 333 ingress rate 333 setup 332 Bandwidth Control screen 332 basic setup tutorial 105 binding table 485 building 485, 489 BPDU (Bridge Protocol Data Units) 474 BPDU guard 474 and Errdisable Recovery 474 port status 474 BPDUs 339 Bridge Protocol Data Units 474 Bridge Protocol Data Units (BPDUs) 339 bridging application 37 broadcast storm control 477 Wizard 82

## С

cable type bandwidth capacity 30 distance limitation 30 transmission speed 30 cables supported 35 Cat 5 cable 29 Cat 5e cable 29 Cat 6 cable 29 Cat 6a cable 29 CDP 273 Certificates screen 534 certifications viewing 642 CFI (Canonical Format Indicator) 367, 599 changing the password 96 Cisco Discovery Protocol, see CDP CIST 361 Class of Service 323

classifier 453 and QoS 453 example 460 logging 459 match order 459 overview 453 setup 454, 456 status 454 clearance Switch installation 40 cloning a port, see port cloning Cloud Connection Status 119 cluster management 537 and switch passwords 541 cluster manager 538, 540 cluster member 538 cluster member firmware upgrade 542 network example 538 setup 539 specification 537 status 538 switch models 537 VID 540 Web Configurator 541 Cluster Management Configuration screen 539 cluster manager 538 Common and Internal Spanning Tree, see CIST 361 Config 1 553 Config 2 553 configuration 424 back up 39 change running config 552, 613 saving 97 configuration file 98 backup 543, 611 restore 98, 543, 611 save 546 Configure Clone screen 547 contact information 621 copying port settings, see port cloning copyright 638 CoS 323 CPU management port 387 CPU protection 479 crossover Ethernet cable 45 Current Configuration 614

current date 158, 565 current time 158, 564 Custom Default 553, 614 customer support 621

## D

date current 158, 565 daylight saving time 158, 565 DDMI Details screen 142 DDMI screen 141 debug port 48 device back label Switch 32 DHCP 411 configuration options 412 modes 411 DHCP (Dynamic Host Configuration Protocol) 411 DHCP Option 82 Profile screen 412, 413 DHCP relay configure 112 tutorial 109 DHCP relay agent 632 DHCP relay option 82 498 **DHCP** server block 489 DHCP snooping 105, 485, 497 configure 499 DHCP relay option 82 498 trusted ports 498 untrusted ports 498 DHCP snooping database 498 DHCP Status screen 412 DHCP Unique IDentifier (DUID) 631 DHCP-assigned IP 618 DHCPv4 global relay 414 global relay example 416 option 82 profiles 412, 413 DHCPv6 enable in Windows 10 637 enable in Windows XP 634 DHCPv6 client 38

DHCPv6 Client Setup screen 185 DHCPv6 relay 38 interface-ID 420 remote-ID 420 DHCPv6 Relay screen 420, 421 diagnostics ping 549 Differentiated Service (DiffServ) 323 DiffServ 323 activate 324 DS field 323 DSCP 323 network example 324 PHB 323 service level 323 DiffServ Code Points 323 Digital Diagnostics Monitoring Interface 141 disclaimer 638 disposal and recycling information EU 640 double-tagged frames 397 DS (Differentiated Services) 323 DSCP 323 what it does 323 dual firmware images 551, 613 duplex mode 45 dust plug 47 Dynamic Host Configuration Protocol for IPv6 (DHCPv6) 631 dynamic link aggregation 218

### Ε

egress port 388 egress rate 333 electrical inspection authority 50 electrician 51 electrostatic discharge (ESD) 46 EMC statement 638 Environment Statement 640 Errdisable Detect screen 482 Errdisable Recovery screen 483 errdisable status 481 error disable 479

XGS2220 Series User's Guide

control packets 481 CPU protection 481 detect 482 recovery 483 status 480 error-disable recovery 479 Ethernet broadcast address 123, 405 Ethernet MAC 148, 559 Ethernet OAM 248 Ethernet port auto-crossover 45 auto-negotiating 45 Ethernet settings default 46 external authentication server 430

## F

Factory Default 553, 614 FCC interference statement 638 fiber cable connecting 47 removal 48 file transfer using FTP command example 536 filename convention, configuration file names 535 filtering 362 rules 362 filtering database, MAC table 129 Filtering screen 362 firmware 559 upgrade 542, 551, 613 ZyNOS 148 Firmware Upgrade screen 551, 613 flow control 265, 587 back pressure 265, 587 IEEE802.3x 265, 587 forwarding delay 356 frames tagged 374, 606 untagged 374, 606 freestanding installation precautions 41

```
front panel 44
FTP 535
file transfer procedure 536
restrictions over WAN 537
full duplex
Ethernet port 45
```

## G

GARP (Generic Attribute Registration Protocol) 367, 600 GARP timer 199, 367, 600 general setup 157 General Setup screen 157, 563 getting help 99 gigabit ports 45 GMT (Greenwich Mean Time) 158, 565 gratuitous ARP 406 green Ethernet 216 and uplink port 216 auto power down 216 EEE 216 short reach 216 grounding for safety 49 GVRP 600 GVRP (GARP VLAN Registration Protocol) 368, 600

## Η

half duplex Ethernet port 45 hardware installation 40 hardware monitor 148, 559 hardware overview 44 hello time 356 hops 356 HTTPS 449 certificates 449 implementation 449 public keys, private keys 449 HTTPS Certificates screen 534 HTTPS example 450

XGS2220 Series User's Guide

646

### 

IANA (Internet Assigned Number Authority) 626 Identity Association (IA) 631 IEEE 802.1x activate 520 port authentication 518 re-authentication 521 IEEE 802.3at 34 IEEE 802.3az 216 IEEE 802.3bt 34 IEEE 802.3bz 29 IEEE standard 35 IGMP filtering 283 profile 292, 293, 596, 597 IGMP leave timeout fast 289, 593 normal 289, 593 IGMP snooping 283 MVR 285 IGMP snooping and VLANs 284 IGMP throttling 290, 593 ingress port 388 ingress rate 333 initial setup 100 Innovation, Science and Economic Development Canada ICES statement 638 installation air circulation 40 desktop 40 freestanding 40 rack-mounting 41 transceiver 46 installation scenarios 40 Interface Setup screen 161, 162 Internet Protocol version 6, see IPv6 IP configuration 166 interface 163 routing domain 163 status 164 IP address 165 Switch management 102 IP Setup screen 163 IP source guard 485 ARP inspection 485, 516

DHCP snooping 485 static bindings 485 IP Status Detail screen 164 IP subnet mask 165 IP table 125 how it works 125 IPv4/IPv6 dual stack 38 IPv6 38, 629 addressing 629 enable in Windows 10 636 enable in Windows 2003 634 enable in Windows 7 635 enable in Windows Vista 634 enable in Windows XP 634 EUI-64 631 global address 629 interface ID 631 link-local address 629 Neighbor Discovery Protocol 38, 629 neighbor table 127 ping 38, 629 prefix 629 prefix length 629 unspecified address 630 IPv6 address size 38 IPv6 cache 633 IPv6 Global Setup screen 173 IPv6 interface 161 DHCPv6 client 184, 185 enable 174, 175 global address 177, 178 global unicast address 173 link-local address 175, 176 link-local IP 172 neighbor discovery 178, 179 neighbor table 183 status 171 IPv6 Interface Setup Edit screen 175 IPv6 Interface Setup screen 175 IPv6 Interface Status screen 172 IPv6 multicast status 294 IPv6 Neighbor Setup screen 183, 184 IPv6 Neighbor Table screen 127 IPv6 screen 170 IPv6 static route configuration 426

## J

Java permission **57**, **620** JavaScript **57**, **620** 

## L

L2PT 271 access port 272 CDP 271 configuration 272 encapsulation 271 example 271 LACP 272 MAC address 271, 273 mode 272 overview 271 PAgP 272 point to point 272 STP 271 tunnel port 272 UDLD 272 VTP 271 LACP 218, 274 system priority 223, 580 timeout 224, 581 Layer 2 protocol tunneling, see L2PT LED behavior CLOUD 31 LED description 31 LEDs 53 limit MAC address learning 532 link aggregation 71, 80, 218 dynamic 218 ID information 219 setup 221, 578 traffic distribution algorithm 220, 577 traffic distribution type 222, 579 trunk group 218 link aggregation (trunking) 578 Link Aggregation Control Protocol (LACP) 218 Link Aggregation screen Wizard 80 Link Aggregation Setting screen 578 Link Aggregation Status screen 576

Link Layer Discovery Protocol 226 LLDP 226 basic TLV 240 global settings 238 local port status 230 organization-specific TLV 241 status of remote device 234 TLV 226 LLDP (Link Layer Discovery Protocol) 226 LLDP-MED 227 classes of endpoint devices 227 example 227 LLDP-MED Location screen 245 LLDP-MED Setup screen 242 local port mirroring 280 lockout 97 Switch 97 log message 150 login 57 password 96 privilege level 188, 569 login account administrator 187, 567 non-administrator 187, 567 login accounts 187, 567 configuring through Web Configurator 187, 567 multiple 187, 567 number of 187, 567 login password edit 188, 568 login user name display 446 Logins screen 187, 567 loop guard 275 examples 276 port shut down 276 setup 277 vs. STP 275 Wizard 82

#### Μ

MAC (Media Access Control) 148, 559 MAC address 123, 148, 559 maximum number per port 532



MAC address learning 199, 532 specify limit 532 MAC Based VLAN screen 383, 384 MAC filter and ARP inspection 516 MAC freeze 531 MAC table 129 display criteria 131 how it works 129 sorting criteria 131 viewing 130 MAC-based VLAN 383 maintenance configuration backup 543, 611 firmware 551, 613 restore configuration 543, 611 Management Information Base (MIB) 195, 570 management IP address 102 management mode 30 management port 388 managing the device using the command line interface, see command line interface 39 managing the Switch cluster management 39 good habits 39 NCC 38 using FTP, see FTP 39 using SNMP 39 Web Configurator 39 ZON Utility 39 man-in-the-middle attacks 516 max age 356 hops 356 maximum transmission unit 136 Maximum Transmission Unit (MTU) 172 Mbuf (Memory Buffer) 554 MDIX (Media Dependent Interface Crossover) 46 Media Access Control 148, 559 Memory Buffer 554 MIB and SNMP 195, 570 supported MIBs 196 MIB (Management Information Base) 195, 570 mirroring ports 280

MLD filtering profile 301, 302 MLD proxy 38 MLD snooping 38 MLD snooping-proxy 295 filtering 299 filtering profile 301, 302 port role 298 VLAN ID 297 models XS1930 28 monitor port 280, 588 mounting brackets attaching 42 MSA (MultiSource Agreement) 46 MST Instance, see MSTI 361 MST region 360 MSTI 361 MSTP bridge ID 354 configuration 355 configuration digest 354 forwarding delay 356 Hello Time 354 hello time 356 Max Age 354 max age 356 max hops 356 path cost 358 port priority 358 revision level 357 status 353 MTU 136 MTU (Multi-Tenant Unit) 198 multicast IGMP throttling 290, 593 IP addresses 283 multicast group 292, 293, 596, 597 multicast IP address 310 multicast MAC address 310 Multi-Gigabit (IEEE 802.3bz) 29 Multi-Gigabit port 29 Multi-Tenant Unit 198 MVR 285 configuration 303, 304 network example 285 MVR (Multicast VLAN Registration) 285 myZyxel account sign up **32** myZyxel account information enter **32** 

### Ν

Nebula Cloud Management 31 switching to 31 Nebula web portal 31 access in three ways 32 Neighbor Details 134 Neighbor Discovery Protocol (NDP) 632 Neighbor screen 132 network applications 29, 35 network element (NE) 569 network management system (NMS) 195, 569 Networked AV mode 34, 556 overview 556 Networked AV screen Wizard 69, 74 NTP (RFC-1305) 158, 564

## 0

OAM 248 details 249 discovery 248 port configuration 248 remote loopback 248, 254 Operations, Administration and Maintenance 248 organization create 32 Organizationally Unique Identifiers (OUI) 381 Org-specific TLV Setting screen 241 overheating prevention 40

#### Ρ

PAgP 274 password 96

administrator 61, 188, 568 change 39 change through Wizard 68, 73, 79 display 446 write down 39 password change through Password / SNMP link 60 password encryption activate 447 Path MTU Discovery 136 Path MTU Table screen 136 Per-Hop Behavior 323 PHB 323 ping, test connection 549 PoF PD priority 260, 585 power management mode 259, 584 power-up mode 258, 583 PoE (Power over Ethernet) 256 **PoE** features by model 34 PoE Setup screen 258 PoE standards 34 PoE Status screen 257 PoE Time Range Setup screen 262 PoE type 35 policy 463, 464 and classifier 463, 464 and DiffServ 462 configuration 463, 464 example 466 overview 462 rules 462, 463 port maximum power 35 setup 264, 586 speed/duplex 265 voltage range 35 Port Aggregation Protocol, see PAgP port authentication guest VLAN 523 IEEE802.1x 520 MAC authentication 521 method 520 port cloning 547, 548 advanced settings 547, 548 basic settings 547, 548

port details 138 port isolation Setting Wizard 388 port mirroring 280 port redundancy 218 Port screen DHCPv4 Global Relay 416 port security 530 address learning 532 limit MAC address learning 532 setup 530 Port Setup screen 264, 586 port status port details 138 port utilization 143 port utilization 143 Port VID (PVID) 101 port VLAN ID, see PVID 374, 606 port VLAN trunking 368, 601 port-based VLAN 386 all connected 388 configure 387 port isolation 388 settings wizard 388 ports diagnostics 550 mirroring 280 speed/duplex 587 standby 219 power maximum per port 35 voltage 148, 560 power connections 51 power connector 51 power cord requirement XGS2220-54HP / XGS2220-54FP 51 Power Sourcing Equipment (PSE) 34 power status 148, 560 powered device (PD) 34, 256 PPPOEIA 315 agent sub-options 317 drop PPPoE packets 319 port state 317 sub-option format 316 tag format 315 trusted ports 317

untrusted ports VLAN **322** PPPoE Intermediate Agent prefix delegation product registration protocol based VLAN example **380** PVID **367**,

## Q

```
QoS 323
and classifier 453
priority setting 86
QoS setting 85
QR code
Switch 32
where to find 32
Quality of Service 323
queue weight 328
queuing 327, 328
SPQ 327
WRR 327
queuing method 327, 329
Quick Start Guide
steps for registering the Switch 31
```

## R

rack-mounting 41 precautions 41 RADIUS 430, 443 advantages 430 setup 430 Rapid Spanning Tree Protocol (RSTP) 338 rear panel 48 reboot load configuration 552, 613 reboot system 552, 613 registration product 642 Registration MAC address 32 Regulatory Notice and Statement 638 remote management 38, 444, 608 service 445, 609 trusted computers 445, 609 Remote Management screen 608 RESET button 97 resetting 97, 545 to factory default settings 545 restore configuration 39 restore configuration 97, 543, 611 RFC 3164 201 Round Robin Scheduling 327 Router Advertisement (RA) 632 routing domain 163 RSTP configuration 346 rubber feet attach 41 running configuration 545 erase 545 reset 545

## S

safety precautions using the Switch 40 safety warnings 639 save configuration 97, 546 Save link 97 schedule type 205 Secure Shell, see SSH serial number Switch 32 service access control 443, 607 service port 444, 608 Service Access Control screen 607 Setup Wizard parts 66, 76 Setup Wizard screen 59 sFlow 334 configuration 334 datagram 334 overview 334

poll interval 335 sample rate 335 UDP port 337 sFlow agent 334 sFlow collector 334 SFP/SFP+ slot 46 Simple Network Management Protocol (SNMP) 569 Simple Network Management Protocol, see SNMP site create 32 SNMP 195 agent 195, 569 and MIB 195, 570 authentication 191, 192, 572, 573 communities 61, 190, 571 management model 195, 569 manager 195, 569 MIB 196 network components 195, 569 object variables 195, 570 protocol operations 195, 570 security 192, 573 security level 191, 572 settings 569 setup 189, 569 traps 193, 573 users 191, 571 version 3 and security 195, 570 versions supported 195, 569 **SNMP** agent enable through Wizard 68, 73, 79 SNMP screen 570 SNMP traps 196 supported 196 **SNMP** version select 68, 73, 79 specifications power cord 51 SPQ (Strict Priority Queuing) 327 SSH encryption methods 448 how it works 447 implementation 448 SSH (Secure Shell) 447 SSL (Secure Socket Layer) 449 stacking mode 29 Standalone mode

XGS2220 Series User's Guide

switch to 33 standby ports 219 static address assignment 38 static bindings 485 static MAC address 364 static MAC forwarding 364 Static MAC Forwarding screen 364, 365 static multicast forwarding 310 static route 424 enable 426 metric 426 overview 424 static VLAN 371, 603 control 373, 605 tagging 373, 605 status 86 MSTP 353 power 148, 560 STP 344 VLAN 369, 601 Storm Control screen 609 STP 273 bridge ID 345, 349 bridge priority 347, 351 designated bridge 339 edge port 347, 352 forwarding delay 347 Hello BPDU 339 Hello Time 345, 347, 349, 351 how it works 339 Max Age 345, 347, 349, 352 path cost 339, 348, 352 port priority 348, 352 port role 345, 350 port state 339, 345, 350 root port 339 status 341, 344 terminology 339 vs. loop guard 275 STP Path Cost 339 straight-through Ethernet cable 45 subnet based VLANs 376 subnet masking 631 Summary screen 556 supply voltage 51 Switch DHCP client 57

fanless-type usage precaution 40 fan-type usage precaution 40 switch lockout 97 Switch reset 97 syslog 201, 517 protocol 201 settings 201 setup 201 severity levels 201 Syslog Setup screen 201 System Info screen 147, 558 system reboot 552, 613

## Т

TACACS+ 430, 443 advantages 430 setup 432 tag-based VLAN example 38 tagged VLAN 367, 599 Tech-Support 553, 614, 615 log enhancement 553, 614 Tech-Support screen 553, 614 temperature indicator 148, 560 time current 158, 564 daylight saving 158, 565 format 158, 564 Time (RFC-868) 158, 564 time server 158, 564 time service protocol 158, 564 ToS 323 trademarks 642 traffic distribution criteria 219 transceiver connection interface 46 connection speed 46 installation 46 removal 47 traps destination 190, 571 troubleshooting 113 trunk group 218

Trunk Tagged port 85 trunking 218 trusted ports ARP inspection 517 DHCP snooping 498 PPPoE IA 317 tutorial basic setup 105 DHCP snooping 105 twisted pair used 35 Type of Service 323 Type Transfer 131

## U

UDLD 274 UniDirectional Link Detection, see UDLD unregister Switch 33 untrusted ports ARP inspection 517 DHCP snooping 498 PPPOE IA 317 uplink connection super-fast 36 user name 58 default 58 user profiles 430 UTC (Universal Time Coordinated) 158, 565

## V

Vendor ID Based VLAN screen 385 Vendor Specific Attribute, see VSA 437 ventilation holes 40 VID 168, 370, 371, 399, 567, 602, 603 number of possible VIDs 367, 599 priority frame 367, 599 VID (VLAN Identifier) 367, 599 Virtual Local Area Network 198 VLAN 198 acceptable frame type 374, 606

and IGMP snooping 284 automatic registration 367, 600 creation 100, 109 ID 367, 599 ingress filtering 374, 606 introduction 198, 367, 599 number of VLANs 370, 602 port number 371, 603 port settings 373, 375, 605 port-based 388 port-based VLAN 386 port-based, isolation 388 port-based, wizard 388 PVID 374, 606 static VLAN 371, 603 status 369, 370, 371, 601, 602, 603 subnet based 376 tagged 367, 599 terminology 368, 600 trunking 368, 374, 601, 606 type 199, 369 VLAN (Virtual Local Area Network) 198 VLAN ID 367, 599 VLAN mapping 393 activating 394 configuration 395 example 393 priority level 393 tagged 393 traffic flow 393 untagged 393 VLAN ID 393 VLAN member port 85 VLAN number 165, 168, 567 VLAN setting Wizard 84 VLAN Setting screen DHCPv4 419 VLAN stacking 397, 399 configuration 399 example 397 frame format 399 port roles 398, 400 port-based Q-in-Q 401 priority 399 selective Q-in-Q 402 VLAN terminology 368, 600 VLAN trunking 374, 606

VLAN Trunking Protocol, see VTP VLAN-unaware devices 101 voice VLAN 381 Voice VLAN Setup screen 381, 382 voltage range port 35 VSA 437 VTP 273

### W

warranty note 642 Web browser pop-up window 57, 620 Web Configurator getting help 99 home 86 login 57 logout 98 navigating components 87 navigation panel 88 online help 99 usage prerequisite 57 weight 328 Windows OS version check 62 Wizard link aggregation 71 WRR (Weighted Round Robin Scheduling) 327

## Ζ

ZDP 62 ZON Utility 62 compatible OS 62 fields description 65 icon description 65 installation requirements 62 introduction 33 minimum hardware requirements 62 network adapter select 63 password prompt 65 run 62 supported firmware version 63 supported models 63 Switch IP address 57 ZON utility use for troubleshooting 618 ZULD example 266 probe time 268 status 267 ZULD (Zyxel Unidirectional Link Detection) 266 ZyNOS (Zyxel Network Operating System) 535 Zyxel AP Configurator (ZAC) 65 Zyxel AP Configurator (ZAC) 65 Zyxel Discovery Protocol (ZDP) 62 Zyxel Nebula Mobile app 32 Zyxel One Network (ZON) Utility 33 Zyxel Unidirectional Link Detection (ZULD) 266